# ELECTRONICS WORLD

FEBRUARY, 1960

formerly

RADIO & TV NEWS

50 CENTS

**SPECIAL FEATURE**

**DIRECTORY OF CITIZENS BAND EQUIPMENT WITH LATEST RULES AND REGULATIONS**

**CONSTRUCTION DETAILS ON A TWO-METER TRANSISTOR TRANSMITTER**

**ROOM ACOUSTICS FOR STEREO**

**Part 2. Reverberation and Room Treatment**

A ZIFF-DAVIS PUBLICATION



# A TUBE WITH A FUTURE

THE NEW **Amperex®**
UHF TWIN-TETRODE
**TYPE 7377**

The need has long existed for stable tubes in the 500-1000 Mc. range. Now, with the availability of the Type 7377, the UHF equipment designer is provided with a uniquely constructed, uniquely efficient twin-tetrode capable of stable operation up to 1000 Mc.

## THE UNIQUE CONSTRUCTION OF THE NEW AMPEREX TYPE 7377....

- The plate lead structure and pins are isolated from the main socket, thereby making the anode pins an integral part of the external circuit.
- Plate lead structure, plus a tuning stub (which extends downwards through a cutout in the socket) permits exceptionally compact equipment packaging.
- Frame grid structure provides optimum reliability.
- Getter structure, and hence getter film, isolated from cage structure.

## PLUS THE COMBINED EXCELLENCE OF THESE IMPRESSIVE FEATURES...

- Delivers 5.5 watts output (ICAS) at 960 Mc.
- Extremely low plate output impedance and capacitance. (Plate output cap: 0.82 $\mu\mu$f for both sections in push-pull operation.)
- Internally neutralized plate-to-grid capacitance (0.145 $\mu\mu$f for each section.)
- High transconductance (10,500 micromhos)
- High gain and high figure of merit.

## IS YOUR GUARANTEE OF UNIQUE SUITABILITY AS AN RF AMPLIFIER OR FREQUENCY MULTIPLIER FOR:

- Telemetering
- TV link communications
- Mobile and small transmitters
- Broadband amplifiers

## TYPICAL OPERATION, CLASS C AMPLIFIER

| | ICAS |
|---|---|
| Frequency | 960 Mc/s |
| Plate Voltage | 250 volts |
| Grid No. 2 Voltage | 170 volts |
| Negative Grid No. 1 Voltage | 15 volts |
| Plate Current | 2 x 40 mA |
| Grid No. 2 Current | 15 mA |
| Grid No. 1 Current | 2 x 0.75 mA |
| Drive Power | 1.4 watts |
| Plate Input Power | 2 x 10 watts |
| Plate Dissipation | 2 x 5.4 watts |
| Plate Power Output | 8 watts |
| Load Power Output | 5 watts |

ask **Amperex**
about tubes for RF, VHF, and UHF applications

**AMPEREX ELECTRONIC CORPORATION**
**230 Duffy Avenue, Hicksville, Long Island, N.Y.**
In Canada: Rogers Electronic Tubes & Components,
116 Vanderhoof Avenue, Toronto, Ontario

# make your first move to ROHN

You Have the Greatest Sales Potential by Far With America's MOST COMPLETE LINE OF

**TOWERS—MASTS**
**ROOF TOWERS**
**Installation Accessories**

From every standpoint, ROHN Towers offer you MORE . . . more quality, more variety, more advanced design, more sales features, more service, more total sales and more PROFITS! Move forward with these ROHN items!



## ROHN TV TOWERS

**ROHN makes the finest towers available for television reception! Illustrated is the No. 25 with amazing "zig-zag" cross bracing design. The entire tower is rated 33⅓% stronger than other similar sized towers. Yes, sell and install the No. 25 up to 50 feet self-supporting or, properly guyed, up to 360 feet!**

**Or if you prefer, sell the popular ROHN No. 6 tower with the famous "Magic Triangle" cross-bracing. Both are fully HOT DIPPED GALVANIZED AFTER FABRICATION! Sections in easy-to-handle 10 ft. lengths.**

## ROHN COMMUNICATION TOWERS

**Here you have FIVE complete lines of heavy-duty, FULLY ENGINEERED communication towers to fulfill any communications requirement. Shown is the ROHN "SS" tower which is self-supporting up to 130 feet. Other models — (30-40-50-60) are available in heights up to 630 feet when guyed! Handle these towers for the demand in your area. There's a complete NEW catalog on this line. Get a copy so you'll have it on hand.**



## AMATEUR "FOLD-OVER" TOWERS

**Specially designed "fold-over" towers are the best ever designed for amateur radio and experimentation. They are the most desired because they "fold-over" completely so you work on the ground for ease and safety. Three sizes, including heavy-duty type to handle any needs. All hot dipped galvanized.**





## TELESCOPING MASTS

**Unexcelled in design, structural strength, and sales appeal. All popular sizes, heights, and weights available. Also, mast tubing in exact specifications that's demanded today.**



## ROOF TOWERS . . .

10, 5, 3, and 1½ fo[ot] heights — very popular[ly] ready shipped — ideal [for] [use] — the best ever [de]signed — in hot dipped galvanized finish . . . truly a big profit item for you!



## BASES AND MOUNTS

**Wide variety of bases and mounts. Special features include "locking" device— also cast aluminum roof mounts—and a host of other installation items . . . get full details.**

## TV SERVICE TABLE

For holding TV sets while servicing, or storing, or for mobile use of set in such places as motels, hospitals, etc. Ideal for dozens of uses —thousands sold. Large casters—a real work-saver.

# ROHN

*Manufacturing Company*

**116 Limestone, Bellevue**
**Peoria, Illinois**

Get complete catalog from your ROHN representative or jobber or MAIL THIS COUPON!

**Gentlemen: Please send me literature on ROHN Towers and Accessories.**

**Firm** _____

**Name** _____ **Title** _____

**Address** _____

**City** _____ **State** _____

**ELECTRONICS WORLD** is published monthly by Ziff-Davis Publishing Company, William B. Ziff, Chairman of the Board (1946-1953), at 434 S. Wabash Ave., Chicago 5, Ill. Second class postage at Chicago, Illinois. Authorized by Post Office Department, Ottawa, Canada, as second-class matter. **SUBSCRIPTION RATES:** one year U. S. and possessions, and Canada $5.00; Pan American Union Countries $5.50; all other foreign countries $6.00.

# ELECTRONICS WORLD

FEBRUARY, 1960

VOL. 63 ■ NO. 2



*Publisher*
**OLIVER READ,** D. Sc., W1ETI

*Editor*
**WM. A. STOCKLIN,** B. S.

*Technical Editor*
**MILTON S. SNITZER,** W2QYI

*Service Editor*
**SIDNEY C. SILVER**

*Associate Editor*
**P. B. HOEFER**

*Assistant Editor*
**J. JUSTER**

*Industrial Consultant*
**WALTER H. BUCHSBAUM**

*Art Editor*
**MILTON BERWIN**

*Art and Drafting Dept.*
**J. A. GOLANEK**
**A. J. LICHOTA, JR.**
**K. W. PAUL, JR.**

*Advertising Director*
**JOHN A. RONAN, JR.**

*Advertising Manager*
**GEORGE E. MORRISSEY**

*Midwest Adv. Manager*
**W. ROBERT WOLFE**

*Western Adv. Manager*
**DON CENA**

ZIFF-DAVIS PUBLISHING COMPANY
William Ziff, President; W. Bradford Briggs, Executive Vice-President; Michael Michaelson, Vice-President and Circulation Director; Hershel B. Sarbin, Vice-President; J. L. O'Donnell, Treasurer.

Editorial and Executive Offices
One Park Avenue
New York 16, N. Y. OR. 9-7200

Member
Audit Bureau of Circulations

MEMBER INSTITUTE OF HIGH FIDELITY MANUFACTURERS, INC.

BRANCH OFFICES: Midwestern Office, 434 S. Wabash Ave., Chicago 5, Ill.; Western Office, 9025 Wilshire Blvd., Beverly Hills, Calif., James R. Pierce, manager.

FOREIGN ADVERTISING REPRESENTATIVES: D. A. Goodall Ltd., London; Albert Milhado & Co., Antwerp and Dusseldorf.


*First in radio-television-audio-electronics*

# CONTENTS


## ELECTRONICS—GENERAL

Spot News ..... *Washington Correspondent* 22
Recent Developments in Electronics ..... 42
Tape Recorder Survives Missile Tests ..... 100
Calendar of Events ..... 141

## HIGH FIDELITY AND AUDIO

Room Acoustics for Stereo—Reverberation & Room Treatment (Part 2) ..... *Abraham B. Cohen* 44
The "Pyramid" Stylus ..... *C. D. O'Neal* 48
Low-Noise Transistor Preamp ..... *David R. Steele* 57
Intermodulation Distortion—What it is and how it's measured ..... *Milton S. Snitzer* 66
Hi-Fi—Audio Product Review ..... 88
How To Make Better Tape Recordings ..... 110
New Audio Test Report (ELECTRONICS WORLD Lab Tested) ..... 122
Certified Record Revue ..... *Bert Whyte* 134
Sound on Tape ..... *Bert Whyte* 138

## TELEVISION-RADIO

Service Notes ..... 32
Radio Service for TV Technicians ..... *Kenneth Bramham* 41
Know Your Electronic Chemicals (Part 1) ..... *Walter H. Buchsbaum* 50
Mac's Service Shop ..... *John T. Frye* 56
De-Bugging the Horizontal Oscillator ..... *Warren J. Smith* 60
Estimating Your Business Potential ..... *Ernest W. Fair* 65
Transistor Radio Circuits (Part 4) ..... 102
Service Industry News ..... 128

## TEST EQUIPMENT

The Scope as a Resonance and LC Tester ..... *A. A. Mangieri* 54
Home-Built Power-Line Regulator ..... *A. V. J. Martin* 94
Troubleshoot Your Own V.T.V.M. ..... *David R. Anderson* 116
New Tube Tester Data ..... 118

## COMMUNICATIONS AND AMATEUR

Citizens Band Calling Frequency (Editorial) ..... *W. A. Stocklin* 8
Citizens Radio Directory ..... 37
Simple Improvements for Short-Wave Receivers ..... *John A. Kirk, W3CRB* 53
Type N Carrier Telephone System ..... *Ronald B. Tipton* 62
Two-Meter Transistor Transmitter ..... *Donald L. Stoner, W6TNS* 68

## ELECTRONIC CONSTRUCTION

The Capacitance Relay ..... *John Potter Shields* 70
A Baby's "Diaper Alarm" ..... *C. M. Sweet, VU2CT* 93

## DEPARTMENTS

Letters from Our Readers ..... 12
Within the Industry ..... 24
Technical Books ..... 126
Manufacturers' Literature ..... 130
What's New in Radio ..... 148



**Net Paid Circulation 242,396**



Radio & TV News ● Radio News ● Television News Trademarks Reg. U. S. Pat. Off.
Copyright © 1960 by Ziff-Davis Publishing Company. All rights reserved.



**SUBSCRIPTION SERVICE:** Forms 3579 and all subscription correspondence should be addressed to Circulation Department, 434 South Wabash Avenue, Chicago 5, Illinois. Please allow at least four weeks for change of address. Include your old address as well as new—enclosing if possible an address label from a recent issue.


**CONTRIBUTIONS:** Contributors are advised to retain a copy of their manuscripts and illustrations. Contributions should be mailed to the New York Editorial Office and must be accompanied by return postage. Contributions will be handled with reasonable care, but this magazine assumes no responsibility for their safety. Any copy accepted is subject to whatever adaptations and revisions are necessary to meet the requirements of this publication. Payment covers all author's, contributor's, and contestant's rights, title, and interest in and to the material accepted and will be made at our current rates upon acceptance. All photos and drawings will be considered as part of the material purchased.

NOW...GET EVERYTHING YOU NEED TO PREPARE TO EARN REAL MONEY IN

# ELECTRONICS

From RADIO • TELEVISION • RADAR
To GUIDED MISSILE CONTROL, etc.

## One of Today's BRIGHTEST Opportunity Fields!

Today's great Electronics field offers you a chance of a lifetime to prepare for highly interesting work and a wonderfully promising future! With so many new developments coming up in Electronics, opportunities for trained men were never brighter. Send coupon for details.

Right in your own home you may now get one of today's most interesting . . . PRACTICAL WAYS to prepare for a good job or your own business in Electronics. No previous technical experience or advanced education are needed! DeVry Tech brings you a unique 3-WAY COMBINATION of texts, home movies and real equipment—the same type of basic equipment as found in our well-equipped Chicago and Toronto Laboratories.

### EMPLOYMENT SERVICE

. . . helps you get started toward a good job, or toward advancement in the company you now work for. FREE to all graduates.

### EARN WHILE YOU LEARN

DeVry Tech's practical program helps you to earn EXTRA MONEY in your spare time, servicing Radio and TV sets.

### 300 EXPERIMENTS

Build over 300 practical projects from many shipments of Radio-Electronic parts. You build and operate TV-Radio circuits . . . wireless microphone . . . and many other major projects—all designed to provide outstanding practical experience at home.

### HOME MOVIES

Thanks to this exclusive home training aid, many important fundamentals quickly become "movie clear." Now you can actually see electrons on the march and other "hidden actions"—a wonderful advantage that is almost like having a teacher at your side.

### BUILD YOUR OWN TEST EQUIPMENT

As part of your home laboratory projects, you BUILD and KEEP a fine quality 5-inch COLOR OSCILLOSCOPE and a Jewel Bearing VACUUM TUBE VOLTMETER. You will find this equipment ideal for helping you earn in your spare time while a student—and later when working full time in the field.

### BUILD AND KEEP A BIG 21-INCH TV SET

For added practical experience, you can also build and keep this quality 21-inch TV SET that provides TV reception at its finest (DeVry Tech also offers another home training without the TV set).

## Your Guide to PROFITABLE JOB OPPORTUNITIES

*See how YOU may get ready for Jobs as:*

TV-Radio Broadcast Technician
Color Television Specialist
Radar Operator • Laboratory Technician
Airline Radio Man • Computer Specialist
Quality Control Manager
Your Own Sales & Service Shop...PLUS MANY OTHERS

## SEND FOR FREE BOOKLET!

*"One of North America's Foremost Electronics Training Centers"*

Accredited Member of National Home Study Council

## DeVRY TECHNICAL INSTITUTE

CHICAGO 41, ILLINOIS

## MAIL COUPON TODAY!

**DeVRY TECHNICAL INSTITUTE**
**4141 Belmont Avenue, Chicago 41, Ill., Dept. EW-2-Q**

Please give me your FREE booklet, "Electronics in Space Travel," and tell me how I may prepare to enter one or more branches of Electronics.

Name _____ Age _____
PLEASE PRINT

Street _____ Apt. _____

City _____ Zone _____ State _____

2046

Canadian residents address DeVry Tech of Canada, Ltd.
626 Rosslawn Ave., Toronto 12, Ont.

*GET THAT SYLVANIA SIGN UP TODAY!*

# ARTHUR GODFREY IS SELLING YOU!

Now sponsored by Sylvania Silver Screen 85 picture tubes, Arthur Godfrey is telling America about you, selling America on you — the independent TV service dealer!

He's spreading the word to millions — on the CBS Radio network — 196 stations coast-to-coast — that you are the man to see for the finest TV service. Millions more are reading about you in the pages of *The Saturday Evening Post*. When Arthur Godfrey tells his audience to look for the "... Sylvania decal in the window of your local independent TV service dealer's shop," are you with it?

See your Sylvania distributor for Sylvania Silver Screen 85 picture tubes and Sylvania quality receiving tubes. Get your display kit of colorful window streamers and posters. Get that Sylvania sign up today!

*Electronic Tubes Division, 1740 Broadway, New York 19, N. Y.*

***See your local paper for time and station***

*"IT'S ARTHUR GODFREY TIME"... brought to you by*

SYLVANIA

*Subsidiary of* **GENERAL TELEPHONE & ELECTRONICS**

**SYLVANIA SILVER SCREEN 85**

**4 WAYS BETTER**

**Sharper focus*
**Clearer picture*
**Greater contrast*
**More light output*

RELIABLE REPLACEMENT

TWIST-PRONG ELECTROLYTICS

A satisfactory repair job means a satisfied customer. To keep your customer happy and to prevent costly call-backs you must depend on a reliable replacement. Aerovox AFH Twist-Prong Electrolytics can always be depended on to give long-life and excellent service because they're made better . . . high-purity aluminum foil construction throughout, 85°C operation, improved hermetic sealing and rugged prongs and mounting terminals.

Available in the widest selection of exact-duplicate replacements including printed-wiring and selenium rectifier types. Your local Aerovox Distributor stocks the replacement you need when you need it. Call on him today for all your capacitor requirements.

BUY THEM BY THE KIT . . .

Your Aerovox Distributor offers you special "Stack-A-Lytic" kits (AK-400 and AK-401) with a selection of 8 or 15 popular TV replacements with a FREE handy metal storage rack with stacking features.

AEROVOX CORPORATION
DISTRIBUTOR DIVISION
NEW BEDFORD, MASS.

# ...for the Record

By W. A. STOCKLIN
Editor

## CITIZENS BAND CALLING FREQUENCY

WE KNOW that it is not quite proper to talk about one's successes or achievements, but we would like to take this opportunity to do just that. Every one of our readers should know that this publication has really "scooped" the entire field on the subject of the Citizens Band. Prior to September, 1958, the FCC had such stringent requirements on equipment and since operation was restricted to the not-very-useful 460-mc. band only a handful were actually sold and used. With the September FCC announcement many of the restrictions and limitations were removed and the 27-mc. band was assigned for Class D Citizens Radio service. In our March, 1959 issue we published an article with the new rules and regulations, along with a complete circuit diagram and construction details on a simple Class D Citizens Band transceiver. Its success and interest to everyone in the field is indicated by the number of companies that produced, virtually overnight, assembled versions and kits following the ideas presented in our article. In a little over one year approximately 70,000 licenses were granted and the FCC is continuing to process some 8000 more each month.

This is a fantastic story but we feel that more can be done to increase the usefulness of this band to all concerned. One of the major applications of this type of equipment is in the marine field. This does not mean that Citizens Radio equipment will take the place of the higher power, regular marine radiotelephone equipment. However, the lower cost of CB equipment will make it attractive to owners of small boats or even larger craft to augment the regular radiotelephone equipment. Unfortunately, and as a result of its tremendous growth, there has been no assignment of certain channels for calling and working as has been done on the other bands. For example, 2182 kc. has been designated as the calling (and distress) channel in the 2-3 mc. maritime radiotelephone band. As soon as contact is established, the operating frequency is shifted to 2638 or 2738 kc. These or other pre-arranged frequencies are then used to work the required traffic.

This has worked extremely well and obviously should set a pattern for Class D Citizens Band operators. Basically, we should have one channel for calling and another for handling communications. As a result of discussions with several manufacturers it seems that Channels 13 (27.115 mc.) and 15 (27.135 mc.) would be good choices to reserve for marine applications—13 being the calling frequency and 15 for continued communications. Since the industrial, scientific, and medical frequency is 27.12 mc., we thought it would be a good idea to select channels near this frequency (skipping one channel to allow for broad selectivity of some of the receivers used). Since the ISM frequency is normally cluttered with all types of interference it doesn't serve much purpose for land-operated equipment, particularly in metropolitan areas. As this type of interference is less troublesome in marine areas and is negligible on weekends, it would seem advisable to choose channels near this frequency.

One problem is that there are many single-channel units on the market today and they obviously cannot be used for two-channel operation as previously suggested. This is rather unfortunate but probably some lenience can be shown in permitting communications to be carried on Channel 13. This may work out for the time being when traffic is still light but we feel that in the not-too-distant future there will be such wide use made of these channels that there will be need for two-channel operation.

We understand that various manufacturers of Citizens Band equipment may get together shortly to discuss this very problem and should their conclusions differ from those suggested here we will report on it in next month's "For The Record." Should the industry fail to get together, it is our hope that all marine users of Class D Citizens Band equipment will work together to promote the use of Channels 13 and 15 as outlined herein.

Our appreciation to F. A. Genochio, *Karr Engineering Corp.;* Ed Manville, *Vocaline Co. of America, Inc.;* G. T. Wilde, *Multi-Products Co.;* and B. H. Ballard, Jr., *Apelco Sales Corp.,* for their thoughts on proper channel selection.

—30—

FREE

# ALLIED'S 1960

## ELECTRONIC SUPPLY CATALOG

*value-packed...send for it!*




**your complete money-saving guide to EVERYTHING IN ELECTRONICS**



- Latest Stereo Hi-Fi Systems—Everything in Hi-Fi Components
- Money-Saving, Build-Your-Own KNIGHT-KITS® for Every Need
- Values in Recorders and Supplies
- Latest Public Address Systems, Paging and Intercom Equipment
- Amateur Receivers, Transmitters and Station Gear
- Test and Laboratory Instruments
- TV Tubes, Antennas, Accessories
- Huge Listings of Parts, Tubes, Transistors, Tools, Books

**ONLY $2 DOWN**

on orders up to $50; only $5 down on orders up to $200; only $10 down over $200. Up to 24 months to pay.

**ALLIED exclusives:**

**MONEY-SAVING KNIGHT-KITS®**—the very best in build-your-own electronic equipment—designed to save you up to 50%. "Convenience Engineered" for easiest assembly; the only kits covered by Money-Back Guarantee. Complete selection of Stereo hi-fi kits, Hobbyist kits, Test Instrument and Amateur kits. KNIGHT-KITS are an exclusive ALLIED product.

**KNIGHT® STEREO HI-FI**—truly the best for less—the finest you can buy, yet far lower in cost. Select super-value KNIGHT components or complete systems and save most. Also see the world's largest selection of famous-name hi-fi components and money-saving ALLIED-recommended complete hi-fi systems.

Get every buying advantage at ALLIED: lowest money-saving prices, fastest shipment, expert personal help, guaranteed satisfaction.

***send for the leading electronic supply guide***

FREE

**ALLIED RADIO**



*our 39th year*

***World's Largest Electronic Supply House***

**ALLIED RADIO CORP., Dept. 1-B**
**100 N. Western Ave., Chicago 80, Ill.**

☐ Send FREE 1960 ALLIED Catalog.

*Name*_____

*Address*_____

*City*_____ *Zone*____ *State*_____

**Hits TV stations right on the nose!** The Channel Master Automatic Tenn-A-Liner is the only rotator that aims the antenna within **one degree** of the precise transmitter location.

Superior parallel circuit delivers a full 29 volts to the rotator, producing higher torque that easily turns even the heaviest antennas. Fewer moving parts—all fully protected from weather extremes — contribute to long, trouble-free service.

For these and other reasons, you can recommend and install the Automatic Tenn-A-Liner with full confidence of customer satisfaction.

from the top of the roof...to the back of the set...

# CHANNEL MASTER

works wonders in sight and sound




**Premium tube features at no extra cost.** Channel Master Electron Tubes are designed for use in television, AM/FM radio, and high fidelity systems. They offer the same outstanding performance, quality, and value you've come to expect from all products bearing the Channel Master name.

Rigid manufacturing controls assure consistent performance characteristics, exact tolerances, long life, low noise, and maximum gain. Channel Master Electron Tubes are engineered to provide the best possible results.

For happier customers, fewer callbacks, higher profits ... put Channel Master tubes in the sets you service.

Copyright 1959 Channel Master Corp.

**CHANNEL MASTER CORP.** ELLENVILLE, N. Y.

TV ANTENNAS • ACCESSORIES • TRANSISTOR RADIOS
STEREOPHONIC HIGH FIDELITY COMPONENTS

# Learn Electronics

## PREPARE FOR YOUR F. C. C. LICENSE—YOUR TICKET TO A BETTER JOB AND HIGHER PAY!

*This booklet* **FREE!**

This free booklet gives details of our training and explains what an F.C.C. license can do for your future.

### F.C.C. LICENSE—THE KEY TO BETTER JOBS

An F.C.C. *commercial* (not amateur) license is your ticket to higher pay and more interesting employment. This license is Federal Government evidence of your qualifications in electronics. Employers are eager to hire *licensed* technicians.

### WHICH LICENSE FOR WHICH JOB?

The THIRD CLASS radiotelephone license is of value primarily in that it qualifies you to take the second class examination. The scope of authority covered by a third class license is extremely limited.

The SECOND CLASS radiotelephone license qualifies you to install, maintain and operate most all radiotelephone equipment except commercial broadcast station equipment.

The FIRST CLASS radiotelephone license qualifies you to install, maintain and operate every type of radiotelephone equipment (except amateur) including all radio and television stations in the United States, its territories and possessions. This is the highest class of radiotelephone license available.

### GRANTHAM TRAINING PREPARES YOU

The Grantham Communications Electronics Course prepares you for a *FIRST CLASS* F.C.C. license, and it does this by TEACHING you electronics. Each point is covered simply and in detail, with emphasis on making the subject easy to understand. The organization of the subject matter is such that you progress, step-by-step, to your specific objective—a first class F.C.C. license.

### CORRESPONDENCE OR RESIDENCE CLASSES

Grantham training is available by correspondence or in resident classes. Either way (residence or correspondence), we train you quickly and well—no previous training required. Even a beginner may qualify for his first class license in a relatively short time.

**FOUR COMPLETE SCHOOLS:** *To better serve our many students throughout the entire country, Grantham School of Electronics maintains four complete Divisions—located in Hollywood, Calif., Seattle, Wash., Kansas City, Mo., and Washington, D.C. All Divisions of Grantham School of Electronics offer the same rapid courses in F.C.C. license preparation, either by home study or in resident classes.*

### Upgrade Your Income with a First Class

# F. C. C. LICENSE

### HERE'S PROOF...

that Grantham students prepare for F.C.C. examinations in a minimum of time. Here is a list of a few of our recent graduates, the class of license they got, and how long it took them:

| | License | Weeks |
|---|---|---|
| Donald E. Mason, 2659 Centinella, Santa Monica, Calif. | 1st | 12 |
| Everett T. Bozard, 411 N. Wash. St., Alexandria, Va. | 1st | 12 |
| Henry M. Best, 1003 Vermont St., Fremont, N. C. | 1st | 11 |
| Harold V. Jones, P. O. Box 705, Alamogordo, N. M. | 1st | 13 |
| Michael F. Aperio, 916 Townsend St., Chester, Pa. | 1st | 12 |
| Earl A. Stewart, 3918 Modesto Dr., San Bernardino, Calif. | 1st | 14 |
| Donald L. Loeburg, Box 1075, Anchorage, Alaska | 1st | 12 |
| J. Milton Condit, 1312 N. 78th Street, Seattle, Wash. | 1st | 8 |
| John R. Bahrs, 72 Hazelton St., Ridgefield Park, N. J. | 1st | 12 |
| Richard Baden, 4226 - 37th St., N.W., Washington, D. C. | 1st | 12 |
| James F. Stewart, 2618½ Prospect Ave., La Crescenta, Calif. | 1st | 12 |
| Norman R. Cook, 130 Olive Street, Neodesha, Kans. | 1st | 12 |

## GRANTHAM SCHOOL OF ELECTRONICS

| | | |
|---|---|---|
| HOLLYWOOD CALIF. | 1505 N. Western Ave. Hollywood, Calif. | (HO 7-7727) |
| SEATTLE WASH. | 408 Marion Street Seattle, Wash. | (MA 2-7227) |
| KANSAS CITY MO. | 3123 Gillham Road Kansas City, Mo. | (JE 1-6320) |
| WASHINGTON D. C. | 821 - 19th Street, N. W. Washington, D. C. | (ST 3-3614) |

## MAIL COUPON TO SCHOOL NEAREST YOU

(Mail in envelope or paste on postal card)

To: GRANTHAM SCHOOL OF ELECTRONICS

1505 N. Western Hollywood • 408 Marion Seattle • 3123 Gillham Rd. Kansas City • 821-19th, NW Washington

Gentlemen:

Please send me your free booklet telling how I can get my commercial F.C.C. license quickly. I understand there is no obligation and no salesman will call.

Name_____ Age_____

Address_____

City_____ State_____

I am interested in: ☐ Home Study, ☐ Resident Classes 06-B

CHANNEL MASTER CORP. ELLENVILLE, N. Y.
STEREOPHONIC HIGH FIDELITY COMPONENTS

*ONLY the ACRO Stereo pre-amplifier gives you these years ahead design features!*

**CHECK THESE EXTRAS that no other kit gives:**

1. Selective Rumble & Scratch Filters
2. 3rd Channel Output
3. Exclusive Mike Dub Switch
4. Phasing Switch
5. Input Level Controls
6. Exclusive Panel Light Matrix
7. Lowest Hum with D.C. Filament Supply

Plus many other features



# ACRO'S STEREO PRE-AMPLIFIER

**EASY TO ASSEMBLE KIT**

Unequaled Versatility; Logical planning; Pre-assembled, tested, printed circuit board makes construction simple. A PERFECT MATE FOR ACRO'S STEREO 20 AND ULTRA LINEAR II AMPLIFIERS.

**SPECIFICATIONS**

**INPUTS** each channel
- Magnetic (Turntable & Changer) Equalized 78, LP, RIAA
- Crystal/ceramic (switched in mag. input) Sensitivity for 1.5V out Low Level 5 MV. High Level 30 MV.
- Tape Head Equalized NARTB Sensitivity 2 MV
- FM • AM • FM Multiplex • Tape Head
- Microphone (switched into one channel for announcing, faded in or out with balance control)

**OUTPUTS** 2 Ampl., 2 Tape, 3rd Channel

**INPUT SELECTOR** (8 position) 78, LP, RIAA1, RIAA2, Tape Head, FM-AM, FM Multiplex & Aux.

**OUTPUT SELECTOR** 7 MODES (Check-A, Check-B, Stereo, Stereo Reverse, Monaural A-B, Monaural A, Monaural B.) 6 panel light Matrix provides selection Mode at a glance.

**CONTROLS** Ganged Volume / Loudness, Balance, Individual Bass & Treble for each channel

**SWITCHED EXTRAS** effective each channel. Filters, scratch and rumble • loudness • phasing • tape input/monitor • mike dub

**AC OUTLETS** 2 switched 2 direct

**TUBES** (4) Type 7199 low noise pentode/triode

**DIMENSIONS** 4-1/2H x 13-3/4L x 6-3/8D

**PRICE:** Kit $69.50 Self powered kit $79.50

*Write today for free folder*

**ACRO PRODUCTS COMPANY KIT DIV.**

410 SHURS LANE, Dept. EW 2
Philadelphia 28, Pa.

**ACRO, THE FIRST NAME IN AUDIO!**

**OUR OCTOBER ISSUE**

To the Editors:

Just a line to compliment you on the publishing of "The Stereo Illusion" and placing it first in your October issue. The article was very enlightening and authentic. Dr. Harris knows how to write, and I certainly hope you will have more of his material in future issues.

BARNEY ASHTEN, VE7BK
Ganges, B. C., Canada

To the Editors:

I must compliment the editors of ELECTRONICS WORLD for putting out such a wonderful issue.

I would like to stress one point very strongly. In many of the articles it seems as though the authors have gotten too involved in the hi-fi field, and have forgotten what it is supposed to be. Just to remind some of you, the approximate definition of the term hi-fi is "faithful reproduction of live sound."

I have been involved in the hi-fi field for about three years, have listened to topnotch equipment only, and unfortunately, have forgotten how live sound really sounds. This summer I attended a live concert and was appalled to realize how much I had missed. Being used to listening to restricted response—even from the best components—I noticed how much my taste had changed, how my ears compromised to sounds not below 30 cps, not higher than 18,000 cps, and to the realization that the speaker was always there!

In my opinion, a compulsory prerequisite for any good hi-fi technician is to attend at least two good concerts a year in order to remember what high fidelity is trying to accomplish.

JEHUDA FRYDMAN
Sound Scription Service, Inc.
Montreal, Quebec, Canada

*We concur with Reader Frydman's views that people in the hi-fi field should certainly know what live music sounds like.—Editors.*

* * *

**REBUILT PICTURE TUBES**

To the Editors:

Your September issue contained an article on rebuilt picture tubes which, on the whole, is the best article on the subject I have seen. However, near the bottom of the first column on page 65, there appears a statement that corded ware (glass shells with surface ripples or irregularities on the face plate) is not ordinarily used in making new tubes. The natural question then is where did the rebuilder obtain the dud with a corded mark on the face plate if it was not used by the so-called tube manufacturer in the first place? The statement is, of course, incorrect as certain of the glass companies' molds developed this trouble when making certain types of bulbs long ago. Therefore, the original new tube manufacturer received the glass with cord marks and the original equipment was built with those tubes. I believe, though, that sometimes cord marks are accentuated by the cleaning process when the dud is being cleaned by a rebuilder before re-use.

MORRIS F. TAYLOR
Morris F. Taylor Co.
Manufacturers' Representative
Silver Spring, Maryland

*Reader Taylor is to be congratulated on his alertness in noting what appears to be a contradiction in the article. His own conjectures as to how corded ware may become available to rebuilders is probaby correct. Some rebuilders also hint that corded glass shells are acquired in ways other than the salvaging of duds, but they are reluctant to divulge details.—Editors.*

* * *

**SERVICING COMMERCIAL EQUIPMENT**

To the Editors:

Many of your magazine articles have been encouraging service men to take on more commercial equipment jobs.

I started servicing radios back in 1925 and am still in the business of servicing radios, TV sets, phonographs, and car radios. Many times customers ask me to service other equipment used by the medical profession and factories. Almost without exception I have had nothing but opposition. When I try to get parts or service information, I am treated very rudely by the factories and supply houses. I am treated much worse than I have ever treated a customer when he brings me a TV set to service with the parts in a sack.

As an example, I have a customer who brought me a sound and motion picture projector. I have attempted getting parts and service instructions for this machine for five months and have been blocked at every turn. I have written several companies and called some trying to get the information, but have been unable to get anything. What would you suggest in a case of this sort? After every such ordeal, I swear I will never accept any service job other than radio, TV, or phonograph.

LESTER BERRY
Berry's Radio & Television Service
Fairborn, Ohio

*There is a great deal of validity in what you have to say about the difficulties in servicing commercial equip-*

# INTERNATIONAL'S

## NEW Executive Citizens Band TRANSCEIVER

**A complete two-way radio station providing dependable communication at the flip of a switch.**

The new smartly-styled, sturdily built Executive Transceiver is the answer for today's Citizens Radio Service. Used in matched pairs, the International Executives are effective between fixed or mobile points.

**The ideal two-way radio for business • farming • ranching • construction • boats • fishing • hunting • warehouses • storage yards • factories.**

Business



Home



Sports



Farm



### FEATURES

Push-to-talk operation, 3 crystal controlled transmit positions, two crystal controlled receive positions, dual conversion superheterodyne receiver tuning all 23 channels.

Five watts plate input. Crisp and clear full modulation. Series Gated automatic noise limiter. 2.5 audio output. Fifteen tube performance. The Executive has 10 tubes and 1 diode. Four tubes are multi-purpose.

Universal power supply, 6 VDC, 12 VDC, 115 VAC is built-in. Certified tolerance .005%. Size 5½" x 8½" x 9". Weighs only 12 pounds.

**WRITE FOR INTERNATIONAL'S 1960 COMPLETE CATALOG**

Executive Citizens Band Transceiver complete with one Channel 9 transmit crystal, AC power cord and operating instructions..... **$169.95**

**(See your local dealer.)**

**INTERNATIONAL**

**CRYSTAL MANUFACTURING COMPANY, INC.**

18 NORTH LEE — OKLAHOMA CITY, OKLAHOMA

*Now... from Sonotone—*

# 4 Big Improvements

*in the quality stereo cartridge*



**Sonotone 8TA cartridge replaces 8T as industry standard**

The new Sonotone 8TA cartridge gives greater than ever stereo performance... has 4 big extras:

- fuller, smoother frequency response
- higher compliance than ever before
- lighter tracking pressure
- practically eliminates dust pile-up

**ONLY $14.50***

**Sonotone 10T unitized stereo at lowest price ever**

New 10T cartridge sells at record low price of $6.45.* And it covers the complete high fidelity range. 10T's unitized construction makes it easiest to install, easiest to replace. Low price means more sales—more profits.



**SPECIFICATIONS**

| | 8TA | 10T |
|---|---|---|
| Frequency Response | Smooth 20 to 20,000 cycles. Flat to 15,000 with gradual rolloff beyond. | Flat from 20 to 15,000 cycles ± 2.5 db. |
| Channel Isolation | 25 decibels | 18 decibels |
| Compliance | 3.0 x $10^{-6}$ cm/dyne | 1.5 x $10^{-6}$ cm/dyne |
| Tracking Pressure | 3-5 grams in professional arms<br>4-6 grams in changers | 5-7 grams |
| Output Voltage | 0.3 volt | 0.5 volt |
| Cartridge Weight | 7.5 grams | 2.8 grams |
| Recommended Load | 1-5 megohms | 1-5 megohms |
| Stylus | Dual jewel tips, sapphire or diamond. | Dual jewel tips, sapphire or diamond. |

*including mounting brackets

Sonotone makes only 6 basic ceramic cartridge models... yet has sold over 9 million units... used in over 662 different phonograph models. For finest performance, replace worn needles with genuine Sonotone needles.

**Sonotone®** CORP. Electronic Applications Division, Dept. C1-20 **ELMSFORD, NEW YORK**

Leading makers of fine ceramic cartridges, speakers, tape heads, microphones, electronic tubes. In Canada, contact Atlas Radio Corp., Ltd., Toronto

*ment with respect to obtaining the cooperation of manufacturers. We are aware of this situation, but also believe that it is changing.*

*The manufacturers involved are reluctant, on the one hand, to entrust work on their equipment to outside technicians who are unknown quantities to them. On the other hand, they insist that such service is burdensome to them, and they would like to see it taken off their hands.—Editors.*

* * *

**SUBDIVIDED SPEAKER ENCLOSURE**

To the Editors:

As a practicing chemist, I would like to call your attention to some inaccuracies that appeared in the article "Subdivided Hi-Fi Speaker Enclosure" in your November, 1959 issue.

Calcium chloride is referred to as "silica gel." Calcium chloride is water soluble while silica gel, chemically similar to sand, is not. Both are good desiccants, but there the similarity ends.

One other thing bothers me a little about your suggestion to increase the compliance of a cone by treating the edge with calcium chloride. Calcium chloride is mildly acidic by nature, and cellulosic materials (such as speaker cones) are degraded by acids. I believe this would shorten the life of a speaker, but only an experiment could determine how much. An organic desiccant such as glycerine or diethylene glycol might be better.

You have an excellent publication. I have subscribed for nearly 15 years, starting with RADIO NEWS, then RADIO & TV NEWS, and now ELECTRONICS WORLD. Your publication gives me just what I want, and the approach combines both the practical and the moderately technical.

ROBERT J. ATHEY
Wilmington, Delaware

*Thanks to Reader Athey for setting us straight on our chemistry.— Editors.*

* * *

**OLD-TIME WIRELESS GEAR**

To the Editors:

I was very interested in your article "Restoration of Old-Time Wireless Gear" in the November issue, chiefly because I once made a living operating some of the old-time receivers you mention. For example, the *Canadian Marconi* receiver shown on the upper right of page 63 was still going strong when I began operating in 1920 and (with the addition of a triode) continued for some years after I moved to the engineering department of *Canadian Marconi* in Montreal in 1923.

I remember one particular unit. I have forgotten the model but not the serial number—13! Six times this was sent back from a Canadian ship as dead. Five times it was thoroughly tested and found perfect. The sixth time, it came back on a Monday when the temperature was 15 below and the furnace at the old plant on William Street was slow to start. That square coilformer that drops over the variometer was the antenna coupler (later used as a tickler coil in a regenerative

WE'RE MAKING IT EASIER THAN EVER TO BECOME A WELL PAID
RADIO-TELEVISION SERVICE TECHNICIAN

NOW — Just $6 Starts You Training in

# RADIO-TELEVISION

the SPRAYBERRY "Learn-by-Doing" Way . . .

**25 BIG, COMPLETE KITS of PARTS & EQUIPMENT**

To help you learn *fast* the practical side of Radio-Television, we send you expertly engineered training kits to test and assemble for interesting, valuable shop-bench practice!

- The new Sprayberry Training Television Receiver, built and tested in 5 sections.
- Now offered . . . this fine modern oscilloscope.
- You build this powerful two-band superheterodyne radio receiver.

BIG New CATALOG and Sample Lesson FREE!



You build the new Sprayberry tester — a complete 16-range Volt-Ohm-Milliammeter test meter.

★ ★ ★ ★ This great industry is begging for trained men . . . to step into good paying jobs or a profitable business of their own! Our new plan opens the doors of Radio-Television wide to every ambitious man who is ready to act at once!

Men by the thousands... trained Radio-Television Service Technicians...are needed at once! Perhaps you've thought about entering this interesting, top paying field, but lack of ready money held you back. Now—*just $6 enrolls you* for America's finest, most up to date home study training in Radio-Television! Unbelievable? No, the explanation is simple! We believe Radio-Television *must* have the additional men it needs as quickly as possible. We are willing to do our part by making Sprayberry Training available for less money down and on easier terms than ever before. This is your big opportunity to get the training you need...to step into a fine job or your own Radio-Television Service Business.

## Complete Facts Free—Act Now; Offer Limited

Only a limited number of students may be accepted on this liberal and unusual basis. We urge you to act at once...mail the coupon below and get complete details plus our big new catalog and an actual sample lesson—*all free.* No obligation...no salesman will bother you.

## HOME STUDY TRAINING IN SPARE TIME

Under world-famous 27-year old Sprayberry Plan, you learn entirely at home in spare time. You keep on with your present job and income. You train as fast or as slowly as you wish. You get valuable kits of parts and equipment for priceless shop-bench practice. And everything you receive, lessons and equipment alike, is all yours to keep.

## LET US PROVE HOW EASILY YOU CAN LEARN!

Radio-Television needs YOU! And Sprayberry is ready to train you on better, easier terms, that any ambitious man can afford. *Just $6 starts you!* Mail coupon today... let the facts speak for themselves. You have everything to gain. Let us prove the kind of opportunity that's in store for you!

**SPRAYBERRY Academy of Radio-Television**
1512 Jarvis Avenue, Dept. 25-G, Chicago 26, Illinois

Mail This Coupon Now—No Salesman Will Call

**Sprayberry Academy of Radio-Television**
**Dept. 25-G, 1512 W. Jarvis Ave., Chicago 26, Ill.**

Please rush all information on your ALL-NEW Radio-Television Training Plan. I understand this does not obligate me and that no salesman will call upon me. Include New Catalog and Sample Lesson FREE.

NAME..... Age.....

ADDRESS.....

CITY..... ZONE..... STATE.....

ELECTRONIC TECHNICIANS
AND INSTRUCTORS—
*You Can*
*Realize*
*Your Full*
*Professional*
*Potential*
*with*
**Burroughs**



Advance your career in the most critical field of tomorrow: integrated DATA PROCESSING for military weapons systems at BURROUGHS, Military Field Service Division. Participate in challenging work on important long range ATLAS and SAGE programs.

You can qualify as TECHNICIAN if you are a graduate of an accredited technical school and/or have military training in radar or communications equipment, plus at least 2 years' experience in electronics. You will receive 8 to 22 weeks of classroom training in Data Processing Systems at full salary. Current field assignments include far-West and Western areas after your training is completed.... You can qualify as INSTRUCTOR if you have a knowledge of electronics theory and some related teaching experience. Work involves the training of technical personnel in the installation, maintenance and repair of electronic and/or electro-mechanical equipment.

The above positions carry these exceptional benefits: 1) Advancement based on individual performance. 2) Starting salary commensurate with experience and ability. 3) Merit review program. 4) Outstanding group insurance and retirement plan. 5) Generous educational assistance program. Inquiries are invited from qualified candidates. Please write Mr. R. F. Johnson, Dept. 2400, Burroughs Corporation, Military Field Service Division, Burroughs Drive, Radnor, Pa. (a suburb of Philadelphia).

**Burroughs Corporation**
*"NEW DIMENSIONS/in computation for military systems"*



circuit). A continuity check showed open circuit—until the room warmed up. A little detective work disclosed that each time the set was returned to the vessel, it stood on a cold wharf for some time before being taken aboard. If the operator had held off his test until the set warmed up and expansion brought the broken ends of wire back together, we might never have gotten the set back a second time.

H. F. SHOEMAKER, Manager
Radio College of Canada
Toronto, Canada

* * *

**AUTOMATIC "TALK SQUELCHER"**

To the Editors:

I have had some correspondence with readers who have had some difficulty with the automatic "talk squelcher" I described in the April, 1959 issue. The problems were insufficient sensitivity and relay chattering.

1. Adjust the relay, if possible, so that the moving armature is closer to the magnet pole; that is, so that the armature will not have as far to travel when the relay is energized. Then adjust the relay contacts so that they just "break" when the relay is de-energized. This will increase the sensitivity of the relay, and it should then operate at a lower setting of the pot.

2. If it is not possible to lower the sensitivity of the relay by adjustment of armature contacts, it will be necessary to modify the talk suppressor amplifier stage ($V_1$) to obtain higher gain and hence higher audio output voltage. At the same time this is done, it will be desirable to add a small filter network which will help to eliminate un-




Fig. 1.

desirable transients, r.f., and other voltages which may otherwise be transmitted to the relay tube grid circuit.

3. If it is necessary to add the filter and to modify $V_1$, it can be accomplished as follows with reference to the schematic of the device (page 61, April, 1959 issue of ELECTRONICS WORLD) and the diagram in Fig. 1.

a. With the receiver disconnected from the a.c. line and the talk suppressor turned off, remove the plate resistor ($R_4$) from the talk suppressor amplifier ($V_1$) and replace it with a 1-watt resistor of 500,000 ohms.

b. Connect a ¼-watt or ½-watt, 50,000-ohm resistor in series with the grid of the relay tube ($V_2$) and the junction of $C_2$, $R_2$, and the diodes of $V_1$.

c. Connect a .005 μf. capacitor between the grid and cathode of $V_2$.

MARVIN L. GASKILL
Marlton, New Jersey

—30—

NOW! at a price you can afford!

# MAKE MORE MONEY in TELEVISION RADIO-ELECTRONICS

**BETTER...MORE COMPLETE...LOWER COST... WITH NATIONAL SCHOOLS SHOP-METHOD HOME TRAINING!**

**BETTER...** Training that is proved and tested in Resident School shops and laboratories, by a School that is the OLDEST and LARGEST of its kind in the world.

**MORE COMPLETE...** You learn ALL PHASES of *Television-Radio-Electronics.*

**LOWER COST...** Other schools make several courses out of the material in our ONE MASTER COURSE . . . and you pay more for less training than you get *in our course* at ONE LOW TUITION!

These two FREE books will show you how!

You get all information by mail . . . You make your own decision . . . at home! NO SALESMAN WILL CALL

## TOP PAY...UNLIMITED OPPORTUNITIES LIFETIME SECURITY CAN BE YOURS!

You are needed in the Television, Radio, and Electronics industry! Trained technicians are in growing demand at excellent pay— in ALL PHASES, including Servicing, Manufacturing, Broadcasting and Communications, Automation, Radar, Government Missile Projects.

**NATIONAL SCHOOLS SHOP-METHOD HOME TRAINING,** with newly added lessons and equipment, trains you in your spare time at home, for these unlimited opportunities, including many technical jobs leading to supervisory positions.

**YOU LEARN BY BUILDING EQUIPMENT WITH KITS AND PARTS WE SEND YOU.** Your National Schools course includes thorough *Practical* training—YOU LEARN BY DOING! We send you complete standard equipment of professional quality for building various experimental and test units. You advance step by step, perform more than 100 experiments, and you build a complete TV set from the ground up, that is yours to keep! A big, new TV picture tube is included at no extra charge.

**EARN AS YOU LEARN.** We'll show you how to earn extra money right from the start. Many of our students pay for their course—and more—while studying. So can you!

**LESSONS AND INSTRUCTION MATERIAL ARE UP-TO-DATE, PRACTICAL, INTERESTING.** Every National Schools Shop-Method lesson is made easy to understand by numerous illustrations and diagrams. All instruction material has been developed and tested in our own Resident School Shops, Laboratories and Studios.

**SEND FOR INFORMATION TODAY . . .** it can mean the difference between SUCCESS and failure for you! Send for your FREE BOOK "Your Future in Television-Radio-Electronics" and FREE Sample Lesson. Do it TODAY, while you are thinking about your future. It doesn't cost you anything to investigate!

**RESIDENT TRAINING AT LOS ANGELES**

If you wish to take your training in our Resident School at Los Angeles, the world's TV capital, start NOW in our big, modern Shops, Labs and Radio-TV Studios. Here you work with latest Electronic equipment — professionally installed — finest, most complete facilities offered by any school. Expert, friendly instructors. Personal attention. Graduate Employment Service. Help in finding home near school — and part time job while you learn. Check box in coupon for full information.

**GET THE BENEFITS OF OUR OVER 50 YEARS EXPERIENCE**

Approved for GI Training

MEMBER

**NATIONAL SCHOOLS**
Los Angeles 37, Calif.

**YOU GET...**

- 19 Big Kits—YOURS TO KEEP!
- Friendly Instruction and Guidance
- Job Placement Service
- Unlimited Consultation
- Diploma—Recognized by Industry
- EVERYTHING YOU NEED FOR SUCCESS!

**SHOP-METHOD HOME TRAINING COVERS ALL PHASES OF INDUSTRY**

1. Television, including Color TV
2. Radio AM & FM
3. Electronics for Guided Missiles
4. Sound Recording and Hi-Fidelity
5. FCC License
6. Automation and Computers
7. Radar & Micro-Waves
8. Broadcasting and Communications

NATIONAL TECHNICAL SCHOOLS
WORLD-WIDE TRAINING SINCE 1905

**MAIL NOW TO**
**NATIONAL SCHOOLS, Dept RH-20**
**4000 S. FIGUEROA ST. LOS ANGELES 37, CALIF.**

Rush free TV-Radio "Opportunity" Book and sample lesson. No salesman will call.

NAME _____ AGE _____
ADDRESS _____
CITY _____ ZONE _____ STATE _____
☐ Check if interested ONLY in Resident School training at Los Angeles.
VETERANS: Give date of Discharge _____

**coming in March ELECTRONICS WORLD:**
**an exclusive full-length report on**

# SCATTER COMMUNICATIONS!

The necessity of linking America's defenses into a cohesive unit has brought sweeping developments in the field of *Scatter Communications.* In next month's ELECTRONICS WORLD, you'll find a wealth of information on the technique of Scatter Communications: the distances covered, advantages and disadvantages, coverage, reliability, technical analysis of frequency, transmission band width, power. In addition, a map of the world pinpoints where these systems are operating right now. Don't miss this important report!

You'll also enjoy these features in March ELECTRONICS WORLD:

NEW TV DESIGNS FOR 1960: Complete analysis of the latest offerings of more than a dozen leading manufacturers—valuable for both service technician and set owner!

TRANSISTORIZED CITIZENS BAND CONVERTER: Complete plans for building a single-channel crystal-controlled converter designed for use with any broadcast-band transistor receiver.

ROOM ACOUSTICS FOR STEREO: Variable sound absorption devices and special speaker setups are featured in Part Three of this four-part series. Learn how any audiophile can adapt these techniques for better listening!

All these authoritative features are coming your way in March ELECTRONICS WORLD—typical of the varied coverage you enjoy month after month in the world's leading technical electronics magazine. That's why it's such a good idea to make sure that ELECTRONICS WORLD is delivered to your doorstep regularly. Become a subscriber today!




REGULAR SUBSCRIPTION RATES

**one year, $5  two years, $9  three years, $12**

**ELECTRONICS WORLD**

434 South Wabash Avenue  Chicago 5, Illinois

# Learn TELEVISION-RADIO

## *Servicing or Communications*

## by Practicing at Home in Spare Time



NRI gives you kits to build these and other equipment

## Electronic Technicians Have High Pay, Prestige Jobs

People look up to and depend on the Technician, more than ever before. His opportunities are great, and are increasing. Become a Radio-Television-Electronic Technician. At home, and in your spare time, you can learn to do this interesting, satisfying work—qualify for important pay. A stream of new Electronics products is increasing the job and promotion opportunities for Television-Radio-Electronic Technicians. Right now, a solid, proven field of opportunity for good pay is servicing the millions of Television and Radio sets now in use. The hundreds of Television and Radio stations on the air offer interesting jobs for Operators and Technicians. The military services reward qualified Technicians with higher rank and pay. Police, Aviation, Mobile Two-Way Radio are expanding. To ambitious men everywhere: here is rich promise of fascinating jobs, satisfaction and prestige, increasing personal prosperity.

## Make Extra Money Soon, $10 to $15 a Week in Your Spare Time

NRI students find it practical and profitable to start fixing sets for friends and neighbors a few months after enrolling. Picking up $10, $15 and more a week gives substantial extra spending money. Use the Tester built with parts NRI furnishes, to locate and correct Radio-TV receiver troubles. Many who start in spare time, soon build full time Television-Radio sales and service businesses; others enjoy profitable spare time businesses and the security of a source of income to fall back on in case of layoffs, hard times or other changes in regular job. Postage free card will bring you complete facts about the NRI tested way to better pay.

**ACT NOW** FIND OUT WHAT NRI OFFERS YOU

## NRI Has Trained Thousands for Successful Careers in TV-Radio

**Studio Engr., Station KATV**
"I am now Studio Engineer at Television Station KATV. Before enrolling for the NRI Course, I was held back by limitation of a sixth grade education." BILLY SANCHEZ, Pine Bluff, Ark.

**Has All the Work He Can Do**
"Since finishing NRI Course I have repaired more than 2,000 TV and Radio sets a year. NRI training certainly proved to be a good foundation." H. R. GORDON, Milledgeville, Ga.

**Has Good Part Time Business**
"Quite early in my training I started servicing sets. Now have completely equipped shop. My NRI training is the backbone of my progress." E. A. BREDA, Tacoma, Wash.

Cut Out and Mail Postage-Free Card NOW

## Sample Lesson and Catalog Both FREE

SEE OTHER SIDE

OLDEST & LARGEST HOME STUDY RADIO-TV SCHOOL

**National Radio Institute**

**Dept. C D , Washington 16, D.C.**

Please send me sample lesson of your Radio-Television Training and Catalog FREE. (No salesman will call.)

Name..... Age.....

Address.....

City..... Zone..... State.....

ACCREDITED MEMBER NATIONAL HOME STUDY COUNCIL

**NRI SUPPLIES LEARN-BY-DOING KITS WITHOUT EXTRA CHARGE**
**Technical Know-How Pays Off in Interesting, Important Work**



### YOU BUILD AC-DC Superhet Receiver

NRI Servicing Course includes all needed parts. By introducing defects you get actual servicing experience practicing with this modern receiver. Learn-by-doing.



### YOU BUILD This 17 Inch Television Receiver

As part of your NRI course you can get all components, tubes, including 17" picture tube, to build this latest style Television receiver; get actual practice on TV circuits.



### YOU BUILD Broadcasting Transmitter

As part of NRI Communications Course you build this low power Transmitter, learn commercial broadcasting operators' methods, procedures. Train for your FCC Commercial Operator's License.

### YOU BUILD Vacuum Tube Voltmeter

Use it to earn extra cash fixing neighbors' sets; bring to life theory you learn from NRI's easy-to-understand texts.

# For Higher Pay, Better Jobs Be a TV-Radio-Electronic Technician

### Servicing Needs More Trained Men

Portable TV, Hi-Fi, Transistor Radios, Color TV are making new demands for trained Technicians. Good opportunities for spare time earnings or a business of your own.

### Broadcasting Offers Satisfying Careers

4000 TV and Radio stations offer interesting positions. Govt. Radio, Aviation, Police, Two-Way Communications are growing fields. Trained Radio-TV Operators have a bright future.

J. E. Smith, Founder

### Train at Home the NRI Way Famous for Over 40 Years

NRI is America's oldest and largest home study Television-Radio school. The more than 40 years' experience training men for success, the outstanding record and reputation of this school—benefits you in many ways. NRI methods are tested, proven. Successful graduates are everywhere, from coast to coast, in small towns and big cities. You train in your own home, keep your present job while learning. Many successful NRI men did not finish high school. Let us send you an actual lesson, judge for yourself how easy it is to learn.

### No Experience Necessary—NRI Sends Many Kits for Practical Experience

You don't have to know anything about electricity or Radio to understand and succeed with N R I Course. Clearly written, well-illustrated NRI lessons teach TV-Radio-Electronic principles. You get NRI kits for actual experience. All equipment is yours to keep. You learn-by-doing. Mailing the postage-free card may be one of the most important acts of your life. Do it now. Reasonable tuition. Low monthly payments available. Address: **NATIONAL RADIO INSTITUTE, Washington 16, D. C.**

### NRI Graduates Do Important Work

**How Quality Control Chief**
"Had no other training in Radio before enrolling, obtained job working on TV amplifiers before finishing course. Now Quality Control Chief." T. R. FAVALORO, Norwich, N. Y.

**NRI Course Easy to Understand**
"I opened my own shop before receiving my diploma. I have had to hire extra help. I am independent in my own business." D. P. CRESSEY, Stockton, Cal.

**Works on Color-TV**
"NRI changed my whole life. If I had not taken the course, probably would still be a fireman, struggling along. Now Control Supervisor at WRCA - TV." J. F. MELINE, New York, N.Y.

FIRST CLASS
Permit No. 20-R
(Sec. 34.9, P. L. & R.)
Washington, D.C.

BUSINESS REPLY CARD
No Postage Stamp Necessary if Mailed in the United States

**POSTAGE WILL BE PAID BY**

**NATIONAL RADIO INSTITUTE**
**3939 Wisconsin Avenue**
**Washington 16, D.C.**

**SAMPLE LESSON**
**64-page CATALOG**
**both FREE**

**SEE OTHER SIDE**

# General Electric VR-22 Stereo Cartridge–Superior in the four vital areas

Stop to think for a moment of all the jobs required of a stereo cartridge: It must track, with utmost precision, in not one but two directions. It must separate the two stereo channels inscribed in a single record groove. It must perform smoothly in mid-range and at both ends of the audible frequency spectrum. And it must do all these things without producing noticeable hum or noise. Only a fantastically sensitive and precise instrument like the General Electric VR-22 can do all these jobs successfully.

General Electric's VR-22 is superior in the four vital areas of stereo cartridge performance: (1) **Compliance**—It tracks precisely, without the least trace of stiffness. (2) **Channel separation**—Up to 28 db for maximum stereo effect. (3) **Response**—Smooth and flat for superior sound from 20 to 20,000 cycles (VR-22-5), 20 to 17,000 cycles (VR-22-7). (4) **Freedom from hum**—The VR-22 is triple-shielded against stray currents.

**Money-back guarantee:** General Electric believes that once you hear the all-new VR-22 in the privacy of your own home, on your own equipment, you'll want this superb instrument for your very own. That's why we are making an offer virtually without precedent in the Hi-Fi field: Try the VR-22 at home for 10 days. If you don't agree that this is **the** stereo cartridge for you, return it to your participating General Electric dealer and the full purchase price will be cheerfully refunded.

**VR-22-5 with .5 mil diamond stylus** for professional quality tone arms, **$27.95***. VR-22-7 with .7 mil diamond stylus for professional arms and record changers, **$24.95***. Both are excellent for monophonic records, too. TM-2G Tone Arm—designed for use with General Electric stereo cartridges as an integrated pickup system, **$29.95***. General Electric Co., Audio Products Section, Auburn, N. Y.

*Manufacturer's suggested resale prices.

**GENERAL ELECTRIC**



# Spot News

*Latest Information on the Electronic Industry*

By ELECTRONICS WORLD'S WASHINGTON EDITOR

ARMED FORCES WANT MORE INVENTIONS—Hundreds of new ideas are still being sought by the Army, Navy, and Air Force, the National Inventors Council revealed recently. In a 48-page report, the governmental agency declared that the need for new technical developments was most acute, with requirements ranging from advancements in aeronautics, missiles, and weapons to blue-sky projects. Heightened interest in electronics was also prompting increased pleas for help. Commenting on the need for improved communication techniques, the Washington book pointed out that today's methods are not usable for the guidance of long-range missiles; they are not sufficiently effective for guiding a missile accurately to a distant target. We need a "new look" in techniques, they said; one that will extend global-contact ranges in the 1000-5000 mc. bands. There also appears to be a need for a method to eliminate radio noise, without distortion of the intelligible signal. Such improvements are important in missile projects, it was disclosed, since guidance and the accuracy of telemetered data are severely affected by noise. Today's systems either limit or dampen noise, or eliminate both the noise and intelligible portions. Also wanted by the Armed Forces is an electronic timer that will measure intervals from 0.1 microsecond to 0.9999999 second, to an accuracy of plus or minus 0.01 microsecond or better.

NEW MEDICAL-DENTAL TV OPTICAL SYSTEM DEMONSTRATED BY NAVY—An optical fiber probe linked to a closed-circuit TV system that permits dentists to view any part of the mouth, highly magnified—up to 35 times, on a TV screen, has been demonstrated at the U.S. Naval Dental School in Bethesda, Maryland. The probe consists of about 10,000 hair-like optical fibers bound together in a whip-like cable with a fingertip-size lens arrangement at the probing end. Each tiny fiber picks up light from a microscopic section of the surface in front of it and transmits a speck of light to the other end. The thousands of fibers provide a picture featuring thousands of light segments. The development, an Avco project, may eventually permit viewing of the interior of other body cavities, highly magnified and in color, Navy authorities noted.

AVIATION RADIO USE UP, FAA SURVEY REVEALS—More than 50 per-cent of all general aircraft now carry two-way radios, a Federal Aviation Agency survey has disclosed. The study noted that nearly 61 per-cent of the nation's 66,000 aircraft are carrying receiver-transmitters.

NEW MEDICAL EMERGENCY RADIO SERVICE IN OFFING—A 17-frequency medical emergency radio service available to physicians, hospitals, and emergency ambulance services for transmission of urgent messages, has been proposed by the FCC. Operating in the 152-162 and 42-50 mc. bands (using 13 and 4 channels respectively), the new medical block would shift allocations of highway maintenance, fire radio, police, and special emergency in the emergency spectrum, in accordance with the recent split-channel recommendations.

HIGH-POWER KLYSTRONS IN NIKE ZEUS ANTI-MISSILE SYSTEM—Klystrons, which can generate more power per wavelength than any microwave tube currently in use, will be placed in Nike Zeus, the Army's anti-missile defense system designed to track oncoming intercontinental ballistic missiles at longer ranges with greater certainty. The new tube, more compact than earlier models which measured up to 12 feet high, is one of several types developed for the Army by Sperry under a multi-million-dollar contract.

NEW LOW-POWER V.H.F. TRANSLATOR RULES PROPOSED—Standards for the licensing of new low-power v.h.f. TV translator stations are now being considered in Washington. Power outputs would be limited to 1 watt. However, those desiring greater powers—up to 100 watts—could ask to operate on the upper 14 u.h.f. channels, where interference possibilities are not so acute. The new rules would also forbid the use of co-channel boosters, which transmit on the same channels as the stations they pick up since they are, according to the Commission, unstable and capable of transmitting false and misleading signals when operated in the v.h.f. band. -30-

three models... superbly styled... covering a wide range of applications

MODEL 988

# ASTATIC'S FUTURA

## SERIES DYNAMIC MICROPHONES

MODEL 888

Most versatile performers in the microphone field are the Astatic Futura Series Dynamic Microphones—Models Metro 788, Tempo 888, and Vogue 988. Beautifully styled, encompassing the newest and most advanced principles in microphone engineering, each model is designed to outperform any other microphone in its price class.

Futura mikes are instantly convertible from hand to stand to lavalier use... offer many special features such as rugged, stable, fatigue-free Mylar diaphragm and, on the 888 and 988, the Cannon XLR-3 connector for instant detachment from cable ("Take the microphone to the cable.")

MODEL 788

| Model No. | Type | Response | Output | Impedance | Finish and Trim | Price |
|---|---|---|---|---|---|---|
| 788 | Omni-Directional | 60-13,000 cps | -55 DB | Hi or 150 | Black and Gold | $ 79.50 |
| 888 | Omni-Directional | 50-15,000 cps | -56 DB | 50, 200, Hi | Black and Chrome | 110.00 |
| 988 | Omni-Directional | 40-20,000 cps | -58 DB | 50, 150, 250 | Black and Gold | 150.00 |

**NOTE** — Exclusive Astatic impedance selector permits instant choice of impedance without special tools.

All three microphones come complete with lavalier and belt clip, 360° swivel adaptor for ⅝ #27 thread.

Twenty-foot, two-conductor, shielded cable supplied with each microphone.

THE Astatic CORPORATION, CONNEAUT, OHIO

In Canada: Canadian Astatic Limited, Toronto, Ontario
Export Sales: Auburn Agencies Inc.
431 Greenwich St., N. Y. 13, N. Y., U.S.A.

FROM WHAT YOU HEAR

CITIZENS BAND RADIO
at it's VERY BEST!

arkay
Kits and Wired

NEW Arkay SQ-9 'SKY-VOX'
Citizens' 2-Way Radio

*Completely Wired and Aligned Front End Makes It The Easiest Kit to Assemble*

Magnificiently engineered for outstanding performance, ease of assembly and operation, the Sky-Vox offers high sensitivity, selectivity, stability and fidelity of sound.—The finest in citizens' band communication for business, pleasure, auto, farm, home, industry, etc.

Advanced design features include: Completely assembled front end with 3 channels aligned ready to install in main chassis • Up-to-the-minute circuitry with 8 tubes and 5 diodes • Supersensitive crystal controlled superhet receiving circuit • Crystal controlled oscillator Pentode RF amplifier transmitting circuit • Front Panel controls include 3 position channel selector • Receive-Transmit switch • Volume control • Squelch control • Mike input • Noise balance control in rear chassis.

Power Requirements: 117 Volts 60 cycles AC or 12 Volts DC. Sensitivity: 1 u/v. 400 cy. at 27.015 Mc. for full output (2.5 Watts); Signal/Noise Better than 35 DB • Image 30 DB • IF Bandwidth 5 KC • Complete with 2 cables, microphone and set of crystals. Attractive metal case. Size: 5"H x 8½"D x 11"W.

Wired and Tested $119.95 • Easy-to-build Kit $79.95



the Arkay MS-5
STEREO Record Playback
TAPE DECK

*Professional quality at a popular price!*

A supreme achievement in tape deck design and performance, the ARKAY records your favorite music with the same superb performance of tape recorders costing many times more. No other tape deck—regardless of price—offers so many important features. Here's just a few:

- Combination Head for 2 or 4 track Stereo-Two Speeds
- 30-16,000 cps @ 7½ ips
- Flutter and wow: ¼ of 1%
- Five-button operation
- —55 db. S/N
- All-metal tape fingers
- Drop-In Loading
- All-metal tape guards
- Large (½" diam.) capstan
- Size: 12-3/16" x 14½"

2 Track Only $129.95 • 4 Track Slightly Higher

ARKAY CS-28
Stereo Amp/Pre-Amp
Complete
Control Center

Full 28 watts stereo or monaural, 60 watts peak • 14 watts each channel • reverse stereo • balance control • two-channel gain control • full range bass and treble controls • IM distortion, < 1 • harmonic distortion, 1% 30-20,000 cps • dual pre-amp 2V output jacks • speaker outputs, 4, 8, 16, 32 ohms • response, 20-20,000 cps • push-pull EL86 Williamson circuit.

Wired and tested $99.95 • Easy-to-build Kit $64.95

ARKAY ST-11 AM-FM
STEREO TUNER

Here, for the first time, is an AM-FM STEREO Tuner within the reach of every audiophile. Unmatched by units costing twice the price, the ST-11 is two distinct receivers in one featuring 4 uV. for 20 db quieting. Variable AFC. Single front panel switch controls AM, FM or STEREO selection.

Wired and tested $74.50 Easy-to-build Kit $49.95

SPA-55 STEREO AMP 55 watts stereo-monaural, 27½ watts each channel. Wired $79.95 Kit $64.95

ARKAY VT-10 6-INCH
MULTI-PURPOSE
VACUUM TUBE VOLTMETER

Advanced design and precision features make the Arkay VT-10 a truly sensational buy, unmatched at this price. You get exclusive larger 6-INCH 400 ua meter movement, within 2% accuracy, and edge-lighted for easier reading. 1% precision multiplier resistors are used throughout the range switch. There are 7 AC (RMS) and DC ranges, 7 AC (peak-to-peak) ranges. Resistance, db and other essential ranges. Durable plastic case.

Wired and tested $47.95. Easy-to-build Kit $25.95

See and hear ARKAY Kits at your dealer.
FREE! Stereo booklet and catalog. Write Dept. EW
All prices 5% higher west of Mississippi

arkay
HIGH FIDELITY
88-06 Van Wyck Expressway Richmond Hill 18, N.Y.


# Within the Industry

**FRED P. BEGUIN** has been appointed head of a new engineering section at the *American Optical Company* in Southbridge, Mass. In his new post he will direct the efforts of the company in highly specialized areas of electro-acoustics.

Prior to his new appointment, Mr. Beguin was associated with *General Electric Company*. He joined that firm in 1950 as a project engineer in the television department. He then became audio consultant with the audio section of the company's radio receiver department.

More recently Mr. Beguin had been serving as technical specialist with the responsibility for technical sales of audio products to original equipment manufacturers in the Eastern region of the country.

* * *

**FREDERICK R. LACK,** former EIA vice-president and director and vice-president of *Western Electric Company* until his retirement in 1958, has been elected director of the Electronic Industries Association's engineering department.

Mr. Lack is a fellow of the IRE and is also a member of the AIEE, American Association for the Advancement of Science, the American Physical Society, and the Harvard Engineering Society. He was awarded the 1959 EIA Medal of Honor for his many contributions to the advancement of the electronic industry.

* * *

**THOMAS E. GOOTÉE** has climaxed a 17-year civilian-military career with the Army by accepting an executive post with *Page Communications Engineers*, a subsidiary of *Northrup Corporation*, located in Washington, D. C.

In his new post, Mr. Gootée will be assistant director of maintenance and operations for the firm which performs governmental and industrial global communications systems engineering, particularly in the fields of tropospheric, ionospheric, and scatter communications.

Prior to his Signal Corps and civilian government service, Mr. Gootée was a field engineer with *NBC*.

* * *

**INSTITUTE OF HIGH FIDELITY MANUFACTURERS** has named Milton D. Thalberg chairman of the nominating committee. Mr. Thalberg, president of *Audiogersh Corporation*, is also treasurer and a member of the Institute's board of directors.

In addition, four new general members have been elected. They are: *Brand Products Inc., Cletron Inc., DeWald Radio Inc.,* and *Telectrosonic Corporation.* * * *

**WILLIAM N. LATSHAW** has been appointed to the newly created post of advertising production manager for *Heath Company*. In this capacity Mr. Latshaw will assist Clifford M. Edwards, director of advertising, in the preparation of advertising for the firm's line of high-fidelity, marine, ham radio, and test equipment kits.

Mr. Latshaw comes to the company from *MacFarland, Aveyard Advertising Agency* where he was production manager. He was formerly art department manager for *Waldie & Briggs Advertising Agency.*

* * *

**H. LESLIE HOFFMAN,** president of *Hoffman Electronics Corp.,* has been appointed chairman of the Electronic Industries Association's spectrum committee for the fiscal year ending July 31, 1960.

Other members of the committee are: Robert C. Sprague, vice-chairman, *Sprague Electric Co.;* F. L. Ankenbrandt, *RCA;* R. S. Bell, *Packard Bell Electronics;* P. L. Chamberlain, *General Electric Co.;* W. P. Corderman, *Litton Industries Inc.;* D. G. Fink, *Philco Corp.;* I. J. Kaar, *Hoffman Electronics Corp.;* W. B. Lodge, *CBS;* D. E. Noble, *Motorola Inc.;* T. C. Rives, *Syra-*

**JOHN R. (JACK) BINNS,** honorary board chairman of Hazeltine Corp., died recently at the age of 75. A pioneer in the field of electronics, Mr. Binns won fame in 1909 for his life-saving role as a wireless operator during the first sea rescue by radio. He sent the distress signal and then guided the rescue ships following the collision of the steamships "Republic" and "Florida" at sea. A founder of the New York Newspaper Club, he was also a member of the Radio Club of America, Institute of Radio Engineers, and the Society of Naval Engineers, among other organizations.

# My new plates behave like plates... not filaments

**(FORGET YOUR LOW-VOLTAGE RECTIFIER PROBLEMS)**

## HOW BACK EMISSION IS ELIMINATED

Back emission from overheated plate to filament causes most rectifier failures. Reverse current mounts . . . filament is stripped . . . overheats . . . burns out.

That's why the new CBS 5U4GB plates are of non-emissive material, are larger, and run cooler. These and many other advance engineered features make the new CBS 5U4GB the best you can buy. Here's typical proof. Dynamic "blast" tests brutally cycle the tube between 4 and 6.8 volts with 800 volts plate potential. Yet back emission is just measurable . . . less than one milliampere!



"My new plates don't heat up and start acting like filaments. They can't because my plate material is designed not to emit wrong-way electrons. So back emission can't build up and burn out my filament. And you aren't pestered with premature failures."

That is right. The new CBS 5U4GB offers you *total reliability* . . . proved in performance by leading TV and radio set manufacturers. You, too, can profit from the *total reliability* of CBS tubes. Just replace with CBS . . . always.

## TOTAL RELIABILITY... proved in performance

*Receiving, industrial and picture tubes transistors and diodes audio components and phonographs*

**CBS ELECTRONICS**

**Danvers, Massachusetts**

A Division of Columbia Broadcasting System, Inc.



**The last preamp-amplifier you'll ever have to buy!**

*A new 40-watt stereo preamp-amplifier in kit form for only $79.95 by*

**PACO**

*also available factory wired for $129.95*

PACO is the kit division of ***PRECISION*** Apparatus Co., Inc., world famous manufacturers of laboratory electronic instruments for over a quarter century. The new Model SA-40 is the first of a series of component high fidelity kits from PACO...engineered for utmost performance and lasting value—designed for maximum eye-appeal.

Whether you're an experienced audiophile or a newcomer to the thrill of high fidelity, the factors you must consider in choosing the amplifier you need are: POWER, DISTORTION, FLEXIBILITY and VALUE.

The PACO SA-40 offers you greater reserve power capacity than any other preamp-amplifier in its category. Its exceptional circuit design assures highly stable performance with extremely low distortion. Step-by-step assembly instructions and giant-size wiring diagrams are so clearly detailed and simple that the technical difference between expert and novice disappears. And...the SA-40 provides maximum flexibility in *any* stereophonic high fidelity system...present or contemplated.

For those interested in engineering details, some of the more important technical specifications are listed below:

**POWER OUTPUT:**
**Steady State Power Output:** 20 watts per channel, 40 watts total.
**Music Waveform Power Output:** 25 watts per channel, 50 watts total.
**Peak Power Output:** 40 watts per channel, 80 watts total.
**RESPONSE:** 30 cps to 90 Kc, ± 1.0 db.
**DISTORTION:**
**Harmonic:** Less than .2% at 20 watts per channel output. Less than .1% at 10 watts per channel output.
**Intermodulation:** Less than 1% at full rated output.
**FRONT PANEL CONTROLS AND SWITCHES:** 14 controls including separate bass and treble controls for complete flexibility with any monophonic or stereo program source.
**INPUTS:** 14 total; 3 dual high-level and 4 dual low-level.
**OUTPUTS:** Dual tape outputs, separate preamp output as well as standard dual speaker outputs.
**HUM AND NOISE LEVEL:**
**High Level Input:** 80 db below rated output.
**Low Level Input:** 70 db below rated output.
**Tape Input:** 65 db below rated output.
**SPEAKER CONNECTIONS:** 4, 8, 16, 32 ohms.
**SENSITIVITY FOR RATED OUTPUT:**
**Aux Input:** .75 V **Phono 1:** (Magnetic) 5 Mv.
**Tuner:** .75 V **Phono 2:** (Magnetic) 5 Mv. or Ceramic .3V
**INVERSE FEEDBACK:** 25 db
**DAMPING FACTOR:** 22
**BASS TONE CONTROL RANGE:** ±15 db at 50 cps.
**TREBLE TONE CONTROL RANGE:** ±15 db at 10 Kc.
**RUMBLE FILTER:** 6 db per octave below 50 cps.
**EQUALIZATION:** Phono: "RIAA"; "EUR"; Tape: 3¾ and 7½ ips, NARTB
**TAPE OUTPUT LEVEL:** 2 volts per channel.
**POWER SUPPLY:** Silicon diode, low impedance for minimum distortion on extended high level passages.
**EXTERNAL DESIGN:** Gold and satin black hooded case, with panel illumination and satin gold panel.
**DIMENSIONS:** 15⅜" wide x 11¾" deep x 5⅝" high
**Model SA-40:** Complete with case and step-by-step assembly-operating manual ..... **Kit Net Price $ 79.95**
**Model SA-40W:** Factory Wired ..... **Net Price $129.95**

*Ask your own Audio-Radio-TV Serviceman about PACO and PRECISION products. He'll tell you that they always live up to their specs. That's why we can say that the PACO SA-40 is the last preamp-amplifier you'll ever have to buy*

*Available at leading electronic parts distributors and wherever good sound is sold.*

*For complete information write to:*

**PACO**

*Electronics Co., Inc.*
*70-31 84th Street*
*Glendale 27, L. I., N. Y.*

*A Division of*
***PRECISION***
*Apparatus Company, Inc.*

*Export:*
*Morhan Exporting Corp.*
*458 Broadway*
*N. Y. 13, N. Y., U.S.A.*

*Canada:*
*Atlas Radio Corp., Ltd.*
*50 Wingold Ave.*
*Toronto 19, Ontario*

**COMING SOON — MODEL ST-45**
**AM/FM STEREO TUNER KIT**
matching companion for the SA-40




*cuse University Research Corp.;* P. F. Siling, *RCA Frequency Bureau;* D. B. Smith, *Philco Corp.;* Dr. W. R. G. Baker (*ex officio*), *Syracuse University Research Corp.:* and L. G. Cumming (*ex officio*), IRE.

* * *

**U. S. DEPARTMENT OF COMMERCE,** electronics division, Business and Defense Services Administration, has announced that first half 1959 shipments of electron tubes, semiconductors, and other principal electronic components increased more than 15 per-cent over the preceding six months. In addition, all were in excess of 30 per-cent above the comparable period during the year 1958.

This sharp rise, the greatest since the Korean War period, confirms employment trends and other general indicators of steadily growing electronics output during the past months.

Although all components shared in the upward movement, there were marked differences in their rates. Semiconductor shipments during the first half of 1959 were more than double those of the first half of 1958, while receiving tube shipments increased only 5 per-cent.

* * *

**RADIO-TELEVISION TRAINING OF AMERICA** is the new name of **RADIO-TELEVISION TRAINING ASSOCIATION.** Expansion of facilities plus the addition of new radio, television, and electronic courses has prompted this change of name. There will be no other changes in its administration . . . **ELECTRONIC RESEARCH ASSOCIATES, INC.** of Cedar Grove, N. J. has announced the acquisition of **ADVANCED ACOUSTICS CORPORATION** as a wholly owned subsidiary. The new subsidiary, formerly located in New York, will occupy new premises in Nutley, N. J. with its offices, laboratory, and production areas all under one roof . . . **FAIRFIELD ENGINEERING CORPORATION,** Springdale, Conn., and **COVE INDUSTRIES, INC.,** Norwalk, Conn., have announced that a merger of the two companies has been completed. Under the terms of the agreement the Springdale company will acquire the assets of the Norwalk firm, in exchange for *Fairfield* stock.

* * *

**HASKEL A. BLAIR** has been elected president of *University Loudspeakers, Inc.,* a subsidiary of *Ling-Altec Electronics, Inc.*

Mr. Blair began his career early in 1923. After forming the *Blair Radio Laboratories,* he worked on the development and manufacture of the first commercial resistance-coupled radio receiver. Under the name of *Blair Service Laboratories* he proceeded to further develop and manufacture amplifier lines for *Lafayette Radio, Federated Purchaser,* and other well-known mail order houses throughout the country.

In 1932 Mr. Blair joined *David Bogen*

# HOW MUCH DO YOU KNOW ABOUT TRANSISTORS?



***Attend the***

**Delco Electronics–One Week –Advanced Training School**

**No tuition charge**
**No laboratory fees**
**Textbooks supplied**

Bring yourself up to date on transistors and other modern electronic equipment with personalized instruction at the Delco Electronic training school to be held soon at a General Motors Training Center near you. Classes are conducted by graduate engineers with special training in your field.

The Delco Radio diploma, awarded only to those who successfully complete the courses, will mean a great deal to you—*and* to your customers.

The Delco Electronics—One Week—Advanced Training Schools will be conducted in the General Motors Training Centers indicated below. One of them is near you. Register now through your local Delco Electronic Parts Distributor or write directly to Delco Radio Division, General Motors Corporation, Kokomo, Indiana, Attention: Service Manager.

## COURSES OF STUDY OFFERED AT NO COST TO YOU:

❶ Transistor Fundamentals—complete coverage of transistor theory without the use of mathematics. ❷ Transistor Circuit Trouble-shooting—lecture and lab work analyzing defects in transistor circuits. ❸ Hybrid-type Automobile Radios—low voltage tube and output transistor circuits. Lecture and lab. ❹ Trouble-shooting procedures for dead or weak low voltage auto radios—factory developed techniques that are foolproof. ❺ Lecture and lab practice on "Signal Seeker" and "Wonder Bar" auto radio tuners and trigger circuits. ❻ Guide-Matic Headlamp Control (Autronic Eye)—lecture and lab. ❼ Twilight Sentinel Automatic Headlight Switch—lecture and lab. ❽ Garage Door Operators—lecture and lab work including the new Delco Radio all-transistor control units. ❾ Auto Portable Radios—lectures on circuitry of both 1959 and 1960 auto portable radios.

DELCO RADIO
DEPENDABILITY
RELIABILITY

DELCO ELECTRONICS TRAINING SCHOOL SCHEDULE

| DATE | REGION 1 | REGION 2 | REGION 3 | REGION 4 | REGION 5 | REGION 6 |
|---|---|---|---|---|---|---|
| 1-11 | Philadelphia | New Orleans | Chicago | | | |
| 1-18 | | | | St. Louis | Dallas | Salt Lake City |
| 1-25 | | Atlanta | Detroit | | | |
| 2-1 | Union | | | | | |
| 2-8 | | | | Omaha | Memphis | |
| 2-15 | Pittsburgh | Jacksonville | | | | Los Angeles |
| 2-22 | Pittsburgh | | Cincinnati | | | |
| 2-29 | | | | Kansas City | | |
| 3-7 | Tarrytown | Charlotte | | Kansas City | Dallas | Portland |
| 3-14 | | | Cleveland | | | |
| 3-21 | | | | Omaha | El Paso | |
| 3-28 | Boston | Atlanta | | | | Los Angeles |
| 4-4 | Boston | | Chicago | Minneapolis | | |
| 4-11 | | | | Minneapolis | Houston | |
| 4-18 | Union | Washington | Milwaukee | | Houston | San Francisco |
| 4-25 | | Washington | | | | |
| 5-2 | | | Cincinnati | Omaha | | Portland |
| 5-9 | Buffalo | | | | Okla. City | |
| 5-16 | | Atlanta | Detroit | St. Louis | | |
| 5-23 | | | | | | Los Angeles |
| 6-6 | Tarrytown | | Chicago | | Dallas | |
| 6-13 | | New Orleans | | | | San Francisco |
| 6-20 | Philadelphia | | | Denver | | |
| 6-27 | | | Cleveland | | Memphis | Salt Lake City |

# YOU PAY A LITTLE MORE FOR VOCALINE CITIZENS BAND RADIO BUT

## *you get a lot more performance!*

The real worth of equipment is measured by its performance—and that's where Vocaline's ED-27 Commaire outdistances them all. If you're serious about Class D Citizens Band communications, then be equally serious about your choice of equipment. Compare Commaire's superlative (and, in most cases) exclusive features with competitive equipment. It makes sense to spend a little more to get so much more!

Model ED-27
**$179.50 each**

| | |
|---|---|
| THE MOST SELECTIVE & SENSITIVE RECEIVER | Crystal-controlled—**double conversion superhetrodyne.** Selectivity: ± 5 kc at points 6 db down. Sensitivity: 0.1 mv. PLUS twice the audio output of any other class D receiver—4.5 watts! |
| SILENT-AIRE SQUELCH U.S. PAT. 2,632,812 | At last a squelch that really works!... Combines with exclusive noise suppression to assure complete silence in stand-by. |
| ½ MORE OUTPUT | 5 watts input, **3 watts output**—for greater range! |
| TRANSISTORIZED POWER SUPPLY | Assures service-free, reliable operation. |
| UNMATCHED AUDIO CIRCUITRY | Combined with the above features—results in the best-performing class D radio on the market... unequalled for range, signal-to-noise ratio, audio fidelity and dependability. |

Supplied with push-to-talk microphone with coiled cord, hanger, universal mount, antenna loading light. 2 models—115 VAC and 12 VDC; 115 VAC and 6 VDC. Ask for Vocaline Antennas and Accessories.

WRITE FOR COMPLETE DATA
Commaire Dept. A

**VOCALINE**
COMPANY OF AMERICA, INC.
OLD SAYBROOK, CONN.

V3


*Company* and in 1945 left to devote himself to the *Blair-Steinberg Co.*

* * *

**CHARLES D. MANHART** has been elected vice-president of *Daystrom, Incorporated* . . . **ABRAHAM B. COHEN** has been appointed president of *Electronic Research Associates, Inc.'s* newly acquired subsidiary, *Advanced Acoustics Corp.* . . . **LEWIS T. STEIN** has been promoted to product merchandiser, industrial components division of *Allied Radio Corp.* . . . **CURTIS A. HAINES** has been appointed vice-president, facilities and manufacturing planning of *Sylvania Electronic Systems.* In addition, **RALPH L. BLOOM** is now sales manager, radio and high fidelity, of *Sylvania Home Electronics Corp.* . . . *National Company, Inc.* has appointed **THOMAS M. STUART** to the position of technical liaison representative. Its subsidiary, *National Radio Co., Inc.*, has announced the appointment of **SYDNEY W. NATKIN** to the post of assistant general manager . . . *Tung-Sol Electric Inc.* has elected **EDWARD J. DANNEBERG** to the newly created position of vice-president for personnel . . . **E. M. HINSDALE** has been named chief engineer, *RCA* communications products department . . . The board of directors of *The Hickok Electrical Instrument Company* has elected **PAUL WILLOUR** vice-president-treasurer and **ROBERT L. PURCELL**, assistant secretary-treasurer . . . **WILLIAM H. KNOTH** has been named general sales manager of the *Mallory Battery Co.*, a division of *P. R. Mallory & Co. Inc.* . . . The appointment of **THOMAS S. KNIGHT, JR.** as sales manager for *General Electric Company's* receiving tubes, television picture tubes, and high-fidelity components has been announced . . . **JERRY MELTZER** has been named sales promotion manager for *Rek-O-Kut Company, Inc.*, and the *Audax Division* of this firm.

* * *

**ELECTRONIC INDUSTRY SHOW CORPORATION** has announced plans for a "double-header" educational program for the 1960 Electronic Parts Distributors Show. Detailed planning is now underway, with the Corporation's educational and program committee in charge. The committee is headed by Jack D. Hughes of *Littelfuse, Inc.* with Robert E. Svoboda of *Amphenol-Borg Electronics Corp.* as co-chairman.

Enhanced 1960 plans, based on last year's experience and on first-hand knowledge of areas where distributors feel education will help them in their own businesses, call for two separate seminars for distributor management and sales personnel. The two seminars will meet simultaneously in separate rooms on May 17 and May 18—in sessions combining talks, films, and special presentations. Participants will be assigned to non-competitive workshop groups sharing similar interests.

The distributor management seminar will cover such topics as sales and financial management, while the sales personnel seminar will explore selling techniques. —30—

# How to Get a Commercial FCC License




## do you know what an FCC license really can do for you in Electronics?

**1 More income for you every week**

**2 A more interesting job in electronics**

The average person spends over 50% of his waking hours on the job (or going to and from the job). Therefore doesn't it make sense to have a job that is really interesting and also pays well?

The chances are very good that if you are reading this magazine you can qualify for the really good jobs in electronics like those shown in the pictures at the left . . . and it won't take long to do it. Your past training and experience in basic electronics (such as radio and TV repair, armed forces electronics, ham operators, etc.) can be the foundation for a profitable career as an "across-the-board" electronics technician.

Whether you run your own shop or work for someone else, the real money, the interesting work, is available to the man who can effectively handle the more complex electronic gear. Home receiver repair can provide a good living, but it can't match the opportunities open to a skilled electronics technician.

The Career Information Material shown below will show you how you can qualify for a government certificate of competency . . . a commercial FCC License . . . and acquire a really fine technical education. Find out how your success with the FCC examination is guaranteed . . . or your money back.

You will also find out which jobs require the FCC License . . . where technicians are needed . . . what a technician needs to know about electronics . . . and many other facts about opportunities for you in electronics.

It will cost you only the price of a postage stamp to get all the facts. If you are in any type of electronics work . . . or if you have had previous training or experience in electronics . . . you owe it to yourself to ask us to send you information on profitable careers in electronics.

**CLEVELAND INSTITUTE OF ELECTRONICS**

**Desk RN-38, 4900 Euclid Ave. Cleveland 3, Ohio**

1. Raytheon Manufacturing Company
2. Radio Corporation of America
3. Jupiter IRBM, Army Ordnance Missile Command
4. Collins Radio Company
5. Radio Corporation of America




# free!

**FIND OUT HOW:**

**1. The new electronic devices can be handled by you**

**2. To solve the problems that will stump your fellow technicians**

**3. Training is Job Insurance when employment is tough to find . . . and more money for you when times are good**

**CLEVELAND INSTITUTE OF ELECTRONICS**

**Desk RN-38, 4900 Euclid Ave., Cleveland 3, Ohio**

Please send FREE Career Information Material prepared to help me get ahead in Electronics. I have had training or experience in Electronics as indicated below:

- ☐ Military
- ☐ Radio-TV Servicing
- ☐ Manufacturing
- ☐ Amateur Radio
- ☐ Broadcasting
- ☐ Home Experimenting
- ☐ Telephone Company
- ☐ Other

**In what kind of work are you now engaged?** _____

**In what branch of Electronics are you interested?** _____

Name _____ Age _____

Address _____

City _____ Zone ____ State _____

RN-38

# NOW take another look at

## NEW E-V MODEL 644

**SOUND SPOT MICROPHONE • LIST $110.00**

If you are in the commercial sound business, you have had your share of . . . "they couldn't be done" . . . jobs at one time or another in your business life. These jobs could not be solved because general purpose microphones just couldn't do the job. That, fortunately, is past history. E-V's new Model 644 ushers in a new era in the concept of microphone pick-up. So *take another look* and see how many of those "tough" jobs the 644 reclassifies to "simple and easy". Your local E-V distributor has all the details on the Model 644. Why not call him today or write Dept. 20N for our new Commercial Sound Catalog No. 132.

Electro-Voice®

## The New E-V Model 644 is in stock now at

**ALABAMA**
Birmingham — Forbes Distributing, 2600 3rd Ave.
**ALASKA**
Anchorage — Yukon Radio Supply, 645 "I" St.
**ARIZONA**
Phoenix — Culver Electronic., 231 N. First Ave.
Phoenix — High Fidelity Sound Systems, 1809 E. McDowell
**CALIFORNIA**
Burbank — Valley Electronic, 1302 W. Magnolia
Fresno — Dunlap Radio, 2617 Tulare St.
Hollywood — Hollywood Radio, 5606 Hollywood
Los Angeles — Kierulff Sound, 820 W. Olympic
Los Angeles — Radio Product Sales, 1501 S. Hill St.
Oakland — Elmar Electronics, 140 Eleventh
Pasadena—Audio Associates, 689 S. Fair Oaks Ave.
Pasadena — Dow Radio, 1755-59 E. Colorado
Pomona — Andersen-Maggs Electronic, 1095 E. 3rd
Sacramento — Dunlap Radio & TV, 1800 22nd
San Diego — Wrights House of Hi Fi, 5140 El Cajon
San Francisco — Columbia Music & Electronics, 1080-86 Market St.
San Francisco — San Francisco Radio, 1284 Market
San Francisco — Eber Electronics, 2355 Market St.
San Jose — Alco Paramount, 79 South Third
San Rafael — Catania Sound, 1541 Fourth St.
Santa Barbara—Channel Radio Supply, 18 E. Ortega
Stockton — Dunlap Radio, 27 North Brant St.
**COLORADO**
Denver — Fistells Electronic Supply, 1001 Bannock
Pueblo — L. B. Walker Radio, 100 N. Victoria
**CONNECTICUT**
Hartford — Dressler Electronics, 401 Trumbull St.
Hartford — Hatry of Hartford, Inc., 100 High St.
Meriden — Business Music, Inc., 99 Colony
Middletown — G. U. Reed, 143 Williams St.
Waterbury — The Bond Radio Supply, 439 W. Main
**DELAWARE**
Wilmington — W. S. Wilson Co., 405 Delaware
**DISTRICT OF COLUMBIA**
Washington — Commissioned Electronics, 1776 Columbia Rd., N.W.
Washington — Electronic Whlslr., 2345 Sherman,NW
Washington — Shrader Sound, 2803 "M" St., NW
Washington — Silberne Radio & Electronic Co., 3400 Georgia Ave., N.W.
Washington — U.S. Recording, 1121 Vermont Ave.
Washington — Wilson-Gill, 1 Thomas Circle, N.W.
**FLORIDA**
Jacksonville — Fidelity Sound, 1427 Landon Ave.
Miami — Electronic Equipment, 2701 N.W. 42nd
Miami — Electronic Supply, 61 N.E. 9th St.
Miami — Flagler Radio, 1068 West Flagler St.
Tampa — Thurow Distributors, 121 South Water
Winter Park — Laird Electronics, 803 Fairbanks Ave.
**GEORGIA**
Atlanta — Calhoun Co., Inc., 121 Forrest Ave., N.E.
Atlanta — Radio Television, 526 Plaster Ave., N.E.
Atlanta — Southeastern Radio Parts Co., 400 W. Peachtree St.
**HAWAII**
Honolulu — Precision Radio, 1160 South Kings St.
**IDAHO**
Boise — Robbies Radio & TV, 3801 Hill Rd.
**ILLINOIS**
Benton — Lampley Radio Co., 452 East Church St.
Broadview — Hi Fi Unlimited, 1303-05 Roosevelt Rd.
Chicago — Allied Radio, 100 North Western
Chicago — deHann HI-FI, Evergreen Shopping Plaza
Chicago — Newark Electric, 223 W. Madison St.
Chicago — Private-Tele-Communications, Inc., 1010 West Diversey Parkway
Chicago — Woodlawn Appliance, 1215 East 63rd
Jacksonville — Bosco, 419 South Mauvaisterre St.
Peoria — Klaus Radio, 403 East Lake
**INDIANA**
Anderson — Seybert's, 1331 Main St.
Bloomington — Stansifer Radio — 1805 S. Walnut
Evansville — Ohio Valley Sound, 20 E. Sycamore
Fort Wayne — Warran Radio, 1716 S. Harrison
Fort Wayne — Workrite Intercommunication Systems, 5341 Gardenview
Indianapolis — Graham Electronics, 122 S. Senate
Indianapolis — Radio Distributing, 1013 N. Capital
Indianapolis — Warren Radio, 732 N. Capitol Ave.
Kokomo — Georges Electronic, 320 W. Superior
Peru — Clingaman Sound, 814 West Main
Richmond — Fox Electronics, 711 South Ninth
Rolling Prairie — Rolling Sound, Rural Route 1
South Bend — Colfax Company, 747 S. Michigan
South Bend — Industrial Sound Engineers, 531½ Eddy St., South
South Bend — Radio Distributing, 1212 S. High St.
Terre Haute — C. T. Evinger Co., 1216 Wabash
Wabash — Mark's Camera & Hi-Fi Shop, 14 Canal
**IOWA**
Council Bluffs — World Radio, 3415 W. Broadway
Des Moines—Radio Trade Supply, 1224 Grand Ave.
Iowa City — Woodburn Sound, 218 East College St.
**KANSAS**
Kansas City — D. Beatty Stereo Hi-Fi, 1616 W. 43rd
Wichita — Radio Supply Co., 115 Laura St.
Wichita — Stark-Suburban Sound, 807-09 South Woodlawn
**KENTUCKY**
Lexington — J. M. Hisle, 405 South Upper St.
Lexington — Radio Equipment Co., 480 Skain St.
Louisville — Universal Radio Service, 533 S. 7th St.
Paducah — Rowtan TV & Sound Corp., 4815 Clarks River Rd.
**LOUISIANA**
New Orleans — Electronic Parts, 3622 Toulouse
**MAINE**
Bangor — Maine Electronic Supply, 494 Broadway
Portland — Maine Electronic Supply, 148 Anderson
**MARYLAND**
Baltimore — Henry O. Berman, 12 E. Lombard St.
Baltimore — Industrial Electronics, 127 Light St.
Baltimore — Kann Ellert Electronics, 9 S. Howard
Baltimore — R. Selway Collmus, 627 N. Bend Rd.
**MASSACHUSETTS**
Boston — Cramer Electronic, Inc., 811 Boylston St.
Boston — DeMambro Radio, 1095 Commonwealth
Boston — The Louis M. Herman Co., 885 Boylston St.
Boston — Radio Shack Corp., 730 Commonwealth
Boston — Tape & Music Inc., 1026 Commonwealth
Boston — Trimount Coin Machine, 40 Watham St.
Cambridge — Hi Fi Lab Electronic, 1077 Mass.
Springfield — Regent Sales, 999 Worthington St.
Worcester — Fred G. Walters Co., 1308 Grafton St.
**MICHIGAN**
Ann Arbor — Wedemeyer Electronic, 213-17 N. 4th
Battle Creek — Electronic Supply, 94 Hamblin Ave.
Detroit — Audio Equipment, 15747 Wyoming
Detroit — KLA Laboratories, 7375 Woodward Ave.
Detroit — Pecar Electronics, 11201 Morang Ave.
Detroit — Rissi Electronic Supply, 14405 Wyoming
Flint — Folsom's Commercial Sound Engineering, 1608 Albert St.
Grand Rapids — Radio Electronic Supply Co., 505 Jefferson, S.E.
Grand Rapids — Radio Parts, 542 Division, S.
Lansing — Offenhauer Company, 5019 W. Saginaw
Lansing — Tape Recording Industries, 3335 East Michigan Ave.
Muskegon — West Michigan Sound, 1932 Peck
Saginaw — Audio Communications, 1511 Janes
**MINNESOTA**
Minneapolis — Lew Bann, 67 South Twelfth St.
**MISSISSIPPI**
Jackson — Swan Distributing, 342 North Gallatin
Tupelo — Pate Electronics, Highway 45 South
**MISSOURI**
Cape Girardeau — Seudekum Electronics, 2215 Broadway
Kansas City — Audio Communications, 1515 Baltimore Ave.
Kansas City — Burstein Applebee, 1012-14 McGee
Kansas City — McGee Radio Co., 1901 McGee St.
Kirkwood — Kirkwood Camera, 122 W. Jefferson
St. Louis — Ebinger Electronics, 2501 S. Jefferson
St. Louis — Gasco, Inc., Box 113, Lambert Field
St. Louis — Hollander & Co., Inc., 3900 W. Pine
St. Louis — Interstate Supply, 4445 Gustine
St. Louis — Phone Craft Co., 427 North Euclid
St. Louis — Van Sickle Radio Co., 1113 Pine St.
**NEBRASKA**
Omaha — J-B Distributing Co., 1616 Cass St.
**NEW JERSEY**
Camden — Radio Electric Service, 513 Cooper
Jersey City — Nidisco-Jersey City, Inc., 713 Newark
Mountainside — Federated Purchaser, 1021 Rte. 22
**NEW YORK**
Albany — Audio-Video Corp., 324 Central Ave.
Albany — Fort Orange Radio, 904 Broadway
Auburn — Dare Radio, 22 East Genesee St.

# those "impossible" sound jobs!

## compare polar patterns yourself

**NON-DIRECTIONAL**




NON DIRECTIONAL MICROPHONE

**CARDIOID**




CARDIOID UNIDIRECTIONAL MICROPHONE

**SOUND SPOT**




SOUND SPOT UNIDIRECTIONAL MICROPHONE

- Four times greater working distance than the best cardioids, depending on acoustics
- Greatly reduces feedback
- Retains "on-mike" presence despite extended working distance
- Excellent outdoors . . . less wind noise
- Priced low to fit most budgets
- Lasts a lifetime

*Another better product for better sound from . . .*

**ELECTRO-VOICE, INC.**

*Commercial Products Division • Loudspeakers-Microphones*

BUCHANAN, MICHIGAN

## your Electro-Voice Microphone Headquarters

Binghamton — Stack Electronics, 25 State St.
Buffalo — Radio Equipment, 147 Genesee St.
East Meadow — South Service Engineers, 1778 Hempstead Turnpike
Elmira — Chemung Electronics, 403 East Third St.
Farmingdale, Long Island — Gem Electronics Distributors, 34 Hempstead Turnpike
Jamaica — Lafayette Radio, 165-08 Liberty Ave.
Mineola, Long Island — Arrow Electronics Inc., 525 Jericho Turnpike
New York — Airex Radio, 64 Cortlandt St.
New York — Goody Audio, 235 West 49th St.
New York — Harvey Radio, 103 West 43rd St.
New York — Heins & Bolet, 68 Cortlandt
New York — Hudson Radio, 37 West 65th St.
New York — Leonard Radio, Inc., 69 Cortlandt
New York — Magic-Vue Television, 323 E. 13th St.
New York — Milo Trading, 215 Fulton
New York — Recording Tape Co., 123 East 88th St.
New York — Sonocraft, 115 West 45th St.
New York — Terminal Radio, 85 Cortlandt
Rochester — Rochester Radio, 600 East Main St.
Syracuse — Brown Sound Equipment, 521 E. Washington
Valley Stream — Sam Goody Green Acres, Inc., 44 North Parking
White Plains — Westchester Electronic Supply, 602-610 Mamaroneck Ave.

**NORTH CAROLINA**
Asheville — Freck Radio & Supply Co., 38 Biltmore
Charlotte — Dixie Radio, 4131 Bryant St.
Gastonia — Stroup Hi Fi Center, 112 Green Drive
Winston Salem — Dalton Hege Radio, 938 Burke

**NORTH DAKOTA**
Fargo — Walter Electronic, 402 North P. Ave.

**OHIO**
Akron — Olson Radio, 69 West State St.
Akron — The Sun Radio Co., 110 East Market St.
Canton — Burroughs Radio, 2705 Fulton Rd., N.W.
Columbus — Associated Sound, 671 Dennison Ave.
Columbus — Electronic Supply, 134 E. Long St.
Dayton — Custom Electronics, 1918 S. Brown
Dayton — Srepco, Inc., 314 Leo St.
Lima — Hutch & Son, Roberts at Lenore
Marion — Servex Electronics, 220 N. Prospect
Massilon — M. H. Martin Co., 1118 Lincoln Way, E.
Steubenville — The D & R Radio Supply 221 S. 3rd
Toledo — Warren Radio Co., 1002 Adams St.
Zanesville — Thompson Radio, 110 South 6th St.

**OKLAHOMA**
Oklahoma City — Johnson Wholesale Electronics, 927 Northwest First St.
Oklahoma City — Trice Wholesale, 800 N. Hudson

**OREGON**
Portland — United Radio, 22 Northwest 9th
Salem — Universal Sound Corp., 1461 Capitol, N.E.

**PENNSYLVANIA**
Allentown — A. A. Peters, Inc., 231 North 7th St.
Allentown — Radio Electronic Service, 1313 Linden
Bethlehem — Buss Radio, 431 West Broad St.
Erie — Warren Radio, Inc., 1313-17 Peach St.
Harrisburg — D & H Distributing, 2535 N. 7th St.
Johnstown — Cambria Equipment, 17 Johns St.
McKeesport—McKeesport Electronics, 1661 5th Ave.
Philadelphia — Airtone, 1710 Sansom St.
Philadelphia — Almo Radio, 913 Arch St.
Philadelphia — General Sound, 3500 N. 9th St.
Philadelphia — Magnetic Recorder & Reproducer, 1533-35 Cherry
Philadelphia — Radio Electric Service Co., N.W. 7th and Arch Sts.
Pittsburgh — Cecil T. Hall Labs, 770 Washington
Pittsburgh — Radio Parts Co., 6401 Penn Ave.
Pittsburgh — Olson Radio Warehouse, 5918 Penn
Pottsville — Meyer Electronic, 330 N. Norwegian
Reading — George D. Barbey, Second and Penn Sts.
State College — Alvo Electronic, 103 S. Pugh
Wilkes-Barre — Shelborne Electronics, 169 N. Penn

**RHODE ISLAND**
Providence — W. H. Edwards, 92 Broadway
Providence — Gertz, Inc., 257 Adelaide Ave.

**SOUTH CAROLINA**
Charleston — Radio Labs, 475-477 East Bay St.
Columbia — Dixie Radio Supply 1628 Laurel St.

**TENNESSEE**
Knoxville — McClung Appliance, 310 Georgia, NE
Knoxville — Roden Electrical, 708 Central, N.W.
Knoxville — Smith Electronic, 301 E. Magnolia
Memphis — Bluff City Distributing, 234 East St.
Memphis — Glenn Allen Co., 1150 Union Ave
Memphis — Lavender Distributors, 180 S. Cooper
Memphis — W & W Distributing, 644 Madison Ave.
Nashville — D & N Dist., 113 19th Ave., S.
Nashville — Electra Distributors, 1914 W. End Ave.

**TEXAS**
Arlington — Audio Acoustics, 130 Fairview
Corpus Christi — Electronic Equipment and Engineering, 805 South Staples
Dallas — All State Distributing, 2411 Ross Ave.
Dallas — Southwest Radio, 1820 W. Harwood
Forth Worth — C. Herring Sound, 1705 7th St., W.
Fort Worth — Rae Gantt Sound, 12th & Throckmarton
Houston — Sound Equipment, 2506 Crawford
Lubbock — R & R Distributing, 1607 Avenue G
Lubbock — Sound Photo Sales, 2107 Broadway
Waco — Best Electronics, 324 North 18th St.

**UTAH**
Ogden — Carter Supply, 3214 Washington Blvd.
Ogden — Ballard Supply, 3109 Washington Blvd.
Salt Lake — Custom Sound by Poll, 1651 S. 11th
Salt Lake — Ballard Supply Co., 44 E. 6th St., S.

**VIRGINIA**
Arlington — Rucker Electronic, 1213 Wilson
Danville — Womack Radio, 513 Wilson
Newport News — General Supply Co., 4215 Huntington Ave.
Norfolk — Cain Electronics, 14th and Monticello
Norfolk — Electronic Engineering, 4201 Hampton
Norfolk — Priest Electronics, 6431 Tidewater Dr.
Norfolk — Radio Parts Dist'ng., 128 W. Olney
Norfolk — Radio Supply Co., 711 Granby St.
Richmond — Cottrell Electronics, 408 East Main St.
Roanoke — L. C. Hartman, 3236 Cove Rd., N.W.
Staunton — Southern Electronic, 818 Greenville

**WASHINGTON**
Everett — Pringle Radio, 2514 Colby
Seattle — Electricraft, Inc., 1408 6th Ave.
Seattle — Western Electronic Supply, 717 Dexter Ave.
Seattle — Pacific Electronic Sales, 1209 First Ave.
Tacoma — C & G Radio Supply, 2502 Jefferson Ave.
Tacoma—Wiblo Radio Supply, 2360 S. Fawcett Ave.

**WEST VIRGINIA**
Charleston — Chemcity Electronic Dist., 1637 4th
Charleston — Mountain Electronics, 708 Bigley Ave.
Parkersburg — Hausfeld Radio Supply, 536 7th St.

**WISCONSIN**
Manitowoc — Harris Radio Corp., 115 N. Tenth St.

**BRITISH COLUMBIA**
Vancouver—D. Eldon McLennan, 1624 W. 3rd Ave.

**NEW BRUNSWICK**
Moncton — Lewis-Price TV Radio, 330 St. George

**ONTARIO — CANADA**
Kitchener — MacDonald Electric, 307 Queen St., S.
London — C. M. Peterson Co., 575 Dundas St.
London — Provincial Electronic Supply, 641 York
Ottawa — Tower Productions, 278 Sparks St.
Scarborough — R. C. Kahnert, 73 Crockford Blvd.
Sudbury — Sonic Northern, 300 Elm St., East
Toronto — Electro-Sonic Supply, 540 Yonge St.
Toronto — Electro-Voice Sound Systems, 126 Dundas
Toronto — General Sound & Theatre, 861 Bay
Windsor — Adams Electronics, 2471 Ouelette Ave.
Windsor — C. M. Peterson & Co., 800 Heward Ave.

**QUEBEC — CANADA**
Montreal — Electric Labs, Reg'd. 7556 St. Hubert
Montreal — Payette Radio, 730 St. James West
Montreal — Radio Service, 2022 McGill College
Quebec City — Crebel, Ltd., 790 Blvd. Charest E.
Quebec City — George Latour, Inc., 1540 Third

**MANITOBA — CANADA**
Winnipeg — Ballard Recording Ltd., 138 Portage

**EXPORT**
New York — Telesco International, 36 W. 40th St.

# A PLEASURE TO BUY at your franchised Thorens dealer's

# A PLEASURE TO OWN... more features, more craftsmanship, more superb music-making quality for monaural or stereo

# A PLEASURE TO RECOMMEND to friend or favored customer, with the confidence-inspiring Thorens 1-year guarantee

## THE THORENS TD-124 TRANSCRIPTION TURNTABLE

**More rotating pounds than any comparable 12" turntable!**
**More features per pound! Look at them:**

- 4 speeds . . . 16⅔, 33⅓, 45, 78
- 11½ pound table for smooth running
- Exclusive double-table with clutch for fast starts
- Precision, hairline adjustment for all speeds
- Built-in illuminated strobe
- Easy arm installation or change . . . no metal drilling, no unsightly holes after arm change
- Built-in precision circular level
- Large, knurled, leveling screws
- Motor operates on 50/60 cps, any voltage from 100 to 250. 0.2

. . . and many more. See the TD-124 at your franchised Thorens dealer's today.

**TD-124**
**$99.75 net**
(Base only $9.00)

**Guaranteed for one full year.**

**Sold only through carefully selected franchised dealers.**

THORENS

**SWISS MADE PRODUCTS**
HI-FI COMPONENTS • LIGHTERS
SPRING-POWERED SHAVERS
MUSIC BOXES
*NEW HYDE PARK, NEW YORK*

### ANDREA: INTERMITTENT SOUND

If sound output is intermittent on TV receivers using the VO-21 and VP-21 chassis, or if audio-output level fluctuates, the cause may lie either in the sound take-off transformer (Part No. SA-373) or the ratio-detector transformer (Part No. SA-374). Before deciding on the removal of either unit, the possibility of a poor external connection should be considered. Accordingly a hot soldering iron should be applied to the lugs of both transformers to make sure that coil wires have proper electrical connection to these lugs.

If the symptoms noted here develop after the receiver has been in use for a long while, and if sweating the connections and replacing the tubes involved do not remedy the condition, then one of the transformers is probably internally defective. If this is the case, it may prove to be more economical to replace both transformers at the same time than to attempt to determine which of the two is specifically defective. The cost of the extra transformer saves bench time.

### OLYMPIC: BUZZ

Some TV receivers using the HE, HJ, JE, and JJ chassis may exhibit a tendency to annoying buzz in the sound when tuned to a relatively strong signal. If this should occur, it indicates that there is probably slight misalignment in the sound strip. While realignment is helpful, a minor revision of the circuit involving three resistors will render the receiver less sensitive to the long-term development of this symptom. As shown in Fig. 1, the 1000-ohm resistor connected to pin 6 of the sound i.f. amplifier ($V_3$, 6AU6) should be changed to 68,000 ohms. A 47,000-ohm resistor should be added between this point and ground. In addition, there is an 18,000-ohm resistor between the 280-volt line and the screen-grid

Fig. 1




circuits of both $V_3$ and $V_4$, the 6DT6 discriminator. This should be changed to 22,000 ohms, 2 watts. This revision applies to all HE and HJ chassis and some JE and JJ units. Late production

# YOU GET THE MOST IN ANY CITIZENS BAND ENDEAVOR WITH THE

# hy-gain Citizen Banders

## AN ANTENNA GROUP DESIGNED SPECIFICALLY FOR MAXIMUM PERFORMANCE

A careful antenna test range development program has resulted in a series of efficient antennas specifically engineered for the particular Citizens Band use involved. Each antenna is perfectly matched to 50 ohms. Rugged commercial construction design assures long, dependable service . . . These antennas are quick and easy to assemble and install in only a matter of minutes.

## Mobile Use

**ONE HOLE, EASY MOUNTING**

Chrome plated, stainless steel telescoping whip extends to 73", down to 22" for easy garaging. Outperforms full length bumper mounted whip. Weatherproof, polyethylene enclosed, high efficiency base loading coil with exclusive "L" matching network. Universal swivel body mount.

Model CM $11.95

**FOR TEMPORARY MOUNT**

For temporary use, the Citizens Whip (Model CW) may be door mounted using the hy-gain Auto Door Mount, Model ADM.

## Auto Door Mount

Complete with SO-239 receptacle for mounting model CW on door top of most autos for Mobile use. Easy, quick attachment.

Model ADM $4.95

Model CC-12. Coax cable kit for use with Model ADM and CW or CM. 12 ft. RG58U with soldered lugs one end, PL259 coax connector on other. $3.95

## Close Range

**FOR INDOORS, OFFICE-TO-OFFICE, ETC.**

Citizens Dipole "Rabbit Ears" is portable with telescoping chrome plated whips (45" down to 15") with uniquely designed suction cup base for mounting on transceiver, wall, windows, etc. May be oriented either vertically or horizontally. Loading coils and "L" matching network enclosed in polyethylene. Six ft. RG58U coax cable.

Model CD $12.95



Citizens Whip:- chrome plated telescoping whip extends to 45", down to 15" for easy storage . . . Base loading coil enclosed in polyethylene cover. PL259 coax connector for simple screw-in attachment. Swivel joint for top or back mounting.

Model CW $6.95

## Base Station Operation with the hy-gain Ground Planes

**HIGH EFFICIENCY POINT-TO-POINT OR BASE STATION TO MOBILE**

The Citizens Ground Plane is a complete kit and includes a ⅞" to ¾" telescoping aluminum radiator, three copper clad steel ground plane radials, screw hooks, 1½" dia. 3-foot mast and universal roof mount. The standard ground plane uses ⅝" dia. radiator and three radials. The Heavy duty ground plane is of rugged commercial construction with ⅞" to ¾" telescoping aluminum radiator and four radials. All are factory adjusted for perfect 50 ohm match and maximum efficiency.

| CITIZENS GROUND PLANE Model CGP | STANDARD GROUND PLANE Model SGP | HEAVY DUTY GROUND PLANE Model GP-1 |
|---|---|---|
| $18.95 | $19.95 | $32.50 |

## Extended Range Citizens Band Use

**CITIZENS BEAM PROVIDES 8.5 DB GAIN; MULTIPLIES POWER 7 TIMES**

3-Element Beam of commercial duty construction . . . light weight ⅞" to ¾" OD aluminum elements and 2" OD aluminum boom. Completely factory preadjusted and beta-matched. Boom: 8 ft. Longest element: 16.5 ft. approx. Weight: 18 lbs. Positive grip U-bolt attaches to masts up to 1⅝" dia. May be rotated by any TV rotator. May also be mounted vertically for extended base-to-mobile coverage over approximately 180° arc.

Model 113-G



$36.95

Model CC-25 (25 ft.) or Model CC-50 (50 ft.) RG58U coaxial cable with PL259 coax connectors both ends. For use with ground planes or beam.

CC-25 $5.95 CC-50 $8.95

Model ADT Adapter, connects VHF coax plug type PL259 to automative type plug. $1.95.

## PROFITABLE DEALER DISCOUNTS

SEE YOUR LOCAL
HY-GAIN DISTRIBUTOR OR WRITE
DIRECT TO HY-GAIN FOR DISCOUNT
INFORMATION AND TECHNICAL LITERATURE

hy-gain antenna products
1135 NO. 22ND • LINCOLN NEBRASKA

Name: _____ Store: _____

Address: _____ City & State: _____

# FIRST TIME . . . a versatile

# DUAL HEAT SOLDERING GUN

FOR ONLY $7.95 LIST

Model 8200K

. . . and best of all, it's a new

Weller®

Here from Weller, long time leader in the soldering field, is the newest and finest soldering gun value on the market.

**WELLER DUAL HEAT FEATURE** saves time, gives greater convenience and greatly increases tip life. A touch of your finger on the Triggermatic control switches heat to high (125 watts) or low (90 watts) as your job requires. It adapts instantly to varying needs, and you use high heat only when necessary.

**HIGH EFFICIENCY WELLERTIP** utilizes copper for superior heat transfer and soldering efficiency, plus iron plating for durability. Flat cross-section design gives added strength and rigidity.

**NEWEST DESIGN** with sturdy plastic housing that resists hard knocks. Compact "feel" and comfortable balance aid precision soldering. Like all other Weller guns, this new model features instant heat, and a spotlight illuminates your work.

**KIT INCLUDED**

In addition to the Dual Heat Soldering Gun you get:

- **Nylon Flux Brush**
- **Soldering Aid for opening old joints, twisting wires**
- **All-purpose Solder**

*On sale now at your Electronic Parts Distributor*

WELLER ELECTRIC CORP. • 601 Stone's Crossing Rd., Easton, Pa.


of the latter chassis incorporates the change.

### WESTINGHOUSE CLOCK RADIO

Battery-operated clock radios H-685/6P8 may use two slightly different clock mechanisms. It is important to recognize this fact if the clock must be replaced, as a slight wiring change may have to be made. If the difference is not properly observed, clock noise (a ticking sound) may be reproduced in the transistor radio's loudspeaker following replacement. The clock used in late production is identified by a red dot on its rear cover. This dot does not appear on clocks used in earlier production.




Fig. 2

Since either type of clock may be furnished as a replacement, the wiring for each of the two units should be kept in mind.

Wiring for the early production clock appears in Fig. 2A. As shown here, the clock case must be externally grounded (the positive side of the battery is ground). Late-production clocks do not require the extra ground lead (Fig. 2B), as the case has been grounded internally. Failure to make sure that the external ground is present when the earlier clock is used can produce the interfering sound of the clock's ticking in the loudspeaker. If the external ground already exists, neither clock should cause trouble.

### MOTOROLA: VIDEO HUM

If a.c. in the picture persists despite tube changes and other normal corrective procedures, check the dress of resistor $R_{12}$ (270,000 ohms) connected to the screen of the mixer-oscillator (5U8) in the tuner. It may be close to pin 4 (a heater connection) on the tube socket. Simply dressing it away from pin 4 should be a sufficient measure to eliminate the symptom. —30—

**Listen to the EICO Hour, WBAI-FM, N. Y. 99.5 MC Mon., Thurs., Sat., 7-8 P.M., & Sat. 3-4 P.M.**

In STEREO and Mono Hi-Fi . . . the experts say your best buy is EICO

"The overall design of the HF-81 is conservative, honest and functional. It is a good value considered purely on its own merits, and a better one when its price is considered as well."
— Hirsch-Houck Labs (HIGH FIDELITY Magazine)

- Advanced engineering • Finest quality components
- "Beginner-Tested," easy step-by-step instructions
- LIFETIME service & calibration guarantee at nominal cost
- IN STOCK — compare, then take home any EICO equipment — right "off the shelf" — from 1500 neighborhood EICO dealers.

Stereo Amplifier-Preamplifier HF81

Stereo Preamplifier HF85

70W Stereo Power Amplifier HF87
28W Stereo Power Amplifier HF86

FM Tuner HFT90 FM/AM Tuner HFT92
AM Tuner HFT94

Stereo Integrated Amplifier AF4

12W Mono Integrated Amplifier HF12
Other Mono Integrated Amplifiers:
50, 30, & 20W (use 2 for stereo)

2-Way Bookshelf Speaker System HFS1
3-Way Speaker System HFS3
2-Way Speaker System HFS5

Over 1 MILLION EICO instruments in use throughout the world

Add 5% on the West

**HF81 Stereo Amplifier-Preamplifier** selects, amplifies, controls any stereo source & feeds it thru self-contained dual 14W amplifiers to a pair of speakers. Provides 28W monophonically. Ganged level controls, separate balance control, independent bass & treble controls for each channel. Identical Williamson-type, push-pull EL84 power amplifiers. **"Excellent"** — SATURDAY REVIEW; HI-FI MUSIC AT HOME. **"Outstanding quality . . . extremely versatile."**—ELECTRONICS WORLD LAB-TESTED. **Kit $69.95. Wired $109.95.** Includes cover.

**HF85 Stereo Preamplifier** is a complete, master stereo preamplifier-control unit, self-powered for flexibility & to avoid power-supply problems. Distortion borders on unmeasurable even at high output levels. Level, bass, & treble controls independent for each channel or ganged for both channels. Inputs for phono, tape head, mike, AM, FM, & FM-multiplex. One each auxiliary A & B input in each channel. Switched-in loudness compensator. **"Extreme flexibility . . . a bargain."**— HI-FI REVIEW. **Kit $39.95. Wired $64.95.** Includes cover.

**New HF87 70-Watt Stereo Power Amplifier:** Dual 35W power amplifiers of the highest quality. Uses top-quality output transformers for undistorted response across the entire audio range **at full power** to provide utmost clarity on full orchestra & organ. IM distortion 1% at 70W, harmonic distortion less than 1% from 20 to 20,000 cps within 1 db of 70W. Ultra-linear connected EL34 output stages & surgistor-protected silicon diode rectifier power supply. Selector switch chooses mono or stereo service; 4, 8, 16, and 32 ohm speaker taps, input level controls; basic sensitivity 0.38 volts. Without exaggeration, one of the very finest stereo amplifiers available regardless of price. Use with self-powered stereo preamplifier-control unit (HF85 recommended). **Kit $74.95. Wired $114.95.**

**HF86 28W Stereo Power Amplifier Kit $43.95. Wired $74.95.**

**FM Tuner HFT90:** Prewired, prealigned, temperature-compensated "front end" is drift-free. Prewired exclusive precision **eye-tronic®** traveling tuning indicator. Sensitivity: 1.5 uv for 20 db quieting; 2.5 uv for 30 db quieting, full limiting from 25 uv. IF bandwidth 260 kc at 6 db points. Both cathode follower & FM-multiplex stereo outputs, prevent obsolescence. Very low distortion. **"One of the best buys in high fidelity kits."** — AUDIOCRAFT. **Kit $39.95*. Wired $65.95*. Cover $3.95.** *Less cover, F.E.T. Incl.

**New AM Tuner HFT94.** Matches HFT90. Selects "hi-fi" wide (20c – 9kc @ –3 db) or weak-station narrow (20c – 5kc @ –3 db) bandpass. Tuned RF stage for high selectivity & sensitivity; precision **eye-tronic®** tuning. **Kit $39.95. Wired $65.95** Incl. Cover & F.E.T.

**New FM/AM Tuner HFT92** combines the renowned EICO HFT90 FM Tuner with excellent AM tuning facilities. **Kit $59.95. Wired $94.95.** Includes cover & F.E.T.

**New AF-4 Stereo Amplifier** provides clean 4W per channel or 8W total output. Inputs for ceramic/crystal stereo pick-ups, AM-FM stereo, FM-multi stereo. 6-position stereo/mono selector. Clutch-concentric level & tone controls. Use with a pair of HFS-5 Speaker Systems for good quality, low-cost stereo. **Kit $38.95. Wired $64.95.**

**HF12 Mono Integrated Amplifier** provides complete "front-end" facilities and true high fidelity performance. Inputs for phono, tape head, TV, tuner and crystal/ceramic cartridge. Preferred variable crossover, feedback type tone control circuit. Highly stable Williamson-type power amplifier circuit. Power output: 12W continuous, 25W peak. **Kit $34.95. Wired $57.95.** Includes cover.

**New HFS3 3-Way Speaker System Semi-Kit** complete with factory-built ¾" veneered plywood (4 sides) cabinet. Bellows-suspension, full-inch excursion 12" woofer (22 cps res.), 8" mid-range speaker with high internal damping cone for smooth response, 3½" cone tweeter. 2¼ cu. ft. ducted-port enclosure. System Q of ½ for smoothest frequency & best transient response. 32-14,000 cps clean, useful response. 16 ohms impedance. HWD: 26½", 13⅜",14⅜". Unfinished birch **$72.50.** Walnut, mahogany or teak **$87.50.**

**New HFS5 2-Way Speaker System Semi-Kit** complete with factory-built ¾" veneered plywood (4 sides) cabinet. Bellows-suspension, ⅝" excursion, 8" woofer (45 cps res.), & 3½" cone tweeter. 1¼ cu. ft. ducted-port enclosure. System Q of ½ for smoothest frequency & best transient response. 45-14,000 cps clean, useful response. HWD: 24", 12½", 10½". Unfinished birch **$47.50.** Walnut, mahogany or teak **$59.50.**

**HFS1 Bookshelf Speaker System** complete with factory-built cabinet. Jensen 8" woofer, matching Jensen compression-driver exponential horn tweeter. Smooth clean bass; crisp extended highs. 70-12,000 cps range. 8 ohms. HWD: 23" x 11" x 9". Price **$39.95.**

**HFS2 Omni-Directional Speaker System** (not illus.) HWD: 36", 15¼", 11½". **"Eminently musical"** — HIGH FIDELITY. **"Fine for stereo"** — MODERN HI-FI. Completely factory- built. Mahogany or walnut **$139.95.** Blond **$144.95.**

**IMPORTANT NOTE:** All EICO kits built according to our instructions, and all EICO factory-assembled equipment, conform to the high standards and specifications as published in EICO literature and advertisements. All EICO factory-assembled equipment is completely and meticulously hand-wired throughout — no printed circuitry; each factory-assembled unit is 100% final-tested throughout for each feature and function — no "spot" or "partial" checking. In EICO's final-test techniques, nothing is left to chance.

**Fill out coupon on next page for FREE CATALOG.**
Ask your dealer about EICO's exclusive 90 STEREO RECORD BONUS

Copyright 1960 by Electronic Instr. Co., Inc. 33-00 N. Blvd., L. I. C. 1, N. Y.

# The specs prove it...your best buy is EICO®



A
**DYNAMIC CONDUCTANCE TUBE & TRANSISTOR TESTER #666**
**KIT $69.95 WIRED $109.95**
**Complete with steel cover & handle**

B
**TV-FM SWEEP GENERATOR AND MARKER #368**
**KIT $69.95 WIRED $119.95**

C
**RF SIGNAL GENERATOR #324**
**KIT $26.95 WIRED $39.95**

D
**PEAK-TO-PEAK VTVM #232 & UNIPROBE (pat. pend)**
**KIT $29.95**
**WIRED $49.95**

E
**COLOR & MONOCHROME DC TO 5 MC LAB & TV 5" OSCILLOSCOPE #460**
**KIT $79.95 WIRED $129.50**
**5" PUSH-PULL Oscilloscope #425: Kit $44.95 Wired $79.95**

**A** **Tests all receiving tubes** (picture tubes with adapter), n-p-n and p-n-p transistors. Composite indication of Gm, Gp & peak emission. Simultaneous selection of any one of 4 combinations of 3 plate voltages, 3 screen voltages, 3 ranges of continuously variable grid voltage (with 5% accurate pot.). Sensitive 200 ua meter. 10 six-position lever switches: freepoint connection of each tube pin. 10 pushbuttons: rapid insert of any tube element in leakage test circuit. Direct reading of inter-element leakage in ohms. New gear-driven rollchart. **CRA Adapter $4.50.**

**B** **Entirely electronic** sweep circuit with accurately-biased increductor for excellent linearity. Extremely flat RF output. Exceptional tuning accuracy. Hum and leakage eliminated. 5 fund. sweep ranges: 3-216 mc. Variable marker range: 2-75 mc in 3 fund. bands, 60-225 mc on harmonic band. 4.5 xtal marker osc., xtal supplied. Ext. marker provision. Attenuators: Marker Size, RF Fine, RF Coarse (4-step decade). Narrow range phasing control for accurate alignment.

**C** **150 kc to 435 mc with ONE generator** in 6 fund. bands and 1 harmonic band! ±1.5% freq. accuracy. Colpitts RF osc. directly plate-modulated by K-follower for improved mod. Variable depth of int. mod. 0-50% by 400 cps Colpitts osc. Variable gain ext. mod. amplifier: only 3.0 v needed for 30% mod. Turret-mounted, slug-tuned coils for max. accuracy. Fine and Coarse (3-step) RF attenuators. RF output 100,000 uv, AF output to 10 v.

**D** **Uni-Probe — exclusive with EICO** — only 1 probe performs all functions: half-turn of probe tip selects DC or AC-Ohms. Calibration without removing from cabinet. Measure directly p-p voltage of complex & sine waves: 0-4, 14, 42, 140, 420, 1400, 4200. DC/RMS sine volts: 0-1.5, 5, 15, 50, 150, 500, 1500 (up to 30,000 v. with HVP probe, & 250 mc with PRF probe). Ohms: 0.2 ohms to 1000 megs. 4½" meter, can't-burn-out circuit. 7 non-skip ranges on every function. Zero center.

**E** **Features DC amplifiers!** Flat from DC to 4.5 mc, usable to 10 mc. Vert. Sens.: 25 mv/in.; input Z 3 megs; direct-coupled & push-pull throughout. 4-step freq.-compensated attenuator up to 1000:1. Sweep: perfectly linear 10 cps — 100 kc (ext. cap. for range to 1 cps). Pre-set TV V & H positions. Auto sync. lim. & ampl. Direct or cap. coupling; bal. or unbal. inputs; edge-lit engraved lucite screen with dimmer control; plus many more outstanding features.

**FREE CATALOG shows you HOW TO SAVE 50% on 65 models of top quality professional test equipment. MAIL COUPON NOW!**

**New Transistor Portable Radio RA-6**
**Kit $29.95**
**Wired $49.95**
Incl. F.E.T.; less 9V batt. Prealigned RF, IF xfmrs; push-pull audio; 6" spkr.

*PAT. PEND.

**NEW Power & Bias Supply for Transistorized Eqpt. #1020 •**
**Kit $19.95**
**Wired $27.95**

**NEW Tube & CRT Fil. Tester #612**
**Kit $3.95**
**Wired $5.95**
Fast-checks radio/TV tubes, pilot lamps, etc.



**Series/Parallel R-C Combination Box #1140**
**Kit $13.95**
**Wired $19.95**

**Tube Tester #625**
**Kit $34.95**
**Wired $49.95**
• tests 600 mil series string type tubes
• illuminated roll-chart
**Pix Tube Test Adapter..... $4.50**

**6V & 12V Battery Eliminator & Charger #1050**
**Kit $29.95**
**Wired $38.95**
Extra-filtered for transistor equipt. **#1060 Kit $38.95 Wired $47.95**

**20,000 Ohms/Volt V-O-M #565**
**Kit $24.95**
**Wired $29.95**
**1000 Ohms/Volt V-O-M #536**
**Kit $12.90**
**Wired $14.90**

EICO®
33-00 Northern Blvd. L.I.C. 1, N.Y.
Add 5% in the West. © 1959
TURN PAGE FOR MORE EICO VALUES

**R-C Bridge & R-C-L Comparator #950B**
**Kit $19.95**
**Wired $29.95**
Reads 0.5 ohms-500 megs, 10 mmfd-5000 mfd, power factor

**VTVM Probes**

| | Kit | Wired |
|---|---|---|
| Peak-to-Peak | $4.95 | $6.95 |
| RF | $3.75 | $4.95 |
| High Voltage Probe-1 | | $6.95 |
| High Voltage Probe-2 | | $4.95 |
| **Scope Probes** | | |
| Demodulator | $3.75 | $5.75 |
| Direct | $2.75 | $3.95 |
| Low Capacity | $3.75 | $5.75 |

EICO EW-2
33-00 Northern Blvd.
L.I.C. 1, N.Y.

Show me HOW TO SAVE 50% on ☐ Test Instruments ☐ Hi-Fi ☐ Ham Gear. ☐ Send free Stereo Hi-Fi Guide. Send me FREE Catalog, name of neighborhood dealer.

Name.....
Address.....
City..... Zone..... State.....

SEE OUR OTHER ADVERTISEMENT ON PAGE 100

**Selecting and using a radio unit for Class D service. Complete listing of available equipment and important specs are included.**

# CITIZENS RADIO DIRECTORY

EVER SINCE the FCC established the Class D Citizens Radio Service in September, 1958, interest and activity in this new service has been growing by leaps and bounds. An article "Build This Citizens Band Transceiver" in our March, 1959 issue started the ball rolling for many hundreds of our readers, and for several equipment manufacturers as well, who wanted to get some gear operating on the new Citizens Band. A recent check with the FCC revealed that over 70,000 Citizens Radio authorizations have been granted, and applications are still coming in at the rate of over 8000 each month. By far the majority of these have been for Class D equipment. What is more, there are now over 48 manufacturers of this type of equipment

## What It Is

The advantage of the new Class D service is that no operator's license or license examination is required. The radio equipment must be licensed, however, but this is usually no more than a mere formality. The user need only fill out a simple form describing the intended use of the equipment, certifying that it meets the technical requirements, and indicating that he is familiar with the rules. The form is mailed to the FCC, Washington, D. C., which then acts on each application in turn. Because of the large number of authorizations being handled, there is usually a time delay of around 60 days before the authorization and call letters are issued.

Twenty-three channels have been assigned between 26.965 and 27.255 mc., which is the old 11-meter amateur band. Stations must use voice modulation only, and AM must be employed. A power limit of 5 watts (final amplifier plate input power) has been set for the transmitter.

## Uses and Abuses

The Citizens Radio Service is intended for "private short-distance radio communications for personal or business use, limited to the minimum practicable transmission time." Citizens Radio units are now being used by business organizations to communicate with delivery trucks. TV service shops, department stores, laundries, dairies, and others can re-route their technicians or delivery men as required. Foremen in industrial plants or on construction projects can communicate with their workers even with considerable distance separating them. Farmers and ranchers can use Citizens Radio units to communicate with tractors, trucks, and other mobile units on the farm or ranch. Doctors and nurses may be paged directly in their cars with this equipment.

Citizen-users are installing units on pleasure boats in order to communicate with shore, with a nearby marina, and with other boats. Units have also been used on com-

Ray Jefferson Model 905 transceiver, manufactured by Ray Jefferson, Inc. Power requirements: 117 volts a.c. at 30 watts; other models available for 12 volts d.c. at 2.5 amps. or for 6 volts d.c. at 5 amps. Receiver: tunable superregenerative type with r.f. stage. Transmitter: 5-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with single crystal for single-channel operation. Cabinet dimensions: 8⅛" x 6¾" x 8½"; weight: 12 lbs. Price: $99.50, including carbon microphone.

Utica "Town and Country" Model PT27 transceiver, manufactured by Utica Communications Corp. Power requirements: 117 volts a.c., 6 volts d.c., or 12 volts d.c. Receiver: single-channel fixed-tuned crystal-controlled superhet type with r.f. stage and two i.f. stages; noise limiter and squelch circuits are provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Price: $159.50, including microphone.

Polytronics "Poly-Comm" PC-1 transceiver, manufactured by Polytronics Lab., Inc. Power requirements: 117 volts a.c. or 6 volts d.c.; also available for 117 volts a.c. or 12 volts d.c. Receiver: 4-channel fixed-tuned crystal-controlled dual-conversion superhet type with r.f. amplifier and three i.f. stages; noise limiter and squelch circuits are provided. Transmitter: 4-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with one set of crystals for single-channel operation. Cabinet dimensions: 11" x 5" x 7½"; weight: 12¾ lbs. Price: $159.50, including carbon microphone.



Morrow Model 5W3 transmitter-receiver unit, manufactured by Morrow Radio Mfg. Co. Power requirements: 117 volts a.c. at 60 watts; models also available for 6 volts d.c. at 8 amps. or for 12 volts d.c. at 4 amps. Receiver: 3-channel fixed-tuned crystal-controlled superhet type with r.f. amplifier and i.f. stage; noise limiter and squelch circuits are provided. Transmitter: 3-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with one set of crystals for single-channel operation. Cabinet dimensions: 9¼" x 4¾" x 8¾"; weight: 10½ lbs. Price: $179.50, including carbon microphone. (Note: Single-channel unit also available as Model 5W1 at $169.50.)

Apelco Model AR-9 transceiver, manufactured by Applied Electronics Co., Inc. Power requirements: 117 v. a.c. at 50 watts; also available for 12 volts d.c. at 5 amps. and 32 volts d.c. at 2.3 amps. Receiver: 5-channel fixed-tuned crystal-controlled superhet type with r.f. and i.f. stages; noise limiter and squelch circuits are provided. Transmitter: 5-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with one set of crystals for single-channel operation. Cabinet dimensions: 9½" x 5¼" x 11½"; weight: 18 lbs. Price: $169.50, including carbon microphone.



Chickasha Model 1000-D transceiver, manufactured by Chickasha Electronics Inc. Power requirements: 117 v. a.c. at 35 watts, 6 volts d.c. at 7 amps., or 12 volts d.c. at 4 amps. Receiver: tunable superhet type with r.f. stage and i.f. stage; noise limiter and squelch circuits are provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 12" x 7" x 6⅝". Price: $59.95 in kit form or $79.95 wired, with microphone.

Chickasha "Custom Dispatcher" transceiver, manufactured by Chickasha Electronics Inc. Power requirements: 117 volts a.c. at 35 watts, 6 volts d.c. at 7 amps., or 12 volts d.c. at 4 amps. Receiver: single-channel fixed-tuned crystal-controlled superhet type with r.f. stage and i.f. stage; noise limiter and squelch circuits are provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 12" x 7" x 6⅝". Price: $69.95 in kit form or $89.95 wired, including microphone.

mercial craft on rivers and in harbors. Explorers and sportsmen have been using units to keep in touch with each other. Equipment may be used where regular communication facilities are not available or when wire facilities break down in an emergency.

Although there are many legitimate uses for the Citizens Radio Service, there have been some users who have gone overboard. Some look on the new service as an easy way to get on the air and have their own broadcasting stations. Space in the radio spectrum is far too valuable to be wasted by even a few capricious individuals who just want to "talk on the radio." If there is a real purpose for the communication, then personal use is perfectly in order. But just talking about the weather or a forthcoming social activity is taboo.

Then there are a few disgruntled amateurs who feel that the 11-meter band is still theirs, except with a limit on transmitter power. As a group, the hams have made many valuable contributions to radio communication, and many have worked hard to get the kind of amateur licenses they hold. Although we are very much opposed to the loss of any of the amateur frequencies, the fact of the matter is that 11 meters is simply not a ham band any more, and it must not be used as such. The calling of "CQ," attempts to work DX, or as many stations as possible are not permitted.

One good reason for the abuses is that the service is still fairly new and many of its users have not really learned its purpose. We feel that once it becomes clearly understood just what can and what cannot be done on the band, there will be a minimum number of rule violators.

Because of the fairly large number of rule violations at present, the FCC has been issuing quite a few violation notices. Being unable to answer some of these may result in loss of license. More serious violations may even carry fines or imprisonment.

## COVER STORY

THIS MONTH'S COVER shows a number of representative examples of Class D Citizens Band transceiver units. Many of the important specifications of these transceivers are included in the following paragraphs. Note that each unit has been identified with a letter, and the description is keyed to the identifying letter.

(Photo by Bob Loeb)




**A** Heathkit Model CB-1 transceiver, manufactured by Heath Co. Power requirements: 117 volts a.c. at 35 watts; separate power supply needed for 6- or 12-volt battery operation. Receiver: tunable superregenerative type with r.f. stage. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 9¾ x 8" x 6"; weight: 10 lbs. Price: $42.95 in kit form or $60.95 wired, including ceramic microphone.

**B** Johnson "Viking Messenger" transceiver, manufactured by E. F. Johnson Co. Also distributed by General Electric Co. Power requirements: 117 volts a.c. or 12 volts d.c.; also available for 117 volts a.c. or 6 volts d.c., and for 117 volts a.c. only. Receiver: 5-channel fixed-tuned crystal-controlled superhet type with r.f. stage and single i.f. stage; noise limiter and squelch circuits are provided. Transmitter: 5-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with one set of crystals for single-channel operation. Cabinet dimensions: 7" x 5⅝" x 11⅜". Price: $139.75, including ceramic microphone.

**C** Knight-Kit "Custom" Model C-27 transceiver, manufactured by Allied Radio Corp. Power requirements: 117 volts a.c.; separate power supply needed for 6- or 12-volt battery operation. Receiver: tunable or single-channel fixed-tuned crystal-controlled dual-conversion superhet with r.f. amplifier and two i.f. stages; noise limiter and squelch circuits are provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 12" x 5" x 12"; weight: 20 lbs. Price: $79.95 in kit form, including speaker-microphone.

**D** RME Model 4303 transceiver, manufactured by Radio Manufacturing Engineers, Inc. (division of Electro-Voice, Inc.). Power requirements: two self-contained 6-volt batteries. Receiver: tunable transistorized superhet with two i.f. stages. Transmitter: single-channel crystal-controlled transistorized type with 90 milliwatts oscillator input power. Cabinet dimensions: 9½" x 3¼" x 1⅞"; weight: ¾ lb. Price: $99.50, including speaker-microphone and built-in antenna.

**E** Vocaline "Commaire" Model ED-27 transceiver, manufactured by Vocaline Co. of America, Inc. Power requirements: 117 volts a.c. at 48 watts or 12 volts d.c. at 4.5 amps.; also available for 117 volts a.c. or 6 volts d.c. at 9 amps. Built-in transistor power supply is used with d.c. supply. Receiver: single-channel fixed-tuned crystal-controlled dual-conversion superhet type with r.f. amplifier and i.f. amplifier stages; noise limiter and squelch circuits are provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 9¼" x 5¼" x 8¼"; weight: 11 lbs. Price: $179.50, including ceramic microphone.

**F** EICO Model 760 transceiver, manufactured by Electronic Instr. Co., Inc. Power requirements: 117 volts a.c. at 60 watts; also available for 117 volts a.c. or 6 volts d.c. at 9 amps and for 117 volts a.c. or 12 volts d.c. at 4 amps. Receiver: tunable superhet type with r.f. amplifier and two i.f. stages; noise limiter circuit is provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 8½" x 6" x 9"; weight: 12 lbs. Price: $59.95 in kit form, including ceramic microphone. Also available factory-wired.

**G** RCA "Radio-Phone Deluxe" type CRM-P2B transceiver, manufactured by RCA Industrial Electronic Products. Power requirements: 117 volts a.c. at 40 watts or 12 volts d.c. at 3.4 amps.; also available for 117 volts a.c. or 6 volts d.c. at 6.8 amps. Receiver: tunable or single-channel fixed-tuned crystal-controlled superhet type with r.f. stage and two i.f. stages; noise limiter and squelch circuits (optional accessory) are provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate power input. Cabinet dimensions: 7" x 9" x 5"; weight: 8 lbs. Price: $159.95, including speaker-microphone.

**H** Globe Electronics "Citizens Broadcaster" CB-100 transceiver, manufactured by Globe Electronics, Inc. Power requirements: 117 volts a.c. at 60 watts or 12 volts d.c. at 5 amps.; separate converter required for 6-volt d.c. operation. Receiver: 3-channel fixed-tuned crystal-controlled superhet type with r.f. amplifier and two i.f. stages; noise limiter and squelch circuits are provided. Transmitter: 3-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with one set of crystals for single-channel operation. Cabinet dimensions: 13" x 3½" x 10½"; weight: 13 lbs. Price: $129.95, including ceramic microphone.

## What About Range?

The prospective user of a Citizens Radio unit is sure to want to know just how much range he can get from the equipment he is going to buy or build. The question of how much distance can be covered cannot be answered simply. It depends on many factors, including transmitter power, type and location of the antenna, sensitivity of the receiver, and type of terrain.

Just about all Citizens Radio transmitters are operated with close to the maximum legal limit of 5 watts final input power. The power specified is actually d.c. plate input power to the final power amplifier. It is calculated by multiplying the plate voltage by the plate current. This does not mean that there will be 5 watts of r.f. power applied to the transmitting antenna. Some output circuits are less efficient than others so that in some cases only 1 watt or less of r.f. is available. With more efficient output circuits, as much as 3 or more watts of r.f. is produced. With a short, properly matched transmission line to the antenna, just about all this r.f. is applied to the antenna. But if the transmission line is long or is not properly matched, then only a portion of this power actually gets into the antenna to radiate a useful signal.

A far more important factor in getting long-distance coverage is the type and location of the antenna. Only one antenna is required per unit, since this antenna is switched from transmitter to receiver as required. A quarter-wave antenna for 27 mc. must be 8⅔-feet (nominally 9 feet) long, while a half-wave type is twice this length. Because such lengths are inconvenient for mobile use, it is common to use shorter whip antennas. These have loading coils inserted in them to increase their length electrically. Such loaded antennas are usually not as efficient in radiating a signal as antennas having the full quarter or half wavelength.

The matter of antenna location is very important. Very little signal will be radiated (or received) if the antenna is inside a house or inside a car. Much better performance will be obtained by a window, or better still, a roof mount-



Knight-Kit "Standard" Model C-11 transceiver, manufactured by Allied Radio Corp. Power requirements: 117 volts a.c.; separate power supply needed for 6- or 12-volt battery operation. Receiver: tunable superregenerative type with r.f. stage. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 10" x 6" x 8"; weight: 10 lbs. Price: $39.95 in kit form, including microphone. (Another Knight-Kit model appears in our cover story.)

Gonset "Citizens' Communicator" Model G-11 transceiver, manufactured by Gonset Div., Young Spring & Wire Corp. Power requirements: 12 volts d.c.; models also available for 6 volts d.c. or 117 volts a.c. Receiver: single-channel fixed-tuned crystal-controlled superhet type with r.f. stage and two i.f. stages; noise limiter and squelch circuits are provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 6¾" x 5¼" x 6¾"; weight: 10 lbs. Price: $124.50, including microphone.

Gonset "Citizens' Communicator" Model G-12 transceiver, manufactured by Gonset Div., Young Spring & Wire Corp. Power requirements: 117 volts a.c. or 12 volts d.c. Receiver: 4-channel fixed-tuned crystal-controlled superhet type with r.f. stage; noise limiter and squelch circuits provided. Transmitter: 4-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with one set of crystals for single-channel operation. Cabinet dimensions: 7" x 4½" x 10"; weight: 11 lbs. Price: $149.95, including microphone.

Multi-Elmac "Citi-fone" CD-5 transceiver, manufactured by Multi-Products Co. Power requirements: 117 volts a.c. at 30 watts or 6 volts d.c. at 5 amps.; also available for 117 volts a.c. or 12 volts d.c. at 2.5 amps. Receiver: 5-channel fixed-tuned crystal-controlled superhet type with r.f. amplifier and two i.f. stages; noise limiter and squelch circuits are provided. Transmitter: 5-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with one set of crystals for single-channel operation. Cabinet dimensions: 8" x 4¼" x 11"; weight: 12 lbs. Price: $124.50, including ceramic microphone.



International Model KB-1 transceiver, manufactured by International Crystal Mfg. Co., Inc. Power requirements: 117 volts a.c. at 60 watts; also available for 117 v. a.c., 6 volts d.c., or 12 volts d.c. Receiver: tunable crystal-controlled dual-conversion superhet type with r.f. stage and i.f. stage; noise limiter and squelch circuits are provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 8¾" x 6" x 10"; weight: 15 lbs. Price: $90 for a.c.-only model in pre-wired sub-assembly kit form.

EDCO "Unicom" 100-C transmitter-receiver unit, manufactured by Electronics Design Co. Power requirements: 117 volts a.c. at 100 watts; also available for 117 volts a.c., 6 volts d.c. at 16.7 amps., or 12 volts d.c. at 8.5 amps. Receiver: single-channel fixed-tuned crystal-controlled superhet type with r.f. amplifier and two i.f. stages; noise limiter and squelch circuits are provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 11¼" x 10½" x 9½"; weight: 15 lbs. Price: $235.00 for the a.c.-only model.

International "Executive" transceiver, manufactured by International Crystal Mfg. Co., Inc. Power requirements: 117 volts a.c., 6 volts d.c., or 12 volts d.c. Receiver: tunable or two-channel crystal controlled dual conversion superhet type with r.f. stage and i.f. stage; squelch circuits and noise limiter are provided. Transmitter: 3-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with single transmitter crystal. Cabinet dimensions: 8½" x 5½" x 9½"; weight: 12 lbs. Price: $169.95.

Raytheon "Raycon" transceiver, manufactured by Raytheon Co. Power requirements: 117 volts a.c. at 50 watts; also available for 12 volts d.c. at 5 amp. and 32 volts d.c. at 2.3 amps. Receiver: 5-channel fixed-tuned crystal-controlled superhet with r.f. and i.f. stage; noise limiter and squelch circuits are provided. Transmitter: 5-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 9½" x 5¼" x 11½"; weight: 18 lbs. Price: $179.50, including carbon microphone.



Transpace Model C-27A transceiver, manufactured by Transpace, Inc. Power requirements: 117 volts a.c. at 60 watts; adapters available for 6 volts d.c. at 9 amps. or for 12 volts d.c. at 4.5 amps. Receiver: 6-channel fixed-tuned crystal-controlled superhet with r.f. stage and two i.f. stages; noise limiter and squelch circuits are provided. Transmitter: 6-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with one set of crystals for single-channel operation. Cabinet dimensions: 10⅛" x 4¼" x 9"; weight: 11 lbs. Price: $169.50, including ceramic microphone.



Tecraft "Falcon" transceiver, manufactured by Tecraft Sales Corp. Power requirements: 117 volts a.c., 6 volts d.c., or 12 volts d.c. Receiver: tunable or single-channel fixed-tuned crystal-controlled dual-conversion superhet type; noise limiter and squelch circuits are provided. Transmitter: 2-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 13" x 4⅝" x 9⅝". Price: $144.95, including microphone.



Shell Model CB-12 transceiver, manufactured by Shell Electronics Mfg. Corp. Power requirements: 117 volts a.c. at 37 watts or 12 volts d.c.; also available for 117 volts a.c. or 6 volts d.c. Receiver: tunable superregenerative type with r.f. stage. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 11½" x 4⅜" x 6¼"; wt.: 7½ lbs. Price: $79.95.

Regency Model CB-27 transceiver, manufactured by Regency Div., Industrial Development Engineering Associates, Inc. Power requirements: 117 volts a.c. at 50 watts; also available for 12 volts d.c. Receiver: tunable dual-conversion superhet with one oscillator crystal-controlled; noise limiter and squelch circuits are provided. Transmitter: 2-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with one set of crystals for single-channel transmitter operation. Cabinet dimensions: 8¾" x 4½" x 6½"; weight: 9 lbs. Price: $124.95, including ceramic microphone.

ing on a house and a bumper or fender mounting on a car. The higher the antenna can be mounted, the greater will be the range covered. It is important that the antenna be no more than 20 feet above the structure on which it is mounted to meet one of the legal requirements for Citizens Band operation. Naturally, a mobile unit in a car parked in a valley would have far less effective range than the same unit would have when the car is atop a high hill. Antennas may also be mounted on towers or poles in order to increase range. Under these conditions, though, the antenna must not exceed the height of the tower. It is also possible to increase range considerably by the use of highly directional antenna arrays.

The characteristics of the receiver are also important in determining range. The more sensitive the receiver is, the greater the distance it will be able to pick up a signal of given strength. Highly selective receivers, although they do not actually increase the coverage range, make it easier to work with a signal that is interfered with by other signals on adjacent channels.

Finally, the type of surrounding terrain is important in determining range. Dense, heavily wooded areas tend to absorb r.f. energy and reduce effective range. On the other hand, clear open fields, or better still, a large body of water, will provide extended coverage.

All in all, a reliable range of 5 to 10 miles can be expected under fairly normal conditions. When communications are tried between two mobile units using short antennas, coverage of about 2 to 3 miles is usual. On the other

(*Continued on page* 139)

## CITIZENS RADIO MANUFACTURERS

**ACTON LABORATORIES, INC.**, 533 Main Street, Acton, Massachusetts
**ALLIED RADIO CORP.**, 100 N. Western Avenue, Chicago 80, Illinois
**APPLIED ELECTRONICS CO., INC.** (APELCO), 213 E. Grand Avenue, South San Francisco, California
**ARKAY**, 88-06 Van Wyck Expressway, Richmond Hill 18, New York
**CHICKASHA ELECTRONICS, INC.**, 828 Choctaw Avenue, Chickasha, Oklahoma
**CITIZENS ELECTRONICS**, P. O. Box 443, Laurelton, N. J.
**DIXON ELECTRONICS**, 13444 W. McNichols, Detroit 35, Mich.
**DUNLAP ELECTRONICS, INC.**, 764 Ninth Street, Des Moines 14, Iowa
**ELECTRONIC INSTRUMENT CO., INC.** (EICO), 33-00 Northern Blvd., L.I.C. 1, N. Y.
**ELECTRONICS DESIGN CO.**, 400 E. Cornell Street, Enid, Oklahoma
**ESSCO C-B HEADQUARTERS**, 58 Walker St., New York 13, N. Y.
**GLOBE ELECTRONICS, INC.**, Div. of Textron Electronics, Inc., 22-30 South 34th Street, Council Bluffs, Iowa
**GONSET DIV.**, Young Spring & Wire Corp., 801 South Main Street, Burbank, California
**GROVE ELECTRONIC MFG. CO.**, 4103 W. Belmont Avenue, Chicago 41, Illinois
**HALLICRAFTERS**, 4401 W. Fifth Ave., Chicago 24, Ill.
**HEATH COMPANY**, Benton Harbor 15, Michigan
**HERSHEL RADIO CO.**, 5249 Grand River, Detroit 8, Mich.
**INTERNATIONAL CRYSTAL MFG. CO., INC.**, 18 N. Lee, Oklahoma City, Oklahoma
**JOHNSON, E. F. CO.**, Waseca, Minnesota
**KAAR ENGINEERING CORP.**, 2995 Middlefield Road, Palo Alto, California
**KAY-TOWNES ANTENNA CO.**, Box 593, Rome, Georgia
**LAFAYETTE RADIO**, 165-08 Liberty Avenue, Jamaica 33, New York
**LAKELAND ELECTRONICS**, Warsaw, Indiana
**MAXWELL ELECTRONICS CORP.**, 229 Garvon Street, Garland, Texas
**MORROW RADIO MFG. CO.**, 2794 Market Street, N.E., Salem, Oregon
**MULTI-PRODUCTS CO.**, 21470 Coolidge Highway, Oak Park 37, Mich.
**NUNAMAKER ELECTRONICS**, 918 Sixth St., Portsmouth, Ohio
**PEARCE-SIMPSON, INC.**, 2295 N.W. 14th Street, Miami, Florida
**PHILMORE MFG. CO., INC.**, 130-01 Jamaica Avenue, Richmond Hill 18, New York
**POLYTRONICS LAB., INC.**, 253 Crooks Avenue, Clifton, New Jersey
**RADIO CORP. OF AMERICA**, Radiomarine Products, Camden, New Jersey
**RADIO MANUFACTURING ENGINEERS, INC.**, Div. of Electro-Voice, Inc., Washington, Illinois
**RADIO SHACK CORP.**, 167 Washington Street, Boston 8, Massachusetts
**RADSON ENGINEERING CORP.**, Macon, Illinois
**RAY JEFFERSON, INC.**, 40 East Merrick Road, Freeport, L. I., N. Y.
**RAYTHEON MANUFACTURING CO.**, Waltham 54, Massachusetts
**REGENCY DIV.**, I.D.E.A. Inc., 7900 Pendleton Pike, Indianapolis 26, Indiana
**SHELL ELECTRONICS MFG. CORP.**, 112 State Street, Westbury, L. I., New York
**SPRINGFIELD ENTERPRISES** (also ELCOLAB), P. O. Box 54, Springfield Gardens 13, New York
**TECRAFT SALES CORP.**, Box 116, River Edge, New Jersey
**TRANSPACE, INC.**, 12902 Foothill Blvd, San Fernando, California
**U. S. ELECTRONICS**, 7400 Jackson, Birmingham, Mich.
**UTICA COMMUNICATIONS CORP.**, 19 S. LaSalle Street, Chicago 3, Illinois
**VANGUARD ELECTRONIC LABS**, Box 12, Hollis 23, N. Y.
**VOCALINE CO. OF AMERICA, INC.**, Old Saybrook, Connecticut
**WESTERN RADIO**, Kearney, Nebraska
**WIGHTMAN ELECTRONIC ENGINEERING CO.**, Easton, Maryland
**WORLD RADIO LABORATORIES**, 3415 W. Broadway, Council Bluffs, Iowa

# Radio Service for TV Technicians

By **KENNETH BRAMHAM**

VOLUMES have been written on the subject of TV servicing for the radio technician. The assumption is that the beginning TV service technician is first experienced in radio repairing, and is familiar with radio circuitry.

The trend in recent years, however, has been towards TV servicing itself as the primary field. As a result, we now have what might be described as a new generation of practical TV technicians, with little or no radio experience. For this growing number, a few hints on radio servicing and a comparison with TV work will be useful.

While a component failure causing trouble in a radio may be identical with a familiar TV fault, the effect can be quite different. Take the case of an open filter capacitor as an example: decreased width, poor sync, 60-cycle hum in the audio, and shading in the picture are all possible and familiar symptoms to the TV technician. In radio servicing, only the 60-cycle hum is possible. There are, however, other related effects. The lack of width in TV would be caused by reduced "B+" voltage—a comparable result in radio work would be reduced output, or no output if the voltage falls below the minimum needed by the "front-end" oscillator. Poor sync due to feedback along the unfiltered "B+" line compares, in radio work, with audible oscillation or "motorboating" arising from the same type of defect.

The very simple "B+" filtering used in small radios makes servicing relatively easy, with the most useful service instrument being a 10-μf. electrolytic capacitor, with good stiff leads, used to bridge out each filter capacitor section in turn. The usual electrolytic capacitor combination is made up of two "B+" filters, the smaller of the two being used at the rectifier or input end of the network, and a lower-rated cathode bypass capacitor, used in the power output stage. Thus it is possible that, while bridging a capacitor may indicate an open condition, the real trouble may be leakage between sections of the multiple unit. In either event, a complete multiple-electrolytic unit should be replaced when one section appears defective in preference to installing a replacement across the one section only.

Oscillation and motorboating are also caused by regeneration other than that of feedback on an inadequately filtered "B+" line. The most frequent offender is an open screen bypass capacitor, which allows an individual stage to oscillate. Again the technique of bridging out individual capacitors (with one known to be good) may be used. Alternatively the grid of each successive stage may be shorted out until the offending stage is located. Then the bypass capacitor in this stage may be bridged out as a final localization check.

Loss of contrast in TV compares in radio servicing with a loss of gain and sensitivity arising from comparable component failures. The most obvious cause of reduced gain is, of course, one or more weak tubes. Other causes are; reduced "B+" voltage, low plate or screen voltages, open coupling capacitors, and defective i.f. transformers. All of these defects are familiar from TV servicing. The major difference between these cases in radio and similar TV faults is that in radio, the available "B" supply current is lower and resistance values used are generally higher. Thus, even a dead short in a radio will seldom burn a resistor to the point where it is easily seen. A shorted screen bypass capacitor, for instance, may drop the screen voltage to zero without burning out the screen dropping resistor or seriously affecting the voltage available to other parts of the set. Fortunately, it takes very little time to check every plate and screen voltage in a small radio. It should be remembered, when checking these voltages, that a "B−" line is usually employed instead of the familiar negative chassis.

Perhaps the most useful "dodge" in radio servicing is that of signal tracing with a screwdriver or solder pick. Applying this "test instrument" to a grid should produce a click and 60-cycle hum in the speaker. Working from the output stage back to the r.f. section

(*Continued on page* 113)



Would you rather tackle a TV set than a simple table radio? Your technique may need a little polishing.

### Inside-Out Picture Tube

A radically new type of thin picture tube that promises increased brightness, detail, and compactness in military and commercial radar systems is under development by *RCA*. The experimental tube, known as a reflected-beam kinescope, has a viewing surface 21 inches in diameter and a total length of only 10 inches. The phosphor screen is over the curved rear inner surface instead of at the tube face. The electron beam approaches the transparent face of the tube, which acts as an "electron mirror" to reflect the beam back to the phosphor. The new tube can display TV pictures but with only one-quarter the efficiency of conventional TV picture tubes.

### Electronic Security System

Detection devices shown here are used with the new integrated building protection and security system introduced by *Minneapolis-Honeywell*. Included are fire and smoke detector heads, tamper-proof magnetic switches to windows, electronic noise and motion detectors, capacitance-type electronic fencing, and many others. Any of the devices can be tied in with the new system's centralized control console. In all instances of alarm, a guard at the console receives both an audible alarm (horn, buzzer, bell) and visual warning (push-button switch lights up).



# Recent Developments in Electronics



### Largest Solar Energy Converter

The world's largest solar energy converter, "Big Bertha," converts sunlight into electricity by means of over 7800 silicon solar cells, similar to those used to power instruments in U. S. earth satellites. "Big Bertha" was used recently for the first time to power a door-opening device during the dedication of the new $2-million *Hoffman* Semiconductor Center in El Monte, Calif. It has been installed permanently on the Center's roof to provide electricity for the Center's solar energy exhibits. The solar cells are attached to a 4- by 8-foot panel. An automatic tracking device keeps the panel faced toward the sun for maximum efficiency. Ten individual panels in the array can be connected in various combinations to provide 6 to 60 volts at currents from .5 to 5 amps.

### ◀ High Voltage for Satellites

A ferroelectric converter, developed by *ITT* laboratories, can produce high voltages directly from the warming power of the sun or other heat source. Unlike solar cells, which depend on light to produce low-voltage d.c., the converter relies on temperature changes alone to produce high-voltage a.c. by means of special ceramic coatings.

### Countermeasures Antennas

Advanced antennas which meet the extremely wide band requirements for electronic warfare weapons are shown below. These were displayed at the formal opening of a major addition to *Sylvania's* Electronic Defense Laboratories at Mountain View, Calif. Antennas having a 30:1 bandwidth have been built here. ▼



### Aircraft Identification System

New *General Instrument* device permits air traffic controller to pick out on radar screen any one "blip" within 200 miles and identify it exactly without communicating with plane's crew. Aircraft radar beacon sets up identifying numbers on indicator at right. ▼



### Power Generator Uses Rocket Exhaust ▶

This electronic system with no moving parts converts the heat of a rocket exhaust directly into electric power to run the steering controls and electronic equipment of the missile. System consists of *RCA* thermionic generator tube in the shape of a hollow cylinder which fits like a sleeve over the flame tube attached to a *Thiokol* solid-fuel rocket motor in a special test mount. Heat from the burning fuel is converted directly to electricity, which is carried through wire leads to measuring equipment used during tests.

# Room Acoustics for Stereo

## Part 2. Reverberation & Room Treatment

By **ABRAHAM B. COHEN** / Advanced Acoustics Corp.



**How the optimum room reverberation is obtained and room resonances are controlled by the use of standard decorative and special acoustic materials.**

ONE requirement for a good listening room is that it have the proper reverberation time—or liveliness—to simulate good concert hall conditions. Control of reverberation may be achieved by using standard home decorative materials and commercial sound absorbent tiles. By means of absorption tables covering architectural materials used in home construction, ordinary decorative materials, and commercially available acoustic tiles, it is fairly simple to calculate and "correct" a room to provide proper reverberation conditions.

### Reverberation

A room in which sound is to be produced or reproduced, whether live speech and music direct from the piano sounding board or reproduced sound from loudspeakers (monophonic or stereo), must meet certain acoustical conditions if the sound is to be heard properly. A good "listening" room should have correct reverberation properties and generate a minimum of multiple echoes.

Analytically, reverberation is a measure of how fast a room will cause sound to be reduced to a certain level *after* the source of sound has ceased to emit its signal, *providing* the sound has been fully built up in and has "saturated" the room before the source was stopped. We naively state that reverberation is the quality of "liveness" of a room (to sound) but what is the actual mechanism of room acoustics that leads to reverberation?

In Fig. 7A let the loudspeaker in the corner generate a constant-frequency and constant-amplitude sound. The wavefront emerging from the loudspeaker builds out in a spherical shell of constantly enlarging radius. As soon as that first wavefront reaches a reflecting surface, as at point P1 on wall A-B, the wavefront will be reflected. This reflection travels outward from the wall just as if there were an additional actual sound source at wall A-B. Again the sound from this new source travels out in ever-increasing spherical fronts until it hits another surface like wall D-C from which it will again be reflected as if there were another sound source at P2 on that wall. Thus these reflections will continue until there are a great number of these reflected rays travelling through the room, as shown in Fig. 7B, producing a generally diffused sound condition throughout the room—*as long as the source continues to operate.*

When the source of sound stops, the diffuse reflections do not stop immediately because the sound that has left the speaker has a finite speed of travel. The sound will keep reflecting in a completely random manner, each reflection being successively weaker than the preceding one. The more absorbent the walls, the less sound power gets reflected and the quicker the sound dies out. When the sound dies out slowly, there is little absorption within the room, and the room would be termed "highly reverberant."

Reverberation, then, is correlated with time—how fast does the sound die out? This is a measure of reverberation—"time." Consequently, "reverberation time" has been defined as the time (in seconds) that a steady-state sound in a room decreases to 1-millionth (1/1,000,000) of its original intensity (after the source has stopped). See Fig. 8. In easier terms, when the intensity of the sound, *after the source has stopped,* decreases by 60 db, the time it took to drop to this level is the reverberation time.

Now, just what sort of reverberation time period should one expect of a listening room, especially one intended for stereo listening? In Part 1 of this series we noted that perhaps a shorter reverberation time for stereo might be desirable since the very essence of stereo itself "psycho-enlarges" the room. This question of optimum reverberation time cannot be answered by complete specifications down to the last decimal place. It is a variable, depending on room or auditorium size and the type of program material being presented. Studies have shown that while an auditorium sounds right—has an accepted reverberation time—for a full symphony orchestra, it may not have the proper reverberation for chamber music or voice.

Many studies have been made of music rooms, auditoriums, concert halls, churches, and similar structures to determine the acceptable range of reverberation times and these figures have been generalized in Fig. 9. While it would be nice to have an instrument at home which would enable us to check the reverberation time of our listening room against this sort of




Fig. 7. When a sound source continues to operate, diffuse reflection builds up until the sound level reaches steady state.




Fig. 8. Reverberation time is the time, in seconds, taken for steady sound to be reduced to a millionth of its original level.

chart, such equipment is quite expensive (for home use) and requires an experienced professional hand at the controls. For such non-critical conditions in the home it is possible to calculate the reverberation time of any room by measuring its physical size and applying information from the charts and tables to be discussed shortly.

In very simple form, $T = .05V/A$, where $T$ is the reverberation time of the room (in seconds), $V$ is the volume of the room (in cubic feet), and $A$ is the *total* absorption of the room and its contents. $V$, the volume of the room, is no trouble to calculate. Total absorption may be judiciously estimated by reference to established tables which give the absorption coefficients of various materials used in the construction and decoration of the room. For purposes of this article, we must, of necessity, limit ourselves in listing absorption coefficients. What we will do is list the more common household materials which may affect the acoustic conditions of our listening room and then work with these.




Fig. 9. Optimum reverberation times.

Table 1 itemizes such common household materials while Fig. 10 illustrates, in chart form, the absorption characteristics, as a function of frequency, of some representative commercial materials available for acoustical correction purposes. It will be observed that, in general, the softer the material, the more it soaks up the sound.

Another interesting item to be observed from Table 1 is that a given material can be arranged so that its absorption characteristic may be varied. Velours, for example, when hung flat, have much less absorption *per unit area*, as shown in Fig. 11 than, if we drape or "bunch" a length of velour into an area one-half its flat length. As Table 1 indicates, we practically double the absorption. This, then, is a basic principle by which highly absorbent surfaces are obtained . . . "amplify" a given absorptive area by providing a dimension *in depth* for more absorption.

## Acoustical Tiles

Most of us are familiar with those off-white squares of "sound absorbent" material widely used on the ceilings of public buildings. Such materials are known as "tiles" in the trade. Fig. 13 shows some typical units of this type. The tiles are generally a foot square and may be obtained in several thicknesses—¾" being standard for home use. The tiles are made in a variety of materials and textures. Some are simply rough surfaces with "cracks" or fissures apparent on the surface while others are of the perforated variety, some with evenly spaced holes and some with randomly spaced perforations.

Although an inspection of Fig. 10 indicates that the absorption characteristics of these materials are roughly similar, the perforated variety has some advantages in absolute absorption, especially in the mid-frequency range, although the "curve" of absorption is not as smooth as for the unperforated type.

If such acoustic tile is to be applied for the purposes of reducing noise due to the human voice alone, as in restaurants and offices, then the perforated material, with its accentuated mid-frequency absorption (where most of the voice frequencies are found) is perhaps most suitable since the ear is especially sensitive in this area.

If, however, we wish to absorb a fuller range of sound than that of the human voice, then the fissured material is preferable because of the smoother absorptive curve, although more of the material may be required. Moreover, as far as the home is concerned, the fissured or sculptured material will fit in with the decor better and look less "industrial" than the perforated variety.

It is interesting to note that the rise in the absorption curve of these materials roughly coincides with the frequency range where the stereo differentiating effect takes place. In the region above 300 cps, spatial differentiation becomes effective and separate speakers reproducing these frequencies are necessary for proper spatial perspective. Thus the effectiveness of these sound absorbing materials roughly matches the frequency range where the stereo effect becomes discernible—making them eminently suited for acoustic adjustments and compensation for stereo reproduction.

## Determining Reverberation

To illustrate the application of the reverberation formulas in conjunction with the tables, let's choose a room with the typical dimensions shown in Fig. 12. In its bare, untenanted state, the room consists of a pine floor with the walls and ceiling of plaster, lime, and sand finish on metal lathing. The

Fig. 10. Average absorption characteristics of representative acoustic tiles.




| CURVE | MANUFACTURER | COMPOSITION |
|---|---|---|
| 1 | INSULITE CO. | COMPRESSED WOOD PULP |
| 2 | ARMSTRONG CORK | CORK |
| 3 | NAT'L GYPSUM | COMPRESSED WOOD FIBERS |
| 4 | AMER. ACOUSTICS | CORK GRANS. & MINERAL BINDER |
| 5 | JOHNS-MANSFIELD | FELTED MINERAL FIBERS |
| 6 | CELOTEX CORP. | MINERAL FIBERS |
| 7 | OWENS CORNING | FELTED MINERAL FIBERS |
| 8 | ARMSTRONG CORK | CORK COMPOUND |




UNIT AREA
ALL THE MATERIAL IN THIS SPACE
DRAPED INTO A SPACE 1/2 AS LARGE
PROVIDES MORE ABSORPTION PER UNIT AREA THAN WHEN STRETCHED OUT FLAT
UNIT AREA

Fig. 11. Here is a simple method of changing the amount of absorption in a typical listening room, as required.

Fig. 12. This completely bare hard room will be too "live", while the room will be too "dead" if completely padded. Figures used are shown below.




| | Surface | Sq.Ft. | × Abs. Coeff. (512 cps) | = Total Abs. | |
|---|---|---|---|---|---|
| Completely bare room | Floor | 500 | .09 | 45 | |
| | Ceiling | 500 | .06 | 30 | |
| | Walls | 876 | .06 | 52.6 | |
| | (2 @ 25 × 10 = 500) + (2 @ 20 × 10 = 400) = 900 − glass (2 @ 3 × 4 = 24) = 876 | | | | |
| | Glass | 24 | .03 | 0.7 | |
| | | | | 128.3 | units |
| | T = (.05 × 20 × 25 × 10) / 128.3 = 1.95 seconds | | | | |
| Completely padded room | Floor (carpeted) | 500 | .37 | 185 | |
| | Ceiling (bare) | 500 | .06 | 30 | |
| | Walls (draped & assuming windows covered by drapes) | 900 | .55 | 495 | |
| | | | | 710 | units |
| | T = (.05 × 5000) / 710 = .35 second | | | | |
| Adjusted room | Floor (carpeted) | 500 | .37 | 185 | |
| | Ceiling (bare) | 500 | .06 | 30 | |
| | Walls (draped 1/5 of area) | 180 | .55 | 99 | |
| | Walls (bare plaster 4/5 of area) | 720 | .06 | 43 | |
| | | | | 357 | units |
| | T = (.05 × 5000) / 357 = .70 second | | | | |

windows, of course, are of standard glass. We know intuitively how a loudspeaker would sound in this bare room, but just as a simple exercise to illustrate the use of our "mathematical tools," let us put down some numbers that will provide the figure of (de)merit for this room.

We are going to apply the reverberation formula ($T = .05V/A$) previously discussed, which relates room volume to total absorption. To get total absorption, we simply add up all the *absorption units* of all the surfaces of the room by *multiplying the areas of the various exposed surfaces by their respective absorption coefficients.* In simple cases such as this, the absorption coefficient for 512 cps is used. Thus, as indicated in Fig. 12, the floor has an area of 25' x 20' or 500 square feet. It is made of pine flooring which has an absorption coefficient of .09 (per square foot). Its total absorption is 500 x .09 or 45 *units.* The "units" for the walls, ceiling, and windows are figured in the same way on the basis of their areas and absorption coefficients. The absorption of the room totals 128 units and, as indicated in Fig. 12, the reverberation time becomes 1.95 seconds. Checking back to Fig. 9 we find that this reverberation time is far too long for proper definition of sound in a room this size (5000 cubic feet). The room will be too "live" which, of course, we knew from the start.

Now let's go to the other extreme and drape all the walls (using a drape which has an absorption coefficient of .55) and lay carpeting on the floor. The second tabulation, Fig. 12, shows that the total absorption will now be 710 units. Again applying our reverberation formula we get .35 second, which we can see from Fig. 9 is far too low—much too dead—which we also probably surmised from the excessive padding added to the room.

Somewhere between the completely live room (128 units) and the over-subdued room (710 units), there must be a happy medium. Without going through the calculations, but following the same general method, we find that if we drape only one-fifth of the area of each wall and carpet the floor we arrive at a total absorption of 357 units (per the third calculation of Fig. 12). This room, now re-adjusted to 357 units, yields a reverberation time of .70 second. Although this figure is a little on the low side, it will insure a reasonable acoustic "liveness."

The room should actually be a bit more on the live side because if you put a couple of upholstered settees in the room (at an absorption figure of 5 units each) and sprinkle generously with seven or eight human beings (4 absorption units each), the total absorption will be gradually increased to approximately 400 units which will tend to pull down the reverberation




Fig. 13. Commercial acoustic tiles. (A) Soft fibers pressed into rigid, but acoustically soft mass with perforations to absorbent body; also with surface absorption. (B) Soft fibers pressed into rigid, but acoustically soft mass with surface cracked, or fissured, for added absorption. (C) Hard panel, such as Masonite, perforated and backed by thickness of absorbent material; no absorption by surface. (D) Same as (B) but with surface sculptured for decorative effect.

properties of the room to near the lower "acceptable" limit.

### Altering the Room

As just demonstrated, much can be accomplished in the line of altering the reverberation of a room by judicious application of various household materials, especially those in the drapery category. Thus, for instance, if one were to hang draw drapes across the four walls of a room (of the dimensions of the one given in Fig. 12) and kept the floor linoleum-covered, as in a playroom, the room could measure from 2.5 seconds with the drapes completely retracted to .46 second with the drapes fully extended to cover the walls. With this type of arrangement, it would be fairly simple for the host to adjust his room to match the number of guests: For a lot of people—open the drapes and expose the walls; for an intimate soiree—draw the drapes. On the basis that each adult is equivalent to 4 absorption units, one could "calibrate" the drapery drawstring in units of number of guests.


SOUND RAYS ON THIS AXIS HIT, AND ARE ABSORBED BY ACOUSTICAL TREATMENT, AND DO NOT REFLECT
REFLECTIVE SURFACE
ABSORPTIVE SURFACE
SOUND RAYS ON THIS AXIS HIT REFLECTIVE SURFACES, BOUNCE BACK TO OPPOSITE REFLECTIVE SURFACE TO SET UP STANDING WAVE

**Fig. 14. Absorbent material on one surface will inhibit a resonance condition between that surface and the opposite one, but will not prevent resonance from being set up between the other room surfaces.**

We may, of course, use materials which have been developed specifically for sound control, such as the acoustic tiles discussed previously. With these tiles we may control the room acoustics more accurately and with smaller areas of material than with conventional drapes, although combinations of tiles and drapes are practical. Tiles are especially useful when the room decor will suffer from an overabundance of drapery. Actually, the acoustic tiles may be quite decorative as well as functional and lend a clean, uncluttered look to the room. With the modern trend toward "airy" interiors, acoustic tile may actually prove a boon in maintaining this feeling while controlling room acoustics. Many such tiles (especially the perforated ones) can be painted to create interesting decorative effects.

One of the most important features of these tiles is that they enable us to treat ceilings as well as walls. Since the ceiling of a room comprises approximately one-sixth of the room's interior surface, it represents a good sized area which cannot be treated other than with tiles. The ceiling cited in our example, 25 feet x 20 feet with an absorption coefficient of .06 when bare has only 30 absorption units but when covered with fissured acoustic tiles its absorption becomes 375 units —more than enough to take care of the whole room without treating the other areas.

## Undesirable Resonances

Although this method of adjusting room acoustics in one grand stroke is fine for general noise abatement, it is not the best approach to the problem of musical acoustics control. The reason for this is that there may be room resonances set up between the sets of untreated parallel walls which can produce quite disturbing effects to musical sounds reproduced within the room. Room resonances may occur when the dimensions of the room are close to the wavelength of the sound propagated in the room and are most prevalent in the low-frequency region.

When the air within the listening room is energized by a sound source, the volume of air enclosed by the walls, ceiling, and floor may be driven into resonance at frequencies which coincide with the wavelength or half wavelength separation of the walls. The very worst shape for a room, acoustically speaking, is a perfect cube because all axes are of equal length and the room is highly excitable acoustically and energetically resonant in all directions at the wavelength (and harmonics of it) which is equivalent to the spacing of the walls. In general, no room dimension should be close to a whole number ratio of another dimension. For normal living rooms, you may consider that if the dimensions of your room are in the ratio of 1:1.25:1.58 then your listening room will be reasonably immune to resonances between the three mutually perpendicular axes.

Although there is usually nothing we can do to the dimensions of our rooms, the statement of the condition, as given, is important in that it allows us to allocate our sound absorbent material intelligently. For instance, if there should be a strong resonant condition between two highly reflecting *walls*, then even large amounts of sound absorbing materials on the floor or ceiling will not affect that particular wall-to-wall resonance to any great extent. See Fig. 14. Thus the technique of treating the ceiling *only* is not the answer to adjusting the room for *music* purposes. We must distribute the "treatment" in random fashion to include all surfaces in order to minimize reflections along all three axes. If we thus distribute the treatment throughout the room, not only will we minimize room resonance but we will improve and equalize the general sound diffusion throughout the room—a condition of considerable importance for stereo.

## Speaker & Listener Locations

One of the prime considerations in setting up a room for music reproduction—live or recorded—is that the sound source be located in a relatively "live" area so that the sound may be projected *into* the room. For monophonic applications, an undraped cor-

(*Continued on page* 106)

**Table I. Absorption coefficients per square foot of some common materials are shown.**

| | ABSORPTION COEFFICIENTS FREQUENCY (cps) | | | | | |
|---|---|---|---|---|---|---|
| **FLOORS** | 128 | 256 | 512 | 1024 | 2048 | 4096 |
| Linoleum on concrete | .02 | .02 | .03 | .04 | .04 | .04 |
| Pine flooring | .08 | .09 | .09 | .10 | .10 | .09 |
| Carpet on ⅛" felt | .11 | .14 | .37 | .43 | .27 | .25 |
| Cork slabs, polished | .08 | .08 | .08 | .19 | .20 | .21 |
| **WALLS AND CEILINGS** | | | | | | |
| Brick wall, unpainted | .02 | .02 | .03 | .04 | .05 | .07 |
| Brick wall, painted | .01 | .01 | .02 | .02 | .02 | .02 |
| Poured concrete, painted | .01 | .01 | .01 | .02 | .02 | .02 |
| Wood veneer on 2 x 3 studs 16" on centers | .11 | 11 | .12 | .11 | .10 | 10 |
| Plaster on hollow tiles | .01 | .01 | .02 | .03 | .04 | .05 |
| Plaster lime, sand finish on metal lath | .04 | .05 | .06 | .08 | .04 | .06 |
| Pine wood sheathing | .10 | .11 | .10 | .08 | .08 | .11 |
| Window glass | .03 | .03 | .03 | .02 | .02 | .02 |
| **WALL FURNISHINGS** | | | | | | |
| Cotton Fabrics 14 oz./yd. draped to ½ width | .07 | .31 | .49 | .81 | .66 | .54 |
| draped to ⅞ width | .03 | .12 | .15 | .27 | .37 | .42 |
| Velours 18 oz./yd. flat | .05 | .12 | .35 | .45 | .38 | .36 |
| draped to ½ own width | .14 | .35 | .55 | .72 | .70 | .65 |
| **FURNITURE AND PEOPLE** | | | | | | |
| Upholstered mohair chair | 2.5 | 3.5 | 4.5 | 4.5 | 4.8 | 5.0 |
| All wood chair | 1.8 | 2.0 | 2.4 | 2.4 | 3.8 | 2.5 |
| Plastic covered chair | 1.5 | 3.3 | 4.3 | 4.0 | 3.8 | 3.6 |
| Child standing | 1.8 | 2.2 | 2.8 | 3.8 | 3.5 | 3.5 |
| Adult standing | 2.5 | 3.5 | 4.2 | 4.6 | 5.0 | 5.0 |
| Adult in upholstered chair | 3.0 | 4.0 | 4.5 | 5.0 | 5.2 | 5.5 |
| Woman in evening dress | 1.8 | 2.0 | 2.3 | 3.6 | 3.6 | 3.5 |



Fig. 1. "Pyramid" tip (left) and conventional tip tracing same record groove.

# The "Pyramid" Stylus

By C. D. O'NEAL
Director of Electronic Research, Fidelitone, Inc.

**Now playback stylus tip shape is said to produce less distortion and noise, plus less record and stylus wear.**

EDITOR'S NOTE: *The announcement of a "Pyramid" playback stylus has produced quite a stir of interest in the industry. Attaining, with precision, the contour specified requires skilled craftsmanship and minute attention to detailed tip shaping. This will add to the cost somewhat, although it may be worthwhile if the performance of the new stylus comes up to expectations. More attention will also have to be paid to mounting and tracking accuracy, but the requirements are not so strict that they cannot be met with present-day equipment.*

THE story of high fidelity is the story of pushing back limitations. With the advent of the single-groove stereo record, many new techniques and specialized equipment—all promising improvements in some unique way—made their appearance. From among these techniques emerged one basic new requirement which, on the whole, is not too well understood by the general public. This was the recommendation for a much smaller needle tip radius to be used with the new type of phonograph pickup.

The RIAA standards committee recommended a .0005-inch radius with a top limit of .0007 inch. Even though the .0005-inch radius is six times smaller than the stylus used to play 78's, it still introduces certain quality limitations in reproduction. Furthermore, such a diminutive size of point greatly limits the tracking force of the pickup with which it may be used.

These are some of the problems which caused *Fidelitone, Incorporated* to sponsor the development of the pyramid-shaped diamond stylus which is to be described.

The underlying principles relating to the reproduction of the stereo record (single-track variety) establish conditions which produce more distortion than the conventional monophonic type of lateral modulation. The limitation is not built into the record itself but is inherent in the playing back of these records using the same size needle tip radius. This, then, becomes the basis for making the point radius smaller so that distortion will not be increased over that experienced with mono discs.

It is not practical to market a round stylus with a radius smaller than .0005 inch because the problem of wear is almost insurmountable. The reason behind this is that reducing the stylus tip radius increases, conversely, the contact pressure per unit area of the stylus in the groove. This, of course, is providing the pickup weight remains the same. This contact force goes up in inverse proportion to the contact area or linear dimension squared. So the stylus tip change, from .001 inch

Fig. 2. Plan and sectional views of cutting and conventional hemispheric playback stylus in a laterally modulated groove.




Fig. 3. Plan and sectional view of cutting and the new "Pyramid" tip playback stylus in a laterally modulated groove.



for monophonic microgroove to .0005 inch for stereo recordings, as recommended by the RIAA committee, means that pressure per unit area on the vinylite record increases four times with a concomitant increase in wear.

The only way to offset this wear is to reduce tone-arm tracking weight by one quarter. If a stereo pickup can be made to track at one gram where the monophonic version needed four grams, we are holding our own with regards to wear. Thus far, however, experience has shown that stereo pickups generally require a little more needle force, to make them work properly, than do monophonic cartridges.

What is needed, then, is a stylus which is designed to overcome the inherent weaknesses of the conventional hemispherical point. To get a better picture of the problem, it is first necessary to point out some stylus limitations.

## Stylus Limitations

Basically, most distortion problems as well as wear arise because the groove is made with a triangular-shaped, sharp-edged cutter while the recording is played back with a smooth, rounded-tip needle. This seems logical enough since the sharp edges of the cutter are needed to cut and the smooth roundness of the playback



Fig. 4. Enlargement of new stylus in groove.

stylus is needed to follow the groove and avoid cutting.

Just as long as the formed groove remains straight, or nearly so, this premise holds true. The trouble comes when the cutting stylus is required to "wiggle" violently when recording high-level, high-frequency program material. This is when the sharp-edged cutting stylus, in its lateral gyrations, forms a groove of many changing dimensions in width and steepness of side walls (Fig. 2, Section BB). This stems from the shape of the cutter which is formed to provide a flat rather than a round cutting area and has a trailing 45 degree clearance angle which only follows the sharp flat front plane doing all of the work.

A round-tipped stylus tracing such a groove is lifted at narrow points in the groove (compare Section C-C with A-A in Fig. 2). At maximum excursion or "corners" of such modulation, the round stylus will again settle back into the groove in a normal manner. This up-and-down motion caused by a round-tipped stylus tracing heavy lateral modulation is known as "pinch effect." This "pinch effect" occurs to some degree twice each cycle for each recorded frequency on the disc. The greater the recorded modulation velocity, the greater this lift effect, up to the point where the modulation sine-wave equals 45 degrees, which should be the high limit created by the 45 degree trailing angle of the cutting stylus. The amount of lateral modulation needed to push the momentary groove angle up to 45 degrees depends on the frequency and the speed of the groove under the stylus. Such severe conditions are most often encountered near the inside grooves of the record. This is where the lower groove speed past the stylus can exactly equal the modulation velocities; thus satisfying the condition for a 45-degree sine wave.

Suffice it to say that reducing the contact radius on the stylus reduces the "pinch effect" in the groove up to the limit where the bottom radius in the groove equals the stylus radius tracing it.

Of even greater importance, however, is the way the stylus contact radius fits into the peak radii of the modulation or the "corners" as previously described. On lateral modulation (as exemplified by conventional monophonic recordings), when the contact radius of the reproducing stylus exactly equals the radius of the "corners" of the modulation, over 30 per-cent odd harmonic distortion is being generated. When this same condition occurs on stereophonic recordings, over 50 per-cent harmonic components are produced.

Here, again, we can understand why the smaller radius (contingent with satisfying the proper needle force per unit area) generates lower values of harmonic distortion. This re-enforces the RIAA recommendation of a .0005-inch radius stylus for stereo records.

We must also point out that harmonic distortion is aggravated by the recording equalization characteristic. It is a "velocity" rather than an amplitude effect. Pre-emphasis above 2000 cps (RIAA curve) will increase the value of generated distortion in this higher frequency region.

One additional point before concluding this discussion on "pinch effect" and that is the fact that it is possible to design monophonic pickups to have less sensitivity to vertical "pinch effect" motion. This is not possible with stereo pickups. Vertical movement of the stylus now has to be used so it is no longer possible to "dispose of it harmlessly." Each 45-degree movement found on the stereo recording can be divided into part lateral, part vertical. Where left and right channels contain identical program material (where the original sound originated from a central position) the lateral parts add and the vertical parts cancel. For sound coming from any other position, there is some vertical movement to represent its "location." Therefore, vertical "pinch effect" becomes even less tolerable.

Now for a solution to these stylus limitations.

## A Solution

If the playback stylus could be made the same shape as the cutter stylus, the problem could be solved. The alternative, which is commonly accepted, is to reduce the stylus tip radius, without changing record groove parameters. The groove, however, must be sharp enough in the bottom to prevent the smaller radius tip from touching bottom since this condition could be objectionable. Here, again, the limitation

(*Continued on page* 144)

Fig. 5. Average reduction in distortion relative to values generated by conventional 1-mil and .7-mil styli for maximum and normal modulation conditions and groove velocities that are found on a conventional 12-inch stereophonic phonograph record.



***These preparations are invaluable, but you should know their limitations as well as their uses and how to pick the right one.***

By **WALTER H. BUCHSBAUM**
Industrial Consultant, ELECTRONICS WORLD

# Know Your Electronic Chemicals

**PART 1**

WHENEVER we visit our electronic parts distributor, we pass a large display rack full of neatly labeled bottles and cans. Often there are several such shelves and it seems that the great variety of bottles, jars, and cans would be more suitable on the prescription counter of a drugstore. This array of chemicals appears bewildering mostly because of the many different names, types, and uses advertised on their labels.

Actually most of these chemicals fit into one of three main categories. They are usually cements, lubricants, or cleaners. Some of the cements may also serve as insulators, and some cleaners may contain a lubricant, but the three main categories still hold. A fourth "miscellaneous" category could be set up to cover such specialty items as enamel-wire stripper and non-slip compounds for dial cords. Paints and finishes are not properly "radio chemicals," since they are used even more widely in other industries and are also sold in painting supply and hobby stores.

Category one, glues and cements, ranges from such specialized types as Bakelite cement to such commonly used glues as rubber cement. Category two is made up of many different types of lubricants and, just as in the case of the cements, the selection of the right one for each job is extremely important. In category three we have included the different cleaners and solvents, and here the damage due to application of the wrong chemical can be considerable.

We would hardly solder a .001-$\mu$f. capacitor in place of a .1-$\mu$f. unit; the choice of the correct chemical can be just as important. Most of our readers are familiar with the system of electrical values and understand the difference between resistance, capacitance, and inductance, but relatively few also understand the basic chemical differences that determine the need for a particular glue, lubricant, or cleaner. This is not the place for a review of chemistry, but it is not necessary that one be a chemist in order to choose the right materials. The technician only needs to know a few fundamentals in order to pick the right compound for a particular job.

## Properties of Cleaners

Obviously the most important property of any liquid that we use for cleaning is its ability to dissolve and remove the substance to be taken off. This depends to some extent on what the "dirt" is and from what surface we want to remove it. For example, if we want to remove a splash of paint, we may use a common paint thinner. However, if the offending spot rests on a plastic surface, this thinner could attack the plastic as well, producing an "etched" spot that may be as bad as the original paint spot, or worse.




The choice of a particular cleaner may be decided as much by the package as by the contents. For accessibility to some spots, a spray can with tube attached (A, B) may be necessary. Spraying over a more generalized area (C) may be preferred in other cases. A free fluid (D) that can be swabbed on may be the choice for other surfaces.

**The term "cleaner" covers a wide variety of completely different preparations, chemically speaking, that are intended for different applications and are not interchangeable. Tuner cleaners (preceding page) are usually of the same type as general volume-control and contact cleaner (A and B, to the right). These two types are therefore generally interchangeable. Picture-tube and glass cleaners (C) are another group entirely. Other classes include preparations for cleaning the magnetic heads of tape recorders, paint-type thinners, and household detergents.**

We can see that the first consideration is to match the cleaner or solvent to both the dirt and its base. Another important consideration is the volatility, toxicity, and flammability of a particular chemical: in other words, how dangerous it is to use. What precautions must we take? Unfortunately many cleaners and solvents suffer from one or the other of these limitations. The outstanding exceptions are soap and most household detergents. Strange as it may seem, a good detergent and warm water, properly applied, can perform a great variety of cleaning chores around a service shop. Many technicians prefer to use detergent or soap with warm water for cleaning picture-tube screens and face masks, although window cleaning fluid and the special "anti-static" preparations work very well.

In choosing cleaning agents for electronic service work, we must also consider their electrical properties, such as the advantage of cleaning a picture tube with a material that will reduce the static charge on the glass. This charge is responsible for attracting much dirt. In cleaning the contacts of a TV tuner, we want to make sure that the cleaner either leaves no insulating residue or else that the film left after the cleaner evaporates will be electrically conductive. A cleaning agent used to clean printed-wiring boards, on the other hand, should leave no film at all.

Most of the cleaners and solvents that are sold at electronic parts distributors are specifically designed to handle a certain job. We find cleaners for magnetic recording heads, contact cleaners, potentiometer cleaners, picture-tube glass cleaners, speaker-cone cement, solvents, and so on. Few service shops carry every one of these materials in stock and frequently one of these cleaners is called on to do a job for which it was not intended. Knowing some of the properties of a cleaner helps us decide if it is safe and worthwhile to apply a particular chemical.

Some cleaning agents, such as alcohol, are very inflammable and burn even at relatively low temperatures. Others give off fumes that may tend to become dangerous. A few leave "drying spots" behind as they evaporate. Most of these troubles are avoided by the specially prepared cleaners sold through electronic parts jobbers, but even there the wrong application can be troublesome.

We know of a service technician who used the thinner intended for polystyrene "dope" as an all-purpose cleaner. It worked well cleaning grease spots off a chrome-plated audio amplifier chassis. TV tuner contacts could also be cleaned with it. However, when he used it to clean the head of a tape recorder, trouble started. The felt pads that hold the tape against the head were soaked through with the thinner and, after a few hours, they fell off. New pads were glued on and the recorder was delivered. However, a few drops of glue had been used to lock the head alignment screws in place, and this glue was loosened by the thinner. Within a few weeks the recorder was returned by the unhappy customer because of "weak sound."

It was found that the head alignment was off. By that time the technician had a small stock of the most frequently used cleaners and other chemicals so that he could be sure that the right material was used each time.

## Contact Cleaners

Probably 50% of all troubles in potentiometers, switches, and tuners are due to dirty contacts. It is therefore not surprising that a host of specially prepared cleaning agents is available just for this purpose. *General Cement's* "De-Ox-Id"; *Walsco's* "No-Ox"; "Quietrole"; *Electronic Chemical's* "No-Noise"; "Hush"; and a number of similar preparations are all specially designed to deal with the contact cleaning problem. They all operate effectively on contacts and potentiometers, but should *not* be used for cleaning glass, printed-wiring boards, or other exterior surfaces because they leave a residue.

Our readers may ask at this point what is so special about contacts that they require a particular chemical? Could we not use carbon tetrachloride or alcohol? The answer is that these simple cleaners could be used. For that matter, even soap and water would have some effect. However, to avoid deterioration of the contacts, a special preparation is better. Most switch and tuner contacts are either solid coin silver or are at least heavily silver plated. Silver oxidizes, as is apparent by the black coloring that develops on it. The oxidized film is a poor electrical conductor. When even small currents are switched through these contacts, some arcing is inevitable, and this promotes further oxidation. Eventually the contacts become intermittent.

In addition to the oxidation of the contact surface there is mechanical wear. If the contacts are lubricated to avoid this wearing process, the lubricant gets saturated with dust until a gritty mixture clings to the contact area. This actually accelerates wear. From this description we see that a cleaner should really do several jobs. It must dissolve the lubricant and wash away the dirt. Then it must be able to dissolve the oxidized coating. After that the contacts should be clean, and now lubrication is needed. Many of the prepared contact cleaners leave a film behind that serves to lubricate the wearing surfaces. To maintain good electrical contact, this film should be conductive.

Irrespective of the type of cleaner used, the applicator is important. Never, never, under any circumstances should contacts be scraped with a metal instrument. Scraping can not only remove dirt and oxide but can also damage the silver plating and wreck the wearing surface. The same goes for the practice of using sandpaper. This habit stems from the early days of electricity when copper contacts were used. In practically all electronic switches, silver or (on more expensive

items) rhodium contacts are used: these should be cleaned only with chemicals. The best way of applying a cleaner is by using a fine artist's brush, cleaning tissues held in tweezers or—the simplest—"Q-Tips" (cotton pads wound on small wooden sticks).

The most effortless way to clean TV tuner contacts is to apply the cleaning agent without removing the chassis. This is often possible if we use one of the special cleaning agents that is available in a spray can, with a special nozzle or injecting needle. The cleaning agent is sprayed directly into the contact area and, since the agent contains a conducting lubricant as well as a cleaner, noisy contacts are usually "quieted down." In a similar manner, noisy volume controls can be cleaned by forcing the liquid cleaner in through the shaft bearing. Whenever such a "quickie" method is used, it is important that the contacts be moved in both directions to clean and lubricate all surfaces properly. A TV tuner should be switched through all channels at least four or five times, and a potentiometer should be turned at least as often, from one extreme of its rotation to the other.

## Basic Cleaners

The technician who is a long way from a well-stocked parts supplier and who finds himself suddenly out of the needed cleaning agents can resort to a number of common cleaning materials that can be adapted to fill almost any need. Some of these are to be found in most homes so that when a house call is made, one can sometimes obtain them from the efficient housewife (poor practice, of course, except in an emergency).

A list of some of these cleaners with their recommended use in electronic work is shown in Table 1. Remember that, unlike the preparations obtainable through a regular electronic supply house, the strength and purity of these items is usually unknown. They may therefore be unsuitable for a particular use. A review of these common cleaning agents shows that most of them are suitable only for general cleaning of chassis, picture tubes, and cabinets. The specific requirements for contact or potentiometer cleaners are not met by any one of them. Two items, gasoline and paint thinner, are not recommended for electronic work because they are dangerous and not really suitable for any application. Both have a tendency to leave a film that often contains chemically active residues.

Most rubbing alcohol is simply denatured alcohol with possibly some aromatic ingredient added. This can be used for cleaning off grease. Occasionally the alcohol is mixed with mint or other oils, and the latter can then leave undesirable residues. It is usually safest to try a questionable cleaner out first on a sample spot, a small area not normally visible, or on a piece of dirt scraped from the area we want to clean. If the reader finds himself without a good contact cleaner he can use alcohol or carbon tet to remove the dirt first, provided that the contacts are accessible enough to be wiped with a "Q-Tip" or similar wiper. Then a mild silver polish can be applied carefully and quickly removed. This takes care of the oxidation—but it is important that *any* residue of the silver polish be completely removed. This can be done either by rinsing the area with water and drying it off with air pressure, or by using alcohol again. Next, the contacts should be lubricated, but never with machine or household oil. In the absence of a good contact lubricant, "Crisco" or a similar vegetable shortening can be used in an emergency. Be careful not to use too much and apply the shortening only to the contact area.

Such "homey" cures may come in handy when a noisy TV tuner is encountered, but they cannot be used easily on a potentiometer. Unless we are willing to disassemble the pot, the only remedy, short of replacing it, is to use one of the specially prepared cleaners. Most of these chemicals are sold with either a long, thin nozzle or needle with a pressure can, or else a special plastic nozzle that fits over the shaft is provided. These applicators help to get the cleaner directly to the moving contact area where the trouble really is.

Table 1. Many chemicals that do not have to be purchased as special preparations are useful. They are listed here, with applications and limitations.

| CLEANER | DISSOLVES | USE ON | REMARKS |
|---|---|---|---|
| Acetone | Lacquer, paints, grease | Chassis, contacts, glass | Attacks some plastics, leaves slight film |
| Alcohol | Grease, oils, rosin | Chassis, contacts, plastics, solder joints, recorder heads | Inflammable, leaves very slight film |
| Ammonia | Grease, grime | Chassis, picture tubes, glass, plastics | Use only in mild solution in warm water |
| Benzene | Grease, oil, wax | Chassis, only some plastics (use sparingly) | Inflammable, some fumes |
| Carbon tet | Grease, oil, wax | Chassis, glass, plastics, non-waxed parts | Toxic fumes, leaves film, extinguishes fire |
| Detergents | Grease, grime | Plastic cabinets, glass, picture tubes | Use only mild solution in warm water |
| Gasoline | Grease, oil, some paints | Not recommended for electronic work | Inflammable, fumes |
| Lighter fluid | Grease, oil, wax, rosin | Chassis, plastics, contacts, solder joints | Inflammable, leaves visible film |
| Paint thinner | Paint, grease, wax, oils | Not recommended for electronic work | Inflammable, fumes |
| Silver polish (water soluble) | Oxidation | Silver contacts | Apply lightly and remove residue before lubricating |
| Turpentine | Grease, oil, wax, paint | Chassis, glass, some plastics | Inflammable, leaves film |
| Window cleaner | Grime, dust | Glass, plastics | Some types leave a light film |

## Recording Head Cleaners

A whole group of special-purpose preparations is available for cleaning magnetic recording heads. Here the cleaning agent must remove the iron-oxide deposits that collect at the head and should leave a lubricating film to reduce tape wear. At the same time, the cleaner should not be damaging to the felt pads or the cement that holds them. It should not attack the plastic material of the recorder case, the epoxy which is usually part of the head, nor should the film left by the cleaner be harmful to the tape itself.

Magnetic head cleaners offered by parts jobbers under various tradenames all fulfill these requirements. Some cleaners like *E. L. Hern's* "X-Sol," are available with a cotton wick that can be inserted into the tape mechanism and pulled through just like the recording tape. This makes for a very simple yet effective cleaning procedure. The wick is squeezed out automatically when it is returned to the bottle and, after a while, the collection of iron oxide at the bottom of the bottle signals that it is time to get another bottle.

## Conclusion

A little understanding of the basic chemistry of cleaning agents is helpful for anyone who services electronic equipment. Common household cleaners can be used for some jobs and can often serve, in a pinch, when the right chemicals are not available. The specially prepared cleaners still give the best results. For switches, tuners and any other contacts, a special contact cleaner that also deposits a lubricating film should be used whenever possible. For noisy potentiometers, a special cleaner and applicator are a necessity. For cleaning the delicate and expensive heads of magnetic tape recorders, only a prepared magnetic head cleaner should be used.

(*Concluded next month*)



# Simple Improvements For Short-Wave Receivers



**Inexpensive circuit changes to increase the performance of many low and moderately priced communications sets.**

By
**JOHN A. KIRK**
W3CRB

THE performance of many low- and moderately priced communications receivers can often be improved by simple, inexpensive modifications. It is the purpose of this article to describe a few of these modifications for which the need is widespread.

### Series Antenna Capacitor

For amateur c.w. operation of a low-priced (no r.f. stage) communications receiver using a longwire antenna, a variable series antenna capacitor is a valuable aid. The usual antenna coil design in such receivers will give good results with a short antenna but produces effective antenna overcoupling with a longwire. Blocking and frequency pulling by strong, undesired adjacent-channel signals make evening operation a nightmare. However, the longwire is very desirable from the standpoint of DX reception, particularly in the daytime.

The solution to the antenna coupling problem on receivers such as the *Hallicrafters* S-38, *National* SW-54, and *Heathkit* AR-3, is the installation of a variable series antenna capacitor of approximately 140 micromicrofarads. When severe interference occurs, the capacity may be reduced to the point where the signals become clear and distinct. Retuning then permits copying of signals which, in many cases, would have been lost in QRM. As capacity is reduced, the effective antenna coupling is reduced, r.f. selectivity increases, image ratio is improved, and strong signal amplitude reduced to an acceptable level at the mixer grid. While the addition of a series variable capacitor is not as beneficial to the more expensive, r.f.-stage-equipped receiver, it will nevertheless be found very worthwhile even with such equipment.

Typical series variable capacitor installations are quite simple to make. The capacitor employed is a 140-$\mu\mu$f. air trimmer with one end plate bent over at the tip so that at full mesh the capacitor may be shorted to make direct contact from the antenna to the receiver's antenna terminal. Each antenna trimmer of the receiver should be peaked near the high-frequency end of its respective band with the series variable capacitor at approximately half mesh when using a longwire antenna. Then, in the presence of strong, undesired adjacent-channel signals, if the series variable capacity is reduced, the r.f. tuning sharpens and is peaked for optimum performance. At full or nearly full mesh, due to the effective antenna overcoupling, receiver r.f. trimmer alignment is broad and non-critical in most normal operating conditions.




Fig. 1. Noise limiter for S-38 receiver.

Fig. 2. Audio limiting for the SX-24.




### Amplitude Noise Limiter

While an effective noise limiter is a very useful feature on any communications receiver, many of the lower-priced sets do not incorporate one. Noting that the *Hallicrafters* S-38B had its 12SQ7 diodes paralleled, it was decided that one of these tubes could be put to better use as a noise limiter (especially after it was found that receiver performance was unaffected if one diode was disconnected). Since the "send-receive" switch is never used by the operator of this particular receiver, a "no-cost" modification was possible. The two leads of the "send-receive" switch were removed, soldered together, taped, and dressed down near the chassis. The lead connecting the 12SQ7 diodes together was clipped and the diode (pin 5) thus isolated was connected to one contact of what was the "send-receive" switch. The other switch contact is connected to the grid of the 50L6 (pin 5). When the switch is closed (placed in the "receive" position), the diode is connected to the 50L6 grid. Limiting occurs with signals even smaller than 0.1 volt at the 50L6 grid. Refer to Fig. 1 for the simple circuit modification.

If it is desirable to retain the "send-receive" switch function, an ordinary toggle switch may be mounted at some convenient place on the receiver panel and wired as described. Where the receiver does not have an unused diode which can be employed as a noise limiter, a 6C4 tube may be added under the chassis. Pins 5 and 6 are tied together permitting the grid and plate to act as a diode plate and cathode pin 7 connects to ground. On series filament a.c.-d.c. receivers, filament pins

(*Continued on page* 145)




A

Fig. 1. Oscilloscope displays obtained (A) when sweep rate ($f_s$) and resonant frequency of the tank ($f_r$) are equal, (B, C) when $f_s$ is a subharmonic of $f_r$, and (D) when $f_s$ is greater than $f_r$.

# The Scope as a Resonance and LC Tester

By A. A. MANGIERI

**Test flybacks, check resonance, measure inductance or capacitance with two resistors and your scope.**

THE MODERN oscilloscope is regarded by many as the most versatile of test instruments. Few people claim to know all the uses to which it may be put. New uses are always being suggested. The possibility of measuring resonance with the oscilloscope was investigated because a convenient method of checking low-frequency tanks, in the range of 1 to 200 kilocycles, was needed. Popular devices normally used to measure resonant frequencies, like grid-dip meters, do not generally extend below 300 kc. As for unknown values of an inductance or capacitance, they can be found by resonating them against known components.

The method worked out was that of exciting a parallel connection of $L$ and $C$ with the saw-tooth output from an oscilloscope. Circuit connections for the technique are shown in Fig. 2. The saw-tooth voltage ($E_1$) is applied to the $LC$ network and an output voltage ($E_2$) is taken from the tank for application to the vertical input of the oscilloscope. Isolation resistors $R_1$ and $R_2$ are not critical: values anywhere from 50,000 to 250,000 ohms are satisfactory.

## Theory of Operation

A saw-tooth wave is an excellent source of a broad band of frequencies. In addition to its fundamental, it contains a sequence of usable odd and even harmonics of progressively smaller amplitude. The parallel $LC$ circuit will exhibit a characteristically high impedance at its single frequency of resonance.

We may understand behavior of the circuit if we first think of the saw-tooth wave, $E_1$, as a pulse that shock-excites the tank circuit. This results in a damped, transient oscillation, $E_2$. The frequency of oscillation is determined by the $LC$ tank and the damping by the "$Q$" of the circuit.

We will call the fundamental sweep frequency or repetition rate of the saw-tooth waveform $f_s$ and the resonant frequency of the $LC$ circuit $f_r$. If the sweep-frequency controls of the scope are adjusted so that these two are equal ($f_s=f_r$), the oscilloscope pattern will resemble Fig. 1A, displaying one cycle of oscillation. If the sweep frequency is one-half the resonant $LC$ frequency ($f_s=f_r/2$), a two-cycle display (Fig. 1B) results, with the second cycle smaller in amplitude than the first. With $f_s$ much lower than $f_r$ ($f_s=f_r/10$), the damped oscillation of Fig. 1C results. If the sweep frequency should differ from the resonant frequency in the other direction—that is, if $f_s$ should be greater than $f_r$, the waveform collapses as shown in Fig. 1D.




B




C

D




If $f_r$ is unknown, how can we determine when sweep frequency $f_s$ is correctly set to it? This is done simply by adjusting the sweep frequency while observing point $A$ in Fig. 1A. This point will extend and retract vertically as we sweep through the resonant frequency. The point of maximum extension (maximum pattern height) occurs when $f_s=f_r$. Similarly, when we sweep $f_s$ gradually through $f_r/2$, point $A$ exhibits like behavior, but with reduced amplitude. During normal adjustment, point $A$ will also seem to move from side to side, and the retrace line ($B$-$C$) will move up and down. These effects reflect the gradual shifting of phase between $E_1$ and $E_2$.

## Calibration

To apply the technique, we must obviously calibrate the sweep frequency controls of the oscilloscope. Where the fine-frequency control is not marked with a subdivided scale, a dial plate with a hundred divisions may be fixed in place behind it. An audio or other low-frequency oscillator may be used. Connect the oscillator output to the vertical terminals of the oscilloscope and, for each frequency at which calibration is made, adjust the scope controls to obtain a single-cycle display.

During calibration, keep the sync-amplitude control of the scope adjusted to its lowest usable setting. This prevents excessive "pulling" of the sweep frequency and permits the greatest possible accuracy. During actual resonance and *LC* tests, the sync-amplitude control is set to zero. Despite the fact that the multivibrator of the scope's sweep generator will be free-running with no sync, its stability will be adequate in most cases. Nearly all oscilloscopes today, including some less expensive ones, use some form of voltage regulation, insuring a reasonable amount of frequency stability.

Arbitrary markings rather than actual frequencies should be marked on the scope panel. Actual calibration frequencies should be plotted on graph paper. In this way, a separate curve for each position of the coarse frequency control can be made up, and all curves may be plotted on the same reference sheet. Semi-log graph paper was found to be most practical.

## Resonance Testing

To determine the resonant frequency of a parallel circuit, connect it to the oscilloscope as shown in Fig. 2, and adjust sweep frequency to obtain a single-cycle display while maximizing pattern height. Resonant frequency may then be read from the calibration curve.

Conversely, to adjust an *LC* circuit to a particular frequency, set the scope controls to that frequency and manipulate the value of either *L* or *C* to produce the characteristic pattern. The direction in which the parallel combination is off may be determined by comparing the shape of the initial pattern observed with those in Fig. 1.

One practical application of the method has been in testing flyback transformers, by measuring their self-resonant frequency. With the TV receiver de-energized, connect the high end of the flyback transformer to the oscilloscope through the two isolation resistors, as shown, and connect the low end of the transformer to the scope's ground terminal. This self-resonant frequency will vary considerably from one type of set to another, depending on design of the transformer itself and differences in circuit loading. It will help to record the normal frequency for each type of circuit design encountered for later comparison.

In testing the flyback circuit of a suspected receiver, moderate deviation from the normal frequency may be expected due to manufacturing tolerances. However circuit defects, such as open or shorted windings and cracked or loose cores, will result in a marked change in inductance and therefore a large change in resonant frequency. Is it also possible, as in other flyback testing techniques, to unload the transformer gradually by disconnecting associated components one at a time to localize a defect.

## Measuring Capacitance

We can determine the value of an inductor or capacitor in a tank circuit if the resonant frequency and the value of the other component in the *LC* combination are known. Of the two methods available for measuring capacitance, the greater accuracy and simplicity of one of them makes it the strongly preferred technique. In addition to one (or more) inductor chosen as a standard reference, it relies on calibration against several known capacitors. A capacitor decade box or a sequence of other accurate capacitors will serve.

Using the arrangement of Fig. 2, each of the capacitors is connected in turn across the reference inductor. The value of the latter need not be known exactly. With each capacitor, the scope's $f_r$ is adjusted to equal $f_r$. A sheet of graph paper is then used to record the position of the sweep-frequency controls for each known value of capacitance, and a curve may be plotted from these individual readings. Calibration in terms of sweep frequency is not necessary.

To measure an unknown capacitor, connect it across the reference inductance in the test circuit and adjust the sweep frequency for resonance. The value of *C* may then be found by direct reference to the calibration curve. Neither the sweep frequency, the exact value of the inductor, nor any other characteristics of the latter need be taken into account once it has been chosen as the standard. Experimentation shows that a choke of about 60 millihenrys can be used to measure capacitance from 100 $\mu\mu$f. to .1 $\mu$f. High-"*Q*" inductors are preferred.

The alternative method of measuring *C* uses the curves already plotted for resonance tests along with the known inductor already noted. In addition, the familiar formulas involving reactance and resonance will have to be used for calculation of values. Even here, the paperwork can be simplified by using a reactance slide rule. One such inexpensive unit is made by *Shure Brothers, Inc.* Nevertheless, the technique must take into account additional factors that will not be involved in the first method described for measuring capacitance. For example, the reference inductor will have a certain amount of distributed shunt capacitance across its terminals, rendering it self-resonant at some frequency. This capacitance, $C_o$, is across any external capacitor that may be in parallel with the inductor.

If the inductance is known to start with, $C_o$ may be found by determining the self-resonant frequency and using the formulas or the reactance slide rule. To measure an unknown capacitor, connect it in parallel with the inductor in the test circuit and find $f_r$. From this frequency and the known value of *L*, the value of *C* may be worked out or read on the reactance calculator. From the value thus obtained, $C_o$ should be subtracted. Circuit "*Q*" also can be a factor if an attempt is made to use an inductor over too wide a range of capacitance values. If circuit "*Q*" is much less than ten, considerable error can result. For a particular inductor, it is wise to limit the values of *C* that are used to measure over a range that insures a circuit "*Q*" of ten or more. The latter factor may also be calculated with the reactance slide rule.

## Measuring Inductance

Capacitors of known value will obviously be needed to determine the inductance of unknown coils, and such factors as "*Q*" and $C_o$ are also important. However a simple method with few pitfalls does exist.

First find the self-resonant frequency, $f_o$, of the unknown inductor. Next, shunt sufficient known capacitance across this inductor so that $f_r$ for the combination is about one-tenth of $f_o$. Under these conditions, $C_o$ will be small compared to *C*, so that the former will not cause significant error. Also, circuit "*Q*" will generally be above ten. Using $f_r$ and the added shunt capacitance as the known quantities, the inductance can be found using the formula $L=1/4\pi^2 f_r^2 C$ or from the reactance calculator.

## Summary

The measurement of low-frequency parallel-resonant circuits and of capacitance, using the methods recommended here based on appropriate calculation curves, are straightforward and reliable. Measurements involving more than one step and the calculator (or formulas) will also be found useful to those who have no other suitable equipment for making such checks.

Accuracies will obviously not approach those obtainable by producing nulls on the bridges in laboratory-quality equipment. However, there is a question as to how much accuracy is actually needed. Most measurements made by the methods described here fell within five per-cent.

A final word of caution: some types of inductors with powdered-iron cores are quite non-linear, inductance varying with applied voltage and frequency. These should be avoided as reference inductors. No simple correction factors will compensate for the errors they introduce. As to capacitors, paper and mica units show relatively small changes in value even at higher frequencies and also have high "*Q*." —30—

Fig. 2. Connections from circuit being measured to the scope are very simple.



By **JOHN T. FRYE**



# MAC'S service shop

## How it Started

"HEY, that's pretty old reading material, isn't it?" Barney remarked as he came into the service shop to find Mac, his employer, deeply intent on one of several age-yellowed, newspaper print magazines spread out on the service bench in front of him.

"Right you are," Mac replied. "A fellow in Peru ran across these the other day, and last night he brought them over and gave them to me. There are nine copies of *Radio Digest Illustrated*, a weekly radio magazine, dating back to October, November, and December of 1923. They present a fascinating picture of this business we are in when it was just a pup with its eyes hardly open yet. Remember that KDKA had started the whole broadcasting business only three short years before when, on the night of November 2, 1920, it came on the air with the returns of the Harding-Cox presidential election. KDKA began transmitting on 833 kilocycles with a whole fifty watts of power."

"Who was listening?" Barney wanted to know.

"The people the magazine calls 'hams,' 'listeners-in,' or 'radiophans' almost interchangeably. You've got to remember that when radio was first discovered it was looked upon as a scientific marvel and a means of communication. Commercial stations 'communicated' by means of high-powered spark transmitters; experimenters and radio amateurs, fascinated by the 'scientific marvel' aspect, toyed around with radio just to see what they could learn about it and do with it in the same way 'rocket societies' play around with rockets today. When some of these experimenters and hams started using radiotelephony instead of radiotelegraphy, they began to entertain each other or anyone listening by playing phonograph records or musical instruments, singing, reading poetry, etc. Right then and there the idea of radio as a means of *entertainment* began to bud. As to who was listening in 1923, the magazine says this:

" 'Radio has divided itself into two distinct groups of broadcast listeners, those who buy a complete set and those who purchase the parts and put them together in a way that suits their fancy. . . . The class who build their own sets are in a majority. . . . When radio came, the man on the street found that he could make his own apparatus at a saving in cost and have a lot of fun doing it'."

"What kind of sets were they using?"

"Well, look at this advertisement for a *Crosley* Model X-J for only $65—but remember those were *big* dollars, son. It is a one-stage t.r.f., detector, and two stages of audio affair. 'Local interference can be easily tuned out and far distant stations quickly and clearly heard,' it is claimed—although I'm not quite sure what 'quickly heard' means. According to the magazine the crystal set was still holding its own pretty well against the more expensive and complicated vacuum-tube receiver. Tubes advertised were the WD-11, WD-12, C-300 or UV-200, C-301 or UV-201, C-301A or UV-201A and the 'New UV-199.' What's more, you could have any of these tubes repaired and 'guaranteed to work like new' for charges varying from $2.75 to $3.50. Since a new tube cost from five to seven dollars, this was an enticing offer.

"The majority of listeners still used earphones as this girl from the *Vanities of 1923* is doing in the picture. Proof is contained in this story headlined *'Radio Ear' is New Pain for Listener*. 'Tight headphones bring on the affection,' the story explains. 'A sharp, shooting sensation in the head is a symptom. Doctors suggest loosening up on headphones.' One assurance is given of benefit from radio headsets, however: 'Youths of this generation will never have as protruding ears as some of their older brothers'."

"I'll bet those radiophans had lots of troubles," Barney hazarded.

"They did that. The magazine confesses: 'With so many constantly varying items in and about a radio set, it is amazing that more trouble is not traced to them directly. There is the "A" battery which tapers off as it is used; there is the detector tube that gradually loses its sensitivity; there is the outside grid leak that is changed by atmospheric conditions; and finally there are the four contact prongs on the vacuum tube that attract dust and dirt and are continually subjected to corrosion.'

"Interference was a problem, too, as you can see from this Letter from a Reader: 'Regarding . . . the subject of spark interference on or around 450 meters, I really hate to start in on this subject, for I get so exasperated every time I mention it. On long-distance work it is enough to drive one crazy to have nice concerts from Los Angeles, New York, Philadelphia, etc., all mussed up by that confounded dot-and-dash stuff. What do folks think of radio when you tune in a nice concert and then have one of those spark fellows slip in with his machine gun noise and gum up the works?' "

"Was he talking about hams?"

"Not necessarily. An editorial in the same issue suggests: 'Some listeners-in keep complaining that amateurs interfere with broadcasting. They do not actually know who is interfering. Half the time it is probably ships which are sending or shore stations handling regular commercial work. What these "knocking" listeners-in should do is to learn to read code so that they can identify the senders'."

"Guess my TVI trouble ain't so bad after all!" Barney said with a grin.

"Of course the antenna was a constant field for experiment and a cause of annoyance," Mac continued. "Doesn't this advertisement for a gadget that obviously uses the light line for an antenna sound hauntingly familiar? 'Cold winter nights won't find you on the roof fixing the aerial, removing snow and sleet, exposing yourself to sickness, if you use Antenella.' "

"I see fading really bugged the boys back there," Barney observed. "Here is one guy, chief radio operator and announcer of a broadcast station, who claims he has found the 'real cause' of fading. It's so simple. Fading is caused by power fluctuations in the power line supplying the transmitter!"

"It would have been nice had it been that simple; but a story in another of those magazines comes lots closer. It says tests carried out through the joint efforts of the Bureau of Standards and the American Radio Relay League in 1920-1921 point to the fact that 'uneven air' and variations in the Heaviside layer are somehow tied in with fading radio signals. Incidentally, all anyone has to do to be convinced of the heavy debt modern radio, television, and electronics owes to the radio amateurs is to leaf through these magazines and see what an active, important part they were playing back there in the very beginning. Here they are holding a Wouff Hong initiation at a hamfest at Atlanta on December 27th, 1923. Here Fred Schnell, 1MO, traffic manager of the ARRL,

(*Continued on page* 146)



# Low-Noise Transistor Preamp

By **DAVID R. STEELE**
Ampex Corporation



**Construction of simple, well-designed phono preamp for magnetic cartridges that can be built for under $15.**

FOR the past decade, the serious record enthusiast has been plagued by problems involving equipment associated with magnetic cartridges. Foremost in this classification is the preamplifier. Commercial or home-made, they have been traditionally beset with microphonics, hum, and other noises that must be suppressed at every turn. This is a never-ending battle that has become more expensive and elaborate as the dynamic range of LP records has been steadily increased. It is now both simple and economical to overcome these problems with a low-noise transistorized preamplifier. Due to the nominal power requirement, it is feasible to use batteries, an excellent source of hum-free supply voltage. Transistors are non-microphonic, making mechanical precautions necessary. Transistors provide an economical approach to a low-noise, high-quality preamplifier.

It is universally accepted that it is the responsibility of the preamplifier to increase the output of the low-level magnetic cartridge and to provide correct equalization to complement the recording characteristic. These are both simple tasks. However, they must be performed without injecting any perceptible noise or distortion into the system. The preamplifier described herein accomplishes this at a total cost of less than $15, including batteries.

This is not intended to be a general-purpose unit. It is designed to do just one job and to do it as well as is technically possible. It should be evaluated on the same basis as any other preamplifier, namely noise, distortion, transient response, and accuracy of equalization. Naturally, the better these figures are, the better the preamplifier. But before any actual design work can be done, it is necessary to know exactly what this preamplifier is expected to do in terms of measurable performance.

These specifications represent desired performance. If subsequent investigation proves them extravagant or unattainable, they may be tempered with reality in the final specifications. Nevertheless, they provide a visible goal at the outset of the development and a yardstick by which its success may be measured upon completion. In this case, the following "wishing list" was compiled: Input impedance: 100,000 ohms; Output: 500 ohms or less; Gain: 35 db mid-frequency (to provide approximately 1 volt r.m.s. output); Distortion: less than 0.2 per-cent harmonic measured at maximum operating level +6 db; Equalization: RIAA ±2 db (RIAA tolerance); Noise: 80 db down from maximum operating level measuring all components in a band of 0 (d.c.) to 20 kc.

If this last specification seems unnecessarily detailed, it should be remembered that the signal-to-noise ratio is most informative when the frequency range of the measured noise is known. Unless otherwise specified, this might be taken only as the noise in the frequency range of interest, in this case, 30 cps to 20 kc. Unfortunately, noise components below 30 cps can be just as offensive to the rest of the system as those above. Therefore, it is felt that the noise measurement should be taken down to d.c.

Other desirable features include good transient response and fast overload recovery. Primarily, this goes to minimize the effect of dropping the stylus into the lead-in groove. It should be immune to stray fields generated by motors and transformers. The preamplifier should be compact and self-powered so that it may be installed close to the tone arm. It should operate reliably at temperatures up to 150°F. It must not use any special, selected, or unduly expensive components.

In consideration of the foregoing requirements, the design philosophy of a two-stage, direct-coupled feedback amplifier followed by a common collector stage, also direct-coupled, is very attractive. This configuration has definite advantages in that:

(*a*) Equalization can be accomplished in a single voltage feedback loop.

(*b*) The series feedback thus produced will elevate the input impedance.

(*c*) Temperature stabilization can be accomplished by a separate d.c. feedback loop.

(*d*) The common-collector output stage will provide a low-impedance output and isolate the equalizing network from the load.

Since the preamplifier is to be battery powered, it is practical to arrange the supply with two identical batteries to provide positive and negative voltage with respect to the mid-point, which is grounded, serving as a "0" voltage reference. The base of the input transistor is conveniently placed at ground potential due to the very low d.c. resistance of the cartridge. The base current of the first stage does flow through the cartridge, however, this is only about 2.5 microamperes and has no perceptible effect on the performance of the cartridge.

## Circuit Employed

Referring to the schematic, Fig. 1, an absence of coupling capacitors will be noted. The direct coupling is responsible for the excellent overload recovery and low-frequency transient response. It is also responsible for the temperature stability, through the d.c. feedback loop between the input and output emitters. This method of temperature stabilization avoids the use of current-consuming divider networks at the base of each stage, resulting in considerably less battery drain than would otherwise be experienced.

For discussion purposes, the amplifier can be divided into three sections. The forward-gain path, the signal-feedback loop, and the d.c.-feedback loop. The forward-voltage gain is provided by $V_1$ and $V_2$, which are used in the common-emitter configuration. $V_3$, an emitter-follower, provides current gain, reducing the output impedance. A 2N-324, a high-*beta*, low-noise transistor, was selected for $V_1$. In order to obtain the desired d.c. distribution throughout the amplifier, it is necessary to use an *n-p-n* transistor for $V_2$. Type 2N169A was selected for this position. $V_3$, the output stage, is not at all critical. Another 2N324 is used here, reducing the number of different types required. These types are manufactured by *General Electric*. No difficulty should be encountered in the substitution of other types as long as they are electrically similar. Most manufacturers publish reliable cross-reference data, which can be used in the selection of other types. The parts list includes some alternate types that have been tried and found satisfactory. The use of an "economy" transistor in the $V_1$ position is not recommended, as this might degrade the noise figure of the preamplifier.

Signal feedback of a negative voltage characteristic is obtained from the collector of $V_2$, and developed across $R_2$, the unbypassed portion of the $V_1$ emitter resistance. This series feedback configuration raises the input impedance of the preamplifier to a value that prevents loading a high-impedance magnetic cartridge. Equalization is obtained through the use of a frequency-discriminating network in this loop. $R_4$, $C_2$, and $C_3$ are selected to produce the RIAA characteristic. $R_4$ and $C_3$ determine the low-frequency turnover point and $C_3$ determines the high-frequency roll-off. Naturally, the feedback is at its minimum at the top of the low-frequency rise. However, at this point there is still approximately 15 db of feedback through this loop.

The d.c. feedback loop includes the emitter-follower. It returns the d.c. component of the output to the input stage emitter. Any shift of d.c. operating points due to temperature, transistor characteristics, etc., would, without this over-all loop, produce a change in the d.c. voltage at the $V_2$ emitter. If this change is applied, in proper phase, to the input of the amplifier, the situation will be self-correcting, as it is in this case. The temperature stabilization realized in this manner is quite effective. Referring again to the schematic, it will be observed that $C_1$ is used to filter the signal out of the d.c. loop. This is necessary, since the signal feedback loop is "inside" the d.c. loop. Signal voltage appearing in the d.c. loop would tend to nullify the action of the equalizing network.

The capacity of $C_1$ is chosen so that, in conjunction with $R_2$, low-frequency feedback occurs in this loop. Actually $C_1$ and $R_5$ have been selected to permit feedback starting at 30 cps and increasing as frequency decreases. This serves to control the subaudible response of the preamplifier. It provides feedback in the region where the signal feedback loop has ceased to function. Three important benefits are derived from this feature. It is generally conceded that it is desirable to attenuate the response of the system below the range of interest to reduce turntable rumble and changer thumps. It reduces the possibility of low-frequency instability, and, most important, it greatly reduces the 1/F or flicker noise produced by transistors.

At first glance, the value of $C_1$ may

Inside view showing the placement of the two batteries used.




Circuit board on which transistors and other parts are mounted.



seem unusually large. To avoid confusion, it should be pointed out that $R_8$ is in series with an amplifier having an open loop gain of about 60 db, therefore, the effective resistance of $R_8$ is 27,000/1000 or 27 ohms. Nearly all LP recordings available today require the RIAA curve for correct reproduction and this is why the RIAA curve was built into this preamplifier. It is conceivable, however, that some users will desire other equalization, or perhaps several different switchable curves. Inasmuch as all of the equalization is accomplished by one network between two points, a single-pole rotary switch can be used to provide as many equalization positions as desired. If a curve having a 500 cps turnover and no high-end roll-off is desired, common to 78 rpm records, $C_8$ is changed to .02 $\mu$f. and $C_2$ is omitted. A capacitive reactance chart or nomograph is useful in determining the appropriate values to produce a particular curve. A general consideration that should be kept in mind is that the amount of equalization must always be less than the amount of feedback determined by $R_4$. Thus, if the turnover frequency is moved up, it should be done by decreasing the capacity of $C_8$ and decreasing the resistance of $R_4$, otherwise, the low-frequency rise may flatten out prematurely. By making $C_8$ very large (10 $\mu$f. or more) and omitting $C_2$, the response may be made essentially flat.

| | |
|---|---|
| **Input Impedance** | **120,000 ohms** |
| **Output Impedance** | **90 ohms** |
| **Gain** | **35 db @ 1000 cps** |
| **Distortion** | **0.17% @ 2 v. r.m.s. output (measured at 1 kc.)** |
| **Noise** | **—85 db, all components d.c. to 20 kc.** |
| **Equalization** | **RIAA** |
| **Output Level** | **Approx. 1 v. r.m.s.** |
| **Operating Temperature** | **165°F** |

**Table 1. Listing of preamp specifications.**

Performance specifications of the preamplifier are given in Table 1 and the response in Fig. 2. All of the original specifications have been met and, in some cases, exceeded. The only maintenance required—in fact the only maintenance possible—is the replacement of batteries when required. The exact battery life is, of course, dependent on how much the preamplifier is used. A good procedure is to check the voltage every three months or so, and discard the batteries when they measure less than approximately 6 volts.

## Layout & Construction

The physical layout and construction shown in the photographs are intended primarily as examples. Parts placement and lead dress are not at all critical. In the event the builder elects to forego sockets for the transistors, the usual precautions regarding soldering should be observed. The use of a d.p.s.t. relay connected to the turntable motor may be used to turn the preamplifier off and on. No doubt several possible innovations will occur to the reader. The "chassis" is 1/16" Fiberglas, but any of the common insulating materials will be satisfactory. The connecting terminals were made by bending a loop in the end of No. 20 tinned wire. The completed preamplifier is housed in a homemade aluminum box. It is recommended that this preamplifier be enclosed in some kind of a metallic shield.




$R_1$—15,000 ohm, 1/2 w. res.
$R_2$—330 ohm, 1/2 w. res.
$R_3$—33,000 ohm, 1/2 w. res.
$R_4$—18,000 ohm, 1/2 w. res.
$R_5$—27,000 ohm, 1/2 w. res.
$R_6$—10,000 ohm, 1/2 w. res.
$R_7$—8200 ohm, 1/2 w. res.
$R_8$—3900 ohm, 1/2 w. res.
$C_1$—250 $\mu$f., 3 v. elec. capacitor (see text)
$C_2$—.0039 $\mu$f. disc ceramic capacitor
$C_3$—.022 $\mu$f., 200 v. capacitor
$C_4$—100 $\mu$f., 6 v. elec. capacitor
$C_5$—1 $\mu$f., 6 v. capacitor
$S_1$—D.p.s.t. switch
$B_1$, $B_2$—9-volt battery (RCA VS300 or Burgess P6M)
$J_1$, $J_2$—Phono jack
$V_1$—"p-n-p" transistor (G-E 2N324, 2N508 or RCA 2N175)
$V_2$—"n-p-n" transistor (G-E 2N169A, RCA 2N585, Sylvania 2N214, or General Transistor 2N446A)
$V_3$—"p-n-p" transistor (G-E 2N324, 2N321, 2N508, 2N190, or RCA 2N109)

**Fig. 1. Total cost of the three transistors used in this circuit runs about $6.50.**

During bench tests, the preamplifier input must be terminated by a low d.c. resistance. A 680-ohm resistor will be satisfactory. The d.c. voltages shown on the schematic were measured with a v.t.v.m. and also with a 100,000-ohm-per-volt multimeter. All readings should be ± 1 volt. The d.c. stability may be checked by connecting a voltmeter between $V_3$ emitter and ground. $V_1$ is then heated by holding a soldering iron in close proximity. The voltage will decrease. When it drops to about +1 volt, remove the soldering iron and grasp $V_1$ between thumb and forefinger. It should feel decidedly hot. The voltage at the $V_3$ emitter should return to normal rapidly as the heat is dissipated by the fingers.

## Installation and Use

It is desirable to mount the preamplifier close to the turntable or changer, keeping the lead from the cartridge short. The higher impedance magnetic cartridges are sensitive to cable capacity. Since the preamplifier is not connected to the a.c. line, the possibility of ground loops in the system is slight. If encountered, the solution is merely to avoid connecting the preamplifier box to ground except by the shields of the input and output leads. It is preferable that the following amplifier have a volume control preceding the first stage, otherwise there is a possibility that the preamplifier will overdrive it, causing distortion. The simplest solution in this case is to insert a fixed attenuator between the preamplifier and the main amplifier. —30—

**Fig. 2. Response curve of preamp shows how closely it follows RIAA characteristics.**





# De-Bugging the Horizontal Oscillator

By **WARREN J. SMITH**

**Phil George gets more bench tips from Harry, this time on horizontal woes.**

THE FACT that small defects can be more difficult to pinpoint than the larger, more dramatic ones has been proved many times on the service bench.

The broad troubleshooting procedures that serve for the majority of likely faults need some additional, refined techniques when it comes to the tricky defects or circuits. Without these refinements, a bench man can find himself enmeshed in some obscure fault for hours. Phil George had good reason to appreciate the meaning of this point:

Harry Gridleak had just buttoned up the FM tuner and was beginning to write up the repair ticket when he spotted Phil mumbling to himself. "What's got you all worked up, Phil?" he asked. "You run into a tough one?"

"I'm afraid so." Phil replied. "If you have a minute to spare a poor, lost soul, come over here and take a look at this portable. It's about to bug me!"

Harry wrapped up his own job and then joined Phil at the bench. "What seems to be the trouble?" he wanted to know.

"Horizontal tearing. Like a lot of other portables, this one uses a multivibrator oscillator with only one frequency adjustment—a slug in the ringing coil. To make the set hold sync, I have to screw the slug all the way in. Even then, it shows a tendency to tear out every so often."

"Make any circuit checks?" Harry asked.

"Are you kidding. I've checked out or substituted for just about every component in the circuit. After isolating the trouble to the oscillator, I plugged in a new tube. That didn't clear up the trouble, so I began checking out voltages, then components, one at a time.

"And what did you find?" Harry wanted to know.

"That's just it—nothing! I figured something must have gone haywire in the frequency-determining networks because sync holds at the extreme setting of the ringing coil. Yet, after checking out every one of these (here Phil pointed successively to each of the components set off with a broken-line circle in Fig. 1), I'm right back where I started nearly an hour ago."

"How about the input grid, Phil? Get an a.c. reading on the v.t.v.m.?"

"Now why should I check the input grid for a.c.? The only voltage that could be there is bias or correction voltage from the a.f.c. circuit trying to hold the oscillator in sync—and it checks out okay."

"Want to make a little bet?" Harry ventured. He sounded very confident.

Phil didn't spend much time thinking over the offer: "Make it coffee and you're on."

Harry nodded, wheeled the scope over to Phil's bench, and clipped its leads into the first grid of the 6CG7. After a few deft adjustments, he got a pattern on the scope screen. "Good grief!" Phil exclaimed. "That's about the meanest-looking signal I've seen on a d.c. grid. What is it?"

"It's a combination of 60- and 15,750-cps signals," Harry replied. "The noise-filter network is defective."

"Bypass the fancy jargon, Harry. Give it to me straight."

"Sure. That means the grid bypass capacitor (.022 μf., in the solid circle of Fig. 1) is probably open. Why don't you try replacing that one?"

"Well doggone; why didn't I think of that?" Phil asked himself. Then he tacked in a new capacitor and fired up the portable. As it came to life, he glanced up at the scope screen: the unwanted signal was gone. After readjustment of the slug in the ringing coil, horizontal sync on the set held tightly. "That's another 'oak-leaf cluster' for you, Harry. You were right again. How did you figure it?"

"I made an educated guess on this one, my young friend. It wasn't so difficult to do after the preliminary work you had done. The input grid of the multivibrator is essentially grounded for a.c. by the noise-filter network. This prevents any random signal that may be heading for the grid, where it could upset oscillator operation, from getting there. Since the tearing was at random and you had eliminated everything else that could affect the operating frequency of the oscillator, there was just about no other conclusion left. Any more questions?"

"Yep. You once showed me a procedure to use in isolating trouble that might involve either the a.f.c. circuit or the horizontal oscillator. (see "Tame TV Dogs with Technique," ELECTRONICS WORLD, July 1959). The idea was to save time by doing things systematically. Now take a case like this one, where isolation went right down to the oscillator. Is there a procedure that

Fig. 1. Harry checked circled components in this multivibrator to no avail.



comes in here? I sure could use one."

"There definitely is, Phil. For top-notch efficiency, any circuit defect should dictate the use of a set procedure. The horizontal multivibrator is no exception. You could have saved about fifty-five minutes of your last hour, in all probability, if you had started out the right way."

"You must be ribbing me, Harry," Phil insisted. "How in the world could I pinpoint the trouble in only five minutes?"

"Well, once you got as far as isolating the trouble to the multivibrator, there are a couple of preliminary quick-checks you should have made right away. In this case, you would have had to go no further."

"All right, then; what are these quick-checks, as you call them?"

"The first is to short out the ringing coil with a jumper to determine whether it is misadjusted or defective. You see, Phil, the ringing coil is actually nothing more than a resonant network to stabilize the operation of an oscillator that is already working: the coil and capacitor simply force the plate current and voltage in the first triode to follow what is essentially a sine waveform. So, if all the other components are within tolerance, the multivibrator should still operate on frequency with the ringing-coil network shorted out."

"And if it doesn't?"

"Then you know the multivibrator itself is off frequency—and you can tell in which direction, too, by the effect on the picture. If it flops over so that the diagonal lines slant upward to the left, the multivibrator is running too slow; if the lines swing upward to the right, the oscillator's too fast."

"I can see that; but how would it have helped me to know?"

"Well, you certainly wouldn't have wasted all that time substituting a new ringing-coil network or cranking the slug."

"But I still wouldn't have pinpointed the trouble, Harry."

"No; but remember that we still have a second quick-check that comes in here. You measure the d.c. grid voltage and check for the presence of a.c. Any a.c. voltage at this point indicates a defective noise-filter network, while excessive d.c. voltage means the multivibrator is unbalanced."

"I begin to see the outlines of what you call a correct approach," Phil said. "But suppose that our trouble wasn't a.c. on the grid. Where would we go from there?"

"Check out the coupling network between the triode stages. Measure the value of the plate ($R_1$ in Fig. 1) and grid ($R_2$) load resistors; and substitute for the coupling capacitor ($C_1$). The free-running frequency of the multivibrator is determined primarily by the time it takes that coupling capacitor to discharge through the grid resistor, so even small changes in value here could result in an off-frequency output that the a.f.c. circuit may not be capable of counteracting. After eliminating this network, we have only the fairly simple waveforming and coupling networks in the output to contend with, and they can be checked out quickly. With a scope, you can check through for correct waveforms in very little time. (Normal waveforms in Fig. 2 are lettered to correspond with the points at which they should appear in Fig. 1) Get it?"




Fig. 2. These waveforms occur at correspondingly lettered points in Fig. 1.

"Got it. I guess we're just about ready to head for Joe's Cafe and the 'big payoff.' Before we do, though, how about helping me get this other set out of the way?" Phil asked nonchalantly.

"What, *another* one?" Harry exclaimed.

"Aw; it shouldn't be tough for an old pro like you. This is the last one to be repaired and I don't want to spend the rest of the day on it," Phil wheedled. He was using the right approach. Harry answered, "All right; what are the symptoms?"

"The picture shimmies all over the screen. It looks like horizontal instability, but it isn't. First I tried new tubes in the tuner, i.f. strip, sync, a.g.c., and horizontal-oscillator circuits, but that got me exactly nowhere. I thought it might be a.g.c. trouble, so I went off in that direction first. Sure enough, clamping the a.g.c. voltage with a fixed external bias cured the shimmy. Then I went through the a.g.c. circuit with a fine-tooth comb, but I couldn't find a thing wrong. The a.g.c. filters all check good. The voltages and signals in the a.g.c. keyer all look normal. Now there almost has to be something wrong with that doggone a.g.c. circuit. My only question is—where?"

"Did you try replacing the horizontal-sweep output tube?"

Phil's tone of voice betrayed his surprise. He asked, "Why in tarnation should I replace the horizontal-output tube?"

"Keyed a.g.c. circuits can get involved in the most peculiar kinds of trouble, Phil. Once you run into something like a gassy horizontal-output tube resulting in mistiming of the plate pulses at the keyer, you don't easily forget it. You don't wind up asking why in tarnation you should replace the output tube."

"Come to think of it, Harry, I can see the possibility. If the timing of the plate pulse at the keyer (Fig. 3) doesn't match the timing of the grid pulse, then the stage isn't conducting when it should be. This means a.g.c. output voltage would be low. Sync pulses would be overamplified or distorted in the i.f. system. That could easily cause sync instability."

While Harry stood patiently by, Phil replaced the 6CD6 and then plugged in the cheater. The picture came up clear and steady, and stayed that way. Phil had only one terse comment: "Simple defects—but, man, can they be tough."

Harry only grinned and said, "Let's go get that cup of java." —30—

Fig. 3. A keyed a.g.c. circuit can be upset by a horizontal-output defect.






Fig. 1. Frequency-division multiplexing in the Type N system.

By RONALD B. TIPTON

**Techniques and circuits employed to permit a single pair of conductors to handle 12 2-way voice channels.**

EVER since 1918 when the first carrier system was put into service, the *Bell System* has been introducing and applying progressively newer versions as they were needed and developed. The first system, designated Type A, has been succeeded by more sophisticated techniques, each of which has been labeled with a letter of the alphabet. In this article the Type N carrier system is described.

### A Carrier System

First, what is a carrier system? In this connotation the term "carrier system" refers to frequency-division multiplexing using open-wire lines, cable pairs, or coaxial cable as the transmission medium. The *Bell System* also employs carrier systems using radio links as the transmission medium but these will not be considered in this article.

"Frequency-division multiplexing," as the term is employed here, is that process of taking several voice channels occupying a band, say from 250 to 3100 cps, and using these voice channels to modulate channel-carrier oscillators—the frequencies of the oscillators being spaced to "stack" the voice channels, leaving a suitable guard space between each channel. For the Type N system, this process is diagrammed in Fig. 1.

The advantages to be gained from such a system are obvious. Without the system a pair of conductors and separate repeater amplifiers would be required for each voice channel. By multiplexing, many channels can be transmitted over a single pair of wires and can be amplified in one wide-band repeater amplifier.

Let us consider the Type N system because the techniques involved are representative of many of the systems in use and because some of its features are of particular interest.

At the end of World War II when material was again available for consumer products and services, the demand for telephone facilities of all types swamped the various operating companies. Much of this demand was for the so-called "short-haul" service, that is, distances from 15 miles to a maximum of about 200 miles. The problem involved was basically an economic one: the high cost of additional equipment for single voice channels in the quantity required *versus* the almost equally high cost of the then-in-use long-distance carrier equipment. It was apparent that a practical solution involved the development of an economical carrier system specifically designed for short-haul use and applicable to existing transmission lines. The result was the Type N carrier system. The various points of this system will be described and then discussed in some detail.

### System Description

The N system is designed to provide twelve two-way voice channels on two pairs of non-loaded cable in two frequency bands, one between 44 and 140 kc. and another between 164 and 260 kc. (Since attenuation and phase shift are functions of frequency in a practical transmission line, series inductance is placed in the line to lessen this effect. This process is called "loading." Obviously, a line without such loading is a "non-loaded" line.) It uses the different bands for transmission in opposing directions. It is a double-sideband system with the carrier being transmitted. The system employs miniaturized equipment and makes use of devices known as "compandors" and a

technique known as "frequency frogging" to improve the system at minimum expense.

The twelve voice channels are evenly distributed through a frequency band of 96 kc., allowing 8 kc. per channel. The voice band is limited to a range of 250 to 3100 cps by a bandpass filter in the terminal equipment. Since double-sideband transmission is used, 6200 cps of each channel is required for the voice band. A signalling or dialing frequency is provided at 3700 cps in each channel, putting another "line" in the spectrum at the channel-carrier frequency, ± 3700 cps. This channel "filling" is indicated in Fig. 2 and, as can be seen, still leaves a guard space between channels.

Transmitting the carrier provides several advantages. It avoids the added expense and complication of requiring accurate channel-carrier supplies at both the receiving and transmitting terminals. Of course, channel-carrier supplies are required at both terminals but they do not have to be maintained to accuracies of only a few cycles-per-second as would be the case with suppressed-carrier transmission. The presence of the carrier also allows gain control in the repeater without transmitting a "pilot frequency" (a steady carrier transmitted over the system for gain regulation). Because this circuit functions much like the automatic volume control in a radio receiver, it needs the carrier to regulate gain according to the carrier's average value.

No. 16, 19, 22, or 24 gauge conductors can be used with the Type N system. Repeater spacing is nominally 8 miles for 19 gauge and 6 miles for 22 gauge. Where geography or other physical limitations determine repeater spacing, they can be located closer together—the missing line attenuation being used up in a "span pad" at the repeater.

Since repeaters are placed wherever convenient, which is usually in the open on a pole, they as well as the transmission lines are subjected to extreme temperature variations. The loss in the conductors is also a function of their temperature and hence the repeater gain must be adjusted to compensate for this temperature-caused variation. Thermistor control elements in the repeater feedback circuit accomplish the regulation.

## Use of Compandors

The word "compandor" is a coined expression derived from the words "compressor" and "expander." The compandor consists of a volume compressor at the sending end of the line and an expander at the receiving end. The compressor provides a gain dependent upon the amplitude of the voice signal applied to it. The expander provides a variable loss which is also dependent on the amplitude of the applied signal. The compandor action on a steady tone is shown in Fig. 3.

What benefits are to be derived from using the compandor? There is always a certain amount of noise on the transmission line, some of it arising from the thermal agitation of electrons in the conductor, some picked up from the atmosphere, and some added by the equipment connected to the line. In the compressor a low-amplitude voice signal is amplified and transmitted at a higher level to override the noise on the line.

Higher voice signal amplitudes need less amplification to maintain the same signal-to-noise ratio. High signal amplitudes are attenuated to help prevent crosstalk between lines. "Crosstalk" is the term used to designate the coupling of energy between parallel lines due to the field produced by one line cutting the field of the other line. Lower transmission amplitudes result in lower intensity fields and hence less crosstalk.

The noise voltage present on an idle line receives the full 28 db attenuation in the expander hence customers are not bothered by a noisy line when neither is talking.

The time-constants of the compandor are chosen for a fast attack of about 3 to 5 milliseconds and a slower release of about 10 times the attack time. This proportion allows the compandor to follow the syllabic speech rate. If the attack were too slow, a high-amplitude speech burst would not receive the proper attenuation and would overload the system. Similarly, too slow a release would allow noise to be audible at the ends of the syllables.

The use of the compandor also offers the following advantages: Operation is possible to a frequency of 260 kc. without the need for far-end crosstalk balancing; repeaters can be spaced about 40 per-cent farther apart than would be possible without the compandor because of crosstalk and line noise; the compandor also makes possible the use of more economical repeater circuitry and transformers since the dynamic range to be handled is narrower—30 db with the compandor as compared with 60 db without it. See Fig. 3.

To avoid degrading the noise advantage of the compandor, the 3700-cps signal frequency is added after the compressor at the sending terminal and removed by filters before the expander at the receiving terminal. Thus the compandor is left to operate only on the voice signals.




Fig. 2. The over-all frequency spectrum for one of the voice channels is shown.




Fig. 3. Compandor action is shown for steady tones at various input levels.




Fig. 4. The "frequency frogging" principle as used in the high-low repeater.

Since many of the lines that were wanted for the Type N system were not originally designed for carrier operation, the compandor keeps the volume on the line contained between the limits acceptable for these lines.

## Frequency Frogging

With "frequency frogging," the output of a repeater is always at a frequency different from the input. For a high-low repeater this is illustrated in Fig. 4. A high-low repeater is one in which the incoming channels are in the high-frequency band (164-260 kc.) and the output is in the low band. A high-low repeater is always followed by a low-high repeater which, in turn, is followed by another high-low unit. The number of repeaters and whether the terminal equipment is high- or low-band must, of course, be determined on the basis of compatibility.

Both the incoming channel groups are mixed with a 304 kc. crystal-controlled signal. Taking the "difference frequency" results in the groups being interchanged or "frogged" in frequency. Selecting the proper sideband after mixing is accomplished by means of filters in the repeater amplifier—a block diagram of which is shown in Fig. 5.

The technique of frequency frogging allows the use of less filtering equipment at the repeaters by eliminating crosstalk around the repeaters. Known as "interaction crosstalk," this results from the output of a repeater being fed back into the input.

In addition to eliminating interaction crosstalk, the channels are inverted in passing through the repeater, that is, the high channel in one line section becomes the low channel in the next line section. Since line attenuation increases with frequency this inversion tends to keep line losses more nearly constant across the twelve voice channels. Repeater gain is also a function of frequency. A curve showing the sum of low-high and high-low repeater gains appears in Fig. 6A as well as a curve of the sum of two cable section losses which appears in Fig. 6B. It can be seen that these curves compensate closely. The residual difference in slopes is easily compensated in the repeater feedback circuit.

Deviation equalization is required at about every tenth repeater to compensate for the mismatch between repeaters and the line.

Although for many applications even the Type N system does not provide adequate facilities for the ever-increasing public demand for telephone service and increased channel systems such as the Types O and ON have been developed to meet these needs, the Type N system is the "father" of short-haul systems in use today.




Fig. 5. Complete block diagram of the repeater amplifier employed in system.

## Acknowledgement

The author wishes to thank John K. Beins of the Toledo (Ohio) Long Lines Department of *American Telephone & Telegraph Company* for his assistance in preparing this article. –30–

Fig. 6. (A) The sum of the low-high and the high-low repeater gains in the carrier system. (B) Curve of the sum of losses that exist along two cable spans which are each 7.5 miles long.









# Estimating Your Business Potential

By **ERNEST W. FAIR** / **Determining your income for the year ahead doesn't have to be all guesswork.**

"WHAT I WOULD give to know how much business we can expect to do next year!" How many shop owners have said something like this at one time or another? Unfortunately, the crystal ball that comes up with complete and infallible answers has not quite been perfected yet.

However, by carefully weighing certain factors that have passed the test of time, one can come quite close in arriving at an estimate. These factors do not speak in exact dollars and cents, but they can give the shop owner a fairly accurate picture of whether he may expect better or worse business in a period just ahead and, to some extent, the degree of such change.

There are many specialists in the fields of economics and statistics who derive their incomes from the ability to anticipate trends in business and industry. The indicators they employ in reaching their decisions can be used, to a great extent, by the individual owner of a small business.

*Area growth.* Your trade area may have become stabilized in the recent past and may no longer be subject to growth in the immediate future. It will be important to recognize this. However, if such growth is happening before your eyes and is certain to carry into the near future—increased industrial or residential construction or improved transportation facilities, for example—it is some assurance that your service area and business can grow.

On the other hand, an examination may indicate actual decline in the area. If so, the probability should be faced. In this, as in all other factors, you are wasting your time if you are not completely honest with yourself. Try to avoid coloring the situation with excessive optimism or pessimism.

*The state of competition.* Even though an increase in the total available business appears probable, your share of it will depend on what other similar businesses in the area will be doing. Are existing competitors becoming more active? Are they enlarging or modernizing their shops, or adding new technicians or trucks? Also, if the pattern of area growth is making new shop locations available, your competitors may increase in number. It is often possible to find out what types of business are scheduled for the new facilities, and every effort should be made to do so. Heavier competition need not mean a decline in your own business. However you can only decide how to counteract it by determining where and how it will come.

*New developments.* New products or significant changes in old ones have important bearing on possible increases in business. There are many reasons for keeping up with every phase of activity in electronics, no matter how unrelated it may seem, and this is one of the most important reasons. Of course, routine improvement in shop equipment, material, and supplies can have some effect in increasing total business, but the real possibilities for greater income exist when new fields are opened up for sales and service. Being alert enough to take advantage of such possibilities can make the difference between a good year and a mediocre one.

*The financial status of customers* will have a profound effect on your own potential. A general sag throughout the nation will be felt by you in one way or another. A prolonged strike in your specific area, involving an industry on which many people depend for their livelihoods, may mean a retrenchment for several months in the future, even after the strike has been settled. Understanding these conditions is useful. For example, the impact of a recession could be relieved with the proper strategy, to some extent. The possibility of saving money by repairing old sets rather than replacing them could be promoted.

*The activities of industries outside of electronics* may have a great effect on your volume, and should therefore be watched. Suppose, for example, that the automotive industry is known to be readying a stepped-up drive for sales in the coming year, based on promotion of design changes. This may mean that some of the consumer money that would ordinarily go to you will end up, along with other money withdrawn from other types of spending, in buying new cars. One industry's gain may be another's loss.

Thus any appraisal of your own future and your own industry must take into account the fact that you are in competition with hundreds of other types of business for customers' dollars, not just with your direct competitors. Do you or your industry have anything "special" to offer (hi-fi, stereo) to counterbalance the enticements of other industries competing for a greater share of consumer spending? Are there any outside industries that promise to grow stronger, attracting more consumer attention in the year ahead?

*Changes in buying and spending habits,* related to the point just mentioned, can have profound effects. Customer

(*Continued on page* 107)

Fig. 1. How intermodulation distortion results from nonlinearity.




# Intermodulation Distortion

## What it is and how it's measured

By **MILTON S. SNITZER** / Technical Editor, ELECTRONICS WORLD

**An important specification in evaluating hi-fi gear that should be thoroughly understood by the audiophile.**

THE earliest and still most common method of checking distortion in hi-fi gear is by the use of a single input frequency in a harmonic distortion check. (See "Harmonic Distortion —What It Is and How It's Measured" in our November, 1959 issue.) Although this method is easy to use and readily duplicated, it may not tell very much about how an amplifier would handle a somewhat more complex input. For example, if we were to apply a mixture of two input signals, one at a low frequency and the other at a high frequency, and we were to check how the amplifier handles these simultaneously and what interactions there are between them, then we would have a better indication of how the even more complex speech and music signals would be handled. This is exactly what we do when we measure intermodulation distortion (IM).

There is currently some disagreement on the value of an IM measurement. There are many in the field who feel that a total harmonic distortion (THD) test made over the entire frequency range adequately describes the amplifier's distortion performance. Following this reasoning, recent standards have been set up for THD measurements but *not* for IM measurement. Despite this, a good many manufacturers quote IM distortion figures so it is important to understand these figures and how they are obtained.

### How IM Is Produced

When two different frequencies are applied to a perfectly linear device (one whose output varies directly in accordance with the input), then the output of the device contains only these two frequencies. On the other hand, when there is any non-linearity, one of the signals is changed or modulated by the other. (See Fig. 1.) When this modulation takes place, additional sideband frequencies are generated just as they are in the modulated stage of a radio transmitter. These additional sideband frequencies are *not* harmonically related to either of the original frequencies. For example, if a large 60-cps signal is combined with a small 6000-cps signal in a non-linear device, the additional frequencies of 5940 (6000−60) cps and 6060 (6000+60) cps are formed. What is more, harmonics of the original two frequencies combine with each other to produce still more "sum and difference" signals. None of these additional signals was present originally, so that we have now introduced distortion.

The amount of this distortion is the r.m.s. sum of all these added sideband signals expressed as a percentage of the modulated signal. In the example just given then, if the square root of the sum of the squares of all the sideband frequencies is 0.1 volt and the amplitude of the 6000-cps signal alone is 5 volts, then the IM distortion is 2 per-cent.

### Audible Effects

There are two audible effects of IM distortion: one of these is the result of the amplitude modulation that occurs and the other is the result of the unharmonically related added frequencies. Assume you are listening to a Bach Chorale with the sopranos being accompanied by a loud, bass passage on the organ. If your equipment has high IM distortion, the voices may have an unpleasant, "fluttery," and unclear sound because these high frequencies are being amplitude modulated by the low-frequency tones of the organ.

Fig. 2. Functional block diagram of IM analyzer. Waveforms at various points in the instrument are shown in Fig. 1.



In addition to this effect, any time that you listen to any combination of tones, or even a single tone that is anything but a simple sine wave, the added frequencies due to IM distortion introduce a roughness or harshness that seems to "muddy up" the original tones. Any added frequencies, whether harmonically related or not, constitute distortion. But when these frequencies are not harmonically related, then the audible effects are quite unpleasant.

## Limits of IM

In measuring IM distortion it is common to apply to the equipment under test a large low-frequency signal along with a small high-frequency signal. The usual ratio between the two amplitudes is 4 to 1 (12 db). Low frequencies in common use are 40 cps, 60 cps, 100 cps, and 150 cps; high frequencies in common use are 3000 cps, 4000 cps, 6000 cps, and 15,000 cps.[1] Depending on which frequencies are used, and their related amplitudes, different IM distortion figures will be obtained. Therefore, it is important to state just what frequencies and amplitudes are used in a given test when specs are quoted. It is also important to state the power level at which the measurement is made.

The amount of IM distortion that should be present in top-quality hi-fi equipment has been the subject of much discussion. According to one authority[2] the following arbitrary grouping is given:

| AMPLIFIER | IM |
|---|---|
| Very high-fidelity (lower test freq., 40 cps) | Less than 2% |
| High-fidelity (lower test freq., 40 cps) | Less than 4% |
| Good fidelity (lower test freq., 60 cps) | Less than 8% |
| Fairly good fidelity (lower test freq., 60 cps) | Less than 2?% |

Recently the *Heath Co.* has set up its own standards for IM distortion l'mits on power amplifiers. Its groupings, using test frequencies of 60 and 6000 cps at a 4:1 ratio, are as follows:

| AMPLIFIER | IM |
|---|---|
| Professional | 1% or less |
| High-fidelity | 2% or less |
| Utility | 3% or less |

In our own lab-tested reports as well as in the specifications quoted by a large number of companies in the field, an IM distortion figure of 1 per-cent is used. If we find that an amplifier will not produce its full rated output power at 1 per-cent IM, then we down-rate the unit. Admittedly this is an extremely strict specification to meet but we feel that it is fair provided all units are subjected to the same criterion.

## IM Compared with THD

In general, when an amplifier has low intermodulation distortion, it also has low total harmonic distortion (THD). When the IM is high, so is the THD. However, it must be remembered that these two methods of measuring distortion are quite different, so it is logical to expect that the percentage figures for IM and THD will not be the same.

The relation between IM and THD in a hypothetical amplifier is shown in Fig. 3. These curves are fairly typical. Note that at low power outputs (up to about 11 watts in this case) the IM distortion is less than the THD, as measured at the extremes of the frequency range to be covered (say 20 or 20,000 cps). At 10 watts output, the IM of this particular amplifier is 1% while the THD is 2%. It is quite accidental that these two figures, which we use as our own standards, occur at the same power level. But observe what happens at the higher power levels. First, the IM goes upward a little more suddenly than does THD. For this reason, many feel that the IM measurement is a much more sensitive indication of amplifier overload. Second, the two distortion curves cross each other so that the value of the IM becomes higher than the value of the THD.

If the harmonic distortion measurements are made at the mid-frequencies (400 or 1000 cps), our amplifier is seen to produce much less THD. Under these conditions, it is not uncommon for the value of THD to be less than the value of IM at all power levels. In the case of our hypothetical amplifier, an output power of 13 watts is produced at a THD of 2 per-cent. At this power level, the IM is close to 8 per-cent, or almost 4 times as great.

It is quite possible to have a totally different relation between IM and THD than is shown in Fig. 3. The design of the amplifier being checked, and particularly how it overloads, may change this picture markedly.

## IM Analyzers

Although IM distortion can be measured with separate audio generators, filter circuits, oscilloscope or meter indicators, common practice is to combine many or even all the functions needed into a single instrument. This instrument may be called an IM analyzer. A block diagram of all the functions performed by such an instrument is shown in Fig. 2.

(*Continued on page* 142)




Fig. 3. Relation between IM and total harmonic distortion in hypothetical amplifier.

Fig. 4. Test setup employed for checking IM distortion of a high-fidelity amplifier.




[1] This method is the one specified by the Society of Motion Picture & Television Engineers.
[2] "Radiotron Designer's Handbook" Fourth Edition—edited by Langford-Smith.




A 9-volt battery runs this 144-mc. transistorized v.h.f. amateur transmitter.

# Two-Meter Transistor Transmitter

By **DONALD L. STONER, W6TNS**

**Two micro-alloy-diffused type v.h.f. transistors are used in this 20-mw. battery-operated ham transmitter.**

Fig. 1. MADT transistors are used in the r.f. portion of this transistorized rig.




*$R_1$—220 ohm, ½ w. res.*
*$R_2$—22,000 ohm, ½ w. res.*
*$R_3$—5000 ohm miniature pot (see text)*
*$R_4$—100 ohm, ½ w. res.*
*$R_5$—1 megohm, ½ w. res.*
*$R_6$—4700 ohm, ½ w. res.*
*$R_7$—270,000 ohm, ½ w. res.*
*$C_1$, $C_2$, $C_4$, $C_9$—.001 μf. button capacitor*
*$C_3$—1.8-8.7 μμf. variable capacitor (E. F. Johnson 9M11 or equiv.)*
*$C_5$—3.5-12 μμf. trimmer (Centralab 827B)*
*$C_6$—4.7 μμf. disc ceramic capacitor*
*$C_7$—1.5-5 μμf. variable capacitor (E. F. Johnson 5M11 or equiv.)*
*$C_8$—3.3 μμf. disc ceramic capacitor*
*$C_{10}$—7-35 μμf. rotary trimmer (Centralab 827D)*
*$C_{11}$, $C_{12}$—20 μf., 10 v. miniature elec. capacitor*
*$C_{13}$—.001 μf. disc ceramic capacitor*
*$RFC_1$, $RFC_2$—40 t. #36 en. wound on 1 megohm, ½ w. res. (see text)*
*$J_1$—BNC style antenna connector (Amphenol)*
*$J_2$—Three-circuit mike jack*
*$T_1$—Plate-to-speaker trans. (Triad TY-44X or equiv.)*
*Xtal.—72.05 mc. fifth overtone crystal (International FA-9)*
*$L_1$—7¾ t. #20 silver-plated wire, ¾" dia., spaced dia. of wire, 16 turns-per-inch (Air Dux 616, see text)*
*$L_2$—4½ t. #20 silver-plated wire, ¾" dia., spaced dia. of wire, 16 turns-per-inch (Air Dux 616, see text)*
*$L_3$—20 t. #32 en. wound on 1 megohm, ½ w. res. (see text)*
*$L_4$—4½ t. #16 silver-plated wire, ½" i.d. spaced dia. of wire*
*$L_5$—3 t. #16 silver-plated wire, ½" i.d. spaced dia. of wire*
*$V_1$—"p-n-p" transistor (Philco 2N500—oscillator)*
*$V_2$—"p-n-p" transistor (Philco 2N502—buffer/doubler)*
*$V_3$, $V_4$—"p-n-p" transistor (2N44 or 2N217—speech amplifier and modulator)*
*$B_1$—9-volt mercury cell (RCA VS312)*
*1—Aluminum chassis, 2⅛" x 5¼" x 3" (LMB TF-780)*

IT WAS just about three years ago that I built my first transistor oscillator circuit. It was a so-called "wireless microphone" that operated at the high end of the broadcast band. I remember thinking at the time that it delivered a tremendous amount of power (probably less than one milliwatt) and at such a high frequency too!

Times have certainly changed. Since then manufacturers have developed "drift," MADT, and MESA high-frequency transistors. It is not at all uncommon to read about a transistor that will deliver a very respectable amount of power at 750 mc. The wide acceptance of these new types is slowly but surely driving the price down to the experimenter's level. Increased production will soon bring the cost down within the reach of everyone.

The *Philco* 2N500 and 2N502 MADT (micro-alloy-diffused type) high-frequency transistors were selected for this two-meter transmitter as a reasonable compromise between performance and price. The 2N500 will set you back about $10.90 while the 2N502 (oscillates to 750 mc.) sells for $12.40. You can obtain much more power output by using the new MESA transistors but their price tags run into the $30-$40 class. A pair of *Philco* 2N588's (also MADT type) can be substituted and they cost only $6.00 each. However, the power output will be somewhat lower with this type.

## The Circuit

The schematic for the two-meter transistor transmitter is shown in Fig. 1. The 2N500 and 2N502 are both employed in a common-base circuit which appears to produce more power output near *alpha* cut-off. The 2N500 is used as a fifth overtone crystal oscillator with the feedback path between the collector tuned circuit and the emitter. The emitter choke, $RFC_1$, provides a low impedance path for the emitter current but effectively blocks the r.f.

Resistor $R_1$ prevents the stage from going into thermal runaway. The stage is biased by connecting the base to the junction of a voltage divider across the battery. Capacitor $C_{12}$ blocks the d.c. while inductance $L_3$ neutralizes the crystal and holder capacity (more about this later). Tank circuit $L_1$ is tuned to the fifth overtone frequency of the crystal, in this case 72.05 mc., with $C_3$.

Output from the oscillator drives the buffer/doubler through $L_2$ and $C_5$. In effect, this is a series-tuned circuit with a low impedance between emitter and ground. This stage is self-biased with r.f. drive. Whenever a positive half cycle arrives at the emitter, the stage conducts. During the negative half cycle period, it "rests," producing true class C operation. Any attempt to apply bias to the 2N502 will reduce the power output! Resistor $R_4$ provides emitter stabilization and the r.f. choke, $RFC_2$, functions the same as in the oscillator section. Although this stage is driven with 72-mc. energy, the collector circuit is tuned to the second harmonic, or 144 mc., with $C_7$ and $L_4$. A small 3.3-$\mu\mu$f. disc capacitor is connected between $L_4$ and the emitter to provide a small amount of regeneration, which enhances the doubling action. The size of this capacitor can be adjusted empirically for maximum power output. The output coil, $L_5$, couples r.f. to the antenna and capacitor $C_{10}$ is used to tune out the link reactance.

The modulator system is ultra-simple and by no means optimum. It served the purpose for contacts and demonstrations but does suffer from the "leave well enough alone" philosophy. There is excessive gain and talking any closer than one foot from the mike produces overmodulation. In addition, core saturation and voltage loss occur in $T_1$. Quite possibly a push-pull collector-to-speaker transformer would produce better modulation (naturally the speaker winding would not be used). Either 2N44's or 2N217's can be used equally well in this circuit. No matter which transistors are used, $R_5$




Fig. 2. Detector load may be 50-75 ohms.

should be adjusted for 1 ma. collector current in $V_3$ and $R_7$ should be set so that $V_4$ draws about 2 ma.

## Construction

The first step in the construction of the unit consists of winding the r.f. chokes and coils. Both $RFC_1$ and $RFC_2$ were wound on tiny powdered iron forms that look like ¼-watt resistors. Half-watt resistors, used as forms, have been substituted with no change in performance or drive. The only requirement is that these chokes be self-resonant at 72 mc. with the leads extended. The exact number of turns is relatively unimportant, but keep the winding neat and avoid scramble winding.

Coil $L_3$ is very important! If it is not resonant at the correct frequency, you will never tame the oscillator. When made as described, the oscillator will be "rock solid," as the saying goes. Wind $L_3$ as instructed in the parts list. Clip the leads to ⅜", solder to the crystal holder, and insert the crystal. Couple a grid-dipper to $L_3$ and measure the resonant frequency. It should be about 5% *higher* in frequency or somewhere between 75 and 77 mc. The meter may show a bit of "gyration" at 72 mc., but there should be a solid dip at the higher frequency. The idea of this coil is to neutralize the crystal and holder capacity. If the coil were not in the circuit, the crystal would look like a small capacitor and the 2N500 would oscillate at whatever frequency $L_1$ and $C_3$ were tuned to. When properly tuned, the path looks like a high impedance, except at the 5th overtone crystal frequency. Coils $L_1$, $L_2$, $L_4$, and $L_5$ are wound with silver plated wire. Whether this increases the circuit efficiency or not is problematical. The books all say that it *should!* The silver-plated "Air Dux" is a standard item, or you can have regular tinned wire plated at the local silversmith.




Audio portion of the 2-meter transmitter. The transistors are supported by means of their leads; no sockets are employed. Either 2N44 or 2N217 types can be used.

The r.f. portion of the transmitter. The rig was properly tuned up with the variable capacitors in the positions shown. $C_6$ was replaced later with a fixed capacitor.




The layout does not seem to be critical and the circuits are very stable with the straight-line construction used. A small potentiometer should be used as there is some crowding at this end of the chassis. If you like, you can substitute a 4700-ohm, ½-watt resistor for the pot as most 2N500's work best with the pot wide open, anyway. I find it handy, however, for impressing people with how low into the microwatt region they can still receive my signal. The mike jack really belongs on the other side of the divider. I must confess I placed it there to fill up a hole! The

(*Continued on page* 82)



By JOHN POTTER SHIELDS

**Basic information and construction details on "debugged" circuits used to detect presence of people or objects.**

# The Capacitance Relay

THE capacitance relay was developed a number of years ago and, since that time, has received a moderate amount of attention from both experimenters and industry. Innumerable circuits have been developed—many of which have been very successful. Unfortunately, many experimenters who have tried either to develop their own versions or build up commercial circuits have obtained unsatisfactory results. It is the purpose of this article to describe the various "bugs" that may be encountered in the design and construction of capacitance relays and outline several novel, but thoroughly "de-bugged," circuits with which the writer has had success.

## Applications

Capacitance relays are quite versatile and, unlike "electric eyes," require no light beam source. They are not directional as are most photoelectric setups and since no light beam is needed, the presence of a capacitance relay alarm can remain undetected by an intruder. For example, suppose you want to signal the entry of a person through a doorway. All that is needed here is a length of wire strung around the door frame. Very fine wire can be used and the control unit placed out of sight, making the installation virtually undetectable.

An installation of this type can also be used to count the number of people or objects passing through a given area, such as an interior doorway or entrance to a building. An installation made by the author is shown in Fig. 1. The wire was strung around the door frame to act as a sensing element. The plate-circuit relay was used to actuate a stepping relay. When a person entered the room, the capacitance relay was tripped, closing the plate relay. This sent a current impulse to the stepping relay, causing it to advance and turn on the room lights. When the person left the room, the capacitance control was again tripped, the relay advanced another step, and the room lights were switched off.

Capacitance relays may also be used to count objects on conveyor belts, in chutes, etc. They are especially useful in places where fumes or dust-ladened atmosphere would quickly cloud the optical system of a conventional photoelectric setup.

Perhaps the most popular use of capacitance relays has been in store window displays. You may have seen setups where a model train or other animated device was set in motion when a bystander placed his hand near a metal plate or wire on the window. Another possible use for capacitance relays is in the industrial field. As an example, the relay could be used to protect the operator of a punch press, drill press, etc. In operation, a wire "sensing probe" could be arranged so that when the operator's hands were in a dangerous area around the machine, it would be automatically shut off.

Now that we have explored some of the applications for capacitance relays, let's take a look at their design and construction. Possibly one of the biggest headaches for the builder of a capacitance relay is that of stability.

Fig. 1. Installation made by the author.




Many a constructor will find that after he has finished and adjusted his relay it will not retain its initial setting. There are several ways of handling this problem and these will be covered later. Now let us consider the basic circuit.

## Basic Circuit

Fig. 2A is a schematic of one of the commercial capacitance relays. There is at least one manufacturer who has developed a special coil for this circuit. Circuit operation is quite simple. The trimmer, $C_1$, is adjusted so that enough feedback voltage is available to permit the circuit to oscillate feebly. In this condition a negative grid voltage will be developed by the tube which will hold the plate current at a low level. When an object approaches the "sensing element" the circuit will be "loaded down" causing it to cease oscillating. When this occurs, the plate current will rise due to the lack of negative grid voltage and the plate circuit relay will close. So far, so good—but—perhaps you have tried to use this circuit with a d.c. plate-voltage supply and found the results unsatisfactory. The reason for this is that with a d.c. plate supply, once the oscillator stops oscillating due to the loading provided by an object approaching the sensing element, it stays stopped. If you will notice, the original circuit probably called for an a.c. plate voltage supply. The reason for this is that with an a.c. plate supply the oscillator will be conducting — hence oscillating — once on every positive half cycle. When the oscillator is loaded to the point where it ceases to oscillate, it will be shocked back into an oscillating condition when the loading is removed by the next positive half cycle of plate voltage.

A d.c. plate supply can be used for




*$R_1$—100,000 ohm, ½ w. res.*
*$R_2$—1000 ohm, ½ w. res. (Fig. 2B)*
*$C_1$—160-500 μμf. mica padder*
*$C_2$—500 μμf. mica capacitor*
*$C_3$—10 μf., 50 v. elec. capacitor*
*$C_4$—.001 μf., 600 v. mica capacitor*
*$L_1$—10 mhy. air-core r.f. choke*
*$RFC_1$—2.5 mhy. r.f. choke*
*$RL_1$—S.p.d.t. relay, 5000-ohm coil (Potter & Brumfield LM5 or equiv.)*
*$V_1$—6AQ5, 6V6, 50L6, etc. tube*

Fig. 2. (A) Circuit of commercial capacitance relay. (B) Circuit with d.c. supply. Sensor, blocking capacitor are not shown.

the capacitance relay, as indicated in Fig. 2B. A resistor is connected between the cathode of $V_1$ and "B—". With this resistor in place the d.c. plate current flowing through $V_1$ will cause a voltage drop across the resistor, making the cathode more positive than the grid. This makes the grid effectively negative with respect to the cathode. Now, when the oscillator is loaded by an object approaching the sensing element, the circuit will not cease to oscillate entirely due to the fact that the grid of $V_1$ is being held slightly negative with respect to its cathode and can therefore "bounce back" to its original oscillating condition after the loading has been removed. This cathode resistor also tends to stabilize the oscillator with respect to temperature and line voltage variations.

Fig. 3 is a practical circuit incorporating the foregoing features. It is a highly sensitive and stable device employing two tubes—a 6J5 oscillator and a 2050 thyratron relay tube. If desired, the tubes' miniature counterparts, a 6C4 and 2D21, can be used. As will be noted, the oscillator stage in this relay is essentially the same as the one shown in Fig. 2B. The 2050 was used to increase the sensitivity of the circuit. In the circuit of Fig. 2B, the relay is inserted directly into the oscillator plate circuit while in the modified circuit of Fig. 3 the relay is in the plate circuit of the 2050 thyratron.

The 2050 is a very interesting tube. Like all thyratrons, it possesses certain properties not shared by the more popular vacuum tube. A thyratron's plate current will remain completely cut off until its control grid is made more positive than the cathode. When this occurs, the gas in the thyratron will suddenly ionize, causing a rather heavy flow of plate current. Once the thyratron has been ionized, the control grid loses all control over the flow of plate current. It is similar to the operation of a s.p.s.t. switch, *i.e.*, "go or no-go." The advantage of this feature is that a very slight voltage differential on the control grid will cause the tube to change from a non-conducting to a conducting state. The 2050 is connected to the grid of the oscillator stage through an isolating resistor and its cathode is connected to the movable arm of a pot which is connected between "B+" and ground. This is the "sensitivity" control.

The adjustment of the "sensitivity" control potentiometer is quite critical and must be done carefully if the capacitance relay is to operate satisfactorily.

The proper adjustment procedure is to set the potentiometer to such a point that the thyratron *just* does not fire with no object near the sensing plate.

Now, when the oscillator is loaded down by the approach of a body to the sensing element, the oscillator grid voltage will drop, causing a corresponding drop in the negative grid voltage on the 2050. This will make the grid less negative with respect to the cathode of the 2050, causing it to fire and closing the plate circuit relay. If great sensitivity is not required, the pot can be adjusted so that the 2050 cathode is somewhat more positive than the negative grid voltage from the oscillator. The sensitivity of this circuit is excellent. For example, with a six-foot length of hookup wire strung around a door frame, a person of average height, standing four feet from the doorway, will trip the relay.

Recently the author was asked to develop a lightweight, portable, and extremely stable capacitance relay. The resulting circuit is shown in Fig. 4 and is somewhat similar to the one shown in Fig. 2B but powered by a six-volt, vibrator-type power supply. If desired, a combination-type power transformer can be used to provide operation on both 6 and 117 volts. Several such transformers are available commercially from most parts jobbers.

The sensing element for the portable capacitance relay consists of one of the metal panels from the *Bud* cabinet which was used to house the device. The metal panel is insulated from the case itself by two ceramic stand-off insulators. The unit is powered by four 6-volt batteries that have been connected in parallel.

This portable capacitance relay was designed for use in a steel mill. The crane operator placed the unit some distance down the crane runway with the contacts of the plate-circuit relay connected so that as the crane trolley approached, the operator could be alerted by means of a warning bell. Other possible uses for this portable capacitance relay include intrusion alarms, portable counter applications, annunciators, etc.

## Another Circuit

Another rather unusual capacitance relay is shown in Fig. 5. Here it was desired to have the sensing element

Fig. 3. Practical circuit of sensitive, stable capacitance relay.




*$R_1$—33,000 ohm, ½ w. carbon res.*
*$R_2$—1800 ohm, ½ w. carbon res.*
*$R_3$—4700 ohm, ½ w. carbon res.*
*$R_4$—68,000 ohm, 1 w. carbon res.*
*$R_5$—20,000 ohm, 1 w. linear-taper pot "Sensitivity")*
*$C_1$—160-500 μμf. mica padder*
*$C_2$—500 μμf. mica capacitor*
*$C_3$—.001 μfd., 600 v. capacitor*
*$C_4$—10 μf., 50 v. elec. capacitor*
*$L_1$—10 mhy. air-core r.f. choke*
*$RFC_1$—2.5 mhy. r.f. choke*
*$RL_1$—S.p.d.t. relay, 5000-ohm coil (Potter & Brumfield LM5 or equiv.)*
*$V_1$—6J5 or 6C4 tube (see text)*
*$V_2$—2050 or 2D21 thyratron (see text)*




Fig. 4. Complete schematic diagram and parts listing for the lightweight, portable capacitance relay unit with vibrator supply described by author. The metal panel sensing element was connected through a blocking capacitor to the high side of coil $L_1$.

*$R_1$—10 megohm, ½ w. carbon res.*
*$R_2$—47 ohm, 2 w. carbon res.*
*$R_3$—15,000 ohm, 10 w. wirewound res.*
*$C_1$—160-500 μμf. mica padder*
*$C_2$—10 μf., 50 v. elec. capacitor*
*$C_3$—.008 μf., 1600 v. paper capacitor*
*Vib.—6-volt vibrator*
*$T_1$—6-volt vibrator transformer*
*$L_1$—456 kc. oscillator coil (Meissner 14-4034 or equiv.)*
*$S_1$—S.p.s.t. toggle switch ("Reset")*
*$RL_1$—S.p.d.t. relay, 5000-ohm coil (Potter & Brumfield LM5 or equiv.)*
*$B_1$—Four 6-volt "A" batteries (wired in parallel)*
*$V_1$—6AQ5 tube*

some distance from the actual device. In order to avoid stray pickup from the lead, a shielded connecting cable had to be used. This ruled out the basic circuit shown in Fig. 2B as the shunt capacitance of the connecting cable would contribute too much additional capacitance. The circuit of Fig. 5 overcomes this problem as follows: Two oscillators, operating at a rather low frequency, approximately 100 kc., are used and their outputs fed into a mixer stage. The output from the mixer stage is fed into a low-pass filter, the output of which is applied to the grid of the 2050 or 2D21 thyratron. One oscillator is fixed-tuned and the other is made variable by means of the trimmer, $C_2$. The sensing element and its shielded cable are connected across the tuned circuit of the variable frequency oscillator. The shunt capacitance of the shielded cable, together with the distributed capacitance of the oscillator coil and associated wiring, determine the variable frequency oscillator's operating frequency. The length of the shielded cable will naturally be the major single frequency determining element. In operation, the variable frequency oscillator is so adjusted that with no object near the sensing element, it will be 1000 cps above the frequency of the fixed frequency oscillator.

There are *two* possible adjustments here. One is where the variable frequency oscillator is set 1000 cps *below* the frequency of the fixed frequency oscillator and the other is where the frequency is set 1000 cps above. The latter setting is the correct one. Thus, when an object approaches the sensing element, the capacitance of the tuned circuit of the variable frequency oscillator will increase, lowering its frequency, causing the output or "beat frequency" obtained from the mixer stage to decrease in frequency. Since a low-pass filter stage is connected between the mixer and thyratron relay stages, the voltage applied to the thyratron grid will increase with a corresponding decrease in the output frequency from the mixer. When this voltage becomes great enough, the thyratron will fire, closing the plate-circuit relay. The same thyratron biasing scheme is used in this circuit as was used in that of Fig. 3. As will be noted, the resultant beat frequency is applied directly to the thyratron grid without benefit of rectification. No improvement was noted when the signal was rectified before being applied to the thyratron grid.

## Construction

Now for a look at some of the "bugs" that can crop up in the construction of capacitance relays. For example, let's consider the construction of the relay just described. In a device of this type, proper mechanical construction is extremely important. Mechanical rigidity is of utmost importance. The chassis should be of fairly heavy gauge material and, if a panel is used, it should be firmly attached to the chassis. All components should be securely fastened to the chassis and/or panel, paying particular attention to those components in the tuned circuits.

Voltage regulation is recommended and, along these lines, the author has found that a small NE-2 neon lamp makes an excellent and inexpensive voltage regulator tube. When constructing several units using the circuit of Fig. 5, the author employed a 100 kc. crystal oscillator as the fixed-frequency oscillator.

There are many other circuits, of course, that could be used in assembling a capacitance relay but space precludes describing all of them. The ones covered in this article are those that the author has actually constructed, tested, and "de-bugged." They really work, so don't hesitate to try any, or all of the circuits, should you have need for a capacitance relay. –30–

Fig. 5. An unusual capacitance relay circuit built by author in which sensing element was some distance from actual device.




*$R_1$, $R_2$—47,000 ohm, ½ w. res.*
*$R_3$, $R_7$—470,000 ohm, ½ w. res.*
*$R_4$—2200 ohm, ½ w. res.*
*$R_5$, $R_9$—100,000 ohm, ½ w. res.*
*$R_6$—150,000 ohm, ½ w. res.*
*$R_8$—4700 ohm, ½ w. res.*
*$R_{10}$—68,000 ohm, ½ w. res.*
*$R_{11}$—82,000 ohm, ½ w. res.*
*$R_{12}$—68,000 ohm, 1 w. res.*
*$R_{13}$—20,000 ohm, 1 w. linear-taper pot ("Sensitivity")*
*$C_1$, $C_2$—500 μμf. mica capacitor*
*$C_3$—160-500 μμf. mica padder*
*$C_4$—300 μμf. mica capacitor*
*$C_5$—.001 μf., 600 v. capacitor*
*$C_6$—.01 μf., 600 v. capacitor*
*$C_7$, $C_8$, $C_9$—.02 μf., 600 v. capacitor*
*$C_{10}$—.05 μf., 600 v. capacitor*
*$C_{11}$—10 μf., 50 v. elec. capacitor*
*$L_1$, $L_2$—456 kc. oscillator coil (Meissner 14-4034 or equiv.)*
*$RL_2$—S.p.d.t. relay, 5000-ohm coil (Potter & Brumfield LM5 or equiv.)*
*Cable—RG/62U shielded coax.*
*$V_1$, $V_2$—12AU7 or 6SN7 tube*
*$V_3$—2050 or 2D21 thyratron*

# GET *more!* DO *more!* MAKE *more!*

PROFIT PROFESSIONALLY ON EVERY CALL WITH

## NEW B&K LOW-COST PROFESSIONAL Model 550 DYNA-QUIK

DYNAMIC MUTUAL CONDUCTANCE TUBE TESTER

Model 550

NET $119.95

Every service-technician now can easily check tubes the B&K professional way! Only with a *genuine dynamic mutual conductance tube tester* can you make a complete and accurate test under the actual dynamic operating conditions of the TV set. The compact new "550" is not just an emission checker. *It completely checks more tubes faster*—with laboratory accuracy. And the cost is so amazingly low, it pays its way over and over again! Take a tip from thousands of professional servicemen—*use B&K Dyna-Quik*. There is nothing like it.

***Get More for Your Money***
**—IN SPEED, ACCURACY, AND VALUE**

***Save Customers***
**—SAVE CALL-BACKS, SAVE COST**

***Sell More Tubes***
**—MAKE MORE MONEY PER CALL**

### MODEL 550 DYNA-QUIK TUBE TESTER

***Tests Each Section of Dual-Section Tubes Separately***

Great new value in professional quick-check at small cost. Provides more tube sockets to test more tubes faster. Accurately checks most of the TV and radio tubes usually encountered in everyday service work. Tests each section of dual-section tubes separately. **Measures true dynamic mutual conductance.** Checks tubes for shorts, grid emission, gas content, and leakage. Completely tests each tube in seconds, checks average TV set in a few minutes, in home or shop. One switch tests everything. Fast, convenient reference listings on socket panel. Patented circuit provides automatic line voltage compensation. 7-pin and 9-pin straighteners on panel. Handsome, luggage-type carrying case. Net, $119.95

### MODEL 650 DELUXE DYNA-QUIK

***Today's Finest Portable Tube and Transistor Tester***

Accurately checks over 99% of the tubes most widely used in television receivers, plus popular home and portable radio tubes. Tests over 600 tube types. Lists over 125 most popular tube types, with settings, on socket panels for maximum operating speed. Complete listing in fast, index-type selector. **Measures true dynamic mutual conductance.** Tests each section of multiple tubes separately for GM, Shorts, Grid Emission, Gas Content and Life. Includes 16 spare sockets and ample filament voltages for future new tube types. **Transistor Section** checks transistors, diodes, and selenium rectifiers. Luggage-type carrying case. Net, $169.95



Model 650

***See Your Distributor or Send Now for Bulletin ST24-N***

B&K

**B&K MANUFACTURING CO.**
1801 W. BELLE PLAINE AVE · CHICAGO 13, ILL.

Canada: Atlas Radio Corp., 50 Wingold, Toronto 10, Ont.
Export: Empire Exporters, 277 Broadway, New York 7, U.S.A.

## EVERYTHING A CLOCK-RADIO CAN OFFER . . . AND PORTABLE TOO!

- Completely portable, all-transistor circuit
- Runs up to 500 hours on standard batteries
- Deluxe features at half the cost
- Easy to assemble

HEATHKIT TCR-1
**$45.95**

### "YOUR CUE" TRANSISTOR CLOCK RADIO KIT (TCR-1)

Take all the deluxe features found in the most expensive clock-radios, add the convenience of complete portability, plus a modern 6-transistor battery operated circuit . . . then slash the price at least in half, and you have the new Heathkit "Your Cue" Transistor Portable Clock Radio.

Packing every modern clock-radio feature into a compact, beautifully styled turquoise and ivory plastic cabinet, "Your Cue" lulls you to sleep, wakes you up, gives you the correct time and provides top quality radio entertainment in and out-of-doors. It can also be used with the Heathkit Transistor Intercom system, opposite page, to provide music or a "selective alarm" system for one or more rooms covered by the intercom system.

An "Alarm-set" hand, hour hand, minute hand and sweep second hand grace the easy-to-read clock dial. All controls are conveniently located and simple to operate. The "lull-to-sleep" control sets the radio for up to an hour's playing time, automatically shutting off the receiver when you are deep in slumber. Other controls set "Your Cue" to wake you to soft music, or conventional "buzzer" alarm. A special earphone jack is provided for private listening or connection to your intercom or music system. At all times crystal-clear portable radio entertainment is yours at the flick of a switch.

The modern 6-transistor circuit features prealigned IF's for ease of assembly. A tuned RF stage and double tuned input to the IF stage assure top performance. The built-in rod-type antenna pulls in far-off stations with outstanding clarity while a large 4" x 6" speaker provides tonal reproduction of unusual quality.

Six easily obtainable penlight-size mercury batteries power the radio receiver up to 500 hours, while the clock operates up to 5 months from a single battery of the same type. Ordinary penlight cells may also be used with reduced battery life.

The handsome two-tone cabinet, measuring only 3½" H. x 8" W. x 7½" D. fits neatly into the optional carrying case for beach use, boating, sporting events, hunting, hiking, or camping.

Wherever you are, you'll find "Your Cue" your constant companion. Shpg. Wt. 5 lbs.

**HEATH COMPANY**/Benton Harbor, Mich.

a subsidiary of Daystrom, Inc.

# New Transistor Intercom Kit

## TALK WITH ANY OR ALL FIVE STATIONS WITH YOUR OWN INTERCOM SYSTEM

- Battery Power Permits Placement Anywhere
- Versatile Unit has Many Important Uses
- Complete Privacy of Conversations Assured

### TRANSISTOR INTERCOM KIT (XI-1 and XIR-1)

A flexible, versatile transistor intercom, has been developed by Heath engineers to enable you to set up your own communications system at an unbelievably low price.

Consisting of a master unit (XI-1) and up to five remote stations (XIR-1), the system is designed for any remote unit to call the master, for any remote station to call any other remote station, or for the master unit to call any single remote unit or any combination of remote units. Complete privacy is assured, since a call to a remote station cannot be interrupted or listened to while the remote unit is in operation unless switched in by the master unit. Used with clock-radio, opposite page, it can serve as a music or "selective alarm" system.

Transistor circuitry means long life, instant operation and minimum battery drain. Eight ordinary, inexpensive "C" flashlight batteries will run a unit for up to 300 hours of normal "on" time. Circuitry is especially designed for crisp, clear intelligible communication and the instant operation feature allows tuning of the units off between calls, extending battery life. Use of battery power does away with power cords, allowing each unit to be placed where most convenient. Only two wires are required between the master unit and each remote station. Beautifully styled, the Heathkit Intercom presents a new approach in design. Both master and remote stations have two-piece cases in ivory and turquoise for a rich, quality appearance. Batteries not included. Shpg. Wt. 6 lbs.

HEATHKIT XI-1 (Master)

**$27.95**



HEATHKIT XIR-1 (Remote)

**$6.95**

Shpg. Wt. 4 lbs.

### AC POWER SUPPLY (XP-1)

A permanent power supply for 24-hour operation of the XI-1 Intercom on household current. Converts 110 V. AC to well filtered 12-volt DC output, eliminating the need for batteries. Power supply is small, compact and fits in space normally occupied by batteries.

HEATHKIT XP-1 ..... $9.95

## NEW IMPROVED DESIGN

### STEREO-MONO PREAMP KIT (SP-2A, SP-1A)

Get the SP-2A Stereo Preamp kit now, or the SP-1A monophonic version which you can easily convert to stereo whenever you choose by assembling the second channel (C-SP-1A) and plugging it into your SP-1A.

The SP-2A permits stereo, two channel mixing, or either channel monophonic use, and includes a remote balance control.

Six inputs (12 in the stereo version) accommodate tape, magnetic phono and microphone, plus three separate high level inputs. Level controls provided on "mag. phono" and high level inputs. Switch selects NARTB equalization for tape head input, and RIAA, LP or 78 RPM compensation for mag. phono input

HEATHKIT SP-1A (monophonic) Shpg. Wt. 13 lbs. ..... $37.95

HEATHKIT C-SP-1A (not shown) (converts SP-1A to SP-2A) Shpg. Wt. 4 lbs. .... $21.95

New

HEATHKIT SP-2A (stereo) Shpg. Wt. 15 lbs.

**$56.95**

$5.70 down. $8.00 mo.

## THE WORLD'S BIGGEST BARGAIN IN A HI-FI AMPLIFIER

### 55 WATT HI-FI AMPLIFIER KIT (W-7A)

Utilizing advanced design in components and tubes to achieve unprecedented performance with fewer parts, Heathkit has produced the world's first and only "dollar-a-watt" genuine high fidelity amplifier. Meeting full 55-watt hi-fi rating and 50-watt professional standards, the new improved W-7A provides a comfortable margin of distortion-free power for any high fidelity application.

The sleek, modern styling of this unit allows unobtrusive installation anywhere in the home. The clean, open layout of chassis and precut, cabled wiring harness makes the W-7A extremely easy to assemble. Shpg. Wt. 28 lbs.

**SPECIFICATIONS—Power output:** Hi-Fi rating, 55 watts; Professional rating, 50 watts. **Power response:** ±1 db from 20 cps to 20 kc at 55 watts output. **Total harmonic distortion:** Less than 2% from 30 cps to 15 kc at 55 watts output. **Intermodulation distortion:** Less than 1% at 62 watts output using 60 cps and 6 kc signal mixed 4:1. **Hum and noise:** 80 db below 55 watts, unweighted. **Damping factor:** Switch on front panel for selecting either maximum (20:1) or unity (1:1). **Output impedances:** 4, 8 and 16 ohms and 70-volt line. **Power requirements:** 117 volts, 50/60 cycles, 90-160 watts. **Dimensions:** 8½" D. x 6½" H. x 15" W.

New

HEATHKIT W-7A

**$54.95**

# Stereo Amplifiers

## YOUR BEST DOLLAR VALUE IN STEREO...

### 14/14 WATT STEREO AMPLIFIER KIT (SA-2)

Complete control is at your fingertips with this versatile Stereo Amplifier-Preamplifier. Providing 14 watts per stereo channel, or 28 watts total monophonic, the SA-2 offers every modern feature in a master stereo control center at a price to please the budget minded. The unit offers selection of dual channel stereo operation, monophonic operation using both channels simultaneously, or using either channel for monophonic program material independent of the other channel. A 4-position input selector switch provides choice of mag. phono, crystal phono, tuner, and high level auxiliary input for tape recorder, TV, etc. Other features include RIAA equalization on mag. phono, channel reversing function, clutched volume control, ganged dual tone controls, speaker phase reversal switch and two AC outlets. Handsomely styled black and gold vinyl-clad steel cabinet. Shpg. Wt. 23 lbs.

**SPECIFICATIONS—Power output:** 14 watts per channel, "hi-fi"; 12 watts per channel, "professional"; 16 watts per channel, "utility". **Power response:** ±1 db from 20 cps to 20 kc at 14 watts output. **Total harmonic distortion:** less than 2%, 30 cps to 15 kc at 14 watts output. **Intermodulation distortion:** less than 1% at 16 watts output using 60 cps and 6 kc signal mixed 4:1. **Hum and noise:** mag. phono input, 47 db below 14 watts; tuner and crystal phono, 63 db below 14 watts. **Controls:** dual clutched volume; ganged bass, ganged treble; 4-position selector; speaker phasing switch. **AC receptacle:** 1 switched, 1 normal. **Inputs:** 4 stereo or 8 monophonic. **Outputs:** 4, 8 and 16 ohms. **Dimensions:** 4½" H. x 15" W. x 8" D. **Power requirements:** 117 volts, 50/60 cycle, AC, 150 watts (fused).

### ECONOMY STEREO AMPLIFIER KIT (SA-3)

This amazing performer delivers more than enough power for pure, undistorted room-filling stereophonic sound at the lowest possible cost. Featuring 3 watts per stereo channel and 6 watts as a monophonic amplifier, the SA-3 has been proven by exhaustive tests to be more than adequate in volume for every listening taste.

You will find its ease of assembly another plus feature. Heathkit construction manuals, world famous for their clarity and thoroughness, lead you a simple step at a time to successful completion of the kit. Larger than life-size diagrams show you exactly what each part looks like, where it goes, and how it is installed.

The amplifier is tastefully styled in black with gold trimmed control knobs and gold screened front and rear panel. A tremendous buy at this low Heathkit price! Shpg. Wt. 13 lbs.

**SPECIFICATIONS—Power output:** 3 watts per channel. **Power response:** ±1 db from 50 cps, 20 kc at 3 watts out. **Total harmonic distortion:** less than 3%; 60 cps, 20 kc. **Intermodulation distortion:** less than 2% @ 3 watts output using 60 cycle & 6 kc signal mixed 4:1. **Hum and noise:** 65 db below full output. **Controls:** dual clutched volume; ganged treble, ganged bass; 7-position selector; speaker phasing switch; on-off switch. **Inputs (each channel):** tuner, crystal or ceramic phono. **Outputs (each channel):** 4, 8, 16 ohms. **Finish:** black with gold trim. **Dimensions:** 12½" W. x 6¾" D. x 3½" H.

HEATHKIT XR-2P
(6 lbs.)
**$29.95**

New

HEATHKIT XR-2L
(7 lbs.)
**$34.95**

### 6-TRANSISTOR PORTABLE RADIOS (XR-2P and XR-2L)

New, improved styling, new vernier tuning, up to 1,000 hours on flashlight batteries . . . are just a few of the plus features you get with these new transistor portables. Carry them with you wherever you go; to the beach, on trips, boating, etc. These new, improved models bring you the outstanding performance of the preceding models plus brand new styling and the additional convenience of vernier tuning for smooth, effortless station selection. The XR-2P features a mocha and beige high-impact plastic case. The XR-2L has a sun-tan color leather case with an identical beige plastic front. Six Texas Instrument transistors are used for high sensitivity and selectivity. A large 4" x 6" PM speaker with heavy magnet provides excellent tone quality. The roomy chassis makes it unnecessary to crowd components, adding greatly to ease of construction. The six standard size "D" flashlight batteries used for power provide extremely long battery life and can be purchased anywhere. Fun to build, and fun to use . . . order one today!



New

HEATHKIT DS-1
**$69.95**
$7.00 DN., $7.00 MO.

- Indicates Depth and Type of Bottom From 0 to 100 Feet
- Detects Submerged Objects (fish, logs, etc.) and Their Depth
- Completely Transistorized . . . Operates From Flashlight Batteries

### TRANSISTOR DEPTH SOUNDER (DS-1)

Weekend boatsman or professional . . . fisherman or skindiver . . . here's the depth sounder for you. Depth is indicated by a flashing neon lamp rotating behind a transparent circle in the molded black plastic dial face. A large hood around the dial enables the viewer to easily read the indicator in bright light or sunshine. The transducer uses a barium titanate element mounted in a faired, molded epoxy resin housing with solid brass through-hull fitting and mounting hardware. While designed for permanent mounting on the bottom of the boat, temporary outboard mounting of the transducer is also possible. The completely transistorized circuit operates from 6 flashlight cells and one long-life battery. Comes complete with splash-proof cabinet, hardware and gimbal-type mounting bracket. Shpg. Wt. 10 lbs.

# New HEATHKIT Amplifiers & Tuners

## A NEW AMPLIFIER AND PREAMP UNIT PRICED WELL WITHIN ANY BUDGET

### 14-WATT HI-FI AMPLIFIER KIT (EA-3)

This thrilling successor to the famous Heathkit EA-2 is one of the finest investments anyone can make in top quality high fidelity equipment. It delivers a full 14 watts of hi-fi rated power and easily meets professional standards as a 12-watt amplifier.

Rich, full range sound reproduction and low noise and distortion are achieved through careful design using the latest developments in the audio science. Miniature tubes are used throughout, including EL-84 output tubes in a push-pull output circuit with a special-design output transformer. The built-in preamplifier has three separate switch-selected inputs for magnetic phono, crystal phono or tape, and AM-FM tuner. RIAA equalization is featured on the magnetic phono input. Shpg. Wt. 15 lbs.

**NOTE THESE OUTSTANDING SPECIFICATIONS—Power output:** 14 watts, Hi-Fi; 12 watts, Professional; 16 watts, Utility. **Power response:** ±1 db from 20 cps to 20 kc at 14 watts output. **Total harmonic distortion:** less than 2%, 30 cps to 15 kc at 14 watts output. **Intermodulation distortion:** less than 1% at 16 watts output using 60 cps and 6 kc signal mixed 4:1. **Hum and noise:** mag. phono input, 47 db below 14 watts; tuner and crystal phono, 63 db below 14 watts. **Output impedances:** 4, 8 and 16 ohms.

HEATHKIT EA-3

**$29.95**

## NEVER BEFORE HAS ANY HI-FI AMPLIFIER OFFERED SO MUCH AT SO LOW A PRICE

New

### "UNIVERSAL" 14-WATT HI-FI AMPLIFIER KIT (UA-2)

Meeting 14-watt "hi-fi" and 12-watt "professional" standards, the UA-2 lives up to its title "universal" performing with equal brilliance in the most demanding monophonic or stereophonic high fidelity systems. Its high quality, remarkable economy and ease of assembly make it one of the finest values in high fidelity equipment. Buy two for stereo. Shpg. Wt. 13 lbs.

**SPECIFICATIONS—Power output:** Hi-Fi rating, 14 watts; Professional rating, 12 watts. **Power response:** ±1 db from 20 cps to 20 kc at 17 watts output. **Total harmonic distortion:** Less than 2% from 20 cps to 20 kc at 14 watts output. **Intermodulation distortion:** Less than 1% at 14 watts output using 60 cps and 6 kc signal mixed 4:1. **Hum and noise:** 73 db below 14 watts. **Output impedances:** 4, 8 and 16 ohms. **Damping factor:** Switched for unity or maximum; maximum damping factor 15:1. **Input voltage for 14 watt output:** .7 volts. **Power requirements:** 117 volts 50/60 cycles, 55 watts. **Dimensions:** 10" W. x 6½" D. x 4¾" H.

HEATHKIT UA-2

**$22.95**

## MORE STATIONS AND TRUE FM QUALITY ARE YOURS WITH THIS FINE TUNER KIT

New

### HIGH FIDELITY FM TUNER KIT (FM-4)

This handsomely styled FM tuner features better than 2.5 microvolt sensitivity, automatic frequency control (AFC) with on-off switch, flywheel tuning and prewired, prealigned and pretested tuning unit. Clean chassis layout, prealigned intermediate stage transformers and assembled tuning unit makes construction simple—guarantees top performance. Flywheel tuning and new soft, evenly-lighted dial scale provide smooth, effortless operation. Vinyl-covered case has black, simulated-leather texture with gold design and trim. Multiplex adapter output also provided. Shpg. Wt. 8 lbs.

**SPECIFICATIONS—Tuning range:** 88 to 108 mc. **Quieting sensitivity:** 2.5 uv for 20 db of quieting. **IF frequency:** 10.7 mc. **Image ratio:** 45 db. **AFC correction factor:** 75 kc per volt. **AM suppression:** 25 db. **Frequency response:** ±2 db 20 to 20,000 cps. **Harmonic distortion:** Less than 1.5%, 1100 uv, 400 cycles 100% modulation. **Intermodulation distortion:** Less than 1%, 60 cycles and 6 kc mixed 4:1 1100 uv, 30% modulation. **Antenna:** 300 ohms unbalanced. **Output impedance:** 600 ohms (cathode follower). **Output voltage:** nominal .5 volt (with 30% modulation, 20 uv signal). **Power requirements:** 105-125 volts 50/60 cycle AC at 25 watts. **Overall dimensions:** 4¾" H. x 13¾" W. x 5¾" D.

HEATHKIT FM-4

**$34.95**

**HEATH COMPANY**/Benton Harbor, Mich.

a subsidiary of Daystrom, Inc.

# New HEATHKIT Tape Recorders

- Choice of 3 Outstanding Models
- Compare With $350-$400 Machines
- Preassembled Tape Mechanism
- Choice of Monophonic or Stereo models
- Complete versatility
- Easy to assemble, easy to use

### PROFESSIONAL QUALITY TAPE RECORDER KITS (TR-1 Series)

Enjoy the incomparable performance of these professional quality tape recorders at less than half the usual cost. These outstanding kits offer a combination of features found only in much higher priced professional equipment, generally selling for $350 to $400. Not the least of these special features is the handsome styling which characterizes the kits . . . a semi-gloss black panel is set off by a plastic escutcheon in soft gold, which is matched by black control knobs with gold inserts. The mechanical assembly, with fast forward and rewind functions, comes to you completely assembled and adjusted; you build only the tape amplifier. And, you'll find this very easy to accomplish, since the two circuit boards eliminate much of the wiring. Separate record and playback heads and amplifiers allow monitoring from tape while recording and a "pause" control permits instant starting and stopping of tape for accurate cueing and tape editing. A digit counter is provided for convenient selection of any particular recording. Push-pull knob provides instant selection of 3¾ or 7½ IPS tape speed. Safety interlock on record switch reduces possibility of accidental erasure of recorded tapes. Shpg. Wt. 30 lbs.

**SPECIFICATIONS—Tape speed:** 7.5" and 3.75" per second. **Maximum reel size:** 7". **Frequency response (record-playback):** ±2.5 db, 30 to 12,000 cps at 7.5 IPS; ±2.5 db, 30 to 6,500 cps at 3.75 IPS. **Harmonic distortion:** 1% or less at normal recording level; 3% or less at peak recording level. **Signal-to-noise ratio:** 50 db or better, referred to normal recording level. **Flutter and wow:** 0.3% RMS at 7.5 IPS; 0.35% RMS at 3.75 IPS. **Heads (3):** erase, record, and in-line stereo playback (TR-1C, monophonic playback). **Playback equalization:** NARTB curve, within ±2 db. **Inputs (2):** microphone and line. **Input impedance:** 1 megohm. **Model TR-1D & TR-1E outputs (2):** A and B stereo channels. **Model TR-1C output (1):** monophonic. **Output levels:** approximately 2 volts maximum. **Output impedance:** approximately 600 ohm (cathode followers). **Recording level indicator:** professional type db meter. **Bias erase frequency:** 60 kc. **Timing accuracy:** ±2%. **Power requirements:** 105-125 volts AC, 60 cycles, 35 watts. **Dimensions:** 15¼" W. x 13½" D. Total height 10¾". **Mounting:** requires minimum of 8¼" below and 1½" above mounting surface. May be operated in either horizontal or vertical position.

**MODEL TR-1C Monophonic Tape Deck:** Monophonic Record and Playback. **$159.95** $16.00 DWN. $14.00 MO.

**MODEL TR-1D Two Track Stereo Tape Deck:** Monophonic Record and Playback, plus Playback of 2-track Pre-recorded Stereo Tapes (stacked). **$169.95** $17.00 DWN. $15.00 MO.

**MODEL TR-1E Four Track Stereo Tape Deck:** Monophonic Record and Playback, plus Playback of 4-track Pre-recorded Stereo Tapes (stacked). **$169.95** $17.00 DWN. $15.00 MO.

**MODEL C-TR-1C Conversion Kit:** Converts TR-1C to TR-1D (see TR-1D description above). Shpg. Wt. 2 lbs. . . . . **$19.95**

**MODEL C-TR-1D Conversion Kit:** Converts TR-1D to TR-1E (see TR-1E description above). Shpg. Wt. 2 lbs. . . . . **$14.95**

**MODEL C-TR-1CQ Conversion Kit:** Converts TR-1C to TR-1E (see TR-1E description above). Shpg. Wt. 2 lbs. . . . . **$19.95**

### STEREO-MONO TAPE RECORDER KITS (TR-1A Series)

Here are the tape recorders the avid hi-fi fan will find most appealing! Their complete flexibility in installation and many functions make them our most versatile tape recorder kits. This outstanding tape recorder now can be purchased in any one of three versions. You can buy the new two-track (TR-1AH) or four-track (TR-1AQ) versions which record and play back both stereo and monophonic programming, or the two-track monophonic record-playback version (TR-1A) and later convert to either two-track or four-track stereo record-playback models by purchasing the MK-4 or MK-5 conversion kits. The tape deck mechanism is extremely simple to assemble. Long, faithful service is assured by precision bearings and close machining tolerances that hold flutter and wow to less than 0.35%. Power is provided by a four-pole, fan-cooled induction motor. One lever controls all tape handling functions of forward, fast-forward or rewind modes of operation. The deck handles up to 7" tape reels at 7.5 or 3.75 IPS as determined by belt position. The TR-1A series decks may be mounted in either a vertical or horizontal position (mounting brackets included). The TE-1 Tape Electronics kits supplied feature NARTB equalization, separate record and playback gain controls and a safety interlock. Provision is made for mike or line inputs and recording level is indicated on a 6E5 "magic eye" tube. Two circuit boards simplify assembly.

**MODEL TR-1A:** Monophonic two-track record/playback with fast forward and rewind functions. Includes one TE-4 Tape Electronics kit. Shpg. Wt. 24 lbs. **$99.95** $10.00 DWN. $9.00 MO.

**TR 1A SPECIFICATIONS—Frequency response:** 7.5 IPS ±3 db 50 to 12,000 cps; 3.75 IPS ±3 db 50 to 7,000 cps. **Signal-to-noise ratio:** better than 45 db below full output of 1.25 volts /channel. **Harmonic distortion:** less than 2% at full output. **Bias erase frequency:** 60 kc (push-pull oscillator).

**MODEL TR-1AH:** Two-track monophonic and stereo record/playback with fast forward and rewind functions. Two TE-4 Tape Electronics kits. Shpg. Wt. 36 lbs. **$149.95** $15.00 DWN. $13.00 MO.

**TR-1AH SPECIFICATIONS—Frequency response:** 7.5 IPS ±3 db 40 to 15,000 cps; 3.75 IPS ± db 40 to 10,000 cps. **Signal-to-noise ratio:** 45 db below full output of 1 volt /channel. **Harmonic distortion:** less than 2% at full output. **Bias erase frequency:** 60 kc (push-pull oscillator).

**MODEL TR-1AQ:** Four-track monophonic and stereo record/playback with fast forward and rewind functions. Two TE-4 Tape Electronics kits. Shpg. Wt. 36 lbs. **$149.95** $15.00 DWN. $13.00 MO.

**TR-1AQ SPECIFICATIONS—Frequency response:** 7.5 IPS ±3 db 40 to 15,000 cps; 3.75 IPS ±3 db 40 to 10,000 cps. **Signal-to-noise ratio:** 40 db below full output of .75 volts / channel. **Harmonic distortion:** less than 2% at full output. **Bias erase:** 60 kc (push-pull oscillator).

**HEATH COMPANY**/Benton Harbor, Mich. a subsidiary of Daystrom, Inc.

# New "Acoustic Suspension" Hi-Fi Speaker System Kit

HEATHKIT AS-2U (unfinished)

**$69.95**

HEATHKIT AS-2M (mahogany) **$79.95**
HEATHKIT AS-2B (birch) **EACH**

## *NOW—FOR THE FIRST TIME —EXCLUSIVELY FROM HEATH*

### ACOUSTIC SUSPENSION HI-FI SPEAKER SYSTEM KIT (AS-2)

A revolutionary principle in speaker design, the Acoustic Research speaker has been universally accepted as one of the most praiseworthy speaker systems in the world of high fidelity sound reproduction. Heathkit is proud to be the sole kit licensee of this Acoustic Suspension principle from AR, Inc., and now offers for the first time this remarkable speaker system in money-saving, easy-to-build kit form.

The 10" Acoustic Suspension woofer delivers clean, clear extended-range bass response and outstanding high frequency distribution is provided by the specially designed "cross-fired" two-speaker tweeter assembly.

Another first in the Heathkit line is the availability of preassembled and prefinished cabinets. Cabinets are available in prefinished birch (blond) or mahogany, or in unfinished birch suitable for the finish of your choice. Kit assembly consists merely of mounting the speakers, wiring the simple cross-over network and filling the cabinet with the fiberglass included. Shpg. Wt. 32 lbs.

**SPECIFICATIONS—Frequency response (at 10 watts input):** ±5 db, 42 to 14,000 cps; 10 db down at 30 and 16,000 cps. **Harmonic distortion:** below 2% down to 50 cps, below 3% down to 40 cps at 10 watts input in corner room location. **Impedance:** 8 ohms. **Suggested amplifier power:** 20 watts minimum. **Suggested damping factor:** high (5:1 or greater). **Efficiency:** about 2%. **Distribution angle:** 90° in horizontal plane. **Dimensions:** 24" W. x 13¼" H. x 11⅜" D.

# New Test Equipment

HEATHKIT FMO-1 Price to be announced

## *AN INSTRUMENT LONG-AWAITED BY SERVICE TECHNICIANS EVERYWHERE!*

### HEATHKIT FM TEST OSCILLATOR KIT (FMO-1)

Here in one compact, easy-to-use instrument are provided all the test signals and sweep frequencies required for fast, easy alignment and troubleshooting of RF, IF and detector sections of FM tuners and receivers. An instrument unique in the test equipment field . . . being the only one of its type designed especially for FM service work.

**SPECIFICATIONS—Output frequencies:** for RF alignment, 90 mc (FM band low end), 100 mc (FM band middle range), 107 mc (FM band high end). **Modulation:** 400-cycle incidental FM. **IF and detector alignment:** 10.7 mc sweep. **Sweep width markers:** 200 kc to over 1 mc, variable, 10.7 mc (crystal), 100 kc sub-markers. **Modulation:** 400-cycle AM. **For other applications:** 10.0 mc (crystal) and harmonics, 100 kc, 400-cycle audio. **Controls:** main frequency selector, modulation switch /concentric level control, marker oscillator switch /concentric level control, sweep width—power switch, output control, AF-RF (source impedance) switch. **Power supply:** transformer, selenium rectifier. **Power requirements:** 105-125 V, 50/60 cycles, 12 watts. **Cabinet size:** 7¾" H. x 4¾" W. x 4⅜" D.

HEATHKIT RF-1

**$27.95**

## *PREASSEMBLED AND ALIGNED BANDSWITCH/COIL ASSEMBLY*

### RF SIGNAL GENERATOR KIT (RF-1)

Moderately priced, and capable of precision performance the RF-1 provides highly accurate and stable RF signals for trouble-shooting and aligning RF and IF circuits of all kinds. Modulated or unmodulated RF output of at least 100,000 microvolts is available, controlled by both fixed-step and continuously variable controls. A built-in 400 cycle audio generator with 10-volt output provides internal modulation of RF signal and is available separately for audio tests. A preassembled bandswitch and coil assembly, aligned to factory precision standards, eliminates the need for special alignment equipment. Shpg. Wt. 7 lbs.

**SPECIFICATIONS—Frequency range:** Band A, 100 kc to 320 kc; Band B, 310 kc to 1.1 mc; Band C, 1 mc to 3.2 mc; Band D, 3.1 mc to 11 mc; Band E, 10 mc to 32 mc; Band F, 32 mc to 110 mc. **Calibrated harmonics:** 110 mc to 220 mc. **Accuracy:** 2%. **Output:** impedance, 50 ohms; voltage, in excess of 100,000 uv on all bands. **Modulation:** internal, 400 cycles approx. 30% depth; external, approx. 3 V across 50 k ohm for 30%. **400 cycles audio output:** approx. 10 V open circuit. **Tube complement:** V1 12AT7 RF oscillator, V2 6AN8 modulator and output. **Power requirements:** 105-125 V 50/60 cycles AC, 15 watts. **Aluminum cabinet dimensions:** 6½" W. x 9½" H. x 5" D.

New HEATHKIT

# Ham Radio Gear



HEATHKIT KS-1

**$169.95**

## TOP POWER WITH ECONOMY AND SAFETY

### KILOWATT POWER SUPPLY KIT (KS-1)

The KS-1 is designed as a companion to the "Chippewa" Linear Amplifier and is also suitable for supplying plate power to most other RF amplifiers in the medium to high power class. The KS-1 features an oil-filled, hermetically sealed plate transformer to minimize corona, a swinging choke in the filter circuit for good regulation, and a 60-second time delay relay to permit adequate heating of the mercury vapor rectifiers before application of plate voltage. All components are conservatively rated and well insulated for long life and dependable service. Shpg. Wt. 105 lbs.

**SPECIFICATIONS—Maximum DC power output:** 1500 watts. **Nominal DC voltage output:** 3000 or 1500 volts. **Maximum DC current output:** Average 500 ma, peak 1000 ma. **Regulation:** 180 to 600 ma (typical linear amplifier), 8%; 0 to 300 ma (typical class C amplifier), 10%; 0 to 500 ma, 15%. **Ripple:** Less than 1%. **Tube complement:** (2) 866A mercury vapor rectifiers. **Recommended ambient temperature:** 50 to 100 degrees F. **Circuit:** Two half-wave mercury vapor rectifiers in a full wave, single-phase configuration with swinging choke input filtering. **Line power requirements:** 115 V, 50/60 cycles, 20 amperes; 230 V, 50/60 cycles, 10 amperes. **Chassis size:** 17¾" W. x 12" H. x 13" D.

HEATHKIT KL-1

**$415.00**

## MOVE TO THE TOP IN TRANSMITTING POWER

### "CHIPPEWA" KILOWATT LINEAR AMPLIFIER KIT (KL-1)

The KL-1 operates at maximum legal amateur power inputs in SSB, CW or AM service using any of the popular CW, SSB and AM exciters as a driver. Premium tubes (4—400's) push the "Chippewa" to top performance levels while a centrifugal blower provides more than adequate cooling. Shpg. Wt. 70 lbs.

**SPECIFICATIONS—RF section:** Driving power required (10 meters); Class AB1 (tuned grid) 10 watts peak; Class C (tuned grid) 40 watts; Class AB1 (swamped grid) 60 watts peak. **Power input:** Class AB1 (SSB-voice modulation) 2000 watts PEP; Class AB1 (SSB-two tone test) 1300 watts; Class AB1 (AM linear) 1000 watts; Class C (CW) 1000 watts. **Power output (20 meters):** Class AB1 (SSB-voice modulation) 900 watts PEP; Class AB1 (SSB-two tone test) 550 watts; Class AB1 (AM linear) 300 watts; Class C (CW) 750 watts. **Output impedance:** 50 to 72 ohms (unbalanced). **Input impedance:** 50 to 72 ohms (unbalanced). **Band coverage:** 80, 40, 20, 15 and 10 meters. **Panel metering:** 0 to 50 ma, grid current; 0 to 100 ma screen current; 0 to 5000 volt plate voltage; 0 to 1000 ma plate current. **Tube complement:** Final tubes, (2) 4-400A; clamp tube, (1) 6DQ6; voltage regulators, (4) OD3, (2) OC3. **Power requirements:** AC (power supply primary circuit), 250 watts, 115 volt, 50/60 cycles; DC, 3000 to 4000 volts, 450 ma. **Cabinet size:** 19½" W. x 11⅝" H. x 16" D.



HEATHKIT XC-2

**$36.95**

### 2-METER CONVERTER KIT (XC-2)

Extends coverage of the Heathkit "Mohawk" Receiver to the 2-meter band. May also be used with receivers tuning a 4 mc segment between the frequencies of 22 and 35 mc when appropriate crystal is used. Shpg. Wt. 7 lbs.

**SPECIFICATIONS—Noise figure:** 4.5 db; 1 uv signal provides 20 db thermal noise quieting. **Sensitivity:** approx. .1 uv input will provide a signal better than 6 db over noise level. **Gain:** approx. 40 db. **Pass band:** essentially flat 144 to 148 mc; approx. 35 db down at 143 and 149 mc. **Image rejection:** better than 100 db (tunable). **Output impedance:** 50 to 75 ohms. **Input impedance:** 50 to 75 ohms; 300 ohms with balun. **Frequency:** input, 144 to 148 mc; output, 22 to 26 mc with crystal supplied. **Tubes:** 6AM4, 6BS8, 6EA8, 12AT7. **Crystal:** .005% 3rd overtone. **Power requirements:** 150 volts DC at 50 ma (dropping resistor supplied for 210 VDC RX-1 operation) 6.3 volts AC/DC at 1.375 amps. **Size:** 9" W. x 5½" H. x 4¾" D.

HEATHKIT UT-1

**$28.95**

### "BEST BUY" UTILITY POWER SUPPLY KIT (UT-1)

This power supply is ideal for converting the Heathkit "Cheyenne" and "Comanche" mobile transmitter and receiver to fixed station operation; or may be used to provide necessary filament and plate voltage for a wide variety of amateur equipment. Features silicon diode rectifiers, high capacity filters for superior dynamic regulation, and line filtering to minimize TVI and reduce receiver line noise. On ICAS basis, provides 150 watts DC plus filament power for 6.3 volt or 12.6 volt filament applications (6.3 VAC., 8 amps. or 12.6 VAC., 4 amps.; 600 VCD., 250 ma or 600 VDC , 200 ma and 300 VDC., 100 ma). Less than 1% ripple; excellent regulation. Housed in attractive green and gray-green cabinet measuring 9" long, 4¾" wide, 6" high. Shpg. Wt. 15 lbs.

# New Citizen's Band Transceiver

## WIRED OR KIT FORM

HEATHKIT CB-1
**$42.95**
(kit model)

HEATHKIT W-CB-1
**$60.95**
(wired model)
$6.10 dwn., $6.00 mo.

Both models include transceiver, crystal, microphone and two special power cords.

- No Tests to Take—No Operator's License Required
- Any Citizen 18 or Older Can Have Own Station
- Hundreds of Business and Personal Uses

### CITIZEN'S BAND TRANSCEIVER KIT (CB-1)

The Heathkit CB-1 Citizen's Band Transceiver is a compact radio transmitter and receiver combination designed to operate on the new 11-meter "Citizen's Band". No tests to take, no special knowledge or operator's license required . . . you need only fill out forms we supply, and mail them to FCC to apply for station license. Operates just like any short wave radio used by police and other communication services. Front panel switch selects both "transmit" and "receive". Two or more Heathkit Transceivers provide you with your own 2-way radiotelephone system for making necessary business and personal contacts with family, friends or associates. A Heathkit accessory power supply makes the CB-1 completely portable for use in cars, trucks, boats, etc., using 6 or 12 volt batteries. With appropriate accessory antenna, the CB-1 can be used for communicating between truck and office, home and automobile, boat and shore, farm-house and field . . . literally hundreds of useful applications. Comes complete with microphone, 2 power cords for mobile or fixed operation, station ID card, call letters, and crystal for one channel and FCC application form. Order power supply and antenna separately. Attractively styled in two-tone "mocha" and "beige". Shpg. Wt. 10 lbs.

**SPECIFICATIONS—Receiver type:** Superregenerative detector w/rf stage. **Power input:** 5 watts maximum to plate of final RF amplifier (FCC requirement). **Transmitter frequency control:** Third overtone type quartz crystal operating within 0.005% of marked channel frequency between −20° and +130° F. **Modulation:** AM plate and screen modulation automatically limited to less than 100% (FCC requirements). **Power supply:** Internal 117 V. 50/60 cycles, AC (3 watts). For 6 V battery power, use Model VP-1-6 Vibrator Power Supply (6.5 amps); for 12 V battery power, use VP-1-12 (4 amps). **Total B+ requirements:** 280 volts at 60 ma; total heater requirements, 6.3 volts at 1.6 amps. or 12.6 volts at 0.9 amps. **Power rectifier:** 2 silicon diodes in full wave voltage doubler circuit. **Microphone:** Combination hand-held and desk type, ceramic element, plastic case, with cord and connector. **RF output impedance:** 50 ohms. **Speaker size:** 3½" (round). **Undistorted audio power output:** Approximately 1 watt. **Line cords:** Two supplied, one for AC operation, one for battery operation. Power circuits automatically switched when appropriate line cord is plugged in. **Cabinet dimensions:** 8" H, x 6" D. x 9¾" W.

### SPECIFY FREQUENCY CHOICE
(1st and 2nd choice)

**CLASS D CITIZEN'S BAND FREQUENCIES**

| | | | |
|---|---|---|---|
| 26.965 mc | 27.035 mc | 27.115 mc | 27.185 mc |
| 26.975 mc | 27.055 mc | 27.125 mc | 27.205 mc |
| 26.985 mc | 27.065 mc | 27.135 mc | 27.215 mc |
| 27.005 mc | 27.075 mc | 27.155 mc | 27.225 mc |
| 27.015 mc | 27.085 mc | 27.165 mc | *27.255 mc |
| 27.025 mc | 27.105 mc | 27.175 mc | |

*This channel shared with Class C Radio Control.

### ANTENNAS

**CBU-1 "UTILITY" ANTENNA.....$9.95**
Good coverage, portable antenna for temporary mobile or fixed installations. 45½" base-loaded antenna, 12' connecting cable, mounting bracket and clip. 3 lbs.

**CBM-1 "MOBILE" ANTENNA.....$19.95**
Best coverage mobile installation. Easy to install spring base, ¼ wave, 9' whip; 15' connecting cable and necessary hardware. 7 lbs.

**CBF-1 "FIXED LOCATION" ANTENNA...$19.95**
Excellent coverage, ½ wave "ground plane", 9' elements; 50' connecting cable and mounting bracket. 7 lbs.

### WIRED AND KIT FORM POWER SUPPLIES FOR MOBILE USE

6 volt Vibrator Power Supply for use with 6 volt batteries.
**KIT**—Model VP-1-6. Shpg. Wt. 4 lbs.....$7.95
**WIRED**—Model WVP-1-6. Shpg. Wt. 4 lbs.....$11.95

12 volt Vibrator Power Supply for use with 12 volt batteries.
**KIT**—Model VP-1-12. Shpg. Wt. 4 lbs.....$7.95
**WIRED**—Model WVP-1-12. Shpg. Wt. 4 lbs.....$11.95

HEATHKIT

## ORDER BLANK

**NOTE: all prices and specifications subject to change without notice.**
Enclosed find ( ) check ( ) money order. Please ship C.O.D. ( )

**On Express orders do not include transportation charges —they will be collected by the express agency at time of delivery.**

On Parcel Post Orders include postage for weight shown. All prices are NET F.O.B. Benton Harbor, Michigan, and apply to Continental U.S. and Possessions only. 20% Deposit required on all C.O.D. orders.

**HEATH COMPANY** BENTON HARBOR 15, MICH.
a subsidiary of Daystrom, Inc.

Name_____
Address_____
City & Zone_____ State_____
(PLEASE PRINT)

SHIP VIA
☐ Parcel Post
☐ Express
☐ Freight
☐ Best Way

| QUANTITY | ITEM | MODEL NO. | PRICE |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | ☐ SEND FREE HEATHKIT CATALOG | POSTAGE | |
| | | TOTAL | |

HEATHKITS are also available at your Dealer see listing on next page

## Here's where to buy your HEATHKIT® locally...

. . . through any of the carefully selected Heathkit Dealers listed below. This service has been established in answer to hundreds of requests, and we think that you, too, will welcome the availability of convenient "over-the-counter" delivery.

Although you will find your local dealers' price somewhat higher than the advertised direct mail price, we're sure you'll agree that this increase is justified . . . as your dealer has absorbed all transportation costs, provides a reliable source for parts and service, offers local display and demonstration facilities, stands ready to counsel or advise you on any problems that might arise . . . and, of course, carries a complete stock of kits for immediate delivery.

**CALIFORNIA**
BERKELEY, CALIF. zackIT Corp.
CHICO, CALIF. Dunlap Radio & TV Supply Co.
EL CAJON, CALIF. Telrad Electronics
FRESNO, CALIF. Dunlap Radio & TV Supply Co.
LOS ANGELES, CALIF. Kierulff Sound Corp.
LOS ANGELES (WEST), CALIF. Kierulff Sound Corp.
LONG BEACH, CALIF. Kierulff Sound Corp.
MARYSVILLE, CALIF. Dunlap Radio & TV Supply Co.
MERCED, CALIF. Dunlap Radio & TV Supply Co.
MODESTO, CALIF. Dunlap Radio & TV Supply Co.
PALO ALTO, CALIF. Zack Electronics
PASADENA, CALIF. Kierulff Sound Corporation
RIVERSIDE, CALIF. Kierulff Sound Corp.
SACRAMENTO, CALIF. Dunlap Radio & TV Supply Co.
SAN DIEGO, CALIF. Telrad Electronics
SAN FERNANDO VALLEY Kierulff Sound Corp.
SAN FRANCISCO, CALIF. Zack Electronics
SANTA ANA-ORANGE, CALIF. Kierulff Sound Corp.
SANTA BARBARA, CALIF. zackIT Corp.
STOCKTON, CALIF. Dunlap Radio & TV Supply Co.
VISALIA, CALIF. Dunlap Radio & TV Supply Co.

**COLORADO**
DENVER Radio Products Sales Corp.

**DELAWARE**
WILMINGTON, DELAWARE Radio Electric Service Co.

**HAWAII**
HILO, HAWAII Radio-Television Corp., Ltd.
HONOLULU, HAWAII Radio-Television Corp., Ltd.

**ILLINOIS**
ALTON, ILLINOIS Radonics-Alton, Inc.

**INDIANA**
FT. WAYNE, INDIANA Ft. Wayne Electronic Supply, Inc.
INDIANAPOLIS, INDIANA Graham Electronic Supply, Inc.
LAFAYETTE, INDIANA Lafayette Radio Supply, Inc.
MUNCIE, INDIANA Muncie Electronic Supply, Inc.

**IOWA**
DES MOINES, IOWA Radio Trade Supply Co.
FT. DODGE, IOWA Radio Trade Supply Co.
MARSHALLTOWN, IOWA Radio Trade Supply Co.
WATERLOO, IOWA Radio Trade Supply Co.

**LOUISIANA**
HOUMA, LOUISIANA Crescent Electronic Supply
LAFAYETTE, LOUISIANA Sterling Electronics, Inc.
NEW ORLEANS, LOUISIANA Crescent Electronic Supply
NEW ORLEANS, LOUISIANA Hi-Fi, Inc.

**MARYLAND**
BALTIMORE, MARYLAND American Distributing Company (2 locations) The Hi-Fi Shop

**MASSACHUSETTS**
BOSTON, MASS. Audionics, Inc.

**MICHIGAN**
ALLEN PARK, MICHIGAN Volta Electronics
DETROIT, MICHIGAN High Fidelity Workshop
PONTIAC, MICHIGAN High Fidelity Workshop

**MINNESOTA**
DULUTH, MINN. Lew Bonn Company
MINNEAPOLIS, MINN. Lew Bonn Company Hi-Fi Sound
ST. PAUL, MINN. Lew Bonn Company Hi-Fi Sound

**MISSISSIPPI**
GULFPORT, MISS. Crescent Electronic Supply

**MISSOURI**
KANSAS CITY BA High Fidelity (2 locations) Burnstein-Applebee Co. (2 locations)
ST. LOUIS, MO. Radonics—Easton Radonics—Jefferson Radonics-West, Inc. Radonics-Gravois, Inc.

**NEW JERSEY**
ATLANTIC CITY, N.J. Radio Electric Service Co.
CAMDEN, N.J. Radio Electric Service Co.
MOUNTAINSIDE, N.J. Federated Purchaser, Inc.
NEWARK, N.J. Federated Purchaser, Inc.

**NEW YORK**
ALBANY, NEW YORK Ft. Orange Radio Distributing Co.
BATH, NEW YORK Rochester Radio Supply Co., Inc.
BELLEROSE, NEW YORK Cross Island Electronics, Inc.
BINGHAMTON, NEW YORK Stack Electronics, Inc.
BROOKLYN, NEW YORK Acme Electronics, Inc.
ELMIRA, NEW YORK Stack Electronics, Inc.
FARMINGDALE, NEW YORK Gem Electronics Dist., Inc.
FOREST HILLS, NEW YORK Beam Electronics, Inc.
GENEVA, NEW YORK Rochester Radio Supply Co., Inc.
HERKIMER, NEW YORK Herkimer Electronics Co., Inc.
HICKSVILLE, NEW YORK Gem Electronics Dist., Inc.
MINEOLA, NEW YORK Arrow Electronics, Inc.
MT. VERNON, NEW YORK Davis Radio Distributing Co.
NEW YORK, NEW YORK Arrow Electronics, Inc. Harvey Radio Company, Inc.
ROCHESTER, NEW YORK Rochester Radio Supply Co., Inc.

**NEW YORK (Cont.)**
SYRACUSE, NEW YORK Syracuse Radio Supply Co., Inc.
UTICA, NEW YORK Genesee Electronics Company
VALLEY STREAM, NEW YORK Elm Electronics, Inc.
WATERTOWN, NEW YORK Watertown Electronics, Inc.

**NORTH CAROLINA**
CHARLOTTE, NORTH CAROLINA Southeastern Radio Supply Co.
FAYETTEVILLE, NORTH CAROLINA Southeastern Radio Supply Co.
GREENSBORO, NORTH CAROLINA Southeastern Radio Supply Co.
KINSTON, NORTH CAROLINA Southeastern Radio Supply Co.
RALEIGH, NORTH CAROLINA Southeastern Radio Supply Co.

**OHIO**
AKRON, OHIO Sun Radio Company
CHILLICOTHE, OHIO Buckeye Electronics Dist., Inc.
CLEVELAND, OHIO Pioneer Electronic Supply Co. (2 locations)
COLUMBUS, OHIO Buckeye Electronics Dist., Inc.
DAYTON, OHIO Srepco, Inc. Ham'n Hi Fi, Inc.
LORAIN, OHIO Pioneer Electronic Supply Co.
MAPLE HEIGHTS, OHIO Pioneer Electronic Supply Co.
NEWARK, OHIO Buckeye Electronics Dist., Inc.
SANDUSKY, OHIO Pioneer Electronic Supply Co.
SPRINGFIELD, OHIO Standard Radio-Springfield, Inc.
TOLEDO, OHIO Lifetime Electronics
YOUNGSTOWN, OHIO Radio & TV Parts Company
ZANESVILLE, OHIO Buckeye Electronics Dist., Inc.

**OREGON**
MEDFORD, OREGON Verl G. Walker Company
PORTLAND, OREGON Eccles Electric Co.
SALEM, OREGON Cecil Farnes Co.

**PENNSYLVANIA**
ALLENTOWN, PA. Federated Purchaser, Inc.
EASTON, PA. Federated Purchaser, Inc.
ERIE, PA. J. V. Duncombe Co. (2 locations)
PHILADELPHIA, PA. Austin Electronics, Inc. Radio Electric Service Co. (3 locations)
PITTSBURGH, PA. House of Audio
WILLOW GROVE, PA. Radio Electric Service Co.
YORK, PA. Radio Electric Service Co.

**RHODE ISLAND**
PROVIDENCE, R. I. Audionics, Inc.

**SOUTH CAROLINA**
ANDERSON, S.C. Dixie Radio Supply Co. of Greenville
CHARLESTON, S.C. Radio Laboratories
COLUMBIA, S.C. Dixie Radio Supply Co. of Columbia
FLORENCE, S.C. Dixie Radio Supply Co. of Florence
GREENVILLE, S.C. Dixie Radio Supply Co. of Greenville
SPARTANBURG, S.C. Dixie Radio Supply Co. of Greenville
SUMTER, S.C. Dixie Radio Supply Co. of Columbia

**TENNESSEE**
JOHNSON CITY, TENNESSEE Chemcity Electronic Distributors
KINGSPORT, TENNESSEE Chemcity Electronic Distributors
KNOXVILLE, TENNESSEE Chemcity Electronic Distributors

**TEXAS**
BEAUMONT, TEXAS Sterling Electronics, Inc.
BRYAN, TEXAS Sterling Electronics, Inc.
DALLAS, TEXAS Hillcrest Records & Hi Fi
HOUSTON, TEXAS Sound Equipment, Inc. Sterling Electronics, Inc.
LUFKIN, TEXAS Sterling Electronics, Inc.

**VIRGINIA**
ARLINGTON, VIRGINIA Key Electronics, Inc.
NEWPORT NEWS, VIRGINIA Cain Electronics Co., Inc.
NORFOLK, VIRGINIA Cain Electronics Co., Inc. (2 locations)
PORTSMOUTH, VIRGINIA Cain Electronics Co., Inc.
RICHMOND, VA. Meridion Electronics, Inc.
ROANOKE, VA. McKnight Electronics, Inc.

**WASHINGTON**
SEATTLE, WASHINGTON Seattle Radio Supply, Inc.
SPOKANE, WASHINGTON Northwest Electronics, Inc.

**WEST VIRGINIA**
BECKLEY, W. VA. Chemcity Electronic Distributors
BLUEFIELD, W. VA. Meyers Electronics
CHARLESTON, W. VA. Chemcity Electronic Distributors
POINT PLEASANT, W. VA. Chemcity Electronic Distributors

**WISCONSIN**
LA CROSSE, WIS. Lew Bonn Company
MADISON, WIS. Hi Fi Corner Satterfield Electronics, Inc.
MILWAUKEE, WIS. Hi Fi Center
PORTAGE, WIS. Satterfield Electronics, Inc.
WISCONSIN RAPIDS, WIS. Satterfield Electronics, Inc.

**New York Service Representative**
Empire State Electronic Serv., Inc.
180-14 Union Turnpike, Flushing 66, Long Island, New York

HEATHKIT
HEATH COMPANY / Benton Harbor, Mich.
a subsidiary of Daystrom, Inc.


## Transistor Transmitter

(*Continued from page 69*)

crystal holder and capacitors $C_4$ and $C_5$ are also mounted on the partition. All adjustments, except $C_{10}$, come out the top of the chassis. A stand-off tie-point is used at the junction of $RFC_2$ and $R_4$, along the side of $V_3$. A BNC-style antenna connector was used, but you can use a type that suits your antenna installation. The r.f. transistors are held securely in place by inserting them in grommets. This eliminates lossy sockets and still holds the transistors firmly. Use extreme care when soldering to the transistor leads—grasp the lead you are soldering with a pair of needle-nose pliers to conduct heat away from the transistor.

Over on the audio side of the chassis you will find that the transistors are mounted by their wire leads. In fact, all the audio components are mounted on an eight-lug terminal strip. The modulation transformer, $T_1$, is at the end of the strip opposite transistor $V_3$.

The entire unit is powered by a 9-volt mercury battery mounted in the other half of the chassis box. It is secured with a small aluminum clip and when the box is assembled the battery lies just above (or below, depending on your point of view) the audio transistors.

### Alignment

You may have noticed that this two-meter transistor transmitter has no metering jacks. The emitter and bias resistors in the oscillator circuit were chosen so as not to exceed any of the transistor ratings, whether the circuit is oscillating or not. The 2N502 cannot be damaged because the oscillator simply will not deliver enough power to run the buffer/doubler out of ratings. During the initial tests, or if you run the transistors at a higher collector voltage (you can go as high as 15 volts), a meter in each emitter lead is recommended. It should be pointed out that the efficiency of the transmitter will increase considerably at higher collector voltages but, I am a coward and don't like to play with high voltage!

Let's fire up the oscillator first. Disconnect the lead between $L_3$ and $C_5$ to disable the buffer/doubler. Apply power to the oscillator only. It should draw between 2 and 3 ma., depending on the setting of $C_3$. When the circuit is oscillating you should be able to detect a weak second harmonic on a two-meter receiver. When you touch $L_1$ (to kill the oscillation), the collector current should drop noticeably. Coil $L_1$ should resonate with $C_3$ meshed from ⅛ to ⅓.

Reconnect $C_5$ and apply power to the 2N502. Adjust $C_9$ and $C_5$ for maximum collector current (about 2 ma.). Build the r.f. detector probe shown in Fig. 2 and connect it to the input of a v.t.v.m. The crystal will rectify the r.f. signal across the 50- to 75-ohm load resis-

tor and provide a relative indication of power output. All the transmitter adjustments should be made for maximum indicated voltage on the v.t.v.m. If everything is working properly, the meter will read between 0.3 and 0.5 volt d.c. This corresponds *roughly* to about 5 mw. power output and indicates an efficiency of 25%—not bad for a doubler operating at that collector voltage. It is very difficult to measure the exact power output because some power is "lost" in the crystal.

### Performance

When transmitting with an antenna connected, you should have some provision for detecting the amount of power radiated by the antenna. As with the dummy load, tune all adjustments for maximum power output.

You will find that you can do some rather amazing things with this "little bomb." When connected to a twin four-beam antenna, it was possible to contact stations in Corona, California about 27 miles away. The signals were very readable and the enthusiastic ham gave me a report of 5-9 plus, plus,—what ever that is! It certainly indicates that the rig can cover a great distance, under the right conditions.

On c.w. this transmitter should be capable of some rather startling feats. For this mode, transformer $T_1$ should be shorted and the emitter of $V_2$ keyed.

-30-

## AUTOMATIC TUNER CLEANING

By KEN RAINS

**EVERY so often, it becomes necessary to clean the contacts of most Standard Coil tuners to maintain satisfactory performance. This periodic task can become quite annoying, but it can be avoided with a simple measure.**

**To keep the tuner contacts clean, simply wrap a small strip of soft cloth around the coil strip (or strips) for any one unused channel, as shown, and replace the strip or strips in their original position. Then saturate the cloth with contact cleaner. Whereas such a cleaner, as normally applied, will dissipate fairly rapidly, the cloth acts as a wick, retaining the cleaner for longer periods.**

**No special measures need be taken to bring about the cleaning action. Rotation of the tuner drum during normal use will clean away grease and dirt, keeping the contacts continuously clean.**

-30-

"Self-cleaner" for Standard Coil tuner.



The Whole Industry Is Excited About the

TARZIAN "HOT ROD" TUNER

It's the finest . . . smallest . . . and lowest-priced tuner on the market today. It has everything:

**PERFORMANCE . . . QUALITY . . . and LOW COST**

Automation in production methods makes it possible to produce this precision-built, high quality unit in great quantities . . . and at lower cost to YOU.

Compare these features with all others:

*Tetrode R.F. stage . . . high gain . . . low noise . . . 13 permanent positions . . . easily converted to UHF . . . adaptable for remote control operation . . . very low oscillator drift . . . individual oscillator front adjustment . . . small and compact . . . good resetability . . . and I.F. output tunable from the front.*

*Call or write for information*

SARKES TARZIAN, INC.

Sales Department, Tuner Division

East Hillside Drive • Bloomington, Indiana




# 20,400 people can study advanced electronic engineering technology via CREI.

*Growth of the electronics industry is not automatic assurance of your own prosperity. You need advanced, modern electronics education to advance yourself. 20,400 CREI students know this—and are taking appropriate action. Can you?*

The electronics industry is now fifth in volume among American industries. In 1958 total sales and services exceeded $13 billion, up about tenfold in a decade. Growing electronics applications in automation, instrumentation, industrial electronics, aeronautical electronics, guided missiles, servo-mechanisms, computers, astronautics and telemetering **point to equally rapid future growth.**

But the entire field of modern electronics is **changing. Industry** growth does not always mean individual growth. Companies actively seeking men with modern technological knowledge are simultaneously firing mediocre men.

CREI students (more than 20,400 are currently enrolled) keep pace with the electronics industry and are eagerly sought by employers who offer solid opportunities for rapid advancement.



Paul S. Lewis, Jr., a research assistant in an AEC-sponsored nuclear physics research program — and a CREI student — writes, "Like most large-scale physics projects, this machine (a proton accelerator) is largely electronic. The need for electronics technicians on basic scientific research projects will no doubt continue to grow."

Charles E. Lawson, another CREI student, brings out another point: "The fact that I am enrolled with CREI caused enthusiasm on the part of my employer (Wright Airborne Electronics). A former student of CREI is now chief engineer for the company."

CREI is now in its 34th year. 1958 marked the start of CREI Atomics, a division of CREI devised to meet the need for advanced home study education in nuclear engineering technology. 1958 also marked the opening of our European Division, bringing advanced professional electronic education to Western Europe.

Since 1927 we have directed technical education of thousands —as individuals and in groups— in electronics engineering technology. We developed the first civilian pilot course for radio mechanics for the Army Signal Corps in 1941, supplied 300,000 texts to the U. S. Navy in a special course for radio technicians in the South Pacific in 1943, trained hundreds of technicians during World War II for the Signal Corps. We co-founded the National Council of Technical Schools, which first established scholastic and business standards for the technical school field. We were among the first three technical institutes whose curricula were accredited by the Engineers' Council for Professional Development. In 1946 we instituted the group training programs used by companies representing the cream of the electronics and aviation industries.

Free 54-Page
Book Presents
Electronics
Facts to Help
You Decide on
Career
Improvement
INSURANCE FOR YOUR FUTURE IN THE NEW WORLD OF ELECTRONICS
This is a Postage Free POST CARD. Fill out ... detach, and mail today For FREE BOOK

First Class
Permit No. 288-R
Washington, D. C.

BUSINESS REPLY MAIL
No Postage Stamp Necessary If Mailed in United States

Postage Will Be Paid By

CAPITOL RADIO ENGINEERING INSTITUTE

3224 SIXTEENTH STREET, N.W.
WASHINGTON 10, D. C.

3-282-7

There's a CREI Home Study Course to fit your career requirements. Please provide all requested data to help us evaluate your qualifications and your needs.

MAIL THIS COUPON FOR FREE 54-PAGE BOOK!

**CAPITOL RADIO ENGINEERING INSTITUTE**
ECPD Accredited Technical Institute Curricula • Founded 1927

Dept. 1102-G1 3224 Sixteenth St., N.W., Washington 10, D. C.

Please send me your course outline and FREE 54-Page Book "Insurance for Your Future in the New World of Electronics" . . . describing opportunities and CREI home study courses in Practical Electronic Engineering Technology.

CHECK FIELD OF GREATEST INTEREST
- ☐ Radar, Servo and Computer Engineering Technology
- ☐ Electronic Engineering Technology
- ☐ Communications Engineering Technology
- ☐ Television Engineering Technology
- ☐ Aeronautical Electronic Engineering Technology
- ☐ Automation and Industrial Electronics Engineering Technology

Name_____ Age_____

Street _____

City_____ Zone____ State_____

Check: ☐ Home Study ☐ Residence School ☐ Korean Veteran

TO OBTAIN FAST, IMMEDIATE SERVICE AND TO AVOID DELAY, IT IS NECESSARY THAT THE FOLLOWING INFORMATION BE FILLED IN:

EMPLOYED BY _____

TYPE OF PRESENT WORK_____

EDUCATION: YEARS HIGH SCHOOL____ OTHER_____

ELECTRONICS EXPERIENCE _____

What does this record of achievement mean to you as a CREI student? It means that industry and the Armed Services alike respect CREI men. It means that your CREI diploma is a door-opener. Significantly, Help Wanted ads often specify "CREI education or equivalent required." Our Placement Bureau, which helps graduates and advanced students find more desirable positions, is always available to CREI men. While no placement guarantees will be made by CREI or any other reputable institution, for many years the demand for CREI graduates and advanced students has far exceeded the supply.

**CREI HOME STUDY ADVANTAGES.**

Technical education is accomplished on your own time, during hours chosen by you. You waste no time in travel. You have plenty of time to do your best. Your work is under the supervision of a regular staff instructor who guides your progress step by step. Courses are prepared by experts, presented in easy-to-understand form, kept up to date by periodic revision. Experience in more than three decades of home-study teaching, during which time we have corrected and commented on many hundreds of thousands of examinations, enables us to anticipate questions in our lesson material and minimize troublesome points.

**CREI STUDENTS** are professional electronics engineers and technicians, all over the world and in every phase of electronics, about one-third military, the rest civilian. Their median age is 28. In 1958 they devoted approximately 1,572,456 hours to 104,831 lesson texts, answered (and were individually graded upon) 1,048,310 searching questions and engineering problems. They studied electronics engineering technology—transistors, microwaves, forward scatter, computers, servomechanisms, radar, electronic navigational devices, and the entire field of modern electronics. New students enrolled during the year are on the missile ranges of Vandenburg AF Base and Cape Canaveral. They are at Alamagordo and China Lake, at SAC bases around the world. They are in the research laboratories and manufacturing plants where the latest electronic equipment is designed and produced. They maintain electronic equipment for United Air Lines, and Trans-Canada Air Lines. They share in electronics at All America Cables and Radio, Inc., and The Martin Co. They work for USIA (Voice of America) and Columbia Broadcasting System, for Gates Radio and Federal Electric, to name but a few. All of the firms mentioned offer their personnel CREI technical education under company plans. CREI men are found by the hundreds among field engineers of major electronic manufacturers. They're across the world and across the street. They're men you'll compete with—to gain or hold your place in the electronics profession.

**QUALIFICATIONS FOR CREI.**

College degree is not essential. If you have had basic electronic education, practical experience in electronics, and a high school education, you can probably qualify. A good way to find out: Use the postage-paid card. It will bring you the free 54-page book which has launched thousands on their advanced careers: "Insurance for Your Future in the New World of Electronics." Tuition is reasonable and may be paid monthly. It takes just one $10-a-week raise to repay your investment in CREI education and leave you a substantial bonus the first year. Available to veterans under GI bill.

**LATEST CREI COURSE:**

Now added to CREI's variety of courses in Electronic Engineering Technology is *Automation and Industrial Electronic Engineering Technology.* Complete course covering all electronic phases of automation. Special emphasis on theory, functioning and applications of servomechanisms and computers. Also noteworthy—lessons on machine control, instrumentation, data processing and telemetry.



*Residence School* in Washington, D. C. for those who can attend classes. Day and evening classes start at regular intervals. Qualified graduates earn AAS degree in 27 months. Electronics experience not required for admission.

Capitol Radio Engineering Institute

*Founded 1927*

*ECPD-Accredited Technical Institute Curricula*

Dept. 1102 G
3224 16th St., N.W. **CC**
Washington 10, D. C.

**CROWN**
Professional Tape Recorder

Model **714-C**
**Four Track Combination Heads and Two Track Play (Stereo-X)**



**THE WORLD'S FINEST FOUR TRACK!** **$695** LESS CASE

**RECORD PERFORMANCE**

| 4T FREQUENCY RESPONSE | IPS SPEED | FLUTTER & WOW | NOISE RATIO |
|---|---|---|---|
| ± 2 db 50-28000 CPS | 15 | .06% | 57 db |
| ± 2 db 40-17000 CPS | 7½ | .09% | 54 db |
| ± 3 db 30-9000 CPS | 3¾ | .18% | 51 db |

**WHY CROWN CAN GUARANTEE ITS ADVERTISED QUALITY**

"WOW", along with every other guaranteed performance feature of each CROWN, is factory tested by electronic craftsmen and a complete record is kept on each machine.

Good "WOW" is possible because of the tremendous flywheel inertia, plus absolute capstan concentricity, besides many features of mechanical stability vibration. The average "WOW" of the CROWN is lower than that of any other recorder within its comparative price class.

The "WOW" measure is marked on each machine, so the owner can see the evidence of the excellence of his machine. No other recorder, American or foreign, has as much performance quality per dollar as the CROWN.

Write Dept. EW-2 for free catalog—also data on professional tape duplicator.

**CROWN INTERNATIONAL**
Division of
INTERNATIONAL RADIO & ELECTRONICS CORP.
ELKHART, INDIANA


# Hi-Fi-Audio Product Review

### FM TUNER

*J. W. Miller Company*, 5917 S. Main St., Los Angeles 3, Calif. is now offering a moderately priced FM tuner which features a tuned r.f. stage, ultra-stable permeability tuning, and dual limiters.

The oscillator stage of the Model 580 is completely shielded to maintain radiation well below FCC requirements.



The tuner has a.f.c. with defeat control and cathode-follower audio outputs which can be FM multiplexed.

A six-tube unit, it is designed for a tuning range of 86 to 110 mc. Frequency response is 15 to 25,000 cps with distortion less than 0.5% at the 2-volt output.

The unit measures 9" x 4" x 7" and is available in black and white with gold trim or brown and white with gold trim. Literature is available on request.

### CHANNEL MASTER TURNTABLE

*Channel Master Corp.*, Ellenville, N. Y. has added a 4-speed professional turntable with transcription tone arm to its line of stereo hi-fi components.

The Model No. 6652 is said to exceed NAB (formerly NARTB) performance standards for wow, flutter, and rumble. The turntable is of heavy cast aluminum with weight concentrated in the rim to provide a smooth flywheel effect. The rotor of the specially designed 4-pole motor is electronically balanced and the motor shielded to prevent hum and keep out dust. A new suspension and mounting system permits the turntable to operate in complete electrical and mechanical silence.

The unit features a built-in, illuminated, easy-to-read stroboscope which gives the listener a continuous speed check during operation. The turntable will handle records at 16⅔, 33⅓, 45, and 78 rpm. There is a vernier fine speed control which permits the user to "tune" his records to the same pitch as musical instruments.

The turntable comes equipped with its own transcription tone arm and features a stereo wired plug-in head to accommodate all popular stereo and mono cartridges. Write the manufacturer for a copy of a data sheet giving full specifications and prices.

### ARKAY STEREO TAPE DECK

*Arkay International, Inc.*, 88-06 Van Wyck Expressway, Richmond Hill 18, N. Y. has added the *Arkay/Harting* MS-5 stereo tape deck to its line of audio components.

The heart of the unit is its combination magnetic tape head, for record and playback of optional stereo or monophonic tape. The ultra-short gap employed assures maximum response from extra-long-playing half-track or quarter-track tape. A separate erase head is coupled with an automatic interlock to prevent accidental erasure.

The oversize capstan, ½" in diameter, provides for constant tape speed and virtually eliminates wow, flutter, and distortion, according to the company. Vertical tape control is achieved by means of an all-metal tape guard. Double-shoe brakes provide instantaneous stops with no tape stretch.

Frequency response is 30 to 16,000 cps ±2 db. The deck provides speeds of 7.5 and 3¾ ips. Rewinding speed is 110 seconds for 1200 feet. The unit includes a recording level indicator, precision digital tape counter, push-button operating controls, and features instant drop-in loading.

For illustrated literature and complete specifications, contact the company.

### MALLORY CONTROLS

*P. R. Mallory & Co., Inc.*, has recently introduced two new series "L" controls which have been especially designed for audio applications.

The "LL" pad provides single-knob adjustment of both channels in a stereo

system for perfect balance. It is of dual tandem design and can be used as a stereo balance or master volume control for low-level, low-impedance audio

circuits. It includes two separate "L" pads mounted in piggy-back arrangement and operated by a common shaft.

The "LA" control was designed as a level control for monophonic equipment and features an extra long bushing to facilitate easier mounting through modern speaker cabinets without need for special extension bushings.

Both controls are so designed that as the gain on volume to the speaker is varied, the impedance between the control and the amplifier will remain constant, eliminating distortion due to impedance mismatch.

Additional details are available from the firm's distributors or from the Distributor Division of the company at P. O. Box 1558, Indianapolis 6, Ind.

### 60-WATT STEREO AMP

*Allied Radio Corporation,* 100 N. Western Ave., Chicago 80, Ill. is now marketing a deluxe 60-watt stereo amplifier as the "Knight" KN-760.

This unit delivers 30 watts per channel on stereo and 60 watts in the mono mode with a peak rating of 152 watts. It features a "stereo separation" control for continuously variable adjustment of channel separation and a loudness-contour switch for compensation at three different listening levels.

The amplifier incorporates precision bridge-T scratch and rumble filters and concentrically clutch-mounted tone

controls that operate separately or simultaneously. The circuit employs the newly developed 6L6GC output tubes which are combined with extra-heavy output transformers for extended response. To permit filling the "hole-in-the-middle" a blended third output is provided for connecting an additional speaker, if desired.

Response is ±.5 db at 60 watts over the range of 25 to 20,000 cps. Harmonic distortion is less than .75% at full rated output while IM distortion is less than 2% at 30 watts per channel. Hum and noise are 74 db below full rated output for tuner and auxiliary inputs.


# RIDER BOOKS

## New titles that mean greater opportunities for you in 1960!

**BASICS OF FRACTIONAL HORSEPOWER MOTORS** (Picture Book Course) *by Gerald Schweitzer.* Do you want to know how to repair fractional horsepower motors? Fractional horsepower motors are used in — air conditioners, fans, refrigerators, washing machines, dishwashers, sewing machines, record changers and turntables, power mowers, power tools and hundreds of other products. You can learn the theory of fractional horsepower motors rapidly and easily from this picture book course. You can readily apply this theory to servicing and maintenance as a money-making career, or to save money on repair bills of home appliances. Written by an expert (Gerald Schweitzer is head of the Technical Publications Dept. of Fedders Corp.), this is a most practical book. #236, $3.90.

**RIDER GLOBAL TIME CONVERSION SIMPLIFIER** *by Lt. Col. John G. Daiger (Ret'd).* What time is it in Oslo? In New Delhi? In San Francisco? In Rio de Janeiro? No matter where you are located you can tell at a glance what time it is anywhere in the world with the greatest of ease. It lists small towns and large cities around the world; large cities and small towns in the United States. It is color-keyed to tell you immediately the correct day. Corrects for areas that have Daylight Savings Time. Has conversion tables for those who use 24-hour calculated system. Ideal for communications personnel, airlines, banks, travel bureaus and travellers. Just a few minutes acquaints you with the easy-to-use, colorful chart and map and makes it usable to anyone. #238, $1.

**PRINCIPLES OF FREQUENCY MODULATION** *by B. S. Camies.* Do you want to know about frequency modulation? You can learn the basic principles underlying the use of frequency modulation, the transmission of frequency-modulated waves and the differences between frequency modulation, amplitude modulation and phase modulation. Starting with frequency modulation theory, a number of simple calculations are logically developed to illustrate the sideband structure and bandwith necessary for FM transmission. Advantages of FM and AM receivers in receiving signals in the presence of various kinds of interference such as from an unmodulated carrier, from white noise, from co-channel and adjacent channel operation, etc. Pre-emphasis and de-emphasis principles and practices are presented, as well as the relationship of time constants to frequency response.

The book then explores the applications of frequency modulation. The reader is gradually introduced to the specifics of FM transmitters and then to the detection of frequency-modulated signals. Limiter stages and various types of FM demodulators are analyzed. Design of broadcast FM receivers is thoroughly covered. In addition to commercial broadcast applications, microwave, point-to-point, doppler radar, telegraphy, facsimile and other types of FM transmissions are presented. #223, $2.50.

**HOW TO TROUBLESHOOT TV SYNC CIRCUITS** *by Ira Remer.* Tells you how to locate troubles in TV sync circuits used in both monochrome (black and white) and color TV receivers, and how to best service them for quickest and surest results. #249, $2.90.

**MASTER RECEIVING-PICTURE TUBE SUBSTITUTION GUIDEBOOK** *by H. A. Middleton.* Quickest and most accurate answers to all receiving and picture tube substitutions! The fabulously popular Receiving Tube Substitution Guidebook* and all four supplements has been reset, expanded and brought up to date in one master book. The original Tube Substitution Guidebooks were considered the most handy and important work books for technicians, engineers and hobbyists—the new Master book is even more valuable. In one Master Book, that is easy to use, the entire range of all radio and television receiving and picture tubes and their substitutions (good or excellent) are at your fingertips.

- 5100 Radio and Television Receiving Tube and 825 Picture Tube substitutions are listed in numerical sequence with accompanying wiring instructions showing the original and substitute socket illustrations.
- features European-American and American-European cross index listing more than 325 American to European substitutions; more than 320 European to American tube substitution.
- special section on ruggedized tubes.

#244—8½ x 11", only $7.45.

*For a short time, the original RECEIVING TUBE SUBSTITUTION GUIDE, its four SUPPLEMENTS will be available.

*For those who have the original RECEIVING TUBE SUBSTITUTION GUIDEBOOK and its SUPPLEMENTS*

**— now available**

**RECEIVING TUBE SUBSTITUTION GUIDEBOOK, 4th SUPPLEMENT** *by H. A. Middleton.* Contains the latest receiving tube and picture tube substitutions. Lists more than 510 new receiving tube substitutions, more than 85 European-American substitutions, and more than 85 American-European substitutions. The television picture tube substitution listing includes almost 300 new TV tube subst.tutions. A new feature is the inclusion of more than 150 ruggedized tube substitutions. A convenient cumulative index lists the tube types in the original GUIDEBOOK and the FOUR SUPPLEMENTS. (Important notice: this 4th supplement is contained in the MASTER RECEIVING PICTURE TUBE SUBSTITUTION GUIDEBOOK) #139-4, $1.35.

*Other new Rider titles*

**HOW TO USE GRID-DIP OSCILLATORS** *by Rufus P. Turner K6AI,* #245, $2.50.

**SHORTWAVE PROPAGATION** *by Stanley Leinwoll,* #231, $2.90.

**VOLUME SIX BASIC ELECTRONICS** *by Van Valkenburgh, Nooger & Neville Inc.,* #170-6, soft cover, $2.90; #170-6H cloth, $3.60.

**HOW TO USE METERS (2nd ed.)** *by John F. Rider & Sol D. Prensky,* #144, $3.90.

*Write for 1960 catalog*

*Prices subject to change without notice. In Canada, 5% higher.* Dept. EW-2

*At your jobber or bookstore or order direct:*

JOHN F. RIDER PUBLISHER, INC. 116 West 14th Street, New York 11, N. Y.
Canada: Chas. W. Pointon, Ltd., 66 Racine Rd., Rexdale, Ont.



*GET INTO*

# ELECTRONICS

V.T.I. training leads to success as technicians, field engineers, specialists in communications, guided missiles, computers, radar and automation. Basic and advanced courses in theory and laboratory. Associate degree in electronics in 30 months. B.S. in electronic engineering obtainable. ECPD accredited. G.I. approved. Graduates in all branches of electronics with major companies. Start February, September. Dorms, campus. High school graduate or equivalent. Catalog.

**VALPARAISO TECHNICAL INSTITUTE**
**Dept. RD** **Valparaiso, Indiana**



# GREAT SURPLUS VALUES ! !

| | |
|---|---|
| BC-603 RECEIVER NEW | $17.00 |
| R-26/ARC5 REC 3-6 mc New | $12.95 |
| R-27/ARC5 REC 6-9 mc New | 12.95 |
| (above ARC-5's used exc.) | 7.95 |
| BC-659—TRANSCEIVER with PE-120 Power | 19.95 |
| T-47/ART-13 TRANSMITTERS | 39.00 |
| BC-603 AC-SUPPLY | 9.95 |
| SYNCHROSCOPES MODEL TS-34/AP | 49.00 |
| SOUND-POWERED DYNAMIC PHONES Pr. | 4.75 |
| REC. MICROWAVE R-111/APR-5 | 39.00 |
| ARB/RCA—SIX TUBE RECEIVER | 17.50 |

RA-62-C POWER SUPPLY A-C for SCR-522 VHF 110/60 cyc. Like new LTD QTY. . . . **$59.50**
KITS only for above. Contains special xformer, rectifier, regulator and connectors w/schematic. SPECIAL ONLY . . . . . **$17.00**

GROUND-PLANE VHF ANTENNAS $9.95
GOOD FOR CITIZENS BAND FROM 30-200 MC—NEW

SEND FOR NEWEST FREE CATALOG
$5.00 Min. - 25% Dep. C.O.D.'S - F.O.B. Conn.

**HI-MU ELECTRONICS**
133 HAMILTON ST. NEW HAVEN, CONN.

*why your next speaker system should be*

# THE NEW AUDAX PARAFLEX

• Only Audax incorporates the **Patented Paraflex Foam Suspension** to give longer travel to the cone, resulting in honest bass without boom or hangover. You get bass with real bottom!

• **New Styrofoam Radial Strut-Bracing** reinforces cone, assures rigid piston action, preventing cone break-up. Eliminates distortion, provides clean reproduction up to the full-rated power output. Needs as little as 10 watts output. You get greater amplifier economy in stereo installations.

• **New Oriented Grain-Processed Magnet** gives 20% more efficiency than standard Alnico V.

• **New Ducted-Slot Enclosure** specifically designed to enhance the depth and striking realism of the Paraflex high-compliance speaker units. Speakers are located symmetrically on each side of the ducted slot, resulting in clean bass without trace of boom or unnatural heaviness.

• **New, dramatic enclosure styling by George Nelson**—featuring... new, three-dimensional Dynel "Acoustiscreen" grille, removable for cleaning!

• **Audax Paraflex Speakers are** lab-tested and a performance seal on each unit indicates its resonant frequency ± 1 cycle.

**Model CA-80** 12" x 12" x 24" with two full range speakers—**$99.95**

**Model CA-100** 15" x 12" x 25" with two 10" full range speakers and 2 matching cone tweeters—**$139.95**

**Also full line of component speakers**

Write for free catalog and specifications, to: **AUDAX Division of the Rek-O-Kut Co., Inc.** Dept. EW-2, 38-19 108th St., Corona 68, N. Y.

Name_____

Address_____

City_____ State_____

Export: Morhan Exporting Corp., 458 Broadway, New York 13
Canada: Atlas Radio Corp., 50 Wingold Ave., Toronto 19, Ont.

Ad-9

The amplifier comes completely assembled in a vinyl-clad case which measures 4⅝" x 15¾" x 15⅛". It is catalogued under Stock No. 92 SU 434.

### DUAL AUDIO MIXER

*Olson Radio Corporation*, 260 S. Forge St., Akron, Ohio is now offering a dual audio mixer unit, the Model VS-




220, which is designed to be used with any amplifier, tape recorder, or system to control any two audio sources.

The unit connects to the microphone or phono input and handles input and output impedances of 500,000 ohms. Dual input jacks take either standard ¼" phone plugs or *RCA*-type phono pin plugs. The output terminates in *RCA*-type phono pin jacks.

The unit is housed in a cabinet which measures 4" x 2⅝" x 1⅝".

### NEW AUDIO TUBE

The Receiving Tube Department of *General Electric Company*, Owensboro, Ky. has registered a new audio tube, the 7355, which is designed to fill the gap getween the 6V6 and the 6L6 and provide economical hi-fi equipment in the 20- to 30-watt range.

This new midpower tube is an octal-based beam pentode which incorporates the company's new five-ply bonded metal plate. With 18 watts plate dissipation per tube possible, a pair of 7355's is rated to deliver 28.5 watts with 2 percent harmonic distortion without feedback in a class $AB_1$ push-pull high-fidelity amplifier.

Maximum ratings include: plate, 440 volts; screen, 400 volts; screen dissipation, 2.5 watts continuous and 5 watts on speech and music peaks; and cathode current, 100 ma. The 6.3-volt heater draws 0.8 amp.

### AUDIO CONTROL CENTER

*Ampex Audio, Inc.*, 1020 Kifer Road, Sunnyvale, Calif. has recently released a new stereo audio control center as its Model 403.

Push-button selection insures proper matching, equalization, and balance for the input signals from tape, records, FM-AM tuner, TV tuner, microphone, or other external sound sources. The unit is designed to be used with any quality audio system.

Separate controls for bass and treble response permit individual adjustment, as desired, with a maximum boost or



cut of approximately 15 db. Two loudness controls, one for each channel, are mounted on concentric shafts and friction-coupled to permit setting and maintaining uniform calibration and balance of audio levels. A push-button control is provided for reversing left and right channels.

Available uncased for built-in installations or with a hardwood cabinet (walnut finish or unfinished) for open

**Clevite Transistor Products is building a new plant in Waltham, Mass. which will provide 165,000 square feet of manufacturing, laboratory, and office space and employ approximately 1500 persons. Completion is set for late spring or early summer. Air-purification and temperature control systems will afford a plant atmosphere of hospital operating room standards. Decontamination locks will enable employees to remove dirt from shoes and change into lint-free clothing before entering key work areas. In all laboratory and production areas, power lines and process liquids and gases will be channeled through a subfloor network. The new plant will be located along Route 128, a superhighway artery feeding the Boston area.**



or shelf mounting, the unit measures 4½" x 14$\frac{15}{16}$" with 9" required behind panel. A data sheet giving complete specifications is available on request.

### TRANSISTORIZED STEREO GEAR

*Transis-Tronics (TEC), Inc.,* 1650 21st. St., Santa Monica, California has announced production of an all-transistor high-fidelity stereo amplifier and



preamp which provides 25 watts per channel on stereo (50 watts peak) and 50 watts on mono (100 watts peak).

The Model S-25 has provision for all possible sources of stereo FM multiplexing, stereo AM sideband tuning, and stereo TV, as well as stereo AM-FM. The unit is designed to operate from either a 12-volt battery power supply or 115-volts a.c.

Specifications include response 20 to 20,000 cps ±1 db at 25 watts; harmonic distortion less than 0.8%; hum 100 db below full output; RIAA equalized low-level phono, high-level phono, NAB equalized low-level tape playback, low-level microphone, high-level tuner, and two high-level auxiliary inputs; and 4-, 8-, and 16-ohm outputs on each channel.

The company is offering this new equipment with a two-year unconditional guarantee of materials and workmanship. Write the manufacturer direct for further details and price.

### TUNER/AMP COMBINATION

*H. H. Scott, Inc.,* 111 Powdermill Road, Maynard, Mass. is now offering a new stereo tuner/amplifier combination, the 399.

The new instrument combines two preamplifiers, two 20-watt power amplifiers, an AM tuner, and an FM tuner



on a single chassis. All that is needed for a complete stereo component system are two speakers. A phonograph can be plugged into the back if desired.

The circuit features separate tone controls on each channel for speaker matching to room acoustics; a phase reverse switch on the front panel; third-channel output; and sensitive AM and FM front ends. Other features include a special non-magnetic chassis, d.c. heaters on all preamp tubes, and a 10 kc. bridged-T AM whistle filter. There are more than 30 separate controls located on the front panel for


# Build This Superb *Schober* Organ From Simple Kits and SAVE OVER 50%!

The Beautiful *Schober* CONSOLETTE

– the only small organ with two full 61-note keyboards and 22 stops. Requires only 2' x 3'2" floor space! Commercial value approximately $1600 or more – yet you save over 50% when *you* build this thrilling instrument!

LET US SEND YOU **FREE DETAILS** HOW TO ASSEMBLE A *Schober* ELECTRONIC ORGAN IN SPARE TIME!

## Give Your Family A Lifetime of Musical Joy With A Magnificent Schober ELECTRONIC Organ!

Now you can build the brilliant, full-range Schober CONSOLETTE or the larger CONCERT MODEL with simple hand tools. No skills are necessary to construct an instrument with one of the finest reputations among electronic organs. No woodworking necessary – consoles come completely assembled and finished. All you do is assemble clearly marked electronic parts guided by clear illustrations and detailed step-by-step instructions. Even teen-agers can assemble the Schober! You build from kits, as fast or as slowly as you please...at home, in spare time – with a small table serving as your entire work shop!

THE GREAT **CONCERT MODEL** meets specifications of **American Guild of Organists**

**Pay As You Build Your Organ; Start With As Little As $18.94!**

You may start building your Schober at once with an investment of as little as $18.94. The musical instrument you assemble is as fine, and technically perfect, as a commercial organ built in a factory – yet you save over 50% on top-quality electronic parts, on high-priced labor, on usual retail store mark-up! In your own home, with your own hands you build an organ with *genuine pipe organ tones* in an infinite variety of tone colors to bring into your home the full grandeur of the Emperor of Instruments. You may build the CONSOLETTE for your home, or you may want to build the great CONCERT MODEL for home, church, school or theatre. You save 50% and more in either case.

**Send For Complete Details On Schober Organs and For Hi-Fi Demonstration Record**

The coupon will bring you a handsome 16-page booklet in full color describing Schober organs in detail, plus articles on how easy and rewarding it is to build your own organ and how pleasant and quick it is to learn to play the organ. In addition, we have prepared an exciting 10" hi-fi LP record demonstrating the full range of tones and voices available on the Schober, which you may have for only $2.00 (refunded when you order a kit). Literature on the Schober is FREE! There is no obligation; no salesman will call.

**Mail This Coupon For FREE Literature and Hi-Fi Record Today!**

The Schober Organ Corp., Dept. RN-3
2248 Broadway, New York 24, N. Y.

☐ Please send me FREE full-color booklet and other literature on the Schober organs.

☐ Please send me the 10" hi-fi Schober demonstration record. I enclose $2.00 (refundable on receipt of my first kit order).

Name.....

Address.....

City.....Zone...State.....

only for those who want the ultimate

SHERWOOD

"TOP RATED" again and again -and NOW AGAIN!

Model S-5000, 20+20 watt "stereo" Dual Amplifier-Preamplifier, Fair Trade Price—$189.50



Model S-2200, FM-AM-MX Stereo tuner, Fair Trade Price—$179.50



AMERICAN AUDIO INSTITUTE

304 EAST 18th ST. PATERSON 4, N.J.

October 27, 1959

Sherwood Electronic Labs., Inc.
4300 North California Avenue
Chicago 18, Illinois

Gentlemen:

We find that the incorporation of a center-channel output and a damping factor selector in July, 1959, increases the Summary Rating of the Sherwood S-5000 to the highest of all 18 Stereo Amplifiers tested in the AAI Evaluation Test Reports.

Sincerely,

AMERICAN AUDIO INSTITUTE

Felix R Breny

Felix R Breny
Executive Director

The "Most honored of them all" S-5000 stereo amplifier-preamplifier is joined by the S-2200 stereo tuner. As with its "Top Rated" predecessors, the S-2200 features FM "Interchannel Hush" plus push button selector, internal plug-in adaptor for Stereo FM Multiplex, 2 "Acro-beam" tuning indicators, simulcast FM/AM stereo. All Sherwood tuners feature FM sensitivity below 0.95 microvolts and ⅓% distortion @ 100% FM. For further details write: Sherwood Electronic Laboratories, Inc., 4300 N. California Avenue, Chicago 18, Illinois.

For complete specifications write Dept. EW-2


the maximum operational flexibility.

Full technical details are available from Dept. P of the company.

### ELECTRONIC ORGAN KITS

*Schober Organ Corporation,* 2248 Broadway, New York 24, N. Y. is now offering two electronic organ models in easy-to-build kit form, the "Concert" and the "Consolette."

The "Concert" model meets the specifications of the American Guild of Organists while the "Consolette" offers the user a full-range organ which is smaller than a spinet. It has two 61-note keyboards, 22 stops, and 13 pedals yet measures only 38 inches wide.

Both organs are available as a series of kits so that the builder may purchase and assemble his instrument at his convenience and to meet his budget. A 10-inch LP demonstration record which shows the quality of performance of both models is available for $2 which is refunded with the first order for a kit.

A booklet describing the two organs is available without charge on request.

## AUDIO CATALOGUES

### TELEFUNKEN BROCHURE

*Audio Fidelity Professional Products Inc.,* 770 Eleventh Ave., New York 19, New York, U. S. distributor of *Telefunken* professional products, announces the availability of a six-page brochure covering the firm's line of microphones, amplifiers, tape recorders, disc playback equipment, loudspeakers, and general accessories for use by the broadcasting, motion picture, radio, recording, and television industries as well as other electronic areas where sound reproduction in communications is involved.

The publication pictures and describes each of the units in considerable detail. Those in professional recording fields are invited to write the U. S. distributor for a copy of the brochure.

### MICROPHONE TIPS

*Shure Brothers, Inc.,* 222 Hartrey Ave., Evanston, Ill. has prepared a new booklet entitled "The Microphone in Public Address Systems" which it will forward without charge to interested persons.

The eight-page booklet has been written for businessmen, educators, entertainers, recording enthusiasts, and all others who have occasion to use a microphone. Contents include a description of a p.a. system's components, tips on buying or improving a system, and facts on the uses and limitations of the basic types of microphones.

Also covered are rules of microphone technique and a list of common microphone usage problems and solutions.

-30-

*Heath Company, Benton Harbor, Michigan has announced the withdrawal of the Model SA-1 14-14 watt stereo amplifier which was announced on pages 89-90 of our January issue. This unit will be replaced by a dual 25-watt amplifier which will be designated as the Model AA-50.*

"Golden eggs, my foot! *This* goose lays JENSEN NEEDLES!"

take a tip from wigo

PRONOUNCE IT WEEGO

Not every speaker that looks good sounds good. Though Wigo may not be the best looking speaker in the world, it is one of the best sounding, now...and for years to come. Hear it at your dealer...then tip off your friends. For literature, write...

united audio

PRODUCTS OF DISTINCTION

*202-4 East 19th St., N.Y.3, N.Y.*

# A BABY'S "DIAPER ALARM"

By C. M. SWEET, VU2CT

OFTEN small babies are left in discomfort when busy mothers fail to notice that a "change" is required. Here is an absolutely safe and easily built alarm which automatically announces, in a pleasant, audible tone of adjustable pitch, when the baby is in need of attention.

The unit is in two parts—(1) the alarm box proper which houses an adjustable audio-frequency oscillator of the low-power transistor type that operates from a 1½-volt flashlight battery. This energizes a PM speaker. The oscillator is connected via a convenient length of twin-lead to (2) a moisture-sensitive contact pad. This pad is placed in the baby's crib above the usual protective waterproof sheet but below the folded napkin or pad of absorbent material which is changed.

Although the author used a Philips OC72 transistor, any low-power audio transistor, such as the Raytheon CK722 or G-E 2N107 can be substituted. Also any PM speaker output transformer having a tapped primary with impedance of 400 ohms or more will do. The designer's intention was to limit the current in the contact pad circuit to a maximum of 50 μa. and in the collector circuit to about 15 ma.

In operation, when the switch is turned on and the absorbent cloth touching the contact pad is moistened, the input circuit is completed. Now the transistor oscillates due to feedback between the two sections of the primary winding of the transformer which are coupled, respectively, to the input and output circuits. The pitch of the note thus produced in the loudspeaker is adjusted by varying the 100,000-ohm pot. A fairly high note is preferable as it is more audible; in addition, current consumption is reduced as the oscillator frequency is increased. If too much moisture collects between the contact strips, they should be wiped dry when the diaper is changed.

The contact pad consists of two flat metal strips, each 10" long and ¼" wide, sewed onto a 12" x 6" pad of waterproof or plastic sheet. The strips should be separated ⅛" and connected to the alarm unit by a 10-foot length of twin-lead.

Considering the small amount of time and cash required to build this alarm, the results are truly gratifying. —30—

Circuit diagram of a safe "moisture" alarm unit which produces pleasant audible tone.








1960 RADIO-ELECTRONIC MASTER

now available at your distributor

NEW...STREAMLINED...28 EASY-TO-USE PRODUCT SECTIONS COVER ALL LATEST PRODUCTS

*• Printed circuit components • Stereo equipment • Miniature and sub-miniature components • Silicon rectifiers • New transistor types • Citizen's band, SSB and new mobile ham gear • Components and equipment for microwave and telemetering..... Plus every new electronic product for servicing, experimenting, design, industrial and military applications.*

GREATER INCOME...SPEEDIER DESIGN & PURCHASING...MORE HOBBY FUN

SERVICE TECHNICIANS
More profitable operation. Covers all items necessary for Radio-TV-audio servicing. Offers thousands of products for extra income in hi-fi, sound and industrial servicing. You can buy, sell and bill direct from The MASTER...it shows list prices!

ENGINEERS & P.A.'s
Save time. Quickest way to get current factory-accurate data on all the products needed for research, design and production. Systematically organized in 28 product sections for rapid product comparison. Minute details so necessary for specifying.

HAMS, HOBBYISTS, EXPERIMENTERS
Get the right product to do the job because you shop in the electronic supermarket — The MASTER. Specifications, descriptions, prices of receivers, transmitters, hi-fi gear, cabinets and hard-to-locate items not found in smaller catalogs.

*No matter what product or component you require...*

YOU'LL FIND IT FASTER IN THE

1960 MASTER

RADIO ELECTRONIC MASTER, 60E Madison Ave., Hempstead, N.Y.

FREE...FROM YOUR DISTRIBUTOR
*24-page Foreign Tube Interchangeability Guide or write direct enclosing 25¢ for handling*

NEW!

RESIST-O-BIN

FREE! with any of 4 Handy-Pak Carbon Resistor Assortments • 34 Values

$24.48 to $48.96 Dealer Net

All-metal • 36 Compartments

IRC

Order from your IRC Distributor

INTERNATIONAL RESISTANCE COMPANY
DISTRIBUTOR SALES DIVISION
414 N. 13th STREET • PHILADELPHIA 8, PA.

# HOME-BUILT POWER-LINE REGULATOR

By **A. V. J. MARTIN**
Carnegie Institute of Technology

**Ferro-resonant a.c. stabilizer uses rewound transformer, capacitor, and resistor. Delivers 0.5 amp. at 117 volts.**

IRREGULAR power-line voltage is a common plague affecting not only the technician in his laboratory but the customer at home. Picture size variation and unstable pictures are two common effects of varying line voltage. In addition, most precision instruments, like generators, are often sensitive to supply voltage variations and for maximum accuracy should be fed stabilized a.c.

### Ferro-Resonant Stabilizer

The so-called ferro-resonant a.c. stabilizer is probably the simplest of all the means which have been devised to keep power-line variations within reasonable limits. A number of commercial versions of the device are available, most of them involving highly sophisticated circuitry, with attendant bulk, weight, and high price.

### Basic Principle

Basically, a ferro-resonant circuit comprises a capacitor and inductor, as shown in Fig. 1. The inductor saturates and its inductance value is not a constant but a function of the applied current or voltage. Such an inductor is said to be "non-linear." Fig. 2A shows the voltage $V_C$ across the capacitor and the voltage $V_L$ across the non-linear inductor as functions of current.

Since the capacitor and inductor are connected in series, the current is evidently the same through the capacitor and the inductor, but the voltages $V_C$ and $V_L$ are opposite in phase. Consequently, the total voltage $V$ across the series combination is given by the difference between $V_C$ and $V_L$ and has been plotted in Fig. 2B. It is seen that $V$ goes down to zero for some value of current, just as it would for some value of frequency in a standard series-resonant circuit, hence the name "ferro-resonant" circuit, which has nothing to do with any "resonance"



The rewound transformer and the capacitor are mounted atop a small chassis.

of the usual kind that is ordinarily discussed.

As it stands, Fig. 2B represents the ideal case when there is no power consumption. If there is power consumption, the zero point $P$ shifts upward and does not give zero voltage any more. The resultant curve is represented in Fig. 2C. The almost horizontal part of the curve has a slope which depends on the power consumption—becoming more horizontal as the power consumption increases.

A variant of the circuit uses a parallel connection of the capacitor and inductor with similar results. It can be seen that these ferro-resonant circuits are highly sensitive to changes in current or voltage. They are extensively used as the basis of different arrangements to provide relatively stabilized voltages or currents.

The non-linear inductor can just as well be the primary of a transformer and this has been put to good use in the stabilizer that is described in the following text.

Fundamentally, then, stabilization can be obtained with a single capacitor and a single inductor and nothing forbids us to use only these two necessary components, as indicated in Fig. 3. This diagram represents the basic ferro-resonant stabilizer. It seems hard to beat for simplicity and economy, although this stripped-down version works well.

Resistor $R$ is a refinement added to provide a discharge path for the capacitor when the stabilizer is switched off. The capacitor then discharges through the primary of the transformer and the resistor, whose value is not at all critical—it can run anywhere between 50,000 and 500,000 ohms. The capacitor can be of any non-polarized, *i.e.*, non-electrolytic, type. For example, paper or oil capacitors are suitable. For the standard power-line voltage, the capacitor should be rated at least 600 volts.

Any value of capacitance can be obtained at will by paralleling several capacitors but it is simpler and more economical to choose a design leading to a standard value of capacitance. Care must be exercised, however, because the tolerances are very wide for capacitors. Unless a precision component is purchased (and they are costly) the best way is to actually measure the capacitance. No precision measurement is necessary, however, since discrepancies up to 10 or even 20 per-cent can be adjusted during the final tune-up.

### Components

The only non-standard element is the transformer.

The core laminations will be stacked transformer fashion, that is, with no air-gap and with alternate orientations. The core cross-sectional area, $S$, will be evaluated with the help of the expression: $S = k\sqrt{P}$ where $P$ is the




◀ Fig. 1. Basic ferro-resonant circuit.




Fig. 2. (A) Individual and (B) total voltage. (C) Effect of load. ▶

wanted power in va., *e.g.*, the product of the regulated voltage, $V_2$, in volts by the load current, $I_2$, in amperes. $S$ is obtained in square centimeters. $k$ is a coefficient depending on the quality of the laminations. For the standard low-grade *armature* steel (28 sheet gauge, .0155 inch thickness, .625 pound per square foot) or for the next better grade, *electrical*, in the same dimensions, $k$ should be about 1.

For the better grade *dynamo* steel, in the same dimensions or in the more common 29 sheet gauge, $k$ should be 0.9.

The primary winding will have a number of turns, $N_1$, given by the formula: $N_1 = 40\ V_1/S$ where $V_1$ is the nominal power-line voltage.

Similarly, the secondary winding will have a number of turns. $N_2$, given by the expression: $N_2 = 30\ V_2/S$.

The correct wire gauge to use is determined by the current through the wire. The primary current will be taken as $I_1 = P/V_1$ and the secondary current as $I_2 = P/V_2$.

Reference to a wire table will indicate what size wire to use, bearing in mind that the current density should not exceed 2.5 amperes per square millimeter. If no wire table is available, dividing the current by 2.5 will give the wire cross-section in square millimeters.

Once the wire size is known, a good precaution is to check that the laminations opening or window is large enough to contain the two windings and the insulation.

For powers up to 100 va., the capacitor should not be smaller than 4 $\mu$f. For power between 100 and 250 va., the capacitor should not be less than 8 $\mu$f. in value. Keeping this restriction in mind, the capacitor value in microfarads is given by: $C = 1.5 + (P/6)$.

It can be seen that the preceding restriction precludes the design of stabilizers for powers lower than 15 va. As previously pointed out, the capacitor value given by the equation above will probably be an awkward number. The nearest standard value will have to be adopted.

This, and the fact that all of the formulas given are empirical, indicates that the calculations will provide only an approximate design. In all cases, final adjustment will have to be made to insure optimum results. Luckily, such an adjustment is not too critical. The easy way to proceed is to be prepared for it by including several taps in the primary winding, as well as some amount of overwinding so as to provide leeway in both directions.

A practical satisfactory minimum arrangement is to provide two taps at 25% and 12% of the total number of turns before the end of the winding. Then, the primary is overwound 25% with a tap at 12%. The adjustment consists of connecting the capacitor to the tap providing the best regulation.

## Practical Design

An example of design will show how to proceed. For example, a stabilizer




Fig. 3. Basic circuit with transformer.




Fig. 4. Design of the transformer and other components employed.

was desired to provide a maximum current, $I_2$ of 0.5 amp at a stabilized voltage, $V_2$, of 117 volts. The power is: $P = 117 \times 0.5 = 58.5$ va., which rounds off at 60 va.

It was desired to use available laminations, with a center limb 1 inch wide. The only trouble was that nobody had any idea of the quality of the steel. Consequently, it was assumed to be good grade material and a $k$ of 1.0 was chosen in the hope that final adjustment could correct for any eventual discrepancy. Luck was with us . . .

The cross-section of the core thus becomes: $S = 1.0 \times \sqrt{60} = 7.75$ square centimeters. A 1¼" thick stack of laminations will give a cross-section of $2.5 \times 3.1 = 7.75$ square centimeters with a good enough approximation.

The primary winding would then have: $N_1 = (40 \times 117)/7.75$ or 600 turns, nominally, but to allow for adjustment we shall wind 750 turns with taps at 450, 528, 600, 672, and 750 turns.

For a primary current of 0.5 amp. and a current density of 2.5 amps. per square millimeter, the primary wire will have a cross-sectional area: $S = 0.5/2.5$ or 0.2 square millimeter, which corresponds to No. 24 AWG.

The secondary will have: $N_2 = (30 \times 117)/7.75$ or 450 turns and will use the same wire size.

Finally, the capacitor value is: $C = 1.5 + (60/6)$ or 11.5 which would normally round off at 12 $\mu$f. However, several available oil and paper capacitors were measured and one 10 $\mu$f. unit turned out to be 11.8 which was nearer the actual value than was hoped for or indeed desired.

The stabilizer was then built according to the diagram of Fig. 4 and tests were made by connecting high-power resistors across the secondary. The tap which provided the best results was the tap at 528 turns.

With the help of a "Variac," the primary voltage was varied and the secondary voltage under load measured. The resulting regulation characteristic is plotted in Fig. 5. It shows a secondary voltage variation of no more than 3.5 volts, *e.g.*, 3 per-cent for a primary voltage variation of ± 24 volts which is practically 40 per-cent. The actual output voltage was not 117 volts originally because of the design approximations. This was immaterial but was easily remedied by suitable adjustment of the number of secondary turns, that is, by adding 40 turns to the existing 450.

Note that the stabilizer should preferably be used under full load. The hardest regimen is the "no-load" condition.

## Advantages & Drawbacks

The main advantages of the simple ferro-resonant stabilizer are economy and ease of design. It can be built and made to work without difficulty and will provide regulation sufficient for most practical purposes without critical adjustments. In addition, the design is inherently about as rugged as could be and is practically trouble-free for life.

The picture is not all rosy, however. For one thing, the design becomes more approximate as the power increases and as the transformer increases in bulk and weight. The temperature rise is somewhat high and easily reaches 70 degrees C in the windings.

The magnetic field around the transformer is intense and precludes installation near any field-sensitive device such as a high-gain amplifier, electromagnetic measuring instrument, or magnetic deflection tube.

The output voltage bears only a faint resemblance to the familiar sinusoid. In other words, the waveform is strongly distorted. This is not too important when the stabilizer feeds a transformer, which is the common case, but may become a drawback in special circumstances.

Finally, the regulator is frequency sensitive. A frequency variation of 1 or 2 per-cent will give rise to an output voltage variation of 2 or 3 per-cent.

All in all, these drawbacks are not serious in a vast number of practical applications. If such is the case, the ferro-resonant a.c. voltage stabilizer will provide year after year of reliable service at small initial cost and with virtually no maintenance. -30-




Fig. 5. The excellent stabilization characteristics of the circuit are shown here. For a change of input voltage from 92 v. to 140 v., output is between 116 v. and 119.5 v.

# newest *knight-kits*® . . . years-ahead

A PRODUCT OF ALLIED RADIO



## incomparable *knight-kit* stereo hi-fi saves you up to 50%

### DELUXE 40-WATT STEREO AMPLIFIER KIT

**Y-774D**

**$79.50**

***$5 Down***

Finest hi-fi stereo amplifier you can buy in money-saving kit form. Features special full-frequency range, extra center-channel output for 3-speaker systems. Dual built-in equalized preamps accommodate every existing sound source; exceptional control versatility, including single knob channel balance and separate dual concentric tone controls for each channel. Outputs for stereo tape recording. Exclusive printed circuit switches and plug-in units for easy assembly. Custom-styled in Cordovan gray vinyl plastic bonded to steel; Desert Beige and Sand Gold extruded solid aluminum escutcheon; 4⅛ x 15½ x 11¼". Shpg. wt. 24 lbs.

**Model Y-774D.** 40-Watt Stereo Amplifier Kit. **$5 DOWN**

### DELUXE STEREO FM-AM TUNER KIT

**Y-731D**

**$87.50**

***$5 Down***

Distinguished for quality and styling, years-ahead in features. Has completely independent FM and AM sections, each with moving-bar "magic eye" tuning indicator. Only tuner kit with Dynamic Sideband Regulation (DSR) on FM for purest, distortion-free reception. Sectionalized construction permits easy addition of "built-in" multiplex. Has 2½μv sensitivity. Double limiter-discriminator FM circuits—adjustable AFC. Separate cathode-follower outputs on FM and AM with level set controls. Precisely aligned RF and IF transformers in FM section. Printed circuit boards for fastest, easiest assembly. Styling matches the 40-watt amplifier; 4⅛ x 15½ x 12". Shpg. wt., 18 lbs.

**Model Y-731D.** Stereo FM-AM Tuner Kit. **$5 DOWN**

## there is a money-saving *knight-kit* for every hi-fi need

**20-Watt Stereo Amplifier**
Truly a super-value. Built-in equalized preamps; single-knob selector switch for control convenience; dual concentric, clutch-type level control. 17 lbs.
**Y-773D.** *$2 Down.* Only **$44.50**

**FM-AM Hi-Fi Tuner Kit**
Amazing buy, featuring: Tuned RF stage; high sensitivity; AFC; flywheel tuning; pre-aligned IF and RF coils; cathode follower output. Truly great value. 14 lbs.
**Y-787D.** *$2 Down.* Only **$49.95**

**18-Watt Hi-Fi Amplifier Kit**
A brilliant performer at unbelievable savings. 18 watts at only 0.5% distortion; RCA 6973 audio output tubes; 8 inputs; 7 record equalization settings. 15 lbs.
**Y-797D.** *$2 Down.* Only **$39.95**

**SEE THEM ALL**
**See the impressive selection of Hi-Fi Knight-Kits (including speaker systems) in the money-saving 1960 ALLIED Catalog. If you haven't a copy, send for it today.**

**FREE**

**ONLY $5 DOWN (OR LESS)** on orders up to $200; up to 24 months to pay. Fast handling—no red tape—take advantage of these easiest-pay terms . . .

# for you who want to build the very best for less . . .

## all-new *knight-kit* citizens band transceivers . . . 2-way radio everyone can afford

### CITIZENS BAND SUPERHET TRANSCEIVER KIT

**Y-712D**

**$79.95**

***$5 Down***

A high-sensitivity do-it-yourself transceiver for efficient, economical 2-way radiotelephone communication. Any citizen, 18 or older, can get a license—no exam required. For mobile or stationary use. Covers up to 20 miles, depending on antenna height and terrain. Works just like an intercom, with talk-listen operation. Receiver is sensitive superhet; tunes all channels continuously. 5-watt transmitter section. Built-in AC power supply. With transmitting crystal (available for any channel from 1 to 22—specify preference) and doublet antenna. Extras available: Y-723, 6-12 v. DC power supply, $10.95; Y-729 vertical antenna, $6.50; Y-714 mobile mounting bracket, $5.35. Distinctive high-impact styrene case; 5 x 12 x 12". Shpg. wt., 20 lbs.

**Model Y-712D.** Superhet Transceiver Kit. **$5 DOWN**

### CITIZENS BAND TRANSCEIVER KIT

**Y-713D**

**$39.95**

***$2 Down***

Low-cost super-regenerative receiver and 5-watt transmitter kit. Readily fits car, boat or desk. Simple, one-switch operation permits talk or listen. Receiver tunes all 22 channels continuously. Built-in AC power supply. With mike, transmitting crystal—specify channel (1 to 22) if you have a preference—and doublet antenna. Handsomely styled case; 6 x 10 x 8". Designed for easy assembly and dependable operation. Available extras: Y-723, 6-12 v. DC power supply, $10.95; Y-729 vertical antenna, $6.50; Y-724 mobile mounting bracket, $5.35. Shpg. wt., 10 lbs.

**Model Y-713D.** Transceiver Kit. **$2 DOWN**

## dozens of exciting hobbyist kits available



**"Span Master" 4-Band Radio Kit**

Famous for world-wide short-wave and broadcast reception. True band-switching; continuous 4-band coverage from Broadcast to 30 mc. Sensitive regenerative circuit; 4" PM speaker. With cabinet. 8 lbs.

**Y-258D.** *$2 Down* Only..... **$25.95**



**5-Transistor Portable Radio Kit**

Popular, low-cost personal portable. Fun to build; superhet circuit; only 22 ounces; big 3½" speaker; built-in ferrite loopstick; phone jack. (Less battery, $1.30.) 2 lbs.

**Y-771D.** *$2 Down.* Only..... **$25.95**

**"Ranger" Clock-Radio Kit**

Easiest superhet of all to build—plug-in modules and printed circuit board eliminate small parts assembly. Excellent AM broadcast reception. Telechron clock has "sleep" switch. With appliance outlet. 6 lbs.

**Y-737D.** *$2 Down.* Only..... **$24.95**

**SEE THEM ALL:** Knight-Kits offer the most exciting hobbyist kits available. See the complete selection in the 1960 ALLIED Catalog. Write for it now—use coupon on page following.

**FREE**

*manufactured and sold exclusively by* **ALLIED RADIO** 100 N. WESTERN AVE., CHICAGO 80, ILL.

# newest knight-kits® ... years-ahead

A PRODUCT OF ALLIED RADIO

## knight-kits break through the professional instrument price barrier

### 5" LAB DC SCOPE KIT WITH IVA

**Y-611D**

**$285.00** *(less preamps)*

For the first time in easy-to-build kit form—a triggered sweep DC precision quality lab scope with plug-in **interchangeable vertical amplifiers** (IVA). Brilliantly engineered with an impressive array of professional features, including: crystal-controlled timing markers; DC amplifiers in both horizontal and vertical channels; electronically regulated power supply; sweep timing adjustable to 1%; built-in voltage regulated peak-to-peak calibrator. Three interchangeable vertical preamplifiers are available: high-gain differential, $35.95; wide-band (to 10 mc), $24.95; dual-trace, $48.95. **There is no other instrument like this in kit form**—here is laboratory precision quality and reliability at far less than the cost of any comparable factory-built unit. Shpg. wt. 50 lbs.

**Model Y-611D.** Lab DC Scope Kit. **$10 DOWN**

*Available in March—reserve yours now*

### LAB AUTOMATIC AC VTVM KIT

**Y-608D**

**$99.50** *$5 Down*

A major achievement in instrumentation! This all-new AC VTVM features **automatic range selection**—by means of an electronically-actuated self-seeking mechanism which **automatically** selects the proper range when you touch probes to the circuit under examination. Simultaneously, a front panel light indicates the range in use. Covers 11 ranges from 3 millivolts to 300 volts full scale; frequency response to 2.5 mc. Reads as low as 100 μv. Highly stable 3-stage amplifier has cathode follower output; ideal for use as preamp for other test equipment or for connection to scope for simultaneous wave form observation. Includes precise trigger circuits; regulated power supply; latest printed circuitry for easy assembly and quality performance. An exclusive Knight-Kit development—there is no other instrument like it on the market, in any form or at any cost. Shpg. wt. 13½ lbs.

**Model Y-608D.** AC VTVM Kit. **$5 DOWN**

## save on every instrument need with knight-kits ... best by design

**Famous-Value VTVM Kit**

Measures DC voltage (11 meg. input) and resistance; AC voltage, rms and peak-to-peak. 4½" meter. Push-pull balanced bridge circuit. 7 lbs.

**Y-125D.** *$2 Down.* Only **$25.75**



**Deluxe Tube Checker Kit**

Checks over 700 receiving type tubes. 16 filament voltages. Tests cathode emission as well as shorts, open elements, etc. 15 lbs.

**Y-143D.** *$2 Down.* Only **$32.95**

**5" Wide-Band Scope Kit**

Top versatility. 5 mc bandwidth; DC coupled p-p output amplifiers; 25 mv/inch vertical amplifier sensitivity. Outstanding value. 29 lbs.

**Y-144D.** *$5 Down.* Only **$65.75**

**SEE THEM ALL**

**You'll find dozens of other fine quality Knight-Kit instrument values fully described in the 1960 ALLIED Catalog. If you haven't a copy, write for it now—use coupon on opposite page.**

**FREE send for the value-packed 1960 ALLIED CATALOG**

# electronic achievements at half the factory-built cost

## years-ahead *knight-kit* amateur gear

### T-400 AMATEUR 400-WATT TRANSMITTER KIT

Y-716D
**$395.00**
*400-Watt CW Transmitter*

Truly the "dream" transmitter—has what it takes to punch out a QRM-busting SSB, AM, or CW signal. 600 watts P.E.P. input on SSB; 400 watts on AM and CW. Covers 80, 40, 20, 10, and 15 or 6 meter bands. Start with the basic CW kit— then add AM and SSB accessory units and other "add-ins" whenever you wish. Has heterodyne VFO to assure a signal which "stays put." Tremendous 14" dial is precision-calibrated for all bands, 80 through 6 meters. SSB features: front panel controls—VOX, anti-trip and adjustable speech compression. Smooth, chirpless screen-clamp keying, plus VFO keying for complete CW break-in. Has 7034/4X150A final—coasts along well within its CCS ratings; silicon rectifier power supply runs cool. Dozens of advanced features put this job in a class all its own. Shpg. wt. 140 lbs.

**$10 DOWN**

**Model Y-716D.** T-400 CW Transmitter Kit.

*Available in March—reserve yours now*

**"Add-In" Accessories:** SSB Generator Kit, $69.95 • AM Modulator Kit, $24.95 • Speech Amplifier Kit, $9.95 • Monitor Scope Kit, $37.95 • 6-Meter Conversion Kit, $7.50.




### R-100 AMATEUR RECEIVER KIT

Y-726D
**$104.50**
*$5 Down*

Incomparable receiver kit with all the features, selectivity and sensitivity of high-priced commercial units. Tunes 540 kc to 30 mc in 4 bands; calibrated bandspread on all Ham bands; 300 cps to 4.5 kc selectivity; exclusive printed-circuit bandswitch; built-in Q-multiplier; constant-running HFO—dozens of other professional features. Truly superior kit value. 30 lbs.

**$5 DOWN**

**Model Y-726D.** R-100 Receiver Kit.

**Y-727D.** S-Meter Kit for above, only..... $10.75
**Y-728D.** 4" Matching Speaker, only..... 7.50

**FREE** Send for the 1960 **ALLIED CATALOG**

Describes the complete KNIGHT-KIT line in detail—the leading Buying Guide for everything in Electronics. Send for your FREE copy. Use coupon at right.

**ALLIED RADIO**

*pioneers in quality electronic kit development*

OUR 39th YEAR




**ALLIED RADIO CORP., Dept. 131-B**
**100 N. Western Ave., Chicago 80, Ill.**

Ship me the following KNIGHT-KITS:

| Quantity | Description | Model No. | Price |
|---|---|---|---|
| | | | |
| | | | |
| | | | |

$.....enclosed. (For parcel post include postage; express shipped collect)

☐ **Send FREE 1960 ALLIED CATALOG**

Name_____

Address_____

City_____ Zone_____ State_____

...Build the Best Portable... EICO

6-TRANSISTOR RADIO RA-6

Kit $29.95 Wired $49.95

INCLUDES P.E.T., LESS 9V BATTERY

Easy creative fun to build . . . a lifetime of big-set entertainment wherever you go . . . designed so that even the novice can build it & obtain a handsome professional assembly & outstanding performance. American-made modern super-heterodyne all-transistor circuitry, plus finest quality parts throughout, assure you of highest durability & stability. • high sensitivity & selectivity • big-set volume & tone quality with 4" x 6" PM speaker & 250 mw push-pull audio output stage • built-in Ferrite rod antenna for good reception in any location • pre-aligned RF & IF transformers • planetary vernier tuning (7:1 reduction) for easy station selection & tuning • high-impedance earphone jack for private listening; eliminates drain of output stage when using earphone • attractive tan leatherette case, retractable handle • compact: 6½" w, 4½" h, 2½" d. Only 3 lbs.

Build the BEST BUYS in "HAM" gear. EICO

*U.S. PAT. NO. D-184,770

90-WATT CW TRANSMITTER* #720

Kit $79.95 Wired $119.95

"Ideal for veteran or novice" — ELECTRONIC KITS GUIDE. "Top quality" — POPULAR ELECTRONICS. "Well designed" — ELECTRONICS WORLD. 80 thru 10 meters with one-knob band-switching. Full "clean" 90W input, 65W external plate mod. Matches loads 50 to 1000 ohms. May be used as basic exciter unit. TVI shielded. Tubes: 6146, 6CL6, 2-6AQ5, GZ34. Attractive "living room" low-silhouette design. 15" w, 5" h, 9" d.

UNIVERSAL MODULATOR-DRIVER #730

Kit $49.95

Wired $79.95

Cover E-5 $4.50

Delivers 50W undistorted audio. Modulates transmitters having r.f. inputs up to 100W. Unique over-modulation indicator. Output transformer matches 500-10,000 ohms. Low-level speech clipping & filtering. Inputs for xtal or dynamic mikes, phone patch, etc. 7 tubes. 6" h, 14" w, 8" d.

GRID DIP METER

Kit $29.95

Wired $49.95 #710

Includes complete set of coils for full band coverage. 400 kc–230 mc in 8 overlapping ranges. 500 ua meter. Plug-in coils are pre-wound, pre-calibrated to 0.5% accuracy. Transformer-operated power supply. 2¼" h, 2⅞" w, 6⅞" l.

ADD 5% IN THE WEST

Compare—judge for yourself—at your neighborhood EICO distributor. For free catalog on 65 models of EICO test instruments, hi-fi & "ham" gear, fill out coupon on Page 36

EICO ELECTRONIC INSTRUMENT CO., Inc. 33-00 N. Blvd., L. I. C. 1, N. Y. © 1960



Instrumentation portion of missile nose cone. Plastic recovery capsule is shown fitted into cone rear at right. Sphere is jettisoned before impact.

# Tape Recorder Survives Missile Tests

## Ruggedized unit occupying less than one-fifth cubic foot provides telemetered re-entry information on nose cone.

A RUGGED little tape recorder recently survived a U. S. Air Force missile flight and nine days in the Atlantic Ocean, yet was able to perform perfectly when retrieved from the water and tested with a new tape and tape turntable. The recorder was used by the Air Force to recover scientific information from outer space on a Thor-Able missile flight that carried an instrumented nose cone. It rode in a plastic sphere which was thrown free, before the cone struck the ocean, to fall independently. The plastic was strong enough to protect the recorder, yet light enough to allow the capsule to float in the water.

The diminutive recorder, produced by *Ampex Corp.*, stores all data to be telemetered from the nose cone during flight. Such data includes temperature, pressure, stress, acceleration, and deceleration information. When radio communication is interrupted, the recorder continues to capture the vital information and will play it back when radio communication can be resumed. For example, when the missile re-enters the atmosphere, it is surrounded by a layer of hot, ionized air which prevents transmission. The recording system allows data to be acquired during this critical time.

The complete system weighs 20 pounds and occupies less than one-fifth cubic foot. It has a frequency response from 300 to 100,000 cps, and will record two tracks on 1400 feet of quarter-inch tape at 60 ips. Potted subminiature tubes and silicon transistors are used in the two record and reproduce amplifiers. —30—

Complete tape transport assembly (left) and the separate electronics unit.



DEALERS SERVICEMEN
TUBE TESTER ROUTE OPERATORS
EXPERIMENTERS
HAMS

# with ZALYTRON QUALITY BRAND RADIO & TELEVISION RECEIVING TUBES

**BRAND NEW**
**INDIVIDUALLY BOXED**
In Famous Green & Black Carton

## GUARANTEED FOR ONE YEAR

We will replace all defective tubes within 12 months from date of purchase, excepting only burned out or broken tubes. Standard Customer Warranty 90 Days.

You "play ball" with "MAJOR LEAGUERS" when you buy ZALYTRON Tubes! "Tubes" are OUR MIDDLE NAME! We have been supplying tubes for many years to service dealers and Tube Tester Route Operators . . . and the ZALYTRON Brand name has achieved a reputation for quality and performance, second to none!

Yes, you "play it SAFE" with Zalytron because you get BRAND NEW Tubes:

**• NOT USED • NOT PULLED** from equipment **• NOT REJECTS**

but Zalytron's First Quality! And, important too: by selling DIRECT to the electronics trade, we pass the middleman's profit on to our customers . . . helping them to meet and beat competition in their areas.

**SEND IN A TRIAL ORDER TODAY!** You'll be delighted with our speedy service — and in due time you will join our host of customer friends who rank ZALYTRON as a First Class Source of Supply for Tubes. Your Trial Order will be shipped on our **FULL MONEY BACK GUARANTEE!** Try ZALYTRON Tubes at **OUR** Risk, and **JUDGE FOR YOURSELF!**

| TYPE | EACH | TYPE | EACH | TYPE | EACH | TYPE | EACH | TYPE | EACH |
|---|---|---|---|---|---|---|---|---|---|
| OZ4 | $ .85 | 5CQ8 | 1.30 | 6BF5 | 1.35 | 6DQ6 | 1.10 | 12AV6 | .60 |
| 1AX2 | .70 | 5J6 | .75 | 6BF6 | .55 | 6DT6 | .60 | 12AV7 | .85 |
| 1B3 | .95 | 5T8 | .86 | 6BG6 | 2.25 | 6J5 | .70 | 12AX4 | .95 |
| 1S5 | .60 | 5U4G/GB | .75 | 6BH6 | .70 | 6J6 | .60 | 12AX7 | .65 |
| 1T4 | .55 | 5U8 | .75 | 6BH8 | .90 | 6K6 | .80 | 12B4 | .70 |
| 1U4 | .45 | 5V6 | .55 | 6BJ6 | .65 | 6L6 | 1.15 | 12BA6 | .60 |
| 1U5 | .55 | 5Y3GT | .55 | 6BK5 | 1.40 | 6S4 | .60 | 12BD6 | .60 |
| 1X2A/B | .95 | 6AB4 | .55 | 6BK7A/B | .90 | 6SA7 | .80 | 12BE6 | .60 |
| 2AF4 | 1.00 | 6AC7M | .90 | 6BL7 | 1.35 | 6SC7 | .80 | 12BH7 | .80 |
| 3AF4 | 1.05 | 6AF4 | 1.05 | 6BN6 | .75 | 6SK7 | .75 | 12BQ6 | 1.10 |
| 3AL5 | .46 | 6AG5 | .65 | 6BQ5 | .70 | 6SL7 | .90 | 12BY7 | .80 |
| 3AU6 | .55 | 6AG7M | 1.25 | 6BQ6 | 1.10 | 6SN7 | .85 | 12C5 | .60 |
| 3AV6 | .45 | 6AH4 | 1.30 | 6BQ7A | 1.10 | 6SQ7 | .85 | 12CU5 | .60 |
| 3BN6 | .75 | 6AH6 | 1.35 | 6BR8 | .95 | 6T4 | 1.00 | 12CU6 | 1.10 |
| 3BU8 | .75 | 6AK5 | .85 | 6BU8 | .70 | 6T8 | .95 | 12DQ6 | 1.10 |
| 3BY6 | .60 | | | | | | | 12F8 | .65 |
| 3BZ6 | .60 | | | | | | | 12K5 | .70 |
| 3CB6 | .60 | | | | | | | 12L6 | .65 |
| 3CF6 | .65 | | | | | | | 12SA7 | 1.00 |
| 3CS6 | .60 | | | | | | | 12SK7 | .85 |
| 3DT6 | .55 | | | | | | | 12SN7 | .90 |
| 3Q4 | .65 | | | | | | | 12SQ7 | .90 |
| 3S4 | .65 | | | | | | | 12V6 | .55 |
| 3V4 | .70 | | | | | | | 12W6 | .75 |
| 4BC8 | 1.00 | | | | | | | 12X4 | .45 |
| 4BN6 | .75 | | | | | | | 19AU4 | .85 |
| 4BQ7A | 1.10 | | | | | | | 19T8 | 1.00 |
| 4BS8 | 1.00 | | | | | | | 25AX4 | 1.15 |
| 4BZ7 | 1.10 | | | | | | | 25BQ6 | 1.10 |
| 4CB6 | .60 | | | | | | | 25CD6 | 1.50 |
| 4DT6 | 1.00 | | | | | | | 25CU6 | 1.10 |
| 5AM8 | .80 | | | | | | | 25DQ6 | 1.10 |
| 5AN8 | .85 | | | | | | | 25L6 | .85 |
| 5AQ5 | .55 | | | | | | | 25W4 | 1.10 |
| 5AT8 | .85 | | | | | | | 35C5 | .65 |
| 5AU4 | .95 | | | | | | | 35L6 | 1.00 |
| 5BK7 | .90 | | | | | | | 35W4 | .50 |
| 5BQ7 | .98 | | | | | | | 35Z5 | .70 |
| 5CG8 | .85 | | | | | | | 50C5 | .70 |
| 5CL8 | .80 | | | | | | | 50L6 | .75 |

**WE PAY ALL SHIPPING CHARGES**
on all orders accompanied by remittance in full.

| | | | | | |
|---|---|---|---|---|---|
| 6AL5 | .55 | 6BX7 | 1.65 | 6U8 | .85 |
| 6AM8 | .85 | 6BY6 | .60 | 6V6 | .80 |
| 6AN8 | .95 | 6BZ6 | .65 | 6W4 | .80 |
| 6AQ5 | .55 | 6BZ7 | 1.10 | 6W6 | .95 |
| 6AS5 | .90 | 6C4 | .50 | 6X4 | .45 |
| 6AT6 | .55 | 6CB6 | .70 | 6X5 | .65 |
| 6AT8 | .85 | 6CD6 | 1.70 | 6X8 | .85 |
| 6AU4 | 1.00 | 6CF6 | .70 | 6Y6 | .95 |
| 6AU5 | 1.75 | 6CG7 | .65 | 8AU8 | .90 |
| 6AU6 | .65 | 6CG8 | .80 | 8AW8 | .95 |
| 6AU8 | .90 | 6CL6 | 1.35 | 8CG7 | .65 |
| 6AV5 | 1.60 | 6CM7 | .70 | 10DE7 | 1.15 |
| 6AV6 | .55 | 6CN7 | .70 | 11CY7 | .75 |
| 6AW8 | .90 | 6CQ8 | 1.35 | 12AD6 | .55 |
| 6AX4 | .95 | 6CS6 | .70 | 12AF6 | .60 |
| 6BA6 | .65 | 6CS7 | 1.15 | 12AQ5 | .56 |
| 6BC5 | .60 | 6CU5 | 1.00 | 12AT6 | .60 |
| 6BC8 | 1.10 | 6CU6 | 1.10 | 12AT7 | .76 |
| 6BD6 | .65 | 6CY7 | .75 | 12AU6 | .60 |
| 6BE6 | .55 | 6DE6 | .70 | 12AU7A | .70 |

## THIS MONTH'S SPECIAL



## NEW ARKAY "SKY-VOX" CITIZEN RADIO TRANSCEIVER

COMPLETE KIT $79.95 PREPAID

Includes Fully Assembled Wired Front End, Ready to Install into Main Chassis!

This is a QUALITY Kit, for those who want the finest in Two-Way Citizen's Band Communication. Superlatively engineered, easy to put together, this transceiver will give outstanding performance! Check these advanced features:

- Up-To-The-Minute Circuitry employs 8 tubes and 5 diodes.
- Crystal Controlled Superhet Receiving Circuit.
- Crystal Controlled Oscillator, Pentode RF Amplifier Transmitting Circuit.
- Front Panel Controls include: 3-position Channel Selector; Receive-Transmit Switch; Volume Control; Squelch Control; Mike Input. Rear Chassis: Noise Balance Control.
- Power Requirements: Will operate on either 117 Volts 60 cycles AC or 12 Volts DC.

ALSO AVAILABLE FACTORY ASSEMBLED, WIRED, TESTED, READY FOR OPERATION, Complete .....$119.95

*WE PAY ALL SHIPPING CHARGES*

Above is only a partial listing of our huge tube stocks. Send today for **FREE** Complete up-to-date Tube Price List and Catalog. We Ship all Orders COMPLETE Same Day Received! **C.O.D. ORDERS:** 25% Deposit with order, balance C.O.D. plus all shipping charges. **MINIMUM ORDER** (Special for This Ad) **$5.00.**

**ZALYTRON TUBE CORPORATION**
220 West 42nd Street New York 36, N. Y.
Telephone: BRyant 9-2542 **DEPT. EW-2**

**FREE!**
Giant New Wholesale Catalog of Radio & TV Receiving Tubes, Electronic Components. Free on Request.

To ZALYTRON Tube Corp., DEPT. EW-2
220 West 42nd Street, New York 36, N. Y.
☐ Send FREE 1960 Catalog.
NAME_____
ADDRESS_____
CITY_____ ZONE____ STATE_____

# C.E.I.
# CITIZEN'S BAND

**Two-Way Transceiver Kits**

**Complete—Low Priced**

No examination required for use of this equipment.

Made from parts of finest quality.

Meets F.C.C. Requirements.

Two models to choose from. Both now available in **KIT FORM.**

Kits are complete, including Cabinet, Prepunched Chassis, Power Transformer, all components, Mike, Crystal, Easy to follow instructions and schematic. F.C.C. form 505 furnished with each order.

**SPECIFICATIONS**

Both models have **Superheterodyne Receiver** with RF Stage. One MV sensitivity, over two watts Audio Transmitter 5 Watts of RF, 100% AM Modulated. 40 to 80 Ohms Antenna Output. Power Transformer operates on 6VDC, 12VDC and 117VAC. All units can be operated as base or mobile.

**CUSTOM DISPATCHER**

Has noise limiter and adjustable squelch. Crystal controlled Receiver and Transmitter.

• In Kit..... **69.95** •



**MODEL 1000 DK**

Has Tuneable Receiver. Receives all 22 channels and 10 meter band. Has fixed squelch and noise limiter.

• In Kit.... **59.95** •

**NEW FROM C.E.I.**

1000-D-6 Kit. 6 Meter Transceiver. Same specifications as 1000-D.

• **58.95** Complete less crystal •

Ground plane antenna.....**$17.00**

Finest quality mobile antenna with 15' of lead-in .....**$16.00**

All units complete. 15% deposit required with all C.O.D. orders or send cash and take 2% discount. F.O.B. Chickasha.

**PROMPT SHIPMENT**

**CHICKASHA ELECTRONICS, Inc.**

**Chickasha, Oklahoma**


# Transistor Radio Circuits

***Part 4. The audio preamp stage and the single-ended audio output stage are covered in this installment.***

EDITOR'S NOTE: *This material on transistor circuits, appearing here and in subsequent issues, is being reproduced with the kind permission of the* Delco Radio Division *of* General Motors Corporation. *Although originally prepared and distributed to those servicing* Delco *auto radio receivers, much of the information is also applicable to other types of transistorized radios and we believe it worthwhile to present this material to our readers.*

## Audio Preamplifier

An audio preamplifier stage is required whenever the detector output is not sufficient to drive the audio stage properly. The amplifier in Fig. 7 employs a 2N109 *p-n-p* transistor which is in the medium-power class, having higher current amplifying characteristics than the low-power transistors used for r.f. and i.f. amplification.

The emitter is connected, through transformer winding $L_2$ and a 100-ohm resistor, direct to the 12-volt supply. The proper base-emitter forward bias is obtained by a series of voltage divider resistors in the base circuit which keep the base less positive than the emitter (necessary for biasing a *p-n-p* transistor in the forward direction). The collector is connected to ground through transformer winding $L_1$ which keeps the collector negative with respect to the other elements for maximum attraction of holes from the emitter. All of these voltages set the d.c. collector current of the transistor to about 5 ma. of current through $L_1$, with no signal applied. Then as signal is applied through input transformer $T_1$, the base voltage and current are changed at the audio rate. This causes corresponding increases and decreases in collector current through $L_1$, but of larger magnitude due to the amplification characteristics of the transistor.

The amplified signal currents in $L_1$ induce a voltage in secondary winding $L_3$ and also a small voltage in the primary winding $L_2$, which is connected to the emitter. The voltages shown are induced during the part of the cycle when the collector current is increasing and it can be seen that the voltage in $L_2$ is degenerative by the way it is connected to the emitter and would try to oppose or cancel some of the original current change. This minimizes distortion since the higher frequency harmonics which cause distortion also induce more voltage in the emitter winding and this has the effect of cancelling the distortion frequencies from the output of this stage.

Fig. 7. Audio stage with "p-n-p" transistor.




The 100-ohm emitter resistor in Fig. 7 is self biasing and stabilizes d.c. collector current, keeping the transistor operating at the best point for minimum distortion. The 100 $\mu$f. capacitor across this resistor prevents the resistor from causing audio degeneration by providing a low-impedance path for bypassing the audio signal. However, d.c. current changes, such as those caused by an increase in transistor temperature, are restrained due to the voltage drop across this resistor.

The tone of the receiver is often controlled in this stage. In Fig. 7 the tone is varied by a four-step control connected to the collector of the transistor through a .25-$\mu$f. coupling capacitor. The control varies the amount of resistance in series with the capacitor to ground. The smaller the value of resistance, the more efficient will be the bypassing characteristic of the capacitor. Since the higher frequencies are more easily bypassed by the capacitor than lower ones, the control has the effect of "shorting" the high-frequency audio signals to ground.

With the control set at stop "L," a maximum amount of high-frequency audio is shorted to "ground" and the tone appears to be low. As the arm is moved clockwise, greater amounts of resistance are added to reduce the effect of the tone capacitor and the higher frequency audio signals remain in the collector circuit, causing a higher tonal response in the receiver.

## Single-Ended Output Stage

Fig. 8 shows an audio-output stage employing a 2N173 high-power *p-n-p* transistor in a class A, common-emitter circuit.

Forward bias is developed across the 10-ohm resistor in the voltage divider network consisting of 10-ohm and 130-ohm resistors and the 60-ohm potentiometer. By adjusting the potentiometer, the voltage drop across the 10-ohm resistor can be varied and since this resistor is connected between the base and emitter of the transistor, the voltage developed across it determines the amount of forward bias between these two elements.

The method normally used to make the bias adjustment is to insert an ammeter in series with the ground connection to output transformer $T_3$ and adjust the bias control until a specified reading of collector current is obtained. A typical value of 930 ma. is shown in the circuit but this specifi-

cation will vary greatly with the transistor and circuit used. This sets the d.c. operating point for the transistor and determines power output as well as the amount of distortion present. The signal induced in the secondary winding of $T_2$ is in series with the base connection to the voltage divider and therefore fluctuates base voltage and current at the audio rate.

Small current changes in the base circuit are greatly amplified by the transistor and produce much larger collector-current changes in transformer $T_3$. The energy in $T_3$ is then coupled to the speaker from a point on the transformer which matches the speaker voice-coil impedance. The 150-ohm resistor across the output transformer protects the transistor from a high surge of back voltage which will occur if the voice-coil winding should open or is disconnected during operation.

Since the collector current in this circuit is near 1 amp and transformer




Fig. 8. High-power "p-n-p" is used class A.

$T_3$ has a d.c. resistance of about 1 ohm, the collector voltage developed is about 1 volt. This voltage will give an indication of whether or not the transistor is drawing current because no collector voltage would be produced if it were not conducting.

The .47-ohm emitter resistor stabilizes collector current and prevents a possible runaway condition due to transistor heating. As temperature increases during operation, the transistor resistance drops which causes it to draw more current. But this produces a change in voltage across the .47-ohm resistor, which adjusts the bias and opposes the original current change. Temperature is also controlled by mounting the transistor tightly to a suitable chassis which acts as a heat sink and absorbs much of the heat. To prevent the transistor case and collector from being grounded, the heat sink chassis will usually be insulated from the main chassis in some manner.

*(To be continued)*

## "UNIMARKET" SYSTEM

**A NEW concept in distribution, involving Western Union private wire communications equipment, jet freight service by American Airlines, and the products of Raytheon, has been set up in Westwood, Mass. as the "Unimarket" system.**

**The new stepped up delivery schedule has cut order-to-delivery time from an average of seven days to one day for Raytheon's 700 distributor customers throughout the country.** -30-


Now Completely SELF-CONTAINED

For Testing & Rejuvenating BLACK AND WHITE and COLOR including 110° TUBES

NEW CRT 440

CATHODE REJUVENATOR TESTER

B&K

TESTS AND REJUVENATES all black & white and color picture tubes at correct filament voltage from 1 to 12 V.

TESTS AND REJUVENATES 110° tubes with 2.34, 2.68, 6.3 and 8.4 volt filaments.

TESTS AND REJUVENATES color picture tubes. Checks each color gun separately same as black & white tubes.

*Used by Thousands of Professional Servicemen*
*MAKES NEW PICTURE TUBE SALES EASIER*

Gives you more value than ever—all-in-one. Quickly checks and corrects most TV picture tube troubles in a few minutes right in the home without removing tube from set. Gives new useful life to weak or inoperative tubes. Checks leakage. Restores emission and brightness. Repairs inter-element shorts and open circuits. Life test checks gas content and predicts remaining useful life of picture tube. Completely self-contained in leatherette-covered carrying case. Net, $69.95

ACCESSORIES for USE ONLY with FORMER B&K Models 400 and 350 CRT

Model C40 Adapter. For use only with all previous B&K Model 400 and 350 CRT's. Tests and rejuvenates TV color picture tubes and 6.3 volt 110° picture tubes. Net, $9.95

Model CR48 Adapter. For use only with all previous B&K Model 400 and 350 CRT's. Tests and rejuvenates 110° picture tubes with 2.34, 2.68, and 8.4 volt filaments. Net, $4.95

*See your B&K Distributor or Send now for Bulletin ST24-N*

B&K MANUFACTURING CO.
1801 W. BELLE PLAINE AVE • CHICAGO 13, ILL.
Canada: Atlas Radio Corp., 50 Wingold, Toronto 10, Ont.
Export: Empire Exporters, 277 Broadway, New York 7, U.S.A.

ALWAYS INSIST ON PROVED BRAND NAMES
Ask By Name For
GENUINE "NO NOISE" PRODUCTS
BEWARE OF CHEAP SUBSTITUTES

NO-NOISE TUNER-TONIC With PERMA-FILM
- Economical — a little does a lot.
- Cleans, lubricates, restores all tuners, including wafer type.
- Non-toxic, non-inflammable.
- Use for TV, radio and FM.

6 Oz. Aerosol Can $3.25 NET to Servicemen

NO-NOISE VOLUME CONTROL and CONTACT RESTORER
- Cleans
- Protects
- Lubricates

Not a Carbon Tet Solution
2 Oz. Bottle $1.00 NET to Servicemen
6 Oz. Spray Can $2.25 NET to Servicemen

NOW AVAILABLE FREE AT YOUR JOBBERS
5" PLASTIC EXTENDER
With Push Button Assembly For Pin-Point Applications Does Not Cause Shorts

ELECTRONIC CHEMICAL CORP. 813 Communipaw Avenue Jersey City 4, N. J.

**For the first time ever: ONE TESTER PROVIDES ALL THE SERVICES LISTED BELOW!**

*SUPERIOR'S NEW MODEL 76*

# ALL PURPOSE BRIDGE

IT'S A **CONDENSER BRIDGE** — IT'S A **RESISTANCE BRIDGE**

IT'S A **SIGNAL TRACER** — IT'S A **TV ANTENNA TESTER**

**Model 76 BRIDGE . . . Total Price $26.95—Terms: $6.95 after 10 day trial, then $5.00 monthly for 4 months if satisfactory. Otherwise return, no explanation necessary!**

**SPECIFICATIONS:**

**CAPACITY BRIDGE SECTION**
4 Ranges: .00001 Microfarad to 1000 Microfarads. Will also locate shorts, and leakages up to 20 megohms. Measures the power factor of all condensers from .1 to 1000 Microfarads. (Power factor is the ability of a condenser to retain a charge and thereby filter efficiently.)

**RESISTANCE BRIDGE SECTION**
2 Ranges: 100 ohms to 5 megohms.
Resistance can be measured without disconnecting capacitor connected across it. (Except, of course, when the R C combination is part of an R C bank.)

**TV ANTENNA TESTER SECTION**
Loss of sync., snow and instability are only a few of the faults which may be due to a break in the antenna, so why not check the TV antenna first? 2 Ranges: 2' to 200' for 72 ohm coax and 2' to 250' for 300 ohm ribbon.

**SIGNAL TRACER SECTION**
With the use of the R.F. and A.F. probes included with the Model 76, you can make stage gain measurements, locate signal loss in R.F. and Audio stages, locate distortion and hum, etc. Provision has been made for use of phones and meter if desired.

***Model 76 comes complete with all accessories including R.F. and A.F. Probes; Test Leads and operating instructions. Nothing else to to buy. Only.....***

**$26.95 NET**

---

*SUPERIOR'S NEW MODEL 79*

# SUPER-METER

**WITH NEW 6" FULL-VIEW METER**

*A Combination*
**VOLT-OHM MILLIAMMETER**
*Plus* **CAPACITY, REACTANCE, INDUCTANCE AND DECIBEL MEASUREMENTS**
*Also Tests* **SELENIUM AND SILICON RECTIFIERS, SILICON AND GERMANIUM DIODES**

**Model 79—SUPER-METER . . . Total Price $38.50—Terms: $8.50 after 10 day trial, then $6.00 per month for 5 months if satisfactory. Otherwise return, no explanation necessary!**

The Model 79 represents 20 years of continuous experience in the design and production of SUPER-METERS, an exclusive SICO development.
In 1938 Superior Instruments Co. designed its first SUPER-METER, Model 1150. In 1940 it followed with Model 1250 and in succeeding years with others including Models 670 and 670-A. All were basically V.O.M.'s with extra services provided to meet changing requirements.
Now, Model 79, the latest SUPER-METER includes not only every circuit improvement perfected in 20 years of specialization, but in addition includes those services which are "musts" for properly servicing the ever increasing number of new components used in all phases of today's electronic production. For example with the Model 79 SUPER-METER you can measure the quality of selenium and silicon rectifiers and all types of diodes—components which have come into common use only within the past five years, and because this latest SUPER-METER necessarily required extra meter scale, SICO used its new full-view 6-inch meter.

***Specifications***

**D.C. VOLTS:** 0 to 7.5/15/75/150/750/1,500.
**A.C. VOLTS:** 0 to 15/30/150/300/1,500/3,000.
**D.C. CURRENT:** 0 to 1.5/15/150 Ma. 0 to 1.5/15 Amperes.
**RESISTANCE:** 0 to 1,000/100,000 Ohms. 0 to 10 Megohms.
**CAPACITY:** .001 to 1 Mfd. 1 to 50 Mfd.
**REACTANCE:** 50 to 2,500 Ohms, 2,500 Ohms to 2.5 Megohms.
**INDUCTANCE:** .15 to 7 Henries, 7 to 7,000 Henries.
**DECIBELS:** −6 to +18, +14 to +38, +34 to +58.
*The following components are all tested for QUALITY at appropriate test potentials. Two separate BAD-GOOD scales on the meter are used for direct readings.*

**All Electrolytic Condensers** from 1 MFD to 1000 MFD.

**All Selenium Rectifiers. All Germanium Diodes.**
**All Silicon Rectifiers. All Silicon Diodes.**

***Model 79 comes complete with operating instructions and test leads. Use it on the bench—use it on calls. A streamlined carrying case included at no extra charge accommodates the tester, instruction book and test leads.....Only***

**$38.50 NET**

---



# GENOMETER

## 7 Signal Generators in One!

✓ *R.F. Signal Generator for A.M.* ✓ *Bar Generator*
✓ *R.F. Signal Generator for F.M.* ✓ *Cross Hatch Generator*
✓ *Audio Frequency Generator* ✓ *Color Dot Pattern Generator*
✓ *Marker Generator*

**A versatile all-inclusive GENERATOR which provides ALL the outputs for servicing:**

**A.M. Radio • F.M. Radio • Amplifiers • Black and White TV • Color TV**

**Model TV-50A—Genometer**
**Total Price .....$47.50**
**Terms: $11.50 after 10 day trial, then $6.00 monthly for 6 months if satisfactory. Otherwise return, no explanation necessary.**

**R. F. SIGNAL GENERATOR:** The Model TV-50A Genometer provides complete coverage for A.M. and F.M. alignment. Generates Radio Frequencies from 100 Kilocycles to 60 Megacycles on fundamentals and from 60 Megacycles to 180 Megacycles on powerful harmonics.

**VARIABLE AUDIO FREQUENCY GENERATOR:** In addition to a fixed 400 cycle sine-wave audio, the Model TV-50A Genometer provides a variable 300 cycle to 20,000 cycle peak wave audio signal.

**BAR GENERATOR:** The Model TV-50A projects an actual Bar Pattern on any TV Receiver Screen. Pattern will consist of 4 to 16 horizontal bars or 7 to 20 vertical bars.

**CROSS HATCH GENERATOR:** The Model TV-50A Genometer will project a cross-hatch pattern on any TV picture tube. The pattern will consist of non-shifting, horizontal and vertical lines interlaced to provide a stable cross-hatch effect.

**DOT PATTERN GENERATOR (FOR COLOR TV):** Although you will be able to use most of your regular standard equipment for servicing Color TV, the one addition which is a "must" is a Dot Pattern Generator. The Dot Pattern projected on any color TV Receiver tube by the Model TV-50A will enable you to adjust for proper color convergence.

**MARKER GENERATOR:** The Model TV-50A includes all the most frequently needed marker points. The following markers are provided: 189 Kc., 262.5 Kc., 456 Kc., 600 Kc., 1000 Kc., 1400 Kc., 1600 Kc., 2000 Kc., 2500 Kc., 3579 Kc., 4.5 Mc., 5 Mc., 10.7 Mc., (3579 Kc. is the color burst frequency)

***THE MODEL TV-50A comes absolutely complete with shielded leads and operating instructions.***

**$47.50 NET**

---

# EXAMINE BEFORE YOU BUY!

## USE APPROVAL FORM ON NEXT PAGE

SUPERIOR'S NEW MODEL TW-11

## STANDARD PROFESSIONAL TUBE TESTER

**Model TW-11—Tube Tester**
**Total Price ..... $47.50**
**Terms: $11.50 after 10 day trial, then $6.00 monthly for 6 months if satisfactory. Otherwise return, no explanation necessary.**

★ Tests all tubes, including 4, 5, 6, 7, Octal, Lock-in, Hearing Aid, Thyratron, Miniatures, Sub-miniatures, Novals, Subminars, Proximity fuse types, etc.
★ Uses the new self-cleaning Lever Action Switches for individual element testing. Because all elements are numbered according to pin-number in the RMA base numbering system, the user can instantly identify which element is under test. Tubes having tapped filaments and tubes with filaments terminating in more than one pin are truly tested with the Model TW-11 as any of the pins may be placed in the neutral position when necessary.
★ The Model TW-11 does not use any combination type sockets. Instead individual sockets are used for each type of tube. Thus it is impossible to damage a tube by inserting it in the wrong socket.
★ Free-moving built-in roll chart provides complete data for all tubes. All tube listings printed in large easy-to-read type.

**NOISE TEST:** Phono-jack on front panel for plugging in either phones or external amplifier will detect microphonic tubes or noise due to faulty elements and loose internal connections.

### EXTRAORDINARY FEATURE

**SEPARATE SCALE FOR LOW-CURRENT TUBES:** Previously, on emission-type tube testers, it has been standard practice to use one scale for all tubes. As a result, the calibration for low-current types has been restricted to a small portion of the scale. The extra scale used here greatly simplifies testing of low-current types.

**The Model TW-11 operates on 105-130 Volt 60 Cycles A.C. Comes housed in a handsome, portable Saddle-Stitched Texon Case. Only..... $47.50**

---

SUPERIOR'S NEW MODEL 82A

## Multi-Socket Type TUBE TESTER



**Model 82A—Tube Tester**
**Total Price ..... $36.50**
**Terms: $6.50 after 10 day trial, then $6.00 monthly for 5 months if satisfactory. Otherwise return, no explanation necessary.**

### TEST ANY TUBE IN 10 SECONDS FLAT!

1. Turn the filament selector switch to position specified.
2. Insert tube into a numbered socket as designated on our chart (over 600 types included).
3. Press down the quality button—

***THAT'S ALL!*** *Read emission quality direct on bad-good meter scale.*

**SPECIFICATIONS**

- Tests over 600 tube types
- Tests OZ4 and other gas-filled tubes
- Employs new 4" meter with sealed air-damping chamber resulting in accurate vibrationless readings
- Use of 22 sockets permits testing all popular tube types and prevents possible obsolescence
- Dual Scale meter permits testing of low current tubes
- 7 and 9 pin straighteners mounted on panel
- All sections of multi-element tubes tested simultaneously
  Ultra-sensitive leakage test circuit will indicate leakage up to 5 megohms

Production of this Model was delayed a full year pending careful study by Superior's engineering staff of this new method of testing tubes. Don't let the low price mislead you! We claim Model 82A will outperform similar looking units which sell for much more — and as proof, we offer to ship it on our examine before you buy policy.

To test any tube, you simply insert it into a numbered socket as designated, turn the filament switch and press down the quality switch — THAT'S ALL! Read quality on meter. Inter-element leakage if any indicates automatically.

**Model 82A comes housed in handsome, portable Saddle-Stitched Texon case. Only ..... $36.50**

---

SUPERIOR'S NEW MODEL 83

## C. R. T. TESTER

### TESTS AND REJUVENATES ALL PICTURE TUBES

**Model 83—C.R.T. Tube Tester**
**Total Price ..... $38.50**
**Terms: $8.50 after 10 day trial, then $6.00 monthly for 5 months if satisfactory. Otherwise return, no explanation necessary.**

***ALL BLACK AND WHITE TUBES***
**From 50 degree to 110 degree types —from 8" to 30" types.**

- Model 83 is not simply a rehashed black and white C.R.T. Tester with a color adapter added. Model 83 employs a new improved circuit designed specifically to test the older type black and white tubes, the newer type black and white tubes and all color picture tubes.
- Model 83 provides separate filament operating voltages for the older 6.3 types and the newer 8.4 types.
- Model 83 employs a 4" air-damped meter with quality and calibrated scales.
- Model 83 properly tests the red, green and blue sections of color tubes individually—for each section of a color tube contains its own filament, plate, grid and cathode.

***ALL COLOR TUBES***
**Test ALL picture tubes—in the carton—out of the carton—in the set!**

- Model 83 will detect tubes which are apparently good but require rejuvenation. Such tubes will provide a picture seemingly good but lacking in proper definition, contrast and focus. To test for such malfunction, you simply press the rej. switch of Model 83. If the tube is weakening, the meter reading will indicate the condition.
- Rejuvenation of picture tubes is not simply a matter of applying a high voltage to the filament. Such voltages improperly applied can strip the cathode of the oxide coating essential for proper emission. The Model 83 applies a selective low voltage uniformly to assure increased life with no danger of cathode damage.

**Model 83 comes housed in handsome portable Saddle Stitched Texon case—complete with sockets for all black and white tubes and all color tubes. Only.. .. $38.50**

---

# SHIPPED ON APPROVAL
# *NO MONEY WITH ORDER — NO C. O. D.*

Try any of the instruments on this or the facing page for 10 days before you buy. If completely satisfied then send down payment and pay balance as indicated on coupon. No Interest or Finance Charges Added! If not completely satisfied return unit to us, no explanation necessary.

**MOSS ELECTRONIC, INC.**
**Dept. D-712, 3849 Tenth Ave., New York 34, N. Y.**

**Please send me the units checked on approval. If completely satisfied I will pay on the terms specified with no interest or finance charges added. Otherwise, I will return after a 10 day trial positively cancelling all further obligations.**

**Name .....**
**Address .....**
**City .....Zone....State.....**

**All prices net, F.O.B., N. Y. C.**

- ☐ **Model 76...Total Price $26.95 $6.95 within 10 days. Balance $5.00 monthly for 4 months.**
- ☐ **Model 79...Total Price $38.50 $8.50 within 10 days. Balance $6.00 monthly for 5 months.**
- ☐ **Model TV-50A Total Price $47.50 $11.50 within 10 days. Balance $6.00 monthly for 6 months.**
- ☐ **Model TW-11...Total Price $47.50 $11.50 within 10 days. Balance $6.00 monthly for 6 months.**
- ☐ **Model 82A.....Total Price $36.50 $6.50 within 10 days. Balance $6.00 monthly for 5 months.**
- ☐ **Model 83.....Total Price $38.50 $8.50 within 10 days. Balance $6.00 monthly for 5 months.**

# WE'VE GOT A SECRET!

Our lips are locked . . . but not for long. You will soon learn about the new Standard Coil Products tuner program. Watch for it. It means better service for your customers—greater profits for you.


## Room Acoustics for Stereo

(*Continued from page 47*)

ner of the room is perhaps the best "projector" area of the room. Many articles have recommended locating the loudspeaker in a corner so that the corner can act as a three-sided horn *feeding* the room. Too little mention is made, however, concerning the acoustic condition of the walls and floors of these "desirable" corners. If the walls and floors are heavily draped and carpeted, as shown in Fig. 15A, the corner would be of very little use. The need for a live backing area behind the sound (Fig. 15B) is dictated by the need for throwing the sound forward—just as is done by an orchestral shell (Fig. 15C). Therefore, absorption techniques that are to be applied should be in the general listening area, with a minimum in the sound generating area.

Putting the absorbent material in the listening area serves to reduce unduly strident echoes from live surfaces (removed from the original source) which by reflectively interfering with the direct sound will cause confusion at the listener's ear. In this connection we must also realize that the closer one sits to the source of the sound, the less effective are the surroundings. This effect is especially noticeable in very live rooms. If one were seated close to a hard plaster wall and the sound source is 20 feet away, there would be considerable interference introduced by reflections off the wall. On the other hand, if the walls were heavily draped then the ear would receive very little reflected sound and its major acoustic stimulus would be direct sound from the speaker. We must, therefore, strive for a balance between direct and reflected sound so that while we hear the performance in front of us, we get some general diffuse sound from around us to "liven" the performance.

### Summary of Principles

Summarizing the various principles outlined for any good listening room—whether for live music, reproduced monophonic or stereo, we have:

*A.* The room should have an absorption characteristic which will provide a reverberation time of from .75 to 1.25 seconds.

*B.* The sound absorption material used to achieve this reverberation figure should be distributed throughout the room rather than be concentrated in one area.

*C.* Large, hard parallel reflecting areas should be avoided as they lead to multiple reflections and resonances.

*D.* The sound source should be located in a comparatively "live" area of the room.

*E.* The listener location should not be adjacent to either a hard reflective surface or a totally absorptive surface since in neither case will the listener receive the proper proportion of reflected-to-direct sound in keeping with accepted reverberation practice.

*(To be continued)*

Fig. 15. Speaker placement should be such as to provide proper "live" coupling.


DRAPES
CARPET
LIVE WALL
LIVE WALL
OUT TO THE ROOM
UP TO THE ROOM
OUT TO THE ROOM
A CORNER IS USELESS FOR COUPLING THE SOUND TO THE ROOM IF THE CORNER SURFACES ARE SO PADDED THAT THEY ABSORB ALL THE SOUND THAT REACHES THEM.
A CORNER WILL PROPERLY COUPLE THE SPEAKER TO THE ROOM IF IT IS LIVE ENOUGH TO PRODUCE SUFFICIENTLY STRONG REFLECTIONS SO THAT THE SURFACES ACT AS EXTENSIONS OF THE SOUND SOURCE ITSELF
A
B
C

## Estimating Your Business

(*Continued from page* 65)

attitudes toward types of businesses, aside from the products or services involved, do change. There may be a tendency to patronize either larger or smaller shops. A growing preference for either more service or more self-service may be evident. Establishments that look impressively expensive or streamlined may be attracting more—or less—public confidence than modest, more personalized businesses. There should be constant awareness of the need for changing the character of the service shop based on unmistakable trends in other businesses, whether they be groceries or drug stores.

*The general outlook.* One of the most difficult factors to assess is what the year ahead promises in general. However, there are always indicators to watch in such areas as business and politics.

An election year, for example, usually has a certain psychological impact. There is generally a feeling of increased confidence on the part of the public that is associated with prosperous conditions. The plan for a centennial, fair, or other such attraction that will be felt in your area also has a stimulating effect.

*Industry-wide plans for the year ahead,* aside from new things to sell, can have a local effect that should not be ignored. Special promotional activities should be watched. Is your local association planning a campaign? Does your distributor have something in the fire that will influence your own business? Are any manufacturers preparing to stage drives? No activity in your own field when there is some in other areas may reduce your income. Broad activity evident along more than one front in your own field can mean a good lift as compared to what other fields will experience.

*The profit ratio.* Aside from actual increases or decreases in volume, your success in the year ahead will depend on how much it costs to keep your business going. Are there any price rises in the offing for parts and components? Is your rent going up? Is your own pricing structure realistic with respect to overhead? You could be making less money while doing more business.

In addition to the factors mentioned, which would apply to most shops, there are others that would be specific and peculiar to each firm. For the most reliable estimate of tomorrow's business, your own alertness in recognizing any factor that may have some bearing is indispensable. Overlooking one or making an estimate too hastily may throw the picture out of focus. However the care required in drawing up a useful advance evaluation is well worth the effort. Readiness to meet the future will make you stronger than reliance on last-minute, ill-considered response to the unexpected. —30—

YOU NEED THIS . . .
FREE GIANT ALL NEW 1960 BA CATALOG
A Complete Buying Guide for Everything in
RADIO TV ELECTRONICS 1960
ANNUAL CATALOG 601
BA
SINCE 1927
Guarantee
204 KING-SIZED PAGES
EVERYTHING IN RADIO TV AND ELECTRONICS
100'S OF NEW ITEMS LISTED HERE FOR 1st TIME
21 PAGES OF BARGAINS NOT IN ANY OTHER CATALOG
RUSH COUPON TODAY!
BURSTEIN-APPLEBEE CO. Dept. M,
1012-14 McGee St., Kansas City 6, Mo.
☐ Send Free 1960 B-A Catalog No. 601.
NAME
ADDRESS
CITY STATE
BURSTEIN-APPLEBEE

**MOVING?**

Make sure you notify our subscription department about any change of address. Be sure to include your postal zone number as well as both old and new addresses. Please allow four weeks' time for processing.

**ELECTRONICS WORLD**
**434 South Wabash Avenue**
**Chicago 5, Illinois**

**ENGINEERING**

Prepare for unlimited opportunities of the Electronic Age! **B.S. DEGREE IN 27 MONTHS**

Students study engineering under accelerated program leading to B.S. degree in 27 mo.; or standard 4-yr. program leading to B.E. degree in 36 mo. B.S. degree (36 mo.) in Math., Chem., Physics. Year-round classes. Comprehensive training in electronics, television, advanced radio theory and design, math., nuclear physics and elec. engineering. Also prep courses. Low rate. Earn board. G.I. approved. Enter March, June, Sept., Dec. Catalog.

**INDIANA TECHNICAL COLLEGE**
920 E. Washington Blvd., Fort Wayne 2, Indiana

Please send me free information on B.S. ENGINEERING DEGREE IN 27 MONTHS as checked.

☐ Electronics ☐ Chemical ☐ Aeronautical
☐ Civil ☐ Mechanical ☐ Electrical

B.E. DEGREE IN 36 MO. in:
☐ Aeronautical ☐ Mechanical
☐ Civil ☐ Electrical (Power or Electronics)
☐ Chemical ☐ Metallurgical

B.S. DEGREE IN 36 MO. IN ☐ Math. ☐ Chem. ☐ Physics

Name .....
Address .....

# Lafayette Superior Quality HI-FI KITS!

*The FINEST . . . through research . . . engineered by LAFAYETTE!*

**KT-250**

IN KIT FORM **64.50**

**LA-250 89.50**
COMPLETELY WIRED

## 50 WATT INTEGRATED STEREO AMPLIFIER

● RESPONSE 17-21,000 CPS ± 1 DB (at normal listening level) ● UNIQUE "BLEND" CONTROL ● PREMIUM EL86 OUTPUT TUBES ● 50 WATTS MONAURAL—25 WATTS EACH STEREO CHANNEL ● CLUTCH-OPERATED VOLUME CONTROL ● SEPARATE BASS & TREBLE CONTROLS

A completely new stereo high fidelity amplifier with a high quality of reproduction, remarkable versatility and new distinctive styling. Full range of controls include a unique "blend" control for continuously variable channel separation—from full monaural to full stereo, 4-position Selector, Mode, Loudness and Phasing switches plus outputs for 4, 8 or 16 ohm speakers. Harmonic distortion less than 0.25%, IM distortion less than 1%. Hum and Noise 74 db below full output. Assembly is simple—no special skills or tools required. Complete with deluxe cabinet and legs, all parts, tubes and detailed instruction manual. Shpg. wt., 26 lbs.

**KT-250 WX** Stereo Amplifier Kit ..... 5.00 Down ..... Net **64.50**

**LA-250 WX** Stereo Amplifier, wired & tested ..... 5.00 Down ..... Net **89.50**

**KT-600**

IN KIT FORM **79.50**

**LA-600 134.50**
COMPLETELY WIRED

## PROFESSIONAL STEREO CONTROL CENTER

● RESPONSE 5-40,000 CPS ± 1 DB ● UNIQUE STEREO & MONAURAL CONTROL FEATURES ● PRECISE "NULL" BALANCING SYSTEM ● CONCENTRIC INPUT LEVEL CONTROLS

A truly professional stereo preamplifier and master audio control center—solves every stereo/monaural control problem. Features unique Bridge Conrol for variable cross-channel feed for elimination of exaggerated channel separation effects—plus controlled 3rd channel output. Has all-concentric controls—including clutch-operated Volume Balance control. Provides complete and advanced facilities for accepting, controlling and providing undistorted gain for any and all program sources. Sensitivity 2.2 mv for 1 volt out (low level inputs). Dual low impedance "plate follower" outputs 1500 ohms. Response 5-40,000 cps ± 1 db. Less than .03% IM distortion. Less than .1% harmonic distortion. Hum and noise 80 db below 2 volts (high level inputs). Uses 7 new 7025 low-noise dual triodes. Size: 14" x 4½" x 10¾". Shpg. wt., 16 lbs. Complete with all parts, tubes, deluxe cabinet and detailed instruction manual.

**KT-600 WX** Stereo Preamplifier Kit ..... 5.00 Down ..... Net **79.50**

**LA-600 WX** Stereo Preamplifier, wired and tested ..... 5.00 Down ..... Net **134.50**

**KT-310**

IN KIT FORM **47.50**

**LA-310 72.50**
COMPLETELY WIRED

## STEREO/MONAURAL POWER AMPLIFIER KIT

● 36 WATT STEREO AMPLIFIER—18 WATTS EACH CHANNEL ● EMPLOYS 4 PREMIUM-TYPE 7189 TUBES ● 2 PRINTED CIRCUIT BOARDS FOR SIMPLIFIED WIRING ● RESPONSE BETTER THAN 35-30,000 CPS ± ½ DB AT 18 WATTS ● LESS THAN 1% HARMONIC OR IM DISTORTION

A superb basic stereo amplifier in easy-to-build kit form. Unit may be used with a stereo preamplifier to provide two 18 watt stereo channels or, at the flick of a switch, as a fine 36 watt monaural amplifier. Controls include 2 input volume controls, Channel Reverse switch and Monaural-Stereo switch. Dual outputs for 4, 8, 16 or 32 ohm speakers. Input sensitivity .45 volts per channel for full output. Tubes are 2-6AN8, 4-7189, GZ-34 rectifier. Size 10-9/16" d x 5¼" h x 13¼" w. Complete kit with cage, all parts, tubes and detailed instruction manual. Shpg. wt., 22 lbs.

**KT-310 WX** Stereo Power Amplifier Kit ..... 2.00 Down ..... Net **47.50**

**LA-310 WX** Stereo Power Amplifier, wired and tested ..... 5.00 Down ..... Net **72.50**



**KT-500**

IN KIT FORM **74.50**

**LT-50 124.50**
COMPLETELY WIRED

## FM-AM STEREO TUNER KIT

● 11 Tubes (4 dual-purpose) + Tuning Eye + Selenium rectifier provide 17 tube performance ● Multiplex Output for new Stereo FM ● Armstrong Circuit with Dual Limiters and Foster-Seeley Discriminator ● Extreme Sensitivity and Wide Frequency Response.

A precision engineered, highly stable tuner—perfect for lifelike stereo FM-AM broadcast reception, FM reception and/or AM reception. Features separate tuning and volume controls for AM and FM. Magic eye on AM and FM, plus automatic frequency control on FM for accurate tuning—stations are "locked" in. Other deluxe features include cathode follower outputs and 5-position Function Selecter. Efficient, broadband circuitry on AM with built-in antenna. FM section features include 2 microvolts sensitivity for 30 db quieting, frequency response 20-20,000 cps ± ½ db and full 200 KC bandwidth. Two printed circuit boards make wiring simple—even for such a complex unit. Complete kit includes all parts, deluxe cabinet and detailed instruction manual. Size is 13¾" W x 10⅜" D x 4½" H. Shpg. wt., 22 lbs.

**KT-500 WX** FM-AM Stereo Tuner Kit ..... 5.00 Down ..... Net **74.50**

**LT-50 WX** Same as above, wired & tested ..... 5.00 Down ..... Net **124.50**



**NEW!**

**KT-236**

IN KIT FORM **52.50**

## LAFAYETTE 36-WATT INTEGRATED STEREO AMPLIFIER KIT

● 36-WATTS MONAURALLY—18 WATTS PER CHANNEL ● FREQUENCY RESPONSE 15-30,000 CPS ± 1 DB ● UNIQUE "BLEND" CONTROL ● CONCENTRIC CLUTCH-OPERATED VOLUME CONTROL ● DUAL CONCENTRIC BASS AND TREBLE CONTROLS ●4-EL84 TUBES IN PUSH PULL

This exciting new amplifier kit combines dual preamplifiers and dual 18 watt power amplifiers on one compact chassis. Instant selection from monophonic to stereophonic is provided by the turn of a switch. An amazing new "Blend" control gives continuously variable channel separation from full monophonic to full stereo. The concentric clutch-operated volume control offers independent or simultaneous level adjustments of both channels. Dual concentric bass and treble controls furnish 4 independent tonal adjustments. Harmonic distortion less than 0.15% at normal listening level. IM distortion is less than .3%. Hum and noise 70 db below rated output. Complete with cage, legs and detailed instructions. Shpg. Wt., 24 lbs.

**KT 236 WX** Stereo Amplifier Kit ..... 5.00 Down ..... Net **52.50**

**LAFAYETTE RADIO** 165-08 LIBERTY AVE., JAMAICA 33, N. Y.
AXtell 1-7000

| NEW YORK, N. Y. | BOSTON, MASS. | BRONX, N. Y. | NEWARK, N. J. | PLAINFIELD, N. J. |
|---|---|---|---|---|
| 100 6th Ave. | 110 Federal St. | 542 E. Fordham Rd. | 24 Central Ave. | 139 W. 2nd St. |
| WOrth 6-5300 | HUbbard 2-7850 | FOrdham 7-8813 | MArket 2-1661 | PLainfield 6-4718 |

# NEW! *Lafayette* 50 Watt Complete Stereo Phono System

**COMPONENTS**

| | |
|---|---|
| LAFAYETTE LA-250 50-WATT STEREO AMPLIFIER . . | 89.50 |
| GARRARD RC121/11 STEREO CHANGER . . . . . | 41.65 |
| NEW GE VR-22 (.7 MIL) DIAMOND STEREO CARTRIDGE . | 24.45 |
| LAFAYETTE PK-111 WOOD CHANGER BASE . . . . | 3.95 |
| 2-LAFAYETTE SK-58 FAMOUS FREE EDGE 12" COAXIAL SPEAKERS at 29.50 . . . . . | 59.00 |
| Regular Catalog Price | ~~218.55~~ |

**COMPLETE STEREO SYSTEM**

# 174.50

**YOUR GUARANTEED BEST STEREO SYSTEM BUY!**

**YOU SAVE 44.05**

This superb system will add a new dimension in living to your home with all the excitement and realism of a live concert. The new Lafayette LA-250, 50-watt stereo amplifier (25 watts each channel) forms the heart of this outstanding stereo hi-fi phonograph music system—the features, versatility and advanced circuitry of this unit are second to none. Also included is the famous Garrard RC121/11 intermix 4-speed automatic record changer with full manual or automatic operation supplied with your choice of stereo cartridges—the new GE VR-22 (.7 Mil) diamond stereo cartridge, Pickering 371-7D (.7 Mil) diamond stereo cartridge, Shure M7D (.7 Mil) diamond stereo cartridge or the new Electro-Voice 31 MD7 (.7 Mil) diamond stereo cartridge. Supplied with the Lafayette wood base cut for the RC121 in your choice of finishes. These outstanding components are coupled with the 2 famous free edge Lafayette SK-58 12" Coaxial speakers with built-in crossover network and brilliance level control. System supplied with plugs, cables and simple instructions. Shpg. wt., 67 lbs.

**HF-681WX** HI-FI STEREO PHONO SYSTEM with choice of cartridge and mahogany, walnut or blond changer base (please specify)
5.00 Down ..... Net **174.50**

**HF-683WX** Same as HF-681, but with 2 Lafayette Eliptoflex Series Bookshelf Enclosures (please specify finish). Shpg. wt., 143 lbs.
10.00 Down ..... Net **229.95**

**HF-682WX** Stereo AM-FM-Phono System. Same as HF-681 but including the Lafayette LT-50 stereo tuner. Shpg. wt., 85 lbs. 28.75 Down,
10.00 Down ..... Net **287.50**

*Our 39th Year*

*Leaders in Hi-Fi*

The most complete selection and largest stocks of hi-fi components and systems—available for immediate delivery at the lowest possible prices. Save even more on Lafayette endorsed "best-buy" complete systems.

# FREE!

## 1960 CATALOG

## *308 GIANT SIZED PAGES*

**The Complete Catalog Featuring**
***"The Best Buys In The Business"***

FOR THE NEWEST AND FINEST IN STEREOPHONIC HI-FI EQUIPMENT AND SYSTEMS

- TAPE RECORDERS
- PUBLIC ADDRESS SYSTEMS
- AMATEUR EQUIPMENT
- INDUSTRIAL SUPPLIES
- MINIATURE COMPONENTS
- RADIO & TV TUBES AND PARTS
- EXCLUSIVE LAFAYETTE TRANSISTOR & HI-FI KITS

Send for Lafayette's FREE Catalog—the most complete, up-to-the-minute electronic supply catalog crammed full of everything in electronics at our customary down-to-earth money-saving prices.

A "must" for the economy-minded hi-fi enthusiast, experimenter, hobbyist, engineer, technician, student, serviceman and dealer.

# *Lafayette Radio*

*"Everything in Electronics"*

**FREE**



**LAFAYETTE RADIO, Dept. RB-6**
**P.O. Box 222, Jamaica 31, N. Y.**
**308 GIANT SIZED PAGES — FREE**

*Name* .....

*Address* .....

*City* ..... *State* .....

A....Always
B....Buy
C....Columbia

*For 15 years—America's outstanding source of the biggest bargains in electronics!*

**APX-6 TRANSMITTER-RECEIVER SPECTACULAR!**
The 31 tubes alone are worth $175.00! These include: 1—3E29/829B; 2—3B24; 1—2C46; 1—2C42; 1—1B40; 5—6A8G; 8—6AK5, etc. 60 MC IF strip, plus tunable cavities. Excel. cond. ONLY ..... **$10.95**

**TS-270 RADAR ECHO BOX**
This is a prime piece of merchandise. 2700-2900 Mc. For radar checkout. Brand new—$95.00. Used, excel..... **$59.50**

**APN-1 FM TRANSMITTER-RECEIVER**
Freq.: 420-460 Mc. 14 tubes. Excel. Complete. Our special at only..... **$3.95**

**MOTOROLA DUAL VIBRATOR SUPPLY**
Input 6 V. Output, 540 V. Uses 2 standard 4-prong vibs and two 0Z4 rectifiers. New. 3 for $10.00..... EA. **$3.95**

**Model 84 Measurements Corp. Sig. Generator**
Yep, this is the one that originally cost $1900.00! 300-1,000 Mc. Ready to go, laboratory checked out ..... **$149.00**
AS IS, but complete. A few at only... $99.50. each

**TG-5 PORTABLE CODE PRACTICE SET**
Battery operated. Complete with key and earphone. New cond. (Less batteries.) TWO for $9.00. EACH ..... **$4.95**

**SPECIAL!!! THIS MONTH ONLY!**
**BC-348 COMMUNICATIONS RECEIVER**
Freq.: 200-500 kc. and 1.5-18 Mc. in 6 bands. Built-in crystal filter. This is the U. S. Air Force rig so you know it's tops! 8 tubes including 2 stages RF. Operates on 110 VAC with additon of power supply. Like new. ONLY **$69.95**

**APR-4 TUNING UNITS**
Make terrific converters! Use with any 30 Mc. Receiver.
TN-16: Frequency: 38-95 Mc. Excellent cond. ..... $19.95
TN-17: Frequency: 90-300 Mc. Excellent cond. ..... 24.95
TN-18: Frequency: 300-1000 Mc. Excellent cond. ..... 29.95

**APN-9 MARINE LORAN RECEIVER**
Gives exact fix in relation to Loran Station. Works on 12 or 24 V. The cheapest insurance a boat owner can have. Excellent cond. **$49.50**

**TECHNICIANS! GENERALS! NOVICES!**
**S C R - 5 2 2 TRANSMITTER RECEIVER** Here 'tis! The oldest, most reliable VHF Transmitter-Receiver in ham history, the greatest 2-Meter rig ever built—at the most sensational price ever offered! Works on 12 or 24 VDC or 115 V 60 cyc. AC. (See below.) Covers 100-156 Mc.—naturally! Crystal controlled. Transmitter has 2-832 tubes, etc., etc. Complete in case, with ALL TUBES. Easily convertible to 6 meters. Excellent condition... **$12.50**
SCR-522-C: Same as above but has electronic squelch. Excellent... $17.50
DOPE FOR CONVERSION TO 6 METERS... 1.00
REGULATED AC POWER SUPPLY for above. Good condition..... 39.95
12 VDC DYNAMOTOR POWER SUPPLY for above. New condition..... 8.95
24 VDC DYNAMOTOR POWER SUPPLY for above. Good condition..... 3.95
BC-1303 LOCAL ADAPTOR CONTROL BOX for above. Like new..... 4.95
ANTENNAS, OTHER ACCESSORIES FOR ABOVE. WRITE IN FOR DATA.
SET OF PLUGS: For SCR-522 and PE-98.... $4.95

**CITIZENS' BAND, ETC.**
**BC-603 RECEIVER**
Covers 20-28 Mc. FM. Terrif for citizens' band. 10 push-buttons. Built-in speaker and squelch cont. May be operated mobile on 12 V. with dynamotor (see prices below) or 110 VAC with power pack. Converts in 1 minute to AM. Info supplied. Like new or renewed cond. **$9.95**
12 V. DYNAMOTOR, for above..... $ 3.95
115 VAC PACK..... 11.95
24 V. DYNAMOTOR..... 2.95
115 V. KIT..... 7.95
CRYSTAL SET FOR ABOVE—80 xtals. New. $4.95
MATCHING TRANSMITTER FOR ABOVE—BC-604: 30 W. 10-channel, push-button FM crystal controlled. 20-27 Mc. New condition, complete with tubes. (Less dyn.)..... **$5.95**
COMBO DEAL! BOTH ABOVE UNITS: BC-603 & BC-604. New cond. BOTH for..... $13.00
ET-237G BRAND NEW MOUNTING RACKS for BC-603. Each only..... $3.95

**BC-620 RECEIVER-TRANSMITTER**
20-28 Mc. 4-watt. Similar to BC-659. New ..... **$14.95**

**RA-120 AC POWER SUPPLY**
For BC-620 or BC-659. 110V. in 60 cyc. New ..... $10.95
TELEPHONE HANDSET, Brand new. Special 3.95
TELESCOPING ANTENNA. New. This is a lulu! ..... 2.95
PE-97: VIBRATOR PACK FOR BC-620 above. 6-12 V. New ..... 3.50

**SCR-625 METAL MINE DETECTOR**
Locate that hidden pipe, search for treasure, use for parts or have a ball! With carrying case. Excel. ..... **$22.50**

**M-M-M! LOOKIT THESE 12 V. DYNAM-M-M-OTORS!**
DM-35: 625 V. @ 225 mile output. Like NEW. Orig. box..... $8.95
WINCO: 5085 TCS. Output 440 V. @ 200 MA. & 225 V. 100 MA. New..... 4.95
EICOR: 6 V. in Out. 600 V @ 175 MA. New. 4.95
CARTER GENEMOTOR: 6 V. in. Out: 420 V. @ 280 MA. New..... 4.95
EICOR: Type 100 TCS Output 400 V. @ 180 MA. New..... 4.95
DY-65: 6 VAC in. Output 600 V @ 175 Ma. New..... 4.95

**T-14/TRC TRANSMITTER**
**JUST REDUCED!** For action this month! 70-100 Mc. 50 W. input power on phone. Single channel. Built-in 110 V. 60 cps power supply. Table top size. Easily converted to 6 meters. Complete. Good condition, excellent buy! ..... **$24.95**

Write for latest flyer! It's a knockout for value! All orders FOB Los Angeles. 25% deposit required. All items subject to prior sale. NOTE: MINIMUM ORDER $3.00. WRITE TO DEPT. R.

Columbia ELECTRONICS
2251 W. WASHINGTON BLVD.
LOS ANGELES 18, CALIF.


# How To Make Better Tape Recordings



## Some simple tips and techniques that can be used to get the best results from your tape recorder.

EDITOR'S NOTE: *The following material was abridged from an article by Warde Adams, Jr., field representative and pioneer recording specialist for Orr Industries, manufacturers of "Irish" brand magnetic tape.*

A MODEST cash investment and a moderate expenditure of your time spent in practice will enable you to make better tape recordings and add new dimensions to the scope of your recorder.

The first step is to become thoroughly familiar with your recorder. Read the operating manual that came with the machine. Read it through from cover to cover—then read it through again. Be sure you understand how your machine operates and know what each switch, button, or knob will do. It is important that you know how to operate your instrument and what makes it work.

Next, practice with your recorder until you know all of its functions intimately. Try your hand at all types of recording in order to gain experience and become familiar with the machine's potentialities.

With experience, you will find yourself instinctively picking a recording site where extraneous noise is minimum. The room itself may not be acoustically ideal but if not so originally you will soon discover how much the over-all sound can be improved by the judicious addition of carpeting and draperies.

### Mike Placement

Correct microphone placement is extremely important. Every type of recording requires a different microphone technique—which can be determined only by experiment. It would be helpful if we could say "Here's where a mike belongs for guaranteed results"—but things just aren't that simple in most cases.

Try to avoid hand-holding the microphone. Mike stands, both floor and table models, are preferable due to their flexibility. Many inexpensive stands, suitable for home use, are commercially available.

A microphone stand is essential for recording groups. Adjust the height of the stand to the average height of the group. Have the "artists" remove their shoes since the scuffling of shoe leather, especially on an uncarpeted floor, will ruin the recording. Vibrations in the floor will reach the microphone through the stand. Professional recording studios spend hundreds of dollars for mike stands with elaborate shock mounts to prevent such transferral of vibration. The best the home recordist can do is to see that the stand rests on carpet and is steady.

Remember that most mikes furnished with home recorders are somewhat directional so take advantage of this characteristic to help keep extraneous noises out of the recordings that you make.

To record your own speech, the mike should be placed at mouth level and from 6 to 12 inches away, as a general rule. Test recordings should be made to determine the proper distance for the mike and the volume control setting on the recorder. Remember—even professionals tend to increase their vocal output as a recording progresses so make allowances for this phenomenon. When recording groups, test tapings should be made for each member of the group.

Don't place the microphone on the same table with the recorder or on a piano, radio, or TV cabinet. It may pick up motor noise from the recorder or cabinet resonance from the piano or TV. Before placing the mike on a table remove ash trays or decorative accessories which might be resonant to certain tones from musical instruments or voices.

For informal recordings, crystal microphones of the type usually supplied with the recorder will do an acceptable job. You will, however, get much better results with a dynamic microphone. These are available in a wide range of prices.

When experimenting, determine the proper setting for the volume control. If you "overload" a tape (record at too high a volume level) you will get distorted reproduction of the original sound. If the record level is too low, the effective dynamic range of the recording will be decreased and, when the playback volume is increased to compensate for this, the inherent noise

of the recorder will rise by the same amount. Once you have determined a good average level setting, try to keep all your recording levels within this range. However, if you are recording a program with wide dynamic range, such as music that starts softly and builds up to a crescendo, you may need to make occasional adjustments in the volume.

Many recorders have one or more neon bulbs or a "magic eye" tube which functions as recording level or volume indicator. While these devices are satisfactory in many cases, a vu meter is preferable because it gives a more accurate indication of signal level.

For timing, your recorder should have an index counter or program indicator. If you are recording several selections on one reel of tape, the indicator will enable you to locate any portion of your recording quickly and accurately. A mechanical counter which measures tape footage is the preferred type.

### Miking and Mixing

To avoid feedback, place the microphone so that the sound from the speaker is not directed toward it. Keep the mike away from audible hum fields such as those produced by fluorescent lamp ballasts and the like.

Remember, your microphone is a delicate instrument. It should receive the same care you would give a fine watch.

You can increase your recorder's versatility by mixing the sounds from several microphones. This will give you better control over the balance among the various sound sources you are recording. Some recorders have built-in mixers. If yours does not, inexpensive, tubeless mixers are available as are the more expensive amplifier-type units.

### Selecting a Tape

Tape recordists should become thoroughly familiar with the various types of tape and their applications. Tapes are made on two bases—cellulose acetate and "Mylar," *DuPont's* polyester film. "Mylar" is tougher, stronger, and more resistant to extremes in temperature and humidity than the acetate type. Recordings that are to be preserved for years should be made on "Mylar" base tapes.

The basic industry standard is 1200 feet of 1½ mil tape on a 7-inch reel and 600 feet on a 5-inch reel. Longer tapes are now available, on standard reels, from some manufacturers.

Beware of so-called "bargains" in unbranded tape or "manufacturers' seconds." If you want a quality recording, always buy a recognized brand tape. You can depend on a brand-name tape because every reputable tape manufacturer will stand behind his product with a comprehensive guarantee.

### Recording Speeds

The recordist should also become


REWARD!



WANTED!
Charles Q. Amateur
to contact Walter Ashe
at once for his
"SURPRISE"
Trade-in allowance

We have a posse out scouring the hills for our man . . . and when we find him we're going to give him the "Surprise" of his lifetime . . . such a big allowance on his present equipment towards the purchase of his new Transmitter or Receiver he won't think of saying anything else but "let's make a trade!" Walter Ashe "Surprise" Trade-In Allowances are next to impossible to beat . . . and our allowance to you will be too. Rush the coupon below and see how handsomely we'll "reward" you!

NEW 1960 CATALOG NOW READY!

*The Only Radio Catalog Compiled and Designed Entirely With The Needs of The Amateur in Mind!*

If you're an amateur, experimenter or a newcomer "coming up" . . . you're invited to ask for a copy of our brand new 1960 Walter Ashe catalog . . . just off the press. It's packed from cover to cover with everything that's new and needed . . . in mobile or fixed station equipment, parts and supplies, transmitters, receivers, test equipment and Citizen Band units. Incidentally, Walter Ashe is one of America's leading suppliers of High Fidelity equipment . . . and mail the coupon below . . . we'll rush your copy to you!

*You Can Be Sure...*
that every piece of used equipment Walter Ashe takes in trade . . . and later sells . . . is checked thoroughly and guaranteed to work the same as new. Whether you're trading up to new or in the market for used equipment . . . you'll always be money and satisfaction ahead at Walter Ashe!

TIME PAYMENT TERMS AVAILABLE ON ALL EQUIPMENT

Walter Ashe RADIO CO.
Dept. R-2-60, 1125 Pine Street, St. Louis 1, Mo.

"SURPRISE TRADE IN" COUPON

Walter Ashe Radio Co. • In Our 38th Year
Your One-Stop Supermarket
Dept. R-2-60, St. Louis 1, Mo.
☐ Rush New Catalog
☐ Send lists of guaranteed Used Equipment
☐ Rush "Surprise Trade-in" offer on My ____
For_____
(Show make and model of equipment desired)
Name_____
Address_____
City_____ Zone____ State____

RADIO PARTS STORES & HI-FI SALONS!

Hundreds of dealers across the nation profit by selling ELECTRONICS WORLD each month to their customers. Are you one of them? ELECTRONICS WORLD helps build store traffic . . . keeps customers coming back month after month for the merchandise you sell—and, best of all, you earn a neat profit on each copy sold—NO RISK INVOLVED.

So get details on selling ELECTRONICS WORLD, the world's largest selling technical electronics magazine. Or, order your copies now. Just use the handy coupon.

Direct Sales Department
Electronics World
One Park Avenue
New York 16, New York
Attn: Jerry Schneider

☐ Send me ..... copies of ELECTRONICS WORLD for resale in my store each month. No risk involved on my part.

☐ Send me details on selling ELECTRONICS WORLD in my store.

STORE NAME_____
ADDRESS_____
CITY_____ ZONE____ STATE_____
SIGNATURE_____
EW 260

**COAX CABLE**

RG8U—52 Ohm Impedance—Fresh Stock—500 feet on sealed wooden spools. Each ..... $32.50

**POWER SUPPLY—BRAND NEW**

PP326/U—Input 110V. AC—Output 24 Volts filtered DC. Rated .9 Amps Capable 1½ Amps. Sel. Rectifier. Size: 6½"x7"x7". Adding a pot. makes ideal transistor supply.. Ea. $9.95

**NEW VACUUM CAPACITORS**

EIMAC VC 12 MMF-32KV.....ea. $6.95
EIMAC VC 25 MMF-32KV.....ea. 7.95
EIMAC VC 50 MMF-32KV.....ea. 8.95
JENNINGS JMC-150 MMF-50KV.....ea. 39.95

**FREQUENCY METER**

Vibrating REED type. Round 3½" Bakelite case. Range 57 to 63 cy. 110V. Ea. $10.95

**BRAND NEW MOBILE DYNAMOTORS**

MADE BY EICOR—SMALL SIZE
Input 12 Volts. Output 400V. 180Ma Cont. Duty. 250 Mil. Int. Duty.... $4.95
Input 12V. Output 440V. 200Ma Cont. Duty. 300 Mil. Int. Duty..... $6.95

**POWER TRANSFORMER**

Pri. 115V. Secs. 320-0-320V. @ 150 Ma. 5V. @ 2 Amps 6.3V. @ 3 Amps... $2.95
Primary 110V. 60 cy., Sec 445-0-445V. @ 150 Ma. 25V. @ .4 Amps. 6.3V. @ 6 Amps. 5V. @ 2 Amps. Fully shielded....Ea. $4.95
*Write for quantity prices*

**FILAMENT TRANSFORMERS**

Primary 110 volts 60 cycle. Secondary 2½ V. 10 Amps. 10,000 V. Insulation. Suitable for pair of 866 tubes..... $3.95
Primary 110V. Sec. 6.3V. @ 20 Amps.....Ea. $3.50
Primary 110V. Sec. 6.3V. @ 60 Amps.....Ea. $8.95

**CHOKE—FULLY CASED**

5 HENRY @ 200 Ma ..... 1.98
5 HENRY @ 250 Ma..... 2.28
4 HENRY 400 Mil ..... 3.98
12 HENRY 500 Mil ..... 8.98
4 HENRY 800 Mil ..... 12.95
6 HENRY 600 Mil ..... 8.95

**BRAND NEW OIL CONDENSERS**

| | | | | | |
|---|---|---|---|---|---|
| 2 MFD | 600 VDC | .50 | 6 MFD | 2000 VDC | 4.95 |
| 3 MFD | 600 VDC | .60 | 8 MFD | 2000 VDC | 5.95 |
| 4 MFD | 600 VDC | .75 | 2 MFD | 2500 VDC | 2.50 |
| 5 MFD | 600 VDC | .80 | 1 MFD | 3000 VDC | 1.85 |
| 6 MFD | 600 VDC | .85 | 2 MFD | 3000 VDC | 3.50 |
| 8 MFD | 600 VDC | .95 | 4 MFD | 3000 VDC | 6.95 |
| 10 MFD | 600 VDC | 1.19 | 1 MFD | 4000 VDC | 3.25 |
| 12 MFD | 600 VDC | 1.50 | 2 MFD | 4000 VDC | 6.25 |
| 3x8 (24 MFD) | 600 VDC | 2.50 | 3 MFD | 4000 VDC | 8.95 |
| 1 MFD | 1000 VDC | .60 | 15 MFD | 5000 " | 39.50 |
| 2 MFD | 1000 VDC | .95 | .5 MFD | 7500 VDC | 2.95 |
| 4 MFD | 1000 VDC | 1.35 | 1 MFD | 7500 VDC | 6.95 |
| 8 MFD | 1000 VDC | 1.95 | 2 MFD | 7500 " | 17.95 |
| 10 MFD | 1000 VDC | 2.50 | 2 MFD | 10,000 " | 29.95 |
| 12 MFD | 1000 VDC | 2.95 | 1 MFD | 12,500 " | 19.95 |
| 15 MFD | 1000 VDC | 3.50 | 2 MFD | 12,500 " | 34.50 |
| 1 MFD | 1200 VDC | .45 | 1 MFD | 15,000 " | 42.50 |
| 1 MFD | 1500 VDC | .75 | .02 MFD | 15,000 " | 3.50 |
| 2 MFD | 1500 VDC | 1.10 | .5 MFD | 25,000 " | 34.95 |
| 4 MFD | 1500 VDC | 1.95 | 1 MFD | 25,000 " | 69.95 |
| 8 MFD | 1500 VDC | 2.95 | 50MFD | 125VAC | 2.50 |
| 1 MFD | 2000 VDC | .85 | 4 MFD | 330 AC. | .85 |
| 2 MFD | 2000 VDC | 1.50 | 10 MFD | 330 AC. | 1.95 |
| 4 MFD | 2000 VDC | 3.50 | 50 MFD | 330 AC. | 4.50 |
| | | | 15 MFD | 440 AC. | 2.50 |
| | | | 8 MFD | 660 AC. | 2.95 |

**SIGMA 5F RELAY**

16,000 ohm in dual 8,000 ohm coils. SPDT adjustable silver contacts and armature tension. Operates on 500 Microamperes or less .....Ea. $3.95
*Write for quantity prices*

**RELAYS**

24V. AC 3PDT.....ea. $1.65
24V. AC 4PDT.....ea. $1.85
110V. AC 3PDT.....Ea. $1.85
ALLIED 110V. AC 4PST.....Ea. $2.75
Potter-Brumfield SMSLS 5000 ohm, 4 Ma. Sens.....Ea. $2.25
Allied Relay 110 V. AC. DPST .....ea. $1.35
Hermetically Sealed Relay Coil 110V AC 60 cy SPDT Contacts 5 Amps.....ea. $1.50
6 Volt DC 3 PST H.S. (Norm. Open)..ea. 99c
12 Volt DPDT DC Relay.....ea. $1.35
SIGMA type 22RJC 8,000 ohm SPDT, small sealed relay..... $2.49
Sealed Relay. SPDT, 6,000 ohm coil..... $1.95
G.E. Relay control, contains 8000 ohm relay, sensitivity 2 mils. 10 for $9.25. ea. $1.10
LEACH ANT. RELAY 110V. AC DPDT Ceramic Ins.....ea. $3.45

**PANEL METERS**

G.E., WESTINGHOUSE, W.E., SIMPSON, etc.

1½" METERS
0-1 Mil.....2.95
0-100 Micro.....3.95

2" METERS
0-50 Micro (0-5 scale).....6.95
0-10 Amps DC ...2.95
0-20 Volts DC... 2.95
18-36 Volts DC...1.98
0-130 V. AC...3.49

3" METERS
100-0-100 Micro Amps DC.....5.95
0-1 Mil DC.....3.95
0-100 Mil DC.....3.95
0-150 Mil DC.....3.95
0-12 Volts AC....3.95
0-15 Volts AC....3.95
Running Time Meter, 0-9,999.9 hrs. 110V. 60 cy.....9.50

4" METERS
4" Rectang. 0-2.5KV 1½% Mirror scale 7.95

**MISCELLANEOUS SPECIALS**

36 OHM 50 Watt Globar Non-Ind.Res. ..60c ea. 2 for $1.00
3-12 MMF Erie Ceramic Trimmers.....21¢
Murdock Headphones—BRAND NEW 10,000 ohm imped. with std. phone plug.....ea. $2.95
Replacement 6' phone cord for Standard Headsets .....39¢
CUTLER-HAMMER TOGGLE SWITCH SPDT (ST42D) 4 for $1.00.....ea. 29c
WILLARD STORAGE CELL—2V. 28 Amp hrs. Clear plastic case. Shipped dry..ea. $2.50

*Write for quantity prices on all special items*

All merchandise sold on a 10 day money back guarantee
Min. Order $3.00—25% with Order—F.O.B. New York

**PEAK**
ELECTRONICS COMPANY
66 W. Broadway, New York 7, N. Y., WO-2-5439


familiar with recording speeds. Most home recorders will have at least two speeds—usually 3.75 and 7.5 ips. These figures indicate the speed at which the tape passes the recording or playback head.

While the speaking voice alone may be recorded acceptably at 3.75 ips, it is advisable to record music, both vocal and instrumental, at 7.5 ips. Most professional recording is done at 15 ips, but few home recorders are designed to operate at this speed. Some home recorders will have a 1⅞ ips recording speed and this should be used for office dictation or for recording informal discussions, committee meetings, and the like.

### Erasing and Storage

Previously recorded material on the tape is automatically erased during the next recording by means of the erase head which is located just in front of the recording head. Saturated tapes, or tapes recorded at too high a level, may be difficult to erase—using the erase head found on many inexpensive recorders.

Small models of the professional "degausser" are now available for home use. They will usually do a satisfactory job of erasing if used according to instructions.

Splicing is easily accomplished by the "free-hand" method, using a pair of scissors or a razor blade, but be sure your "tools" are demagnetized before you bring them near the tape. Use a "degausser" for this operation, not a permanent magnet. *Caution:* Dual-track tape cannot be conveniently edited since when you cut out sections of one track you also delete portions of the second track that is recorded.

Tape may be stored at room temperature. Best storage conditions are at a temperature of around 70 degrees F and a humidity of from 40 to 60 percent. Keep tapes away from excessive heat and dampness. Recorded tape may be stored in its original cardboard box or in metal or plastic containers. Mark and label each tape for future reference and easy filing.

Do not store tape near electrical appliances or motors which may generate magnetic fields. If stored in cabinets in or near your hi-fi system, keep the tapes away from power amplifiers, loudspeakers, and magnetic microphones.

Recorded tapes should always be left on the take-up reel for storage. Tape wound at slow speed will have a much more uniform wind from the standpoint of tension and stack. If the tape is wound too tightly, it will distort due to the extreme pressure. Be sure the tape is wound evenly. If any edges are left sticking out of the stack, the tape may be damaged in handling.

Stored recorded tapes should be rewound at least once every six months and, preferably, once every three months. Rewinding is necessary to relieve any tension due to improper winding which could result in permanent distortion of the film base.

If all the above suggestions are followed, you will get the greatest amount of pleasure and profit from your recorder. Above all, don't be afraid to experiment and make mistakes. Each recording session will teach you something new. One unique advantage of a tape recorder is that you erase mistakes simply by re-recording. —30—

---

Allied Radio's Fall Amateur Radio Course drew a record-breaking enrollment which includes nine father-son teams, numerous husband and wife combinations, as well as a complete father-mother-son unit. Over 160 students took the training to pass the FCC examinations for the Novice Amateur operator license. The course, which is offered without charge by Allied as a service, covers a period of 14 weeks. Classes meet one evening a week. Students are instructed in sending and receiving code. Lectures cover basic radio theory. Keys, headphones, and other practice materials are supplied by the company for classroom use. Instructors George Bercos, W9WOV, and Joe Huffman, W9BHD, of Allied are in charge of lectures and practice sessions.

## Radio Service for TV Techs

(*Continued from page* 41)

should make this indication louder, as each stage provides amplification. Thus absence or reduction of gain can be pinned down to an offending stage: such a stage will not contribute its share of increase in the loudness of the click and the hum. After such localization, it is usually easy, with such conventional techniques as voltage measurement and capacitor bridging, to determine the defective component. This method of "wet-finger" circuit tracing is also useful in TV work, but is less frequent with TV technicians who are used to handling elaborate service equipment than with the "old-timers" of radio servicing.

Intermittent faults, in radio as in TV, are the most elusive. The most common intermittent condition is that caused by one of the half-dozen or so coupling and bypass capacitors. Time and money can often be saved by replacing all the possible offenders. This is, in fact, routine in some shops, whenever a chassis is pulled.

"Front-end" oscillator circuitry, as used in small AM radios, is very different from that used in TV tuners, a heptode or pentode mixer-oscillator taking the place of the triode oscillator and triode or pentode mixer. Servicing this circuit, however, is not very different. A negative voltage at the oscillator grid still indicates that the oscillator is working and loss of output may still be caused by failure of the mixer section of this stage. Since few components are used, the interdependence of oscillator and mixer-amplifier often makes substitution the fastest method of fault finding. Partial oscillator failure may occur: the resultant loss of higher-frequency stations compares with the loss in TV of channels 7 to 13.

The technician who is experienced in looking for visible defects will have little trouble adapting to radio (or any other) servicing. Dry solder joints, leaking electrolyte, and cracked printed wiring are common to any kind of servicing. Also extra-bright tube filaments still indicate a possible short in a filament string, and a glowing output-tube screen still suggests loss of plate voltage due to an open output transformer. All these will be familiar to the experienced TV technician.

Printed wiring is hardly a novelty to the TV technician: he may have had far more experience with this kind of chassis than have most radio technicians. The same unsoldered joints, dirty tube sockets making poor contact, and broken printing are encountered, but printed boards used in radio are generally not so well mounted as their TV counterparts and, consequently, suffer more externally caused damage. Little difficulty will be experienced with printed boards. A start made on radio sets that use this type of chassis makes an easy introduction to the radio repair business. —50—


# you get so much more in

KNIGHT
A PRODUCT OF ALLIED RADIO

# hi-fi speakers



KN 3000

**high-compliance speaker system with two built-in Arthur Janszen electrostatic tweeters**

Allied's own hi-fi speaker value extraordinary. Features patented Arthur Janszen design dual electrostatic tweeters right in the cabinet—no clumsy "add-ons" needed. High compliance woofer is all-new controlled-mass design. The results are phenomenal: Distortion is held to a mere 0.5% at full 50 watts input. Response is clean and level, 30-25,000 cps. Meets the most critical professional requirements—transparent high frequencies beyond audible limits—smooth, honest bass. (Ask for impartial lab performance report.) Impedance, 8 ohms. The attractive, acoustically-sealed enclosure is hand-finished on four sides; 14 x 26½ x 13"; available in mahogany, limed oak or walnut. U.L. Approved. Unconditionally guaranteed for one full year. Shpg. wt., 50 lbs. ...*Only* **$129.50.** *$5 down.*



**Built-In Arthur Janszen** design patented dual electrostatic radiators—rated the best again and again. Built-in power supply; certified response to beyond 25,000 cps.

**New High-Compliance** 12" woofer, featuring weighted cone in solid cast-aluminum alloy frame...provides extremely solid, very low bass performance.

**15-Day Trial & Moneyback Guarantee:** Try the KN-3000 Speaker System under your own operating conditions for 15 days; if you are not completely satisfied, your purchase price will be refunded by Allied upon return of equipment.

**New Easy Terms: Only $5 down** (or less) on orders up to $200. Up to 24 months to pay




**SEE YOUR FREE 1960 ALLIED CATALOG**

for the largest selection of money-saving hi-fi speakers and speaker systems (true high compliance shelf speaker systems begin as low as $59.95). See hundreds of top buys on everything in Hi-Fi in the 1960 Allied Catalog. Write for your FREE copy today.

*order from*

**ALLIED RADIO**

ALLIED RADIO, Dept. 187-B
100 N. Western Ave., Chicago 80, Ill.

☐ Ship me_____ KN-3000 Speaker System(s).
☐ Mahog. ☐ Oak. ☐ Wal.

$_____ encl. (Shipped F.O.B. Chicago)

☐ SEND FREE 1960 CATALOG. I am interested in saving money on everything in Hi-Fi.

☐ Send impartial Lab Report on KN-3000 Speaker.

Name_____

Address_____

City_____ Zone_____ State_____

# NOW YOU CAN HAVE YOUR CHOICE OF CENTURY'S UNIQUE Peak-to-Peak VACUUM TUBE VOLT METERS

Model VT-10
LINE OPERATED

WITH LARGE EASY-TO-READ 6" METER
featuring the sensational new
**MULTI-PROBE** *(Patent Pending)*

Model VT-1
BATTERY OPERATED

**No extra probes to buy! The versatile MULTI-PROBE does the work of 4 probes**

❶ DC Probe ❷ AC-Ohms Probe
❸ Lo-Cap Probe ❹ RF Probe

No longer do you have to cart around a maze of entangled cables, lose time alternating cables or hunting for a misplaced probe. With just a twist of the MULTI-PROBE tip you can set it to function as either a DC Probe, AC-Ohms Probe, Lo-Cap Probe or RF Probe.

**LINE OPERATED**
Ideal for use on the test bench. Designed to run cool even under continuous operation . . . Line isolated.

**BATTERY OPERATED**
Completely portable . . . Invaluable wherever line connection is undesirable or unavailable . . . Unique circuitry assures low battery drain.

Model VT-10 **$58.50** Net
**TERMS:** $14.50 within 10 days. Balance $11 monthly for 4 months.

Model VT-1 **$58.50** Net
**TERMS:** $14.50 within 10 days. Balance $11 monthly for 4 months.

## FUNCTIONS OF VT-1 and VT-10

**DC VOLTMETER** . . . Will measure D.C. down to 1.5 volts full scale with minimum circuit loading, and give accurate readings of scale divisions as low as .025 volts . . . Will measure low AGC and oscillator bias voltages from .1 volts or less up to 1500 volts with consistent laboratory accuracy on all ranges . . . Zero center provided for all balancing measurements such as discriminator, ratio detector alignment and hi-fi amplifier balancing.

**AC VOLTMETER** . . . True Peak-to-Peak measurements as low as 3 volts of any wave form including TV sync, deflection voltages, video pulses, distortion in hi-fi amplifiers, AGC and color TV gating pulses . . . Scale divisions are easily read down to .1 volts . . . Measures RMS at 1/20th the circuit loading of a V.O.M. . . . Unlike most other V.T.V.M.'s there is no loss in accuracy on the lowest AC range.

**ELECTRONIC OHMETER** . . . Measures from 0 to 1000 megohms . . . Scale divisions are easily read down to .2 ohms . . . Will measure resistance values from .2 ohms to one billion ohms . . . Will detect high resistance leakage in electrolytic and by-pass condensers.

**RF and LO-CAP MEASUREMENTS** . . . With these extra VT-1 functions you can measure voltages in extremely high-impedance circuits such as sync and AGC pulses, driving saw tooth voltages, color TV gating pulses, mixer output levels, I.F. stage-by-stage gain and detector inputs.

## FEATURES OF VT-1 and VT-10

- New advanced pentode amplifier circuit
- Large 6" 100-microampere meter, many times more sensitive than meters used in most V.T.V.M.s
- Simplified multi-color easy-to-read 4-scale meter
- No heat operation assures stability and accuracy
- Amplifier rectifier circuit with frequency compensated attenuator — a feature found only in costly laboratory instruments
- Meter completely isolated
- Hand-crafted circuitry eliminates the headaches of printed circuitry
- 1% resistors used for permanent accuracy
- Rugged gray hammertone steel case provides necessary shielding and eliminates plastic case drawbacks of cracking or melting
- Deep brushed long lasting etched aluminum panel
- Matching cover protects instrument face — snaps on and off instantly.

## SPECIFICATIONS OF VT-1 and VT-10

- **DC Volts** — 0 to 1.5/6/30/150/300/600/1500 volts
- **AC Volts (RMS and Peak-to-Peak)** — 0 to 3/12/60/300/1200 volts
- **Ohms** — to a billion ohms, 10 ohms center scale — RX1/10/100/1K/10K/100K/1M
- **RF** — Peak reading demodulator supplied for use on all DC ranges
- **Zero Center** — available on all DC volt ranges with zero at mid-scale
- **Decibles** — from —10 Db to +10/22/36/50/62 based on the Dbm unit: ODb-1MW in 600 ohms
- **Impedance** — 11 megohms DC, 1 megohm AC, 10 megohms Lo-Cap
- **Input Capacity** — 130 mmfd. RMS, 250 mmfd. Peak-to-Peak, 25 mmfd. Lo-Cap

# Model CT-1 IN-CIRCUIT CONDENSER TESTER

**Here is an IN-CIRCUIT CONDENSER that DOES THE WHOLE JOB!** The CT-1 actually steps in and takes over where all other in-circuit condensers fail. The ingenious application of a dual bridge principle gives the CT-1 a tremendous range of operation . . . and makes it an absolute 'must' for every serviceman.

### *in-circuit checks:*

- Quality of condensers even with circuit shunt resistance . . . (This includes leakage, shorts, opens, intermittents)
- Value of all condensers from 200 mmfd. to .5 mfd.
- Quality of all electrolytic condensers (the ability to hold a charge)
- Transformer, socket and wiring leakage capacity

### *out-of-circuit checks:*

- Quality of condensers . . . (This includes leakage, shorts, opens and intermittents)
- Value of all condensers from 50 mmfd. to .5 mfd.
- Quality of all electrolytic condensers (the ability to hold a charge)
- High resistance leakage up to 300 megohms
- New or unknown condensers . . . transformer, socket, component and wiring leakage capacity

## OUTSTANDING FEATURES

- Ultra-sensitive 2 tube drift-free circuitry
- Multi-color direct scale readings for both quality and value . . . in-circuit or out-of-circuit
- Simultaneous readings of circuit capacity and circuit resistance
- Built-in hi-leakage indicator sensitive to over 300 megohms
- Cannot damage circuit components
- Electronic eye balance indicator for even greater accuracy
- Isolated power line
- Deep brushed long lasting etched aluminum panel
- Housed in sturdy gray hammertone finish steel case . . . comes complete with test leads



Model CT-1 **$34.50** Net
**TERMS:** $9.50 within 10 days. Balance $5 monthly for 5 months.

# 10 DAY *FREE* TRIAL ON CENTURY INSTRUMENTS OF YOUR CHOICE

See for yourself at no risk why thousands of servicemen all over the country selected CENTURY test equipment above all others. Send for instruments of your choice without obligation . . . try them for 10 days before you buy . . . only then, if satisfied, pay in easy-to-buy monthly installments — without any financing or carrying charges added.



Housed in hand-rubbed oak carrying case — complete with MULTI-HEAD

Model CRT-2 **$57.50** Net

**TERMS:** $13.50 within 10 days. Balance $11 monthly for 4 months.

# Model CRT-2 CRT TESTER-REACTIVATOR

## TESTS, REPAIRS and REACTIVATES

- ***ALL BLACK AND WHITE PICTURE TUBES*** *(including 110° tubes)* . . . from 8" to 30", whether 12 pin base, 8 pin base, 14 pin base . . . and the very latest 7 pin base.
- ***ALL COLOR PICTURE TUBES*** . . . Each of the red, green and blue color guns is handled separately.

### CHECK THESE EXCLUSIVE FEATURES

- **THE MULTI-HEAD** (Patent Pending) . . . **A SINGLE PLUG IN CABLE AND UNIQUE TEST HEAD** —A tremendous advance over the maze of cables and adapters generally found with other testers.
- **WATCH IT REACTIVATE THE PICTURE TUBE** — You actually see and control the reactivation directly on the meter as it takes place. This allows you for the first time to properly control the reactivation voltage and eliminates the danger of stripping the cathode of the oxide coating. It also enables you to see whether the build-up is lasting.
- **CONTROLLED "SHOT" WITH HIGHER VOLTAGE FOR BETTER REACTIVATION** — Stronger than any found in other testers — high enough to really do the job — yet controlled to avoid damage to the picture tube.
- **UNIQUE HIGH VOLTAGE PULSE CIRCUIT** — Will burn out inter-element shorts and weld open circuits with complete safety to the picture tube.

### THE CRT-2 DOES ALL THIS RIGHT IN THE CARTON, OUT OF THE CARTON OR IN THE SET

**TEST**
- For quality of every black and white and color picture tube, employing the time proven dynamic cathode emission test principle.
- For inter-element shorts and leakage up to one megohm. Separate short test provided for each element in the picture tube.
- For life expectancy.

**REPAIR**
- Will clear inter-element shorts and leakage.
- Will weld open elements.

**REACTIVATE**
- The "SHOT" (high voltage controlled pulse) method of reactivation provided by the CRT-2 will restore picture tube to new life in instances where it was not possible before. The high voltage is applied without danger of stripping the cathode as you always have perfect control of the high voltage pulse.
- The "BOOST" method of reactivation also provided by the CRT-2 is used effectively on tubes with a superficially good picture but with poor emission and short life expectancy. It will also improve definition, contrast and focus greatly and add longer life to the picture tube.

- **VISUAL LIFE TEST** — Enables both you and your customer to see the life-expectancy of any picture tube right on the meter . . . helps eliminate resistance to picture tube replacement when necessary.
- **SPECIAL LOW SCREEN VOLTAGE TUBES** — Will handle new type picture tubes with special low voltage of approximately 50 volts.
- **SEPARATE FILAMENT VOLTAGES** — Including the very latest 2.35 volt and 8.4 volt types as well as the older 6.3 volt types.
- **NEW 'SF' PICTURE TUBES** — Accommodates the different base pin connections of this new type picture tube.



Housed in hand-rubbed oak carrying case complete with CRT ADAPTER

Model FC-2 **$69.50** Net

**TERMS:** $14.50 within 10 days. Balance $11 monthly for 5 months.

# Model FC-2 FAST-CHECK TUBE TESTER

## Simply set two controls . . . insert tube . . . and press quality button to test any of over 900 tube types completely, accurately . . . IN JUST SECONDS!

The FAST-CHECK enables you to cut servicing time way down, eliminate unprofitable call-backs and increase your dollar earnings by selling more tubes with very little effort on your part. You make every call pay extra dividends by merely showing your customer the actual condition and life expectancy of the tube. The extra tubes you will sell each day will pay for the FAST-CHECK in a very short time.

### PICTURE TUBE TEST ADAPTER INCLUDED WITH FAST-CHECK

Enables you to check all picture tubes (including the new short-neck 110 degree type) for cathode emission, shorts and life expectancy . . . also to rejuvenate weak picture tubes.

### RANGE OF OPERATION

- Checks quality of over 900 tubes types, employing the time proven dynamic cathode emission test. This covers more than 99% of all tubes in use today, including the newest series-string TV tubes, auto 12 plate-volt tubes. 0Z4s, magic eye tubes, gas regulators, special purpose hi-fi tubes and even foreign tubes.
- Checks for inter-element shorts and leakage.
- Checks for gas content.
- Checks for life-expectancy.

### SPECIFICATIONS

● No time consuming multiple switching . . . only two settings are required instead of banks of switches on conventional testers ● No annoying roll chart checking . . . tube chart listing over 900 tube types is located inside cover. New listings are added without costly roll chart replacement ● Checks each section of multi-section tubes and if only one section is defective the tube will read "Bad" on the meter scale ● 41 phosphor bronze beryllium tube sockets never need replacement ● 7-pin and 9-pin straighteners mounted on panel ● Large 4½" D'Arsonval type meter is the most sensitive available, yet rugged — fully protected against accidental burn-out ● Special scale on meter for low current tubes ● Compensation for line voltage variation ● 12 filament positions ● Separate gas and short jewel indicators ● Line isolated — no shock hazards ● Deep brushed long lasting etched aluminum panel.

***NOTE:*** The Fast-Check positively cannot become obsolete . . . circuitry is engineered to accommodate all future tube types as they come out. New tube listings are furnished periodically at no cost.

**MAIL FREE TRIAL COUPON TODAY!**

## CENTURY ELECTRONICS CO., INC. 111 Roosevelt Ave., Dept. 202, Mineola, N. Y.

- ☐ Model VT-10 Vacuum Tube Volt Meter.....$58.50 — $14.50 within 10 days. Balance $11 monthly for 4 months.
- ☐ Model VT-1 Battery Vacuum Tube Volt Meter.....$58.50 — $14.50 within 10 days. Balance $11 monthly for 4 months.
- ☐ Model CT-1 In-Circuit Condenser Tester.....$34.50 — $9.50 within 10 days. Balance $5 monthly for 5 months.
- ☐ Model CRT-2 CRT Tester-Reactivator.....$57.50 — $13.50 within 10 days. Balance $11 monthly for 4 months.
- ☐ Model FC-2 Fast-Check Tube Tester.....$69.50 — $14.50 within 10 days. Balance $11 monthly for 5 months.

Prices Net F.O.B. Mineola, N. Y.

Yes, I want to take advantage of your 10 day FREE try-before-you-buy offer. Ship on approval the instruments I have checked. After I have tried the equipment for 10 full days I will either send you the down payment and agree to pay the balance in the monthly payments shown, or I will return the units and owe nothing.

Name.....
Please print clearly

Address.....

City.....State.....

# TROUBLESHOOT YOUR OWN V.T.V.M.

By DAVID R. ANDERSON

**Time lost while this key unit is being repaired on the outside can be costly. You can do a quick job yourself with sectional analysis and isolation.**

WHENEVER you turn to look at someone working in electronics, you are also likely to see a v.t.v.m. Especially in the case of the service technician, it is a constantly used and valuable instrument. Although he is quite likely to have at least one other meter in addition, failure of the v.t.v.m. generally leaves him in a tight spot. Despite the fact that actual work on this instrument is not a customary thing for its owner, he can greatly simplify the task of troubleshooting by dividing the v.t.v.m. into sections and checking each individually, or only those sections in which trouble is indicated.

The v.t.v.m. can conveniently be broken down into four principal sections: the bridge circuit, together with its power supply; the d.c. multipliers; the a.c. multipliers, including the a.c. rectifier; and the ohmmeter section.

The bridge circuit is the heart of the instrument. Other sections simply serve to process and apply a proper voltage to the input grid of the bridge for measurement. A typical bridge is shown in Fig. 2. With no voltage at the grid of the input triode the tubes are balanced out so that the same amount of current flows through each one. The "Zero Adjust Pot" is used to establish this condition, since there may be some imbalance inherent in the tubes or circuit components.

Since current through one triode equals that in the other and since the cathode resistors are equal, the voltage at point *A* will equal that at point *B*. No current will thus flow through the meter because it is connected between these two equipotential points. When an applied input signal throws the bridge out of balance, there is a voltage difference between points *A* and *B*, and a current flows through the meter, deflecting the latter in proportion to the imbalance, which is in proportion to the applied voltage.

There are other versions of the bridge circuit than the common one illustrated. For example, the meter movement may be connected between a point in the plate circuit of one triode and a like point in the other triode. However, fundamental operation is the same and the approach to isolating faults is also similar.

Let us assume, to deal with a not unusual defect, that we cannot zero the meter with the adjusting pot provided for that purpose. The cause of this abnormal degree of imbalance could lie in either of two directions. There is either a defective component in the bridge itself, or a defect in some other section is allowing an undesired voltage to leak to the input of the bridge. Shorting the grid to ground will tell us which way to look. Since this removes any stray voltage from the input grid, the trouble must lie in the bridge itself if zero adjustment still cannot be achieved.

With this additional localization, finding the point of defect is relatively simple if it is in the bridge, as only a few possibilities exist. Tube substitution will either remedy the situation or eliminate that component from suspicion. A voltage check at the triode plates narrows things down even more.

A high plate voltage indicates an open condition or excessive resistance in the cathode circuit of Fig. 2. With this indication, only three possibilities remain: either of the cathode resistors or the potentiometer. An ohmmeter should then provide the final answer.

If plate voltage is low, a short or leakage in the cathode circuit, or low output from the simple power supply, is probably responsible. Again, only a few components, all of which may be checked easily, are involved.

The purpose of capacitor $C_1$ is to filter out any a.c. that may reach the input grid. If $C_1$ opens, erratic readings result. If it shorts, any voltage applied to the input of the bridge will be bypassed, and reading will not be possible on any scale.

The d.c. multipliers, shown in Fig. 1, are switched into the circuit when the function switch of the v.t.v.m. is set to read d.c. voltage. In effect, they form a voltage divider that is tapped by the range switch, which applies voltage from the proper tap to the input grid of the bridge circuit. If trouble appears on one or more d.c. ranges but not in other functions, the multipliers may be checked with an ohmmeter for an open or shorted resistor.

**Fig. 1. Switch-tapped string of d.c. multipliers, plus resistor for probe.**




When the meter is set to read d.c., a calibration pot for this function, shown in Fig. 2, is also switched into the circuit in series with the meter by the function switch. If the pot is open, no readings will be possible at all. If the pot changes value appreciably or shorts, calibration will not be possible. The latter procedure consists of adjusting the pot to provide an accurate reading when a d.c. voltage value is applied. Calibration is performed, of course, after zero adjustment has been properly made. Since much switching is done in the d.c. and other functions, the switches themselves may be involved in many faults. The switches will be discussed later.

Although all circuits used for measuring a.c. are roughly similar, there is quite a bit of specific variety among them. The multipliers may be quite similar to those used for d.c. readings. However, Fig. 3 shows a commonly used variation in which the set of multipliers is broken up into two sections with the a.c. rectifier between the sections. The resistors before the rectifier protect this tube against voltages that exceed its ratings, becoming effective in dropping the input voltage, in this case, when it exceeds 150 volts. Multipliers for ranges below this value only are located after the rectifier. Purpose of the rectifier is to convert the a.c. voltage being measured to a d.c. voltage that can be applied to the bridge circuit and meter movement.

There are also several types of rectifier circuits used in v.t.v.m.'s, with the a.c. scales on the meter face calibrated to show equivalent r.m.s. values. The rectifier shown actually measures peak-to-peak voltages. It is a form of voltage doubler that measures the peak values of the positive and negative half-cycles of the input voltage and adds these together. A v.t.v.m. using this rectifier may also have a scale for reading peak-to-peak voltages. The converted r.m.s. scale will be accurate only for sinusoidal a.c. voltages.

Also switched into the circuit along with the a.c. multipliers is the balancing network shown in Fig. 3, con-




Fig. 2. The bridge, heart of the v.t.v.m., and its power supply. The version shown is typical but variations exist.




Fig. 3. The a.c. multipliers and rectifier. The multiplier string is often broken into two sections, as shown, with higher taps ahead of the rectifier to protect it. ▶

sisting of $R_1$, $R_2$, and $R_3$. Due to contact potential, some current will flow through the rectifier even when no voltage is being applied for measurement. Small as this current is (it may be less than a microampere), it flows through the large resistance of the multipliers to ground, and a voltage drop occurs across this divider.

Switching from the input of the multipliers to the grounded end will cause a change in the voltage applied to the input grid of the bridge. This, in turn, causes the meter pointer to move off zero when the a.c. voltage range is changed. To prevent this shift, a small variable voltage is tapped off the power supply to buck out the voltage due to contact potential. There are other methods for counteracting a.c. shift, but they can be identified if we keep in mind the fact that the principle is the same: the voltage due to contact potential must be balanced or bucked out in some fashion.

As with the d.c. multipliers, the a.c. multipliers, whether they appear before or after the rectifier, can be easily checked for open resistors, changes in value, or shorting. Substituting a new rectifier will eliminate the old one as a possible source of trouble.

When the meter is set to read a.c., a calibration pot, as shown in Fig. 2, is also used, but the a.c. calibration pot is not the same as the one used to calibrate d.c. Selection of the proper potentiometer is usually accomplished by the function switch, which also puts the correct set of multipliers in the circuit.

A common fault in the a.c. function that does not exist for others is the inability to obtain a.c. balance. This may be caused by a rectifier whose contact potential is abnormally high, and therefore cannot be bucked out, or a bucking voltage that is too low. Changing the tube and checking the bucking voltage will show where such trouble lies.

The ohmmeter section of the v.t.v.m. is shown in Fig. 4. A battery is used to apply voltage to the string of resistors. A single, 1.5-volt cell is commonly used, although higher voltages are sometimes found. Note that, when the ohmmeter function is not used, the top of the resistor string is not returned to ground. Thus the battery is not loaded and the full 1.5 volts, or whatever battery voltage is used, is available at any tap on the divider. When the meter is set to read ohms, full battery voltage is therefore applied to the input of the bridge on any range, as long as the probe is not connected to the external resistor that is to be measured. To indicate this full voltage, the meter pointer should read full-scale, on ohms, or infinity. The "ohms adjust" pot, which is switched into the position of the calibration pot shown in Fig. 2, is adjusted to give this full-scale reading before any resistance measurement is attempted.

When the external resistor to be measured is connected between the probe and ground, it is in series with one or more resistors in the string (depending on the range chosen), the entire combination appearing across the battery. Thus the external resistor forms a voltage divider with the selected range resistor(s). Since the input of the bridge taps this voltage divider, the drop from full battery voltage will cause the meter pointer to swing down from infinity or full-scale indication in proportion to the resistance being measured. Shorting the probe to ground removes all voltage from the input of the bridge and should produce a zero-resistance reading. This zero adjustment is also checked before resistance readings are attempted.




Fig. 4. The ohmmeter section. Connecting the probe to a resistor to be measured produces a voltage-dividing action that is proportional to the value of the unknown.

Inability to obtain full-scale adjustment generally indicates a weak battery. However, a change in value of a resistor in the string or of the "ohms adjust" pot may also be the cause. No movement of the meter pointer indicates an open condition in one of the resistors or the pot.

Of necessity, the various sections of the v.t.v.m. are chosen or connected together through a series of switches. To simplify the troubleshooting, the switches should also be analyzed. They are best broken down into functional switch sections, without too much regard as to which sections are ganged together on the same switch, so that each section can be considered separately.

Of the five functional sections generally found, one connects the probe to the proper set of multipliers for the type of measurement desired. Another switch section connects the output of the multipliers being used to the input of the bridge. A third section connects the proper calibration or "ohms adjust" potentiometer in series with the meter. This section usually also has a position for reversing the connections to the meter so that negative instead of positive d.c. voltages can be read without changing external probe connections. The sections already mentioned are usually associated with the function selector.

The fourth section selects the proper taps on the a.c. or d.c. voltage multipliers and the fifth chooses the desired tap on the string of "ohms" resistors.

(*Continued on page* 121)

NEW FOR 1960! EXCLUSIVE OFFER

# FREE! CHOOSE any 2 PAKETTES WITH EVERY 12 PAKETTE ORDERS

6 PAKETTE ORDERS — CHOOSE 1 PAKETTE FREE

**6 SUBMINIATURE DIODES** ☐ Germanium & silicon. Only ¼" long. Excellent for transistor circuits. Color coded. Equivalent to 1N34A, 1N48, 1N56, 1N38A, 1N69. Some worth $2 ea. $1

**TRANSISTOR RADIO BASIC** ☐ Incl. transistor & socket, diode, loop-stick. In handy pakette. $1

**2 POWER TRANSISTORS** ☐ Handles 10 watts. For audio circuits in cars, etc. Worth $10 ea. $1

**2 SILICON RECTIFIERS** ☐ 500 mil. Axial leads. Size of 1W resistor. Reg. $3 ea. $1

**8-PC. NUTDRIVER SET** ☐ Molded, lucite handle. Steel socket wrenches. 3/16, 7/32, ¼, 5/16, 11/32, 7/16". In carry case. $1

**10 PANEL SWITCHES** ☐ 115 VAC, micro, slide, etc. Some worth $1.50 ea. $1

**4 OUTPUT XFMRS** ☐ 50L6, 6V6, 6K6, etc. Open frame types. Some worth $2.50 ea. $1

**2 FLEA POWER MOTORS** ☐ 1½ VDC. Powerful. 100's of control uses. $1

**40 TUBE SOCKETS** ☐ 4, 5, 6, 7, 8, 9 pins. Octals, mini types. Some shield, mica, ceramic. Reg. $10. $1

**40 DISC CONDENSERS** ☐ Incl. world's tiniest; only ⅛" x 10mmf to 1000 VDC. $1

**30 "SEALED" CIRCUITS** ☐ Built-in resistor coupling networks. Reg. $20. $1

**40 MOLDED CONDENSERS** ☐ 0.0001 to .1 to 1000 VDC. Oils, porcelain, black beauties. Reg. $30. $1

**65 RESISTOR SPECIAL** ☐ W.W., & carbon, precision, power, variable, mini, types too. ½W to 50W. Reg. $17. $1

**40 POWER RESISTORS** ☐ 5 to 50W to 10,500 ohms. Reg. $15. $1

**80 TRANSISTOR COND.** ☐ Mini condensers. 0.00025 to 0.1 mf. In 100's of trans. sets. Reg. $7. $1

**100 HALF WATTERS** ☐ Resistors: carbon, 10 ohms to 2 meg. 10% tol. Pop'lr makers. Reg. $10. $1

**15 "GRAIN-O-WHEAT"** ☐ Lamps: by G-E. 1.5 VDC. For mini. work. Worth 25¢ ea. $1

**70 MICA CONDENSERS** ☐ 0.00025 to .01 to 1000 VDC. "Silvers" too. 20 values. Reg. $13. $1

**35 TWO WATTERS** ☐ 10 radio & TV values; 100 ohms to 500K. 5% too. Reg. $8. $1

**15 ROTARY SWITCHES** ☐ 1, 2, 3 gang; long shafts, Pop'lr types. Reg. $15. $1

**15 VOLUME CONTROLS** ☐ Long & useable shafts. Up to 1 meg. Singles, duals, switch types. Reg. $20. $1

**2 SOLAR BATTERIES** ☐ Generates power from Sun & "bulb" light. 100's of projects. Reg. $4. $1

**20 TWIST DRILLS** ☐ 1/16 thru ¼" with calibrated case. For electric drills. Reg. $2.50. $1

**24 ARTISTS BRUSHES** ☐ 1 to 6 sizes. 100% pure camel hair bristles. $1

**40 HI Q CONDENSERS** ☐ NPO's, standoff types too. 20 values. Finest porc. prec. quality. Reg. $9. $1

**Free! Write for Giant Bargain Catalog**

**15 "POLY PAKETTES"** ☐ Incl. poly boxes, vials, asst. sizes. For radio, TV submini parts. $1

**15 ELECTROLYTICS** ☐ FF & tubular paper & can types. Single, duals & triple values. 10 to 500 mf to 450 VDC. Reg. $20. $1

**100 CERAMIC SPECIAL** ☐ Incl. discs, NPO's, moldeds, tubulars, dog bones. 25 values. $1

**75 ONE WATTERS** ☐ Resistors incl. 1 & 5% carbons. 30 popular values. Reg. $18. $1

**2 POSTAGE STAMP MIKE** ☐ Crystal. By Brush. 1" sq. Nifty, hide-away unit. 100 to 7000 cps response. $1

**70 COILS & CHOKES** ☐ RF, ant. osc., slug-tuned, & IF styles. 15 types. Reg. $22. $1

**60 PLUGS & REC'T'LS** ☐ Power, battery, audio: 15 types. $1

**15 POLY VIALS** ☐ For stocking submini & transistor parts, F-Z to see, to read, to "stack." Asst. sizes. $1

**CRYSTAL PHONE** ☐ Use as mike too! W/cord & plug set. Hearing aid type. 100 to 6000 cps resp. $1

**60 TERMINAL STRIPS** ☐ Solder lug type; 0.1 to 10 lugs. Used in every elec. proj. $1

**925 SURPRISE PAKETTE** ☐ Wide variety of radio 'n popular electronic parts. $1

**70 TUBULAR CONDENSERS** ☐ 20 values 0.0001 to .5 mfd to 1000 VDC. Reg. $10. $1

**30 "SILVER" MICAS** ☐ 1 & 5%. Asst. values. Finest made. $1

**70 INSULATED RESIST'S** ☐ Carbon, 1 & 5% too! 10 ohms to 10 meg. 30 values. ½, 1, 2W. Reg. $15. $1

**10 RCA PLUG 'N JACK SETS** ☐ Matched pairs. For tuners, amps, recorders. $1

**300-FT. HOOK-UP WIRE** ☐ 16 thru 24. Plastic, glass, insulated. Asst. colors. Tinned. $1

**60 RADIO-TV KNOBS** ☐ Asst. colors, set screw type too! Plastic ½" to 4" dia. Some $1 ea. $1

**50 ONE PERCENT-ERS** ☐ Precision carbo-film resistors. Nifty lab case. 15 values, 100 ohms to 1 meg. Reg. $26. $1

**60 CONDENSER SPECIAL** ☐ Incl. molded, porcelain, oils, electrolytic mica, disc. Reg. $15. $1

**3 ROLLS MICRO-WIRE** ☐ #24 to #32. Asst. colors; insulation. Tinned. Reg. $5. $1

**1500 PCS HARDWARE** ☐ Nuts, bolts, screws, brackets, etc. Handy shop pakette. $1

**3 HOBBY TRANSISTORS** ☐ For experimental & shop use. Specs unknown. Worth $3 ea. $1

**WORLD'S SMALLEST RADIO** ☐ Kit. Germanium powered. Lasts for life. Incl. all parts, instructions. $1

**12 GERMANIUM DIODES** ☐ For radio & TV detectors, limiters, rectifiers. Glass sealed, long leads. $1

**125 RESISTORS** ☐ Non-insulated, 30 popular values; ½, 1, 2W. 5% too. 10 ohms to 10 megs. Reg. $15. $1

**10-IN-1 PAKETTE** ☐ Incl. diodes, resistors, electros, sockets, lites, wire, knobs, v-controls, strips, condensers. $1

**NEW! 20-in-1 PAKETTE**

Introductory Special! Carbons, wirewounds, volume control, precision condensers, electros, ceramics, micas, paper, discs, hi-Q, moldeds, oils, variables, wire, switches, transistor, diodes, sockets, tie strips, coils; in handy PAKETTE. Satisfaction guaranteed.... **$2.00**

**Minimum Order $2.00** down; rated, not 30 days. Include check or M.O. with sufficient postage; excess returned. C.O.D. orders, 25% address. (Canada postage, 48¢ 1st lb.; 28¢ ea. additional lb.) INCLUDE POSTAL ZONE in

My FREE Pakettes are
1. .....
2. .....

- Check each item wanted
- Return ad with order
- Avg. wt. 1 lb. per Pakette
- Each Pakette guaranteed

CLIP 'N' MAIL—USE AS ORD-A-GRAM

**LEKTRON** 133 Everett Ave. CHELSEA 50, MASS.


# New Tube Tester Data

**Additional listings for the charts of five Sylvania tube testers: Models 137, 139, 140, 212, and 220.**

## MODELS 137, 139, AND 140

| TYPE | A | B | C | D | E | F | G | TEST |
|---|---|---|---|---|---|---|---|---|
| 6EM5 | 6.3 | 0 | 4 | 0 | 4 | 026 | 23 | Y |
| | 6.3 | 0 | 6 | 0 | 4 | 024 | 23 | Y |
| 6EW6 | 6.3 | 0 | — | 0 | 4 | 36 | 32 | V |
| 12AF3 | 12.6 | 0 | 3 | 0 | 4 | — | 17 | Y |
| 12DS7 | 12.6 | 0 | — | 0 | 3 | 67 | 37 | X |
| | 12.6 | 0 | — | 0 | 1 | — | 84 | T |
| | 12.6 | 0 | — | 0 | 4 | — | 84 | T |
| 12DT5 | 12.6 | 0 | 4 | 0 | 4 | 026 | 24 | Y |
| | 12.6 | 0 | 6 | 0 | 4 | 024 | 24 | Y |
| 12DV7 | 12.6 | 0 | 5 | 0 | 3 | 7 | 76 | T |
| | 12.6 | 0 | 5 | 0 | 2 | — | 63 | X |
| | 12.6 | 0 | 5 | 0 | 5 | — | 63 | X |
| | | | | Special Test | | | | |
| 12ED5 | 12.6 | 0 | 5 | 0 | 3 | 26 | 20 | X |
| | 12.6 | 0 | 2 | 0 | 3 | 56 | 20 | X |
| 17DE4 | 12.6 | 0 | 7 | 1 | 3 | — | 17 | Y |
| 18FW6 | 12.6 | 0 | — | 0 | 4 | 36 | 33 | W |
| 18FX6 | 12.6 | 0 | — | 0 | 5 | 3 | 59 | X |
| | 12.6 | 0 | — | 0 | 4 | 64 | 33 | V |
| 18FY6 | 12.6 | 0 | — | 0 | 3 | 3 | 47 | T |
| | 12.6 | 0 | — | 0 | 4 | — | 55 | T |
| | 12.6 | 0 | — | 0 | 5 | — | 55 | T |
| 32ET5 | 35 | 0 | 5 | 0 | 3 | 26 | 24 | Y |
| | 35 | 0 | 2 | 0 | 3 | 56 | 24 | Y |
| 36AM3 | 35 | 0 | 6 | 0 | 4 | — | 18 | Y |
| | 35 | 0 | 6 | 2 | 4 | — | 18 | Y |
| 7199 | 6.3 | 0 | — | 0 | 2 | 067 | 64 | W |
| | 6.3 | 0 | — | 0 | 1 | 5 | 20 | W |

## MODELS 212 AND 220

| TYPE | A | B | C | D | E | F | G | K |
|---|---|---|---|---|---|---|---|---|
| 6EM5 | 6.3 | 4 | 56 | 17 | 5 | 013Z | 9 | 7 |
| | 6.3 | 4 | 35 | 17 | 5 | 016Z | 9 | 7 |
| 6EW6 | 6.3 | 3 | 4 | 67 | 4 | 16SU | 5 | 2 |
| 12AF3 | 12.6 | 4 | 25 | 12 | 4 | Z | 9 | 1 |
| | | | | Use External Adapter | | | | |
| 12DS7 | 12.6 | 4 | 5 | 25 | 5 | 37SU | 6 | 8 |
| | 12.6 | 4 | 5 | 39 | 5 | T | 1 | 8 |
| | 12.6 | 4 | 5 | 39 | 5 | T | 9 | 8 |
| 12DT5 | 12.6 | 4 | 56 | 19 | 5 | 013Z | 9 | 7 |
| | 12.6 | 4 | 35 | 19 | 5 | 016Z | 9 | 7 |
| 12DV7 | 12.6 | 4 | 159 | 37 | 5 | 7T | 6 | 8 |
| | 12.6 | 4 | 589 | 44 | 5 | T | 2* | 1 |
| | 12.6 | 4 | 589 | 44 | 5 | T | 3* | 1 |
| 12ED5 | 12.6 | 3 | 45 | 15 | 4 | 26V | 7 | 1 |
| | 12.6 | 3 | 24 | 15 | 4 | 56V | 7 | 1 |
| 17DE4 | 19.0 | 7 | 8 | 11 | 8 | Z | 5 | 3 |
| 18FW6 | 19.0 | 3 | 4 | 45 | 4 | 16Z | 5 | 7 |
| 18FX6 | 19.0 | 3 | 4 | 40 | 4 | 067T | 5 | 2 |
| | 19.0 | 3 | 4 | 30 | 4 | 1X | 6 | 2 |
| 18FY6 | 19.0 | 3 | 4 | 35 | 4 | 1T | 7 | 2 |
| | 19.0 | 3 | 4 | 40 | 4 | T | 6* | 2 |
| | 19.0 | 3 | 4 | 40 | 4 | T | 5* | 2 |
| 32ET5 | 35.0 | 3 | 24 | 18 | 4 | 56Z | 7 | 1 |
| | 35.0 | 3 | 54 | 18 | 4 | 26Z | 7 | 1 |
| 36AM3 | 35.0 | 3 | 46 | 12 | 4 | Z | 5* | 7 |
| | 35.0 | 3 | 46 | 12 | 6 | Z | 5* | 7 |
| 7199 | 6.3 | 4 | 58S | 50 | 5 | 037Z | 2 | 6 |
| | 6.3 | 4 | 56 | 15 | 5 | 9Y | 1 | 8 |

ANOTHER WAY RCA SERVES EDUCATION THROUGH ELEC-TRONICS

# LET RCA TRAIN YOU IN ELECTRONICS

*RCA Institutes, one of the leading technical institutes in the United States devoted exclusively to electronics, offers a Home Study Course in . . .*

## *ELECTRONICS FOR AUTOMATION*

. . . Now you have four comprehensive courses for your electronic training . . . from basic electronic theory to the more advanced principles of color TV and Automation.




Practical work with your very first lesson. Pay as you learn. You need pay for only one study group at a time.

**Send for our 64 page Home Study Catalog**

**FREE!**




CANADIANS — take advantage of these same RCA Courses at no additional cost. No postage, no customs, no delay. Send coupon to:
**RCA Victor Company, Ltd., 5001 Cote de Liesse Rd., Montreal 9, Quebec**

SEE OTHER SIDE

**CUT OUT AND MAIL THIS POSTAGE-FREE CARD TODAY!**

## RCA INSTITUTES, INC.

*A Service of Radio Corporation of America*

Without obligation, please send me the FREE catalog checked below. No salesman will call.

☐ Home Study Catalog ☐ Resident School Catalog

NAME ..... AGE.....
(Please Print)

ADDRESS .....

CITY..... ZONE.... STATE.....

KOREAN VETS! ENTER DISCHARGE DATE.....

HOME STUDY SCHOOL

# 6 REASONS WHY RCA TRAINING IN ELECTRONICS

## can be the smartest investment you'll make in your *entire lifetime!*

1. **You get the finest training-at-home** under the supervision of the RCA Institutes, experts in technical training for over 50 years. The very name "RCA" means dependability, integrity, and scientific advance.
2. **You get comprehensive training** in your choice of four complete, up-to-date Courses . . . from basic electronics theory to color TV and Automation.
3. **You get an evaluation of your aptitude** for advanced training. RCA determines, for your benefit, whether you have the requirements for a career in the electronics field.
4. **You get prime quality equipment** as a regular part of your Course . . . equipment that you keep and use on the job. You never have to take apart one piece to build another.
5. **You get each study group on a pay-as-you-go basis.** Should you wish to interrupt your training at any time, you will not owe RCA Institutes a penny more, unless and until you decide to resume the course.
6. **You get top recognition — worldwide.** Graduates of RCA Institutes are now working for leaders in the electronics field, and many have their own businesses. This record is true tribute to the high quality of RCA Institutes training.

Fill in the other side of this postage-free card for complete information on Home Study courses.

RESIDENT SCHOOL

# LET RCA TRAIN YOU IN ADVANCED ELECTRONICS

Here is college-level training that will enable you to work with professional engineers on research or production projects in fields such as automation, guided missiles, radar, television, computers, and other advanced electronic applications. Other courses available include TV and General Electronics, Radio & TV Servicing, and Technical Writing. Thousands of Resident School graduates are today engaged in important government or industrial projects. Now is the time to prepare yourself for a promising new career.

Coeducational classes start 4 times each year. Applications now being accepted. Approved for veterans. Convenient New York City location.

SEE OTHER SIDE

First Class
U.S. Postage
**PAID**
Permit No. 10662
New York, N. Y.

**BUSINESS REPLY CARD**
No Postage Stamp Necessary if Mailed in U. S.

Postage will be paid by —

**RCA INSTITUTES, INC., DEPT. E.W.-20**
350 West Fourth Street
New York 14, N. Y.

**Send for this FREE catalog today! Fill in other side of postage-free card and check Resident School.**

**RCA INSTITUTES, INC.**
SCHOOLS OF TELEVISION
AND ELECTRONIC TECHNOLOGY
*A Service of Radio Corporation of America*

## Troubleshoot Your V.T.V.M.

(*Continued from page* 117)

These sections are associated with the range switch.

The principal problems in which switches become involved are leakage and dirty or worn contacts. Dirty or worn contacts can generally be detected by visual inspection, with the large number of contacts involved in all switch sections being the chief difficulty to this check. However, the technique of isolating a defect to a particular portion of the v.t.v.m. circuit, already described, reduces the number of contacts to be inspected to a reasonably small number. With this narrowing down, it is relatively simple to check the few contacts that may be involved. Conventional methods for cleaning or repairing a contact or contacts thus found to be faulty may then be followed.

As for leakage through switch sections in the voltage-measuring functions, a comparison v.t.v.m. known to be good and a source of fairly high voltage can be used. A thousand volts, or as close t• it as may be obtained, should be used. The v.t.v.m. known to be operating properly is connected across the voltage source, and the reading is noted. This meter is left connected and the v.t.v.m. suspected of leakage is then connected across the source in addition. If this causes a significant drop in the voltage reading on the v.t.v.m. known to be good, then excessive loading by the suspected instrument is probable, and a leaky or shorted switch is the likeliest cause.

This still leaves several switch sections probably involved, but further localization is possible: the input to the range switch on the suspect unit is clipped off and the test is repeated. If the loading effect is still noted, the function switch should be investigated for leakage; if the loading effect disappears, the range switch is probably at fault.

Calibration of a v.t.v.m. may be performed with sufficient accuracy by using materials generally available in every service shop. The filament transformer of a tube checker is an excellent source of variable a.c. voltage. Fresh batteries offer an accurate source of d.c. If multiplier resistors are correct in value, calibration on one range should be enough to bring the instrument up to tolerance on all ranges.

For troubleshooting purposes, the basic philosophy has already been stated: isolation to a specific section is essential in that it reduces the components possibly involved to a small enough number so that they may be individually checked without much inconvenience. This, plus a general understanding of the instrument's circuitry, is sufficient to enable the rapid and fairly simple detection and correction of the faults most likely to be encountered. —30—


IMMEDIATE "IN STOCK" SHIPMENT
from "the house the hams built" . . . the
CITIZENS BROADCASTER CB-100

NO CODE!
NO TESTS!
NO EXAMS!

★ TOP TRADE-INS
★ PERSONALIZED SERVICE
★ FAST SHIPMENT FROM THE CENTER OF THE U.S.A.

low cost, smartly styled, practical and sturdy 2-way 3-channel Radio Station complete *

ONLY $129.95
$13.00 down
$7.60 per mo.

*with microphone and crystals for one channel

FREE 1960 CATALOG
200 Pages - Hundreds of Bargains for the Ham.

FCC FORM 505 FOR STATION LICENSE SUPPLIED

send for FREE DETAILED BROCHURE TODAY

WORLD'S MOST PERSONALIZED RADIO SUPPLY HOUSE
World Radio LABORATORIES
PH 2-0277
3415 W BROADWAY · COUNCIL BLUFFS IA

Please send me Free Catalog . . . and complete info on the CB-100. EW-2
Name: _____
Address: _____
City & State: _____

NOW EVERY CITIZEN CAN HAVE
TWO WAY RADIO

• CAR
• OFFICE
• HOME
• BOAT

$99.95 MODEL 905

COMPLETE WITH CRYSTAL FOR 1 CHANNEL & MICROPHONE

FEATURING
• 5 CHANNEL TRANSMITTER
• 22 CHANNEL RECEIVER
• 2-10 MILE RANGE
• PRESS-TO-TALK MIKE
• COMPACT, MODERN STYLING

WRITE FOR FREE BROCHURE

RAY JEFFERSON, INC.
Manufacturers Communications Equipment
40 E. MERRICK RD. FREEPORT, N. Y.
Please rush me your brochure describing the model 905 Citizens Band Radio.
NAME .....
ADDRESS .....
CITY ..... STATE .....

EXCLUSIVE DISTRIBUTOR for LINK RADIO CORP.
All parts for present & past equipment available.



SPECIAL!
UNIVERSAL 6/12 VOLT VIBRATOR POWER SUPPLY WIRED, Mfg. by DUMONT. Rating 300 V. @ 100 mill. Ideal for all types of mobile applications. Chassis measures 3¼"x5¼"x8" Brand New..... $11.95

MOBILE RADIO EQUIPMENT



2 PIECE MODEL FMTR 30-50 MC ED. 7 FM MOBILE TRANS. & REC.—6 VOLTS
Unit complete with Peak Modulation control head, mike, antenna, cables & crystals ground to your specific frequency. Modified for 20F3 emission..... $109.95
MODEL FMTR—12V. operation.....$149.95

MODEL 2210 152-162 MC FM MOBILE TRANSMITTER & RECEIVER—6 VOLTS
Trans. modified in accordance with latest FCC Reg. for 20F3 emission. Complete with antenna, cables, control head, mike & crystals ground to your specific frequency. Ready for immediate installation. Specially priced..... $139.50
MODEL 2210—12V. operation.....$162.50

MODEL 50 UFS 60 WATT 30-50 MC BASE STATION
Housed in a 34" upright cabinet, modified for 20F3 emission. Operates on 110AC. Reconditioned, checked out..... $249.50

Include 25% deposit with order—balance COD. 50¢ handling charge on all orders under $5.00. All shipments FOB our warehouse, NYC.

PLATT ELECTRONICS CORP.
20 MURRAY ST., NEW YORK 7, N. Y.
Telephone: COrtlandt 7-2575

## RADIO SHACK *flash!*

Send Coupon for *Latest*

**FREE**

**ELECTRONICS Catalog**

plus every new issue for 1960

Act today! See the newest, the best, the most complete line of electronic equipment in America—stereo, hi-fi, ham radio, LP records, tapes, optical goods and scores of others. Over 100,000 items—everything for the amateur, the pro, the devotee or just the interested.

Mail the coupon now! We will send you immediately, Free and Postpaid, not only our latest 312 page Electronics Catalog but every new issue for the next 12 months—a full year's Free subscription to the finest in electronics and associated products all at famous money-saving Radio Shack prices. Satisfaction guaranteed on every order or your money back. Invest in the best—and save money too—shop at Radio Shack.

**Just one** of thousands of **RADIO SHACK buys**

**Transistor Battery Radio 19.95 Value only**

**$9.95**

Exclusive Radio Shack transistor battery radio. Only 2⅝x4x1¼ inches in size. Weighs less than 10 ounces. Built-in speaker and ferrite antenna. Conelrad markings, handsome molded case.

**RADIO SHACK**
**CORPORATION DEPT. 6086**
**730 Commonwealth Ave. • Boston 17, Massachusetts**

**Radio Shack Corporation Dept. 6086**
**730 Commonwealth Ave.**
**Boston 17, Massachusetts**

Please send me, FREE and POSTPAID, your latest Electronics Catalog. Also send me every new issue for the next 12 months—a full year's subscription FREE.

Name_____

Address_____

Postoffice or City_____ Zone____ State_____


# New Audio Test Report

LAB TESTED ELECTRONICS WORLD

## "KNIGHT" SHELF-TYPE SPEAKER SYSTEM

THE advent of stereo has brought with it a rash of shelf-type or bookshelf speaker systems. The compactness of these systems makes it very convenient to tuck away a pair of the units in a moderately sized listening room. The big problem with a compact enclosure has been its performance compared to a larger, more space-consuming enclosure. Much effort has been expended by manufacturers in getting the maximum possible quality of reproduction from these compact units—and with various degrees of success. The better systems use specially designed loudspeakers in acoustically matched enclosures. The best results obtainable compare quite favorably with many larger systems, some of which may not represent an optimum design.

A recent entry in the field of shelf-type speaker systems is *Allied Radio's* "Knight" KN-3000 shown here. In its 2-cubic foot volume, there is a special high-compliance 12-inch woofer along with two Janszen-designed push-pull electrostatic radiators. The radiators are each 6 inches square and are capable of producing useful output from 700-1000 cps up to the upper frequency limit of human hearing. In this system, the crossover frequency is around 2000 cps. The two high-frequency units are mounted in such a way as to improve the high-frequency dispersion of the system.

The special woofer, with its ceramic magnet, uses die-cast aluminum rings to weight the apex of the cone. Because of the increased mass and high compliance, the resonant frequency of the unmounted woofer is only about 25 cps. When mounted in its 2-cubic foot enclosure, this resonance rises to about 55 cps.

The enclosure itself, measuring 26½" wide by 14" high by 13" deep, is made of ¾" stock, finished on four sides so that it can be used either horizontally or vertically. No ducts or ports are employed and the cabinet is lined on three sides with half-inch fiberglass. Mounted inside the enclosure on the back panel is the crossover network and the 1100-volt power supply for the electrostatic speakers (see diagram below). No high-frequency level control is provided as this would upset the impedance characteristics of the system. Instead the outputs of both high- and low-frequency sections have been matched for flattest response. Any desired adjustments can be made easily with the amplifier tone controls.

Fig. 1. Schematic diagram of the crossover network and 1100-volt power supply for the electrostatic radiators in system.




The over-all acoustic response of the system was measured (on axis) in an anechoic room and it was found to be within about ±3 db from 47 cps to around 10 kc. (except for a narrow dip just above 7 kc.) with respect to a common reference level. Measurements taken about 15 degrees off axis showed high-frequency response within ±3 db out to about 17 kc. Actual low-frequency performance of the system would be even better when used near a room wall or particularly in a live corner. Also, listening in a live room and at various positions would result in substantial output up to and beyond 20 kc. High-frequency distortion measurements were also taken and a comparison was made with a high-quality 8-inch cone speaker. The latter had a total harmonic distortion ranging from 1.8 to 5.6 per-cent in the frequency range 1000 to 10,000 cps. A single unselected electrostatic radiator was checked and distortion ranged from .16 to .5 per-cent in the same frequency range. These measurements were taken at a power input level of 3 watts, although the KN-3000 will readily handle 50 watts of musical program material.

A listening test of the new system disclosed the clean, transparent upper mid-range and highs associated with high-quality electrostatic speakers. The bass may be a little thin for some ears unless the system is placed in a corner. In general, the over-all per-

*your best buy . . .*

# TRU-VAC®



## REMARKABLE TUBE VALUES AT 1950 PRICES

**ALL TUBES INDIVIDUALLY BOXED, CODE DATED AND BRANDED "TRU-VAC®"**

Typical TRU-VAC® Bargains!

**THIS IS A PARTIAL LIST** — Thousands More Always In Stock

6SN7GT ..... ALWAYS 30c

6W4GT ..... ALWAYS 30c

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| OY4 | 3AU6 | 6A6 | 6B8 | 6CH8 | 6S7 | 7B4 | 12AT6 | 12SA7 | 36 |
| OZ4 | 3BC5 | 6AB4 | 6BA6 | 6CL6 | 6S8GT | 7B5 | 12AT7 | 12SJ7 | 38 |
| 1A7GT | 3BN6 | 6AC7 | 6BC5 | 6CM6 | 6SA7 | 7B6 | 12AU6 | 12SK7 | 39/44 |
| 1B3GT | 3BZ6 | 6AF4 | 6BC8 | 6CM7 | 6SD7GT | 7B7 | 12AU7 | 12SN7GT | 41 |
| 1C6 | 3CB6 | 6AG5 | 6BD6 | 6CN7 | 6SF5 | 7B8 | 12AV6 | 12SQ7 | 42 |
| 1C7 | 3Q4 | 6AH4GT | 6BE6 | 6CQ8 | 6SF7 | 7C4 | 12AV7 | 12V6GT | 43 |
| 1F4 | 3S4 | 6AH6 | 6BF5 | 6CR6 | 6SG7 | 7C5 | 12AX4GT | 12W6GT | 45 |
| 1F5 | 3V4 | 6AK5 | 6BG6G | 6CS6 | 6SH7 | 7C6 | 12AX7 | 12X4 | 50A5 |
| 1G4 | 4BQ7A | 6AL5 | 6BH6 | 6CU5 | 6SJ7 | 7C7 | 12AZ7 | 14A7/12B7 | 50B5 |
| 1H5GT | 4B58 | 6AM8 | 6BJ6 | 6CU6 | 6SK7 | 7E5 | 12B4 | 1486 | 50C5 |
| 1L4 | 4BZ7 | 6AN8 | 6BK5 | 6D6 | 6SL7 | 7E6 | 12BA6 | 14Q7 | 50L6 |
| 1L6 | 4CB6 | 6AQ5 | 6BK7 | 6DE6 | 6SQ7 | 7E7 | 12BA7 | 19 | 56 |
| 1N5GT | 5AM8 | 6AQ6 | 6BL7GT | 6DG6GT | 6SR7 | 7F7 | 12BD6 | 19AU4GT | 57 |
| 1R5 | 5AN8 | 6AQ7 | 6BN6 | 6DQ6 | 6T4 | 7F8 | 12BE6 | 19BG6G | 58 |
| 1S5 | 5AT8 | 6AR5 | 6BQ6GT | 6F5 | 6U8 | 7G7 | 12BF6 | 19J6 | 71A |
| 1T4 | 5AV8 | 6AS5 | 6BQ7 | 6F6 | 6V6GT | 7H7 | 12BH7 | 19T8 | 75 |
| 1U4 | 5AZ4 | 6AT6 | 6BR8 | 6H6 | 6W6GT | 7N7 | 12BQ6 | 24A | 76 |
| 1U5 | 5BR8 | 6AU4GT | 6BS8 | 6J4 | 6X4 | 7Q7 | 12BR7 | 25Z6GT | 77 |
| 1V2 | 5J6 | 6AU5GT | 6BY5G | 6J5 | 6X5GT | 7S7 | 12BY7 | 26 | 78 |
| 1X2 | 5R4 | 6AU6 | 6BZ6 | 6J6 | 6X8 | 7X6 | 12CA5 | 27 | 80 |
| 2AF4 | 5U4 | 6AU8 | 6BZ7 | 6J7 | 6Y6G | 7X7 | 12CN5 | 35 | 84/6Z4 |
| 2BN4 | 5U8 | 6AV5GT | 6C4 | 6K6GT | 7A4/XXL | 7Y4 | 12D4 | 35A5 | 117Z3 |
| 2CY5 | 5V4G | 6AV6 | 6CB6 | 6K7 | 7A5 | 7Z4 | 12F5 | 35B5 | |
| 3A4 | 5V6GT | 6AW8 | 6CD6G | 6N7 | 7A6 | 12A8 | 12K7 | 35C5 | |
| 3A5 | 5X8 | 6AX4GT | 6CF6 | 6Q7 | 7A7 | 12AB5 | 12L6 | 35W4 | |
| 3AL5 | 5Y3 | 6AX5GT | 6CG7 | 6S4 | 7A8 | 12AQ5 | 12Q7 | 35Z5 | |

## 35¢ ea.

## $33 PER HUNDRED

## For any used or factory second tube!

### 1 YEAR GUARANTEED PICTURE TUBES

Brand New* — Allied A-1 Tubes — Brand New

**Below Listed prices do not include dud. Add Additional $5.00 Deposit on tube sizes to 20"; on 21" and 24" tubes - $7.50. Deposit refunded immediately when dud is returned prepaid. Aluminized tubes - $4.00 extra.**

**Picture tubes shipped only to continental USA and Canada — All tubes F.O.B. Harrison, N. J.**

| | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 10BP4 | 7.99 | 16HP4 | 12.19 | 17CP4 | 16.99 | 19AP4 | 18.39 | 21AYP4 | 18.79 | 21FP4 | 18.39 | 21YP4 | 18.39 |
| 12LP4 | 10.49 | 16KP4 | 11.99 | 17GP4 | 17.89 | 20CP4 | 15.89 | 21AMP4 | 17.99 | 21KP4 | 18.39 | 21ZP4 | 17.49 |
| 14B/CP4 | 11.99 | 16LP4 | 12.19 | 17MP4 | 16.99 | 20DP4 | 15.89 | 21AU4 | 18.79 | 21MP4 | 22.39 | 24AP4 | 39.49 |
| 16AD4 | 16.09 | 16RP4 | 11.99 | 17VP4 | 16.99 | 20HP4 | 17.89 | 21AV9P4 | 18.79 | 21VP4 | 18.39 | 24CP4 | 27.79 |
| 16BP4 | 12.19 | 17AVP4 | 15.49 | 17QP4 | 13.89 | 21AP4 | 21.49 | 21AW9P4 | 17.49 | 21WP4 | 17.49 | 24DP4 | 29.79 |
| 16GP4 | 16.09 | 17BP4 | 13.49 | 17TP4 | 16.99 | 21ALP4 | 18.79 | 21EP4 | 17.29 | 21XP4 | 17.49 | | |

**ATTENTION!**

Get More For Your Money . . . Get Quality And Bigger Selection . . . Get Truly Remarkable Tube Values When You Buy At TRU-VAC

**FREE FUSE CLIP!**

Sent With Any Order Of $5 Or More

**GUARANTEE**

Only TRU-VAC guarantees to replace free any tube which becomes defective in use within one year of date of purchase.

**USED TV CONSOLES**

GUARANTEED To Work When You Receive Them

| | |
|---|---|
| 10" & 12" | $29 |
| 14" & 16" | $37 |
| 17" | $45 |
| 19" | $59 |
| 20" & 21" | $70 |

All sets shipped in two cartons to avoid breakage. Sets shipped express to continental U.S.A. and Canada only. F.O.B. Harrison, New Jersey.

**FREE BONUS—RABBIT EARS**

$7.95 Value

FREE with each set purchased

**ATTENTION QUANTITY USERS!**

Big Discounts Are Yours . . . Call or Write For Our 1000 Tube "Private Label" Special! Attention Branding Dept. MGR.

**MONEY CHEERFULLY REFUNDED WITHIN FIVE (5) DAYS, IF NOT COMPLETELY SATISFIED!**

**TRU-VAC® PAYS YOUR POSTAGE**

On orders of $5 or more in U.S.A. and Territories. Send approximate postage on Canadian and foreign orders. Any order less than $5 requires 25c handling charge. Send 25% on C.O.D.'s. All orders subject to prior sale.

Complying with Federal regulations, the following statement appears in all Tru-Vac advertising: Tubes appearing in this ad may be FACTORY SECONDS or USED tubes and are clearly marked.

Write Dept. L For FREE LIST Of Other Tube Types and Products Sold By TRU-VAC®

# TRU-VAC® Electric Company

Harrison Avenue Box 107 Harrison, New Jersey

HUmboldt 4-9770

Visit Our Huge Testing Dept. In The Heart Of Harrison, N. J.'s Electronics Industry

**These men are getting practical training in...**

**Train in *NEW* Shop-Labs of**

# COYNE

**In Chicago—Electrical and Electronic Center of the World.** Prepare for a better job and a successful future in a TOP OPPORTUNITY FIELD. Train on real full size equipment at COYNE where thousands of successful men have trained for 60 years—*largest, oldest, best equipped school of its kind.* Professional and experienced instructors show you how, then do practical jobs yourself on more than a quarter of a million dollars worth of equipment. No previous experience or advanced education needed. Employment Service to Graduates.

**Start Now—Pay Later**—Liberal Finance and Payment Plans. Pay most of tuition after graduation. Part-time employment help for students. Choose from nine yearly Starting Dates.

**Mail Coupon or Write to Address Below for Free Book**—"*Guide to Careers.*" Whether you prefer ELECTRICITY, TELEVISION-RADIO or COMBINED ELECTRONICS, which includes both fields, this book describes all training offered.

***Information comes by mail. No obligation and NO SALESMAN WILL CALL.***

B. W. Cooke, Jr., Pres. Founded 1899

**COYNE ELECTRICAL SCHOOL**

*Chartered as an Educational Institution Not For Profit*

1501 W. Congress Pkwy., Chicago 7, Ill., Dept. 20-6C

**MAIL COUPON** OR WRITE TO ADDRESS BELOW

**COYNE ELECTRICAL SCHOOL**
**New Coyne Building Dept. 20-6C**
**1501 W. Congress Pkwy., Chicago 7, Ill.**

Send BIG FREE book and details of all the training you offer. I am especially interested in,

☐ Electricity ☐ Television ☐ Both Fields

Name_____

Address_____

City_____ State_____

*(I understand no Salesman will call)*


formance of the two-way system, which costs $129.50, is good with a minimum amount of tone coloration and a maximum amount of presence.

## DUAL 4-WATT STEREO AMPLIFIER KIT

ONE of the simplest of all integrated stereo amplifiers that we have seen to date is *EICO's* Model AF-4. Not only is the design and construction simple, but it provides about the lowest power output, 4 watts per channel, that is available in component design. The unit consists of two single-ended amplifiers with 27 db of negative feedback in each channel.

Neither we nor the manufacturer refer to this unit as a truly high-fidelity design, but it does provide a good quality of reproduction for its price. It is ideal for the youngster, for the novice kit builder, or for the economy minded.

It features separate stereo pairs of inputs for ceramic or crystal cartridges and stereo tape. Note that this unit is not sensitive enough for use with magnetic cartridges. Inputs are also provided for AM and FM tuners and an FM multiplex adapter. In addition to these features, it also includes a switch to parallel both power amplifiers to provide 8 watts output. A separate power amplifier could then be used to drive a second stereo speaker system.

Our lab results are as follows:

*Sensitivity:* (for 4 watts output at 1000 cps). Crystal and all low-gain circuits, .113 volt; ceramic input, .275 volt.

*Frequency response:* + 1 db, −0 db




Response curve of the EICO Model AF-4 stereo amplifier. The unit is rated 4 watts power output per channel and is designed for those not requiring true hi-fi.




Schematic diagram of the AF-4 dual stereo amplifier. The conventional power circuit, using an EZ-81 full-wave rectifier tube, is omitted.

The AF-4 4-watt stereo amplifier.

from 30 to 15,000 cycles per second.

*Bass control:* In view of circuit simplification, only bass attenuation is provided, −11.7 db at 30 cps.

*Treble control:* Only treble attenuation is provided, −15 db at 15 kc.

*Loudness control:* Although no separate loudness control is provided, the design incorporates a loudness control circuit that provides about 6 to 8 db bass boost at low levels.

*Harmonic distortion:* To conform to the standards set up by the Institute of High Fidelity Manufacturers, we have included power output curves taken at 1% and 2% total harmonic distortion. Note that these are power response measurements and do not represent the frequency response of the unit. The input signal was not kept constant but adjusted to produce a constant level of distortion in the amplifier output.

Another standard set up by the Institute is that of power-bandwidth taken at the −3 db points. This amplifier could be rated as a 4.2-watt unit at 2% distortion from about 62 cps to 13 kc. It could also be rated as a 3.9-watt unit at 1% distortion from about 85 cps to 12 kc.

*Channel separation:* At 1000 cps, 37 db.

*Hum:* (from 2 watts output). All low-gain circuits, −61 db for shorted input and −46 db for open-circuit input; ceramic input, −46 db for shorted input and −36 db for open-circuit input.

*IM distortion:* The Institute of High Fidelity Manufacturers has omitted, at least for the time being, IM distortion measurements from its new standard on amplifiers. There is a legitimate reason for this as can be seen in this example. On this particular unit the IM distortion measured at 2 watts was 4.4% and at 3 watts it was 13.2%. These figures are extremely high compared to the 1% figure which we have used as our standard in the past. The figures obtained in this case are not truly indicative of IM distortion alone, however.

In view of the reduced bass response of this amplifier, the IM distortion characteristic, when using 60 and 6000 cps at a 4:1 ratio, is found to be abnormally high as it combines the effect of the amplifier's low bass response. If we had used 100 and, say, 5000 cps the IM distortion measurement would have been more reasonable.

The price of the unit is $38.95 in kit form and $64.95 wired. —30—

**BUY . . . LEASE . . . RENT**

The **EDCO** equipment can be bought outright, we will supply equipment to you on a 2 year lease purchase plan, or the equipment can be rented by the month.

Enjoy the many advantages of two-way communications system without the need of a large investment with EDCO equipment.

**QUALITY DESIGN FEATURES** are included at no extra cost. A full transmitter-receiver, for greater reliability. A full 5-watt power input, produces 3-watts power output. Universal power supply: 115vac/6 or 12vdc.

**Push-to-Talk**

Squelch adjustable. Noise Limiting. Designed for remote control option.

**TUBE LINE UP**

Receiver: 6BK7B, 6U8A, (2) 6BH6, 6AL5, 12AX7, 6AQ5. Transmitter: 5763, 6AK6, (2) 12AT7, 6AQ5.

**Electronics Design Company**

**400 East Cornell Street**

**P. O. Box 401** **Enid, Oklahoma**

**MICRO**

*ELECTRON TUBE*

INTRODUCES FOR THE FIRST TIME ANYWHERE A SELECT STOCK OF USED TUBES AT A FABULOUS LOW PRICE

**37¢ ea.**

FOR any TUBE LISTED

Jan Surplus Tubes!

**$35** PER HUNDRED ASSTD.

ALL TUBES SENT POSTAGE PAID

Please send 25c handling for orders under $5. Send 25% deposit on C.O.D. orders. Send approximate postage on Canadian and foreign orders.

- Each and every tube is tested in our own laboratory for mutual conductance and life test.
- We guarantee FREE replacement for one year of any tube purchased from us which fails to function efficiently under any or all operating conditions. Prompt refunds are made on any defective merchandise.
- The advertised tubes are not necessarily new, but may be electrically perfect factory seconds or used tubes—each is clearly so marked.

0A2, 0Z4, 1A7GT, 1B3GT, 1H4G, 1N3GT, 1L4, 1L6, 1N5GT, 1Q5GT, 1R5, 1S5, 1T4, 1U4, 1U5, 1V2, 1X2, 2A3, 2AF4, 3BC5, 3BN6, 3BZ6, 3CB6, 3CF6, 3C56, 3LF4, 3Q4, 3S4, 3V4, 4BQ7A, 4BZ7, 5AS8, 5AT8, 5AV8, 5AW4, 5BK7, 5J6, 5T8, 5U4G, 5U8, 5V4G, 5V6GT, 5X8, 5Y3GT, 5Y4G, 6A7, 6A8, 6AB4, 6AC7, 6AF4, 6AG5, 6AQ7, 6AH4GT, 6AH6, 6AK5, 6AL5, 6AL7, 6AM6, 6AN8, 6AQ5, 6AQ6, 6AQ7GT, 6AR8, 6AS5, 6AT6, 6AT8, 6AU4GT, 6AU5GT, 6AU6, 6AU8, 6AV5GT, 6AV6, 6AW8, 6AX4GT, 6AX5GT, 6B8, 6BA6, 6BC5, 6BC8, 6BD6, 6BE6, 6BF5, 6BF6, 6BG6G, 6BH6, 6BJ6, 6BK5, 6BK7, 6BL7GT, 6BN6, 6BQ6GT, 6BQ7, 6BY5G, 6BZ6, 6BZ7, 6C4, 6C5, 6C6, 6CB6, 6CD6G, 6CF6, 6CG7, 6CL6, 6CM6, 6CM7, 6CN7, 6CS6, 6CU6, 6DE6, 6DQ6, 6F6, 6H6, 6J4, 6J5, 6J7, 6K6GT, 6K7, 6K8, 6L7, 6N7, 6Q7, 6S4, 6S8GT, 6SA7, 6SC7, 6SF5, 6SF7, 6SJ7, 6SK7, 6SL7GT, 6SN7GT, 6SQ7, 6SS7, 6T4, 6T8, 6U8, 6V6, 6W4GT, 6W6GT, 6X4, 6X5, 6X8, 6Y6G, 7A4/XXL, 7A5, 7A6, 7A7, 7A8, 7B4, 7B5, 7B6, 7B7, 7B8, 7C4, 7C5, 7C6, 7C7, 7E6, 7E7, 7F7, 7F8, 7H7, 7N7, 7Q7, 7X7/XXFM, 7Y4, 7Z4, 12A8, 12AQ5, 12AT6, 12AT7, 12AU6, 12AU7, 12AV6, 12AV7, 12AX4GT, 12AX7, 12AZ7, 12B4, 12BA6, 12BA7, 12BE6, 12BF6, 12BH7, 12BQ6, 12BR7, 12BY7, 12CA5, 12J5, 12K7, 12L6, 12Q7, 12SA7, 12SQ7, 12SJ7, 12SK7, 12SN7GT, 12SQ7, 12V6GT, 12W6GT, 12X4, 12Z3, 14A7/12B7, 14B6, 14Q7, 19, 19AU4GT, 19BG6G, 19J6, 19T8, 24A, 25AV5, 25BQ6, 25DN6, 25L6GT, 25W4GT, 25Z5, 25Z6, 26, 35A5, 35B5, 35C5, 35L6GT, 35W4, 35Y4, 35Z5GT, 37, 39/44, 42, 43, 45, 50A5, 50B5, 50C5, 50L6GT, 50X6, 56, 57, 58, 71A, 75, 76, 77, 78, 80, 84/6Z4, 117Z3, 117Z6

WRITE DEPT. EW-2 FOR OUR FREE COMPLETE LIST OF TUBES & SPECIAL PURPOSE TUBES

**MICRO** ELECTRON TUBE CO. P.O. Box 55, Dept. EW-2, Park Sta., Paterson 3, N. J.

**Field Tested and PROVEN!**

**Philmore**
**11-Meter Citizens' Band**

# TRANSCEIVER KIT

**COMPLETE KIT** for 115V AC. **$39.95**
INCLUDES MICROPHONE, CRYSTAL AND CABINET.

Designed with the CITIZEN in mind, this kit is so carefully engineered and assembly instructions are so thoroughly worked out that ANYONE, even without electronic knowledge or skill, can build it—and get superlative results!

Advanced features include:

- **Any three channels individually switch-selected, with receiver and transmitter frequencies different, if desired, to meet local conditions.**
- **Interchangeable power supplies for 115V AC or 6/12V DC operation.**
- **Low flat modern appearance, sleek cabinet perfect for desktop, or on or under dashboard.**
- **Crystal controlled transmitter.**

TC11 Transceiver for 115V AC, less antenna. **$39.95**
TC612 Transceiver for interchangeable 6 & 12 V DC, less antenna. ..... **$44.49**
TC15 7-Section Whip Antenna Short Range... **$ 4.50**

AVAILABLE AT LEADING DISTRIBUTORS FROM COAST TO COAST. Free Literature on request.

**COMPLETE TWO-WAY COMMUNICATION** for
- **BUSINESS HOME**
- **COMMERCIAL**
- **FARMS**
- **BOATING**

**NEWLY ENGINEERED** TO CONFORM WITH LATEST F.C.C. REGULATIONS

**PHILMORE MANUFACTURING CO., INC.**
130-01 Jamaica Avenue • Richmond Hill 18, N. Y., U.S.A.

# SEND ELECTRONICS WORLD EVERY MONTH

name

address

city zone state

Check one:

☐ 3 years for **$12**
☐ 2 years for **$ 9**
☐ 1 year for **$ 5**

In the U. S., its possessions, and Canada.

☐ Payment enclosed ☐ Bill me

Foreign rates: Pan American Union countries, add .50 per year; all other foreign countries, add $1.00 per year.

Mail to: **ELECTRONICS WORLD**
Dept. EW 260
434 S. Wabash Ave. Chicago 5, Ill.

**"101 WAYS TO USE YOUR SIGNAL GENERATOR"** by Robert G. Middleton. Published by *Howard W. Sams & Co., Inc., Indianapolis.* 117 pages. Price $2.00. Soft Cover.

This is a companion volume to the author's books on using the sweep generator, oscilloscope, the v.o.m. and v.t.v.m. The format is identical to the previous "101 Ways" books and covers equipment checks, antenna tests, AM-FM receiver tests, TV receiver tests, component tests, and miscellaneous applications.

The text material is lavishly illustrated with schematics, block diagrams, and photographs with commentary held to a minimum. Each "Way" has sections covering the equipment needed, the required connections, the procedure to be followed, and an evaluation of the results obtained by means of the tests.

We believe that amateurs, experimenters, and hobbyists will find this book almost as useful as the professional radio and television technician for whom it was originally prepared.

* * *

**"BASIC ELECTRONICS"** by Van Valkenburgh, Nooger & Neville, Inc. Published by *John F. Rider Publisher, Inc.,* New York. 123 pages. Price $2.90. Soft binding. (Vol. 6 in series).

This is a companion volume to the five-volume "course" on basic electronics and has been prepared to permit individuals, schools, and industrial programs to upgrade their training to expand into areas of semiconductors, transistors, and frequency modulation (fields not covered in the first five volumes).

As was the case with the "Basic Electronics" course, the text uses the "picture" approach. The text material on each page carries with it a specially conceived illustration which amplifies and clarifies the discussion. The first half of the book deals with semiconductors and transistors while the second section covers the fundamentals of frequency modulation—including both transmitters and receivers.

Those who have completed the "Basic Electronics" course represented by the first five volumes will find this a welcome and instructive extension of the original material.

* * *

**"SIMPLIFIED RADIO SERVICING BY COMPARISON METHOD"** by M. N. Beitman. Published by *Supreme Publications,* Highland Park, Ill. 46 pages. Price $1.50. Soft binding.

This handbook is intended to help technicians speed repair jobs by eliminating aimless and time-consuming prodding of radio chassis. The text outlines simple tests which may be made to obtain electrical, visual, and other reactions from radio parts and circuits and explanations how to determine if the indications thus secured are "normal" or "abnormal."

The first section of the book covers symbols and abbreviations; practical electrical facts; resistors, capacitors, coils; reading schematics; the mechanical parts of the radio; printed circuitry; vacuum tubes and transistors; etc. The balance of the text covers specific circuits including screen-grid t.r.f. sets, small a.c.-d.c. receivers, small superhets, a.v.c., vibrator power supplies, early and modern auto radios, battery portables, combination portables, transistor portables, and test equipment.

A handy index at the back of the book guides the user to the pertinent circuit or component that comparison testing has indicated at fault. —30—

## LORAN R-65/APN-9 RECEIVER & INDICATOR



Used in ships and aircraft. Determines position by radio signals from known xmitters. Accurate to within 1% of distance. Complete with tubes and crystal. Exc. used. Value $1200.00.

Our Price ..... **$79.50**

12 Volt Inverter Power Supply for above. BRAND NEW..... $32.50

Circuit diagram and connecting plugs available.

## AN/APA-38 PANORAMIC ADAPTER

And Wave Analyzer. 30 Mc Center Frequency, 2 Mc Band Width. Total scan 10 Mc at one clip. Regular saw-tooth sweep. Variable sweep freq. control 1600 cycles. Use it as regular service scope! Including 11 tubes and 3" scope tube type 3DF1. **LIKE NEW.** **$19.50**

## NAVY AIRCRAFT RADIO RECEIVER

ARB/CRV 46151—190 to 9050 Kc in 4 bands. 6 Tube Superhet communications receiver, with local and remote tuning, band change. Sharp and broad tuning. AVC, CW. Illuminated dial. Complete with tubes and dynamotor, used..... **$17.95**

Like New ..... **$26.50**

Power Supply 110 V. AC. Wired..... **$8.50**

**BC-733 VHF 10-TUBE AIRCRAFT RECEIVER.** 6-channel xtal control. Freq. 108.3 to 110.3 Mc. Dual filter range. Easily converted for tracking Sputniks!

Exc. used. Complete with tubes..... **$7.95**

Brand New complete with tubes..... **$8.95**

Dynamotor for above 24 V..... New **$5.95**



## RADIO CONTROL RECEIVER 30-42Mc.

R64/ARW-17. Small size, lightweight FM radio Receiver for 5 control channels. Signal outputs actuate control relays up to 3 channels simultaneously. Complete with 10 tubes: 5—6AK5, 3—6J6, 1—6AS6, 1—6AL5, and dynamotor for 24V DC.

BRAND NEW..... **$12.95**

## FM TRANSMITTER-RECEIVER

**APN-1.** 420 to 460 Mc Aircraft Radio altimeter equipment. Tubes: 4—955, 3—12SJ7, 4—12SH7, 2—12H6, 1—VR150. Complete with all tubes and mount. For 27 V DC.

BRAND NEW..... **$8.95**

Original operating manual for above..... **$1.00**

## SCR-522 2-METER RIG!

Terrific buy! VHF Transmitter-receiver, 100-156 Mc. 4 channels. Xtal-controlled. Amplitude modulated voice. They're going fast! Excellent condition. **SCR-522 Transmitter-Receiver, complete with all 18 tubes, top rack and metal case.**

COMBINATION..... Special **$32.32**

Transmitter Only, with all tubes..... **$17.50**

Accessories for above available.

## LORAN APN-4 FINE QUALITY NAVIGATIONAL EQUIPMENT

Determine exact geographic position of your boat or plane. Indicator and receiver complete with all tubes and crystal.

INDICATOR ID-68/APN-4, and RECEIVER R-98/APN-4, complete with tubes. Exc. used **$49.50**

Receiver-Indicator as above. BRAND NEW.. **$69.50**

Inverter for above unit available from stock.

## LORAN APN/4 OSCILLOSCOPE

Easily converted for use on radio-TV service bench.

**Completely Assembled**

LIKE NEW! Supplied with 5" Scope, type 5CP1 only ..... **$14.95**

Brand New ..... **$19.50**

## BC-906 FREQ. METER—SPECIAL

Cavity type, 145 to 235 Mc. BRAND NEW, complete with antenna. Manual included. OUR LOW PRICE..... **$10.88**

### STANDARD TUBES

Removed from Brand New Gov't Equipment

| RECEIVING | | 6AC7 ..... .55 | 815 ..... 2.15 |
|---|---|---|---|
| 6AQ5 ..... .38 | | 6J6 ..... .52 | 837 ..... .65 |
| 12AT7 ..... .45 | | | 1625 ..... .29 |
| 6AK5 ..... .35 | SPECIAL PURP. | | 1629 ..... .29 |
| 6C4 ..... .25 | 3E29 ..... 4.29 | | 2013 ..... .39 |
| 6AL5 ..... .33 | 807 ..... .95 | | 2014 ..... .39 |
| 6J4 ..... .59 | 813 ..... 6.95 | | 4X-150 ..... 8.95 |
| 6X5 ..... .35 | 814 ..... 2.25 | | 3BP1 ..... 1.49 |

**GOLD PLATED SPECIAL!**

**TS-1/ARR-1 TEST OSCILLATOR**

Portable, complete with two 955 tubes, cavity and antenna. BRAND NEW in metal housing 9¾" x 6¾" x 7" high. OUR LOW PRICE, each **$3.45**

**SCHEMATIC DIAGRAMS** For any equipment on this page, each.. **65c**

SEND FOR FREE CATALOG, many more Wonderful Surplus Buys!

## AN/ART-13 100-WATT XMTR

**11 CHANNELS**
**200-1500 Kc**
**2 to 18.1 Mc**

**$48.50** Complete with Tubes

Famous Collins Autotune Aircraft Transmitter, AM, CW, MCW. Quick change to any of ten preset channels or manual tuning. Speech amplifier/clipper uses carbon or magnetic mike. Highly stable, highly accurate VFO. Built in Xtal controlled calibrator. PP811s modulate 813 in final up to 90%, class "B." A Real "HOT" Ham buy at our low price!

Orig. cost $1800. Exc. Used..... **$48.50**

0-16 Low Freq. Osc. Coil for ART-13..... 7.95

24V Dynamotor for ART-13..... 11.95

Accessories available for xmtr. Inquiries invited.

## THIS MONTH'S SPECIAL!
## BC-946 BROADCAST RECEIVER

550 to 1500 Kc. Brand new in original carton, complete with all tubes. 24V DC. Limited quantity at this sensational low price!..... **$49.50**

### MICROPHONES

| Model | Description | Excellent Used | BRAND NEW |
|---|---|---|---|
| T-17 | ...Carbon Hand Mike..... | | $5.45 |
| T-30 | ...Carbon Throat Mike... | $ .34 | .74 |
| T-45 | ...Army and Navy Lip Mike..... | | 1.25 |
| TS-9 | ...Handset..... | | 3.88 |
| TS-11 | ..Handset..... | | 3.95 |
| TS-13 | ..Handset..... | | 4.25 |
| RS-38 | ..Navy Type..... | | 4.75 |

### HEADPHONES

| Model | Description | Excellent Used | BRAND NEW |
|---|---|---|---|
| HS-23 | ..High Impedance..... | $2.19 | $4.65 |
| HS-33 | ..Low Impedance..... | 2.69 | 4.65 |
| HS-30 | ..Low Imp. (featherwt.) | .90 | 1.65 |
| H-16/U | .High Imp. (2 units)... | 3.75 | 7.95 |

TELEPHONICS—600 ohm Low Impedance HEADSETS. BRAND NEW, PER PAIR ..... **$3.25**

CD-307A Cords, with PL55 plug and JK26 Jack ..... .99

Earphone Cushions for above—pair..... .50

## BC-314-F 4-BAND RECEIVER

150 to 1500 Kc Continuous tuning, complete with self-contained dynamotor for 14V DC. Like New ..... **$55.00**

## MOBILE-MARINE DYNAMOTOR

Input 12V DC. Output: 625 V DC @ 225 Ma. for press-to-talk intermittent operation. Shpg. wt. 14 lbs. OUR LOW PRICE... **$6.45**

| OTHER DYNAMOTOR VALUES: Type | Input | Output | Excellent Used | BRAND NEW |
|---|---|---|---|---|
| DM-25 | 12V 2.2A | 250V .050A | | $4.50 |
| DA-1A | 28V 1.6A | 230V .100A | | 3.95 |
| DM-28 | 28V | 224V .07A | 2.75 | 4.75 |
| DM-32A | 28V 1.1A | 250V .05A | 2.45 | 4.45 |
| DM-33A | 28V 5A | 575V .16A | | |
| | 28V 7A | 540V .25A | 1.95 | 3.75 |
| DM-34D | 12V 2A | 220V .080A | 4.15 | 5.50 |
| DM-53A | 28V 1.4A | 220V .080A | 3.75 | 5.45 |
| DM-64A | 12V 5.1A | 275V .150A | | 7.95 |
| PE-73C | 28V 20A | 1000V .350A | 7.95 | 10.50 |
| PE-86 | 28V 1.25A | 250V .050A | 2.75 | 3.85 |

## MOBILE DYNAMOTOR SPECIAL

INPUT: 9 Volts DC @ 7.5 Amps. OUTPUT: 405 Volts DC @ .095 Amps. May be used for 6 Volt operation. Brand new in original carton..... **$3.95**

**PE-103 DYNAMOTOR.** INPUT 6/12 Volts DC. OUTPUT: 500 V. @ .160 Amps. Brand new, complete with filter base, shock mount and cables..... **$24.50**

## TG-34A CODE KEYER

Self-contained automatic unit, reproduces code practice signals recorded on paper tape. By use of built-in speaker, provides code-practice signals to one or more persons at speeds from 5 to 25 WPM.

BRAND NEW **$22.50**

Checked out, exc. used **$17.95**

Please include 25% Deposit with order—Balance C.O.D., or Remittance in Full. 50c Handling Charges on all orders under $5.00. All shipments F.O.B. Our Warehouse, N.Y.C. All Merchandise subject to Prior Sale and Price Change.

**G & G Radio Supply Co.**
Telephone: CO 7-4605
51 Vesey St., New York 7, N. Y.

## ASB-5 'SCOPE INDICATOR

**BRAND NEW,** including all tubes, **together with 5BP1 'Scope Tube.** Originally used in Navy Aircraft RADAR equipment. Easily converted for AC operation.

VALUE $250.00!
OUR LOW PRICE... **$16.95**

## ARC-5/R28 RECEIVER

2-meter Superhet. 100 to 156 Mc in 4 crystal channels. Complete with 10 Tubes. BRAND NEW **$24.45**

110V AC Power Sup. Kit for above **$9.75**

## ARC-5/T-23 TRANSMITTER

100-150 Mc Includes 2—832A, 2—1625 Tubes. BRAND NEW..... **$21.50**

**SPECIAL OFFER!** Limited quantity ARC-5/T23 xmitters. Excellent Used, less tubes..... **$5.95**

**MD-7 MODULATOR** for T-23, complete with 4 tubes. LIKE NEW..... **$9.95**

### ARC-5 MARINE RECEIVER-TRANSMITTER

Navy Type Comm. Receiver 1.5 to 3 Mc BRAND NEW with 6 tubes..... **$16.95**

Navy Type Comm. Transmitter 2.1-3 Mc BRAND NEW with 4 tubes and Xtal **$12.45**

MODULATOR for above, new with tubes..... $5.95

## 234-258 MC RECEIVER
### AN/ARR-2

BRAND NEW 11-tube UHF Tunable Receiver with schematic. Only a few at this low price!

Complete with tubes **$8.88**

## SCR-274 COMMAND EQUIPMENT

ALL COMPLETE WITH TUBES

| Type | Description | Used | Like NEW |
|---|---|---|---|
| BC-453 | Receiver 190-550 KC..... | $14.50 | $16.50 |
| BC-454 | Receiver 3-6 Mc..... | 9.45 | 12.45 |
| BC-455 | Receiver 6-9 Mc..... | 10.45 | 12.45 |
| BC-450 | 3-Receiver Control Box..... | 1.29 | 1.75 |

**110 Volt AC Power Supply Kit, for all 274-N and ARC-5 Receivers.** Complete with metal case. Instructions ..... **$7.95**

Factory wired, tested, ready to operate... $11.50

**SPLINED TUNING KNOB for 274-N and ARC-5 RECEIVERS.** Fits BC-453, BC-454 and others. Only ..... **49c**

BC-457 TRANSMITTER—4-5.3 Mc. complete with all tubes and crystal. BRAND NEW.. **$7.85**

BC-458 TRANSMITTER—5.3 to 7 Mc. Complete with all tubes and crystal. BRAND NEW..... **$9.75**

BC-459 TRANSMITTER—7-9.1 Mc. complete with all tubes and crystal. **$13.95**

ARC-5/T-19 TRANSMITTER—3 to 4 Mc. BRAND NEW complete with all tubes & crystal ..... **$10.95**

BC-456 Modulator ..... USED 3.45 NEW 5.95

BC-451 Transmitter Control Box.. 1.35 NEW 1.49

ALL ACCESSORIES AVAILABLE FOR COMMAND EQUIPMENT.

## BC-603 FM RECEIVER



**20 TO 27.9 MC.**

Used..... **$129.95**

Like New ..... $14.95

BRAND NEW..... $16.95

Convert to 20-50 Mc., and A.M.! (See CQ Sept. '58).

10 Channel, pushbutton tuning or continuous tuning. Complete with speaker, tubes, squelch.

12 or 24V Dynamotor for Above Exc. Used $4.25..... Brand New $3.50

**BC-683** same as above except 27 to 38.9 Mc. Used ..... **$23.50**

Brand New ..... $37.50

**AC POWER SUPPLY FOR BC603, 683**

Interchangeable, replaces dynamotor. Has On-Off Switch. NO RECVR. CHANGE NEEDED. Provides 220 VDC @ 80 Ma. 24VAC @ 5 Amps..... $10.45

Complete 240-peare Technical Manual for BC-603, 604 ..... $2.95

**BC-604 TRANSMITTER**—Companion unit for BC-603 Rcvr above. With all tubes. BRAND NEW..... **$10.95**

**BC-684 TRANSMITTER**—Companion unit for BC-683 Rcvr above. Complete with all tubes. Like NEW..... **$7.95**

BRAND NEW..... **$12.95**

**POWER SUPPLY for BC-620, 659,** available for 6, 12 or 24 Volts DC. Specify..... **$8.95**

## BC-659 TRANSMITTER & RECEIVER

27 to 38.9 Mc. F.M. Two preselected channels crystal controlled. 5 to 10 watts. Complete with speaker, tubes. Exec. Used..... **$11.95**

Less tubes, exec. used..... $7.95

Antenna for BC-659. Telescoping 20" to 8-Ft.... $2.95

## WILLARD 6-VOLT MIDGET STORAGE BATTERY

3 Amp. Hour. BRAND NEW. 3⅝" x 1-13/16" x 2⅜". Uses Standard Electrolyte ..... Only **$2.95**

## 2 VOLT BATTERY "PACKAGE"



1—2V, 20 Amp. Hr. Willard Storage Battery, Model #20-2. 3" x 4" x 5⅛" high..... $2.79

1—2V, 7 prong Synchronous Plug-in Vibrator ..... 1.49

1—Quart Bottle Electrolyte (for 3 cells) ..... 1.46

ALL BRAND NEW! Combination Price ..... **$5.45**

**NEW FROM HOWARD W. SAMS**

**"From Tinfoil to Stereo"**

**The Evolution of the Phonograph**

*by Oliver Read & Walter L. Welch*

**Here is the most complete history of the phonograph ever written—from the use of tinfoil to the revolutionary stereo record—the whole exciting story of the men and events responsible for the development of the phonograph!**

You'll be fascinated by this masterful account of the evolution of the phonograph. Covers *everything:* man's earliest dreams of imitating sound; the Edison tinfoil phonograph and the development of the earliest prototypes; the patent struggles; the development of cylinders and discs; the coin-slot phonograph; the introduction of the internal horn; the beginnings of radio and its contribution to recording and reproduction; sound pictures and the phonograph; the war of the record speeds; growth of component systems; tape vs. discs—right down to today. Includes dozens of rare photographs. A wonderful book for every hi-fi enthusiast and phonograph connoisseur. 576 pages, 6 x 9", fully illustrated. Only..... $9.95

**MORE NEW SAMS BOOKS**

**"101 Ways to Use Your Ham Test Equipment"**

*by Bob Middleton*

A practical "how-to-do-it" book for amateur radio operators and service technicians who specialize in the repair of ham radio equipment. Gives concise applications for grid dip meters, antenna impedance meters, oscilloscopes, bridges, simple noise generators and reflected power meters. Each use is clearly described, with full data on connections required, proper test procedures and evaluation of results. 144 pages; 5½ x 8½"; illustrated. Only..... $2.00

**"Servicing Hi-Fi and FM in the Customer's Home"**

*by Milton S. Kiver*

Describes a wide range of quick, easy test methods for hi-fi amplifiers, AM-FM receivers, record changers, turntables and tape recorders. Includes several unusual new methods, such as the use of an AM detector probe to trace FM circuits. Methods are selected for their quick, practical application and their ability to locate actual and potential trouble spots in hi-fi equipment. Indispensable to anyone interested in servicing hi-fi. 176 pages; 5½ x 8½"; illustrated. Only.... $2.95

**HOWARD W. SAMS & CO., INC.**

Order from your Sams Distributor today, or mail to Howard W. Sams & Co., Inc., Dept. B-10 1720 E. 38th St., Indianapolis 6, Ind.

Send me the following books:

☐ "From Tinfoil to Stereo" (EPR-1)

☐ "101 Ways to Use Your Ham Test Equip." (TEM-6)

☐ "Servicing Hi-Fi in the Customer's Home" (SHK-1)

$.....enclosed. ☐ Send Free Book List

Name _____

Address _____

City _____ Zone____ State_____

(outside U.S.A. priced slightly higher)


# Service Industry News

NOTEWORTHY developments this month include the fact that the impact of the manufacturer-propelled campaign to "Buy American" is being felt on the service level and another fact that is something of an oddity: two highly regarded officials of an important east-coast association have resigned their offices—to the satisfaction of their supporters.

The latter puzzler obviously needs further clarification—so we'll hold you in suspense for a while. As to the first point, association officials are far from showing the unanimity expressed by the EIA in urging a virtual boycott of Japanese (and other foreign-made) electronic products to preserve the American economy. The "Hoosier Test Probe," organ of IESA of Indiana, says, "If the American standard of life is to be maintained, each of us must do our part. That foreign car or truck you purchase tends to steal pay from your customer, the auto worker. Likewise, when you sell foreign-made products to your customers, that many sales are lost to American business." Note is taken of the argument that the domestic economy, if it is forced to compete against other economies with lower standards of living, runs the risk of a similar lowering.

The Electronic Assn. of Mo., in its "TEAM News," does not take a final stand on the issue, but does note the existence of arguments on the other side of the fence. It points out the possibility that it may be important for us, in our own interests, to give needed support to the economies of other countries by acting as their customers. The healthy stimulus that outside competition can provide is also mentioned: "U. S. manufacturers talked vaguely for ten years or more about the 'coming' vest pocket radios. Only since foreign competition has put a burr under their tail have U. S. manufacturers made any effort to build them . . . Small, economical, foreign cars also pointed out a potential market which American motor car builders had ignored."

Another interesting point in this dispute is the ambiguous position in which some domestic manufacturers find themselves. On the one hand, they urge that finished products brought in from abroad be shunned in favor of their own competitive merchandise. On the other hand, how many of them are using foreign-made components (transistors, capacitors, etc.) in their "American-made" units? Like "TEAM News," we have no final answer.

### Resignations in ESFETA

New York's Empire State Federation has seen the resignation, in rapid succession, of two high-ranking officers: Bob Larsen, president, and George Carlson, secretary. While both have been very active, neither action reflects strife within ESFETA or a weakening of that organization. Larsen was simultaneously serving as president of ESFETA and of its local affiliate (RTGLI) on Long Island. In addition, he is now devoting most of his efforts to what he considers the most important project before the service industry in his state; the development of an acceptable licensing law that will have a good chance of being passed by the state legislature and the maintenance of close contact with state officials to the end that such a law will indeed be passed. Feeling that he could not do full justice to all three responsibilities at once, he let the ESFETA presidency go.

George Carlson has dropped out for somewhat similar reasons. His election as NATESA's eastern secretary left him with too much for one man.

Newly elected ESFETA officers include Irv Toner of Buffalo, president; Bob Henderson of Long Island, vice-president; O. Capitelli of New York City, recording sec'y.; and Mel Cohen of northeastern New York, corresponding sec'y.

### NCFEA Technician Training

The North Carolina Federation of Electronic Associations, in cooperation with the State Educational Department, is in the midst of an extensive campaign to make sure that TV service technicians are adequately trained and to issue cards to those found qualified.

Ed Kemp of NCFEA (right) issues certification card to Joseph Warren. On hand are Kenneth LaRue (left), NCFEA head, Bruce Roberts, a director of education program, and instructor Jim Hornaday.

Any full-time service technician may take a qualifying test on a voluntary basis. If he passes (he may try a second time, if he fails the first test) he receives a card certifying him as a "TV serviceman." If he cannot pass, he may enter a "journeyman" course of instruction, following the successful completion of which he receives the card.

There is also an advanced course, including color TV. Successful completion entitles the student to a card certifying him as a "TV technician." The cards are expected to help the public identify competent men and also assist those who may be seeking employment or employees. North Carolina technicians interested in the program should contact local Directors of Vocational Education or L. L. Leathers, chairman of the NCFEA Educational Committee, 221 Southerland St., Durham, N. C.

### Miami Robbery

With the onset of the winter season, a new wave of break-ins and thefts is striking the Miami area, as it did last year. *George's Radio & TV Hospital* of that city suffered a loss of about $4000, only part of which was covered by insurance. The thieves chose Saturday night to break into the back door, pull up a truck, and make off with an extensive stock of new car radios, a tube caddy, test equipment, and electric drills.

Similar waves of thefts, giving the appearance of systematic technique, have occurred in parts of Indiana, Texas, and other areas of the country. TV receivers are also taken on these forays, many of the sets belonging to customers. The thieves have been showing quite a bit of judgment in the value of the equipment they have been taking or leaving behind. The uptrend in robberies gives greater urgency to the demands by service associations that set manufacturers begin stamping serial numbers and other identifying markings in such a way that they cannot be removed easily. The present difficulty in tracing stolen equipment encourages highjacking.

### Service Fees

President Lou Ristau of TSA of Northeastern New York is urging the recommendation of a minimum fee of $5.50 for a service call. He gives some impressive statistics to show that anything less must be unprofitable. Some west-coast groups are urging minimum fees of $7 and $7.50.

### ARTS Officers

The last semi-annual meeting of Associated Radio and Television Servicemen, Chicago, Ill., voted in a new slate of officers as follows: Joseph Ehlinger, chairman; Harold Mueschen, vice-chairman; Yuki Minaga, secretary-treasurer; and Delmar Kotrba, sergeant-at-arms. Carried over from last year were Anthony Mallin as historian and Stephen Jacyna as press representative. -30-


# Service Technicians! YOU EARN MORE... YOU RATE with the public when you own the PHOTOFACT® service data library!


"Sams PHOTOFACTS are as important to my shop as the instruments I use. Sams are a must in an up-to-date service department."
—Louis Michael
Aliquippa, Penna.

**YES, if you are one of the thousands of owners of a complete PHOTOFACT Service Data Library, you are enjoying maximum earnings. It's inevitable, because no matter how expert you are, you can always *save more time* on *any* job, get *more* jobs done daily—EARN MORE, DAY IN AND DAY OUT...**

**Moreover—as the owner of a complete PHOTOFACT Library, *you* know your customers' sets *best*. You can actually show each customer you have the PHOTOFACT Folder covering his very own set. Result: You command public respect and acceptance which paves the way to more business and earnings for you...**

***HOW TO STAY AHEAD...***

Today, the truly successful Service Technicians are those who own the complete PHOTOFACT Library, who can meet and solve any repair problem—faster and more profitably. And these men *keep ahead* because they're on a Standing Order Subscription with their Distributors to receive all new PHOTOFACTS as they are released monthly.

For **PHOTOFACT** Library Easy-Buy Plan details and Standing Order Subscription, see your Sams Distributor today, or write to Howard W. Sams...

"PEET" PROGRAM **BIG NEW PLUS!** *get the details*

**If you now own a PHOTOFACT Library, you can apply for membership in the powerful new "PEET" program, designed to build prestige and business for the Service Technician who qualifies. Ask your Sams Distributor for the "PEET" details, or mail coupon today!**

**HOWARD W. SAMS & CO., INC.**
**1724 E. 38th St., Indianapolis 6, Ind.**

☐ Send me full details on the new "PEET" Program. Include full information on the Easy-Buy Plan and Free File Cabinet deal.

☐ I'm a Service Technician: ☐ full-time; ☐ part-time

My Distributor is:_____

Shop Name_____

Attn:_____

Address_____

City_____ Zone____ State_____

# S-T-R-E-T-C-H YOUR BUDGET WITH BARGAINS FROM PRE-SELECTED SURPLUS

## RECEIVERS AND TRANSMITTERS

**RCA NAVAER ARB RECEIVER.** 195-9,050 kc continuous in 4 bands. AM superhet. Voice, cw, mcw. Six tubes include RF and 2 IF. Exc. cond. with 24v dynmtr. 30 lbs fob Los Angeles. **$14.95**

**CAT. SC3** is schematic for ARB, alignment chart, instructions for 12v or 115v, 60 cy conversion. Postpaid **$3.00**

**SCR-522.** 2-meter rcevr and separate xmtr, clean as new, with all tubes, mounted in rack and case. 100-156 mc AM, 4-channel, crystal control. 60 lbs **$11.95** FOB Los Angeles

**CAT. 16C3** is the original schematic for above set, with parts list, I.F., xtl formulas, instructions for an AC power supply, for rcevr continuous tuning, for xmtr 2-meter use, and for putting xmtr on 10 or on 6 meters. Postpaid **$3.00**

**NAV AER RT-18/ARC-1** 10-channel xtl-controlled Autotune xmtr-rcevr, 100-156 mc. Like new, with all tubes, some xtls, schematic, and adjustment & operating instructions. FOB Corpus Christi, Texas. Never before at only **$49.50**

**NAVY MAR.** Rcvr-xmtr AM voice and mcw, 225-390 mc, tunes down to 220 mc. 10-channel xtl-controlled Autotune. 12 watts to antenna, input 12/24/115/230 vdc, or 115/230 v, 60 cy. Complete with modulator, universal power supply, all tubes, all plugs, antenna, xtl oven, and reprint of the schematics and operating and tune-up instructions. Excellent condition, **$49.50** fob Hartford, Conn., only

**MAR antenna only.** FOB Los Angeles **$7.95**

**MAR xtl oven only.** FOB Los Angeles **$7.95**

**MAR booklet only,** described above. 22 pages plus 4 big pullouts. Postpaid **$5.00**

**SPEECH AMPLIFIER/PWR SUPPLY** for 100 watt xmtr. No splatter. AGC holds 30 watt AF output to +5% for input blast of +78% above the 90%-modulated level. For dyn. or carbon mike. Has keyed 1 kc tone osc. 115 v 1 ph 50/60 cy power supply has 4 mercury-vapor 3C23's and 2 blower-cooled selen. stacks furnishes 600 vdc, 445 ma; 300 vdc, 175 ma; 12 vdc, 1 A; and adjustable 0 to −150 vdc, ½ A. With schematics and AGC-adjust. instructions. FOB Milpitas, Calif., all for only **$29.95**

Same as above but less the tubes **$14.95**

## TEST OSCILLOSCOPES READY TO USE

**TS-34/AP.** Portable, but with magnifying lens, same as a 5" screen. In addition to the 10-50,000 cy internal variablerate sweep, it can be triggered by incoming pulses, with sweep choices of 5, 50, or 250 u-secs. duration. In carrying case. With 16-page booklet. Flat 11 cy to 3½ mc. Clean used, checked OK. 40 lbs fob Los Angeles **$49.50**

SAME, but brand new, with all cords **$69.50**

**TS-34A/AP.** No carrying case. Same as above except that the triggered sweeps can be varied 4½-8, 20-50, and 120-250 u-secs. Used, but checked out and guaranteed same as new **$69.50**

**DUMONT 241.** 5" screen. X, Y, and Z amplifiers. With reprint of the instr. book. Used but checked out and guaranteed. 75 lbs fob Los Angeles. A rare buy at only **$79.50**

## SIGNAL SOURCES, AUDIO TO L-BAND

**400 CY ± .001%.** Am. Time Prod. tuning-fork-driven oscillator chassis with 2 6AU6 tubes. Tested and ready to use upon application of 150 vdc, 20 ma, and 6.3 vac, 600 ma. With schematic. 4 lbs. Tested & guaranteed, fob Los Angeles **$37.50**

**MODEL 400-A.** Above chassis mounted into neat bench cased unit with 115/230 v, 50/60 cy pwr supply, VR150 regulator, 6V6 gain-controlled output, and handy bench 9± 0-390 v, 120 ma, plus 6.3 vac, 4A, brought out to front-panel posts. Ready to plug in and use. (Schematic. 24 lbs. FOB Los Angeles **$97.50**

**1000, 500, 250, 125, & 62½ cy., ± .02%.** Am. Time Prod. fork osc. & 4 binary countdowns, ready to use upon application of 250-300 vdc, 3 ma, and 6.3 vac, 2.1 A, both handy at front panel of the ±400-A unit described above. New and guaranteed. With schematic, **$79.50** and waveform pics. 4 lbs fob Los Angeles

**NOTE:** The precision fork in each of the three units described above is worth over $100.00!

**MEAS. CORP. MODEL 75-B.** Pulse & Sq.-Wave Generator. Brand new, w/instr. book, in original packing. ± pulses 60-10,000 cy, adjustable ½-40 u-secs. each. Can pulse-modulate an external RF source and can be synched to an external sine source. 40 lbs fob Harrisburg, Pa. Only **$97.50**

**I-208. FM** microveiller 1.9-4.5 and 19-45 mc. Guaranteed OK. FOB Los Angeles **$39.50**

**NAVY LM.** 125-20,000 kc ± .01%, w/AF modulation. Combination heterodyne-type freq. meter & signal generator. Crystal calibrated. You build simple power supply. Guaranteed OK. FOB Los Ang. **$69.50**

**TS-173/U.** Similar to above except 90-480 mc. Guaranteed OK. FOB Los Angeles **$99.50**

Same as above, but less the calibration book **$59.50**

**MEAS. CORP. MODEL 80** Microvolter, 2-400 mc, certified OK by Standards Lab. FOB Los Angeles **$299.50**

**NAVY LAX** Microvolter, 7½-330 mc in metal case for low leakage. Certified. FOB Los Angeles **$149.50**

**NAVY LAF** Microvolter 90-600 mc, certified by Standards Lab. FOB Los Angeles **$89.50**

**NAVY LAE** Microvolter 520-1300 mc. Brand new, original pack. FOB Charleston, S. C. Includes many Tech Manuals. Add 25¢ for chart explaining AN Nomenclature. Example of new listings: AN/ARC-1 schem., tune-up operation **$119.50** $2.00

## OTHER LABORATORY EQUIPMENT

**TS-148/UP** Spectrum Analyzer 8470-9630 mc. Certified. 50 lbs fob Los Angeles **$299.50**

**BALLANTINE 220-A** decade amplifier steps up very low ac voltages (10-150,000 cy) by 10X or 100X (±2%) so they can be measured by ordinary meters. New, fob Los Angeles **$49.50**

**I-177** dynamic mutual conductance tube tester, used excellent, checked out and guaranteed, with 20-page 8½" x 11" booklet which is compilation of the tech manual, schematic, diagram for Socket Adapter MX-949/U, and all tube data to March, 1957. FOB Los Angeles **$29.50**

**DATA BOOK** described above, postpaid **$5.00**

**AUTOMATIC TUBE CHARACTERISTIC PLOTTER.** A console unit which visually plots all vacuum-tube parameters on a test oscilloscope. Made at cost of $75,000.00 by the Naval Ordnance Lab and written up for an I.R.E. presentation. Excellent condition, fob Silver Spring, Md. **$1995.00**

**COND. PROD. CO. PS30-1M60** miniature bench power supply, 0-32,000 vdc with 1% ripple. Input 115v 60 cy to 6L pri. and 0-118 v, 60 cy to plate pri. Certified **$69.50**

**KAY MEGANODE** power supply, certified **$129.50**

**AN/PDR-8C** Radiac set measures Beta & Gamma radiation on 4 scales, 0-500 MR/hr. Excellent cond., fob Los Angeles **$49.50**

**TS-250/APN** Test Set, like new **$199.50**

## VISUAL RECORDERS AND THEIR AMPLIFIERS

**PHOTRON F2.** 2-pen portable electric-writing recorder. Galvanometers are 1900 ohms, 3.1 mm/volt. Chart speeds 5/25/125 mm/sec. Certified, fob Los Angeles **$179.50**

**BRUSH BL-202.** 2-pen ink-writing portable recorder has specs like above plus extra-slow chart speed. Certified, fob L.A. **$199.50**

**BRUSH** 1-channel dc amplifier, certified, fob Los Angeles **$79.50**

**SOUND APPARATUS FR-1** is a standard 5"-roll-chart ink recorder in 19" rack/panel mount with a differential amplifier operating the pen's servo motor. A high-imped, voltage-sensitive device. At max. sensitivity setting, less than 1 u-volt applied to the panel terminals will drive the pen clear across the chart. Chart speeds 6"/12" per minute. Chart motor is reversible. Certified condition, fob Los Angeles **$249.50**

**RADIO FREQ. LAB.** (Navy 50214) dc amplifier in 19" rack/panel mount. Brown chopper references, batteries calibrate. Very high gain. Certified, FOB Los Angeles **$99.50**

## CONSTANT-VOLTAGE TRANSFORMERS

**SOLA 30808.** 500 VA. 60 cy. 95-125 v in, 115 v ± 1% out. Certified. FOB Los Angeles, only **$49.50**

**SOLA 30710.** 2 KVA. 4 inputs: 95-125 v, 190-250 v, 50 cy, or 60 cy. Output always 115.0 v ± 1% from 0-17.4 amps. Can use as a step-down. New. FOB Harrisburg, Pa. **$147.50**

**G.E. 2.3 KVA.** 57-63 cy, 100-135 v in, to link-switch selected 113/115/117 v ± 2% out. New. 594 lbs fob Seattle, Wash **$49.50**

**AUTOMATIC-TURNING POWERSTAT 1 KVA** stabilizer. Sensed output drives servo motor. Select 100-120 v out for 90-130 v line variations. 50/60 cy. Metered. No harm. dist. FOB El Paso, Tex. **$125.00**

## TIME PAY PLAN

Purchases must total $133.33 or more. Pay 25% down and balance in 12 monthly payments each 6⅔% of your purchase total. Send deposit and sales tax (if applicable) with your order.

## SCHEMATICS/CONVERSIONS, SURPLUS GEAR

List G. NEW! Send long stamped addressed envelope.

**California Buyers Add 4% Sales Tax**

**R. E. GOODHEART CO. P. O. BOX 1220-A** BEVERLY HILLS, CALIFORNIA



# TAPE RECORDERS

**HI-FI COMPONENTS**
**SLEEP LEARN KITS**

**MERITAPE** — Low cost, high quality recording tape, in boxes or cans.

**UNUSUAL VALUES FREE** — 1960 Catalog

**DRESSNER,** 69-02 RA, 174 St., Flushing 65, N.Y.



# HI-FI RECORDING TAPE

**FREQ. RESPONSE 30-15 KC.**
**10 DAY MONEY BACK GUARANTEE**

| | 3 | 10 | 25 |
|---|---|---|---|
| 1200' Acetate, each | $1.29 | $1.17 | $ .99 |
| 1800' Acetate, each | 1.79 | 1.59 | 1.45 |
| 1800' Mylar, each | 2.09 | 1.99 | 1.85 |
| 2400' Mylar, each | 3.29 | 2.99 | 2.75 |

Any assortment permitted for quantity discount. Add postage—15¢ per spool—25 or over 10¢.

IN STOCK—Hi-Fi under mfgs. franchise—A. R., Bell, Bogen, Dynaco, E.V. Elco, ESL, Fisher, Garrard, Har.-Kar., Norelco, Pilot, Rek-o-Kut, Shure, Thorens, Univ. Wollensack & many, many other components & Tape recorders. Send for low, low return mail quotation. "We Guarantee to Save You Money." Wholesale catalog free.

**HI-FIDELITY CENTER**
1799-E 1st Ave. New York 28, N. Y.



# MAIL ORDER HI-FI

You can now purchase all your Hi-Fi from one reliable source and be assured of perfect delivery. Carston makes delivery from NY stock on most Hi-Fi, Recorders and Tape within 24 hours. *SEND US A LIST OF YOUR HI-FI REQUIREMENTS FOR OUR WHOLESALE QUOTATION and our FREE wholesale catalogue.*

**CARSTON STUDIOS**
125-TD East 88 St. New York 28, N.Y.

### RCA TUBE TYPES

*RCA,* Electron Tube Division, Commercial Engineering, Harrison, N. J., has issued a revised edition of its list of preferred tube types for new equipment design. A free copy of this pamphlet, No. PTL-501G, may be obtained from the company on request.

This revised and expanded list covers entertainment types, including TV picture tubes; vacuum types for r.f. and a.f. power applications; vacuum types for pulsed-power applications; "Special Red," voltage-regulator, glow-discharge, and computer types; thyratrons, power rectifiers, oscillograph tubes, storage tubes, phototubes, and photoconductive cells; broadcast camera and television studio types; and industrial television types.

### NEWARK ELECTRIC CATALOGUE

*Newark Electric Company,* 223 West Madison Street, Chicago 6, Ill., is now distributing its new "1960 Industrial Electronics Catalogue," No. 70. Free copies of the catalogue are available through the firm's branch at 4747 W. Century Blvd., Inglewood, Calif., or at the main office in Chicago.

Geared specifically to the industrial user, the catalogue features wide range of quantity price breakdowns. The entire book is fully illustrated and contains comprehensive descriptions of all listed items. A separate "Product" and "Manufacturer" index facilitates easy, faster reference to any specific item listed.

### SWITCHING TRANSISTORS

*Sylvania Electric Products Inc.,* 1100 Main Street, Buffalo 9, N. Y., has published a new booklet entitled, "Medium and High Speed Switching Transistors." Copies may be obtained direct from the company.

The 24-page booklet lists maximum ratings and electrical characteristics for all *p-n-p* and *n-p-n* medium and high speed types in the firm's switching transistor line. It also contains nine transistor switching time measurement circuits, diagrams illustrating mechanical specifications and connections, and a section on transistor switching time requirements.

### SERVICING TRANSISTORS

*CBS Electronics,* 100 Endicott Street, Danvers, Mass., is making available a new bulletin entitled, "Servicing Transistor Equipment." It may be obtained through the firm's transistor and tube distributors or direct from the company's Information Services.

Written by Robert "Bud" Tomer, the bulletin recommends tools and equip-

# DON'T throw your money down the drain . . .

## Get Rad-Tel's First Quality Brand New TUBES

BETTER THAN 70% OFF!

GUARANTEED ONE FULL YEAR

ON USED AND "PULL OUT" TUBES!

**EACH TUBE INDIVIDUALLY AND ATTRACTIVELY BOXED! YOU CAN RELY ON RAD-TEL'S SPEEDY ONE DAY SERVICE!**

| Qty. | Type | Price | Qty. | Type | Price | Qty. | Type | Price | Qty. | Type | Price | Qty. | Type | Price | Qty. | Type | Price | Qty. | Type | Price |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 0Z4M | .79 | | 4BA6 | .51 | | 6AN4 | .95 | | 6CD6 | 1.42 | | 7A8 | .68 | | 12AU7 | .60 | | 12DL8 | .85 | | 17L6 | .58 |
| | 1AX2 | .62 | | 4BC5 | .56 | | 6AN8 | .85 | | 6CF6 | .64 | | 7B6 | .69 | | 12AV5 | .97 | | 12DM7 | .67 | | 17W6 | .70 |
| | 1B3GT | .79 | | 4BC8 | .96 | | 6AQ5 | .50 | | 6CG7 | .60 | | 7Y4 | .69 | | 12AV6 | .41 | | 12DQ6 | 1.04 | | 19AU4 | .83 |
| | 1DN5 | .55 | | 4BE6 | .54 | | 6AR5 | .55 | | 6CG8 | .77 | | 8AU8 | .83 | | 12AV7 | .75 | | 12DS7 | .79 | | 19BG6 | 1.39 |
| | 1G3 | .73 | | 4BN6 | .75 | | 6AS5 | .60 | | 6CM7 | .66 | | 8AW8 | .93 | | 12AX4 | .67 | | 12DZ6 | .56 | | 19T8 | .80 |
| | 1J3 | .73 | | 4BQ7 | .96 | | 6AT6 | .43 | | 6CN7 | .65 | | 8BQ5 | .60 | | 12AX7 | .63 | | 12EL6 | .50 | | 21EX6 | 1.49 |
| | 1K3 | .73 | | 4BS8 | .98 | | 6AT8 | .79 | | 6CR6 | .51 | | 8CG7 | .62 | | 12AZ7 | .86 | | 12EG6 | .54 | | 25AU4 | .87 |
| | 1L6 | 1.05 | | 4BU8 | .71 | | 6AU4 | .82 | | 6CS6 | .57 | | 8CM7 | .68 | | 12B4 | .63 | | 12EK6 | .56 | | 25BQ6 | 1.11 |
| | 1LA6 | .69 | | 4BZ6 | .58 | | 6AU6 | .50 | | 6CU5 | .58 | | 8CN7 | .97 | | 12BA6 | .50 | | 12EZ6 | .53 | | 25C5 | .53 |
| | 1LC6 | .79 | | 4BZ7 | .96 | | 6AU7 | .61 | | 6CU6 | 1.08 | | 8CX8 | .93 | | 12BD6 | .50 | | 12F5 | .66 | | 25CA5 | .59 |
| | 1LN5 | .59 | | 4CB6 | .59 | | 6AU8 | .87 | | 6CY5 | .70 | | 8EB8 | .94 | | 12BE6 | .53 | | 12F8 | .66 | | 25CD6 | 1.44 |
| | 1R5 | .62 | | 4CS6 | .61 | | 6AV6 | .40 | | 6CY7 | .71 | | 10DA7 | .71 | | 12BF6 | .44 | | 12FM6 | .45 | | 25CU6 | 1.11 |
| | 1S5 | .51 | | 4DE6 | .62 | | 6AW8 | .89 | | 6DA4 | .68 | | 11CY7 | .75 | | 12BH7 | .73 | | 12K5 | .65 | | 25DN6 | 1.42 |
| | 1T4 | .58 | | 4DK6 | .60 | | 6AX4 | .65 | | 6DB5 | .69 | | 12A4 | .60 | | 12BK5 | .70 | | 12SA7M | .86 | | 25EH5 | .55 |
| | 1U4 | .57 | | 4DT6 | .55 | | 6AX7 | .64 | | 6DE6 | .58 | | 12AB5 | .55 | | 12BL6 | .56 | | 12SK7GT | .74 | | 25L6 | .57 |
| | 1U5 | .50 | | 5AM8 | .79 | | 6BA6 | .49 | | 6DG6 | .59 | | 12AC6 | .49 | | 12BQ6 | 1.06 | | 12SN7 | .67 | | 25W4 | .68 |
| | 1X2B | .82 | | 5AN8 | .86 | | 6BC5 | .54 | | 6DQ6 | 1.10 | | 12AD6 | .57 | | 12BY7 | .74 | | 12SQ7M | .73 | | 25Z6 | .66 |
| | 2AF4 | .96 | | 5AQ5 | .52 | | 6BC7 | .94 | | 6DT5 | .76 | | 12AE6 | .43 | | 12BZ7 | .75 | | 12U7 | .62 | | 35C5 | .51 |
| | 2BN4 | .60 | | 5AT8 | .80 | | 6BC8 | .97 | | 6DT6 | .53 | | 12AF3 | .73 | | 12C5 | .56 | | 12V6GT | .53 | | 35L6 | .57 |
| | 2CY5 | .71 | | 5BK7A | .82 | | 6BD6 | .51 | | 6EU8 | .79 | | 12AF6 | .49 | | 12CA5 | .59 | | 12W6 | .69 | | 35W4 | .52 |
| | 3AL5 | .42 | | 5BQ7 | .97 | | 6BE6 | .55 | | 6EA8 | .79 | | 12AJ6 | .46 | | 12CN5 | .56 | | 12X4 | .38 | | 35Z5GT | .60 |
| | 3AU6 | .51 | | 5BR8 | .79 | | 6BF6 | .44 | | 6EB8 | .94 | | 12AL5 | .45 | | 12CR6 | .54 | | 17AX4 | .67 | | 50B5 | .60 |
| | 3AV6 | .41 | | 5CG8 | .76 | | 6BG6 | 1.66 | | 6H6GT | .58 | | 12AL8 | .95 | | 12CU5 | .58 | | 17BQ6 | 1.09 | | 50C5 | .53 |
| | 3BA6 | .51 | | 5CL8 | .76 | | 6BH6 | .65 | | 6J5GT | .51 | | 12AQ5 | .52 | | 12CU6 | 1.06 | | 17C5 | .58 | | 50DC4 | .37 |
| | 3BC5 | .54 | | 5EA8 | .80 | | 6BH8 | .87 | | 6J6 | .67 | | 12AT6 | .43 | | 12CX6 | .54 | | 17CA5 | .62 | | 50EH5 | .55 |
| | 3BE6 | .52 | | 5EU8 | .80 | | 6BJ6 | .62 | | 6K6 | .79 | | 12AT7 | .76 | | 12DB5 | .69 | | 17D4 | .69 | | 50L6 | .61 |
| | 3BN4 | .63 | | 5J6 | .68 | | 6BK5 | .80 | | 6S4 | .48 | | 12AU6 | .50 | | 12DE8 | .75 | | 17DQ6 | 1.06 | | 117Z3 | .61 |
| | 3BN6 | .76 | | 5T8 | .81 | | 6BK7 | .85 | | 6SA7GT | .76 | | | | | | | | | | | | |
| | 3BU8 | .78 | | 5U4 | .60 | | 6BL7 | 1.00 | | 6SK7GT | .74 | | | | | | | | | | | | |
| | 3BY6 | .55 | | 5U8 | .81 | | 6BN4 | .57 | | 6SL7 | .80 | | | | | | | | | | | | |
| | 3BZ6 | .55 | | 5V6 | .56 | | 6BN6 | .74 | | 6SN7 | .65 | | | | | | | | | | | | |
| | 3CB6 | .54 | | 5X8 | .78 | | 6BQ5 | .65 | | 6SQ7 | .73 | | | | | | | | | | | | |
| | 3CF6 | .60 | | 5Y3 | .46 | | 6BQ6GT | 1.05 | | 6T4 | .99 | | | | | | | | | | | | |
| | 3CS6 | .52 | | 6AB4 | .46 | | 6BQ7 | .95 | | 6T8 | .80 | | | | | | | | | | | | |
| | 3CY5 | .71 | | 6AC7 | .96 | | 6BR8 | .78 | | 6U8 | .78 | | | | | | | | | | | | |
| | 3DE6 | .62 | | 6AF3 | .73 | | 6BS8 | .90 | | 6V6GT | .54 | | | | | | | | | | | | |
| | 3DK6 | .60 | | 6AF4 | .97 | | 6BU8 | .70 | | 6W4 | .57 | | | | | | | | | | | | |
| | 3DT6 | .50 | | 6AG5 | .65 | | 6BY6 | .54 | | 6W6 | .69 | | | | | | | | | | | | |
| | 3Q5 | .80 | | 6AH6 | .99 | | 6BZ6 | .54 | | 6X4 | .39 | | | | | | | | | | | | |
| | 3S4 | .61 | | 6AK5 | .95 | | 6BZ7 | .97 | | 6X5GT | .53 | | | | | | | | | | | | |
| | 3V4 | .58 | | 6AL5 | .47 | | 6C4 | .43 | | 6X8 | .77 | | | | | | | | | | | | |
| | 4AU6 | .54 | | 6AM8 | .78 | | 6CB6 | .54 | | 7AU7 | .61 | | | | | | | | | | | | |

**Brand New JAN 3BP1 Cathode Ray Tube**

6.3v Deflect. Sensit.
Five X 5BP1—Electrostatic Focus & Deflection

**$1.45 each**

**Use This As Your Order Blank**

Rad-Tel Tube Co. 55 Chambers St. Newark, N. J.

NAME .....

ADDRESS .....

.....

# RAD-TEL TUBE CO.

Est. 1945

55 Chambers Street
Newark 5, N. J.
Mitchell 2-3147

**NOT AFFILIATED WITH ANY OTHER MAIL ORDER TUBE CO. . . . SPEEDY ONE-DAY SERVICE**
**TERMS: 25% deposit must accompany all orders, balance C.O.D. Orders under $5, $1 handling charge. Subject to prior sale. All shipments F.O.B. Newark warehouse. No C.O.D.'s outside continental U.S.A.**

**KEEP CANDEE HANDEE!**

**MODEL 84 MEASUREMENTS CORP. SIGNAL GENERATOR**
Frequency 300-1000 MC in one band. Individually calibrated direct reading dials. Frequency Accuracy ± 0.5%. Output voltage continuously variable from 0.1-100,000 microvolts. Output impedance 50 ohms. Modulation 0-30%. Choice of 400, 1000, 250 cycles. Pulse frequency 60-100 kc. in three ranges: 60-1,000, 600-10,000; and 6,000-100,000 pulses per second. Power supply 117 V., 50/60 cycles. Dim.: 13 x 26 x 12½". Approx. ship. wt. 160 lbs. **$149.95**
Excellent. Checked out..... **$100.00**
AS IS. Not checked out.....

**LP-5 SIGNAL GENERATOR**
Freq. 9.5-30,000 Kc. ± 1% in 7 bands. 30-50 Mc. ± 3% (extended range) Output imp. 10 ohms. Amplitude modulated. With power supply. Excel. Checked out. **$195.00**

**TS-182 ATTENUATOR SYNCHROSCOPE**
Calibrated! This unit also serves as 150-240 Mc Receiver **AND** a Signal Generator. Built in 115 V power supply. Measures peak RF power to 4 KV. Sig. generator built in. Excellent ..... **$19.95**

**APN-1 FM TRANSCEIVER**
420-460 Mc. Compl. with tubes. Exc. Ea. **$2.95**
Save by buying two for..... **$5.00**

**BC-603 FM RECEIVER**
**This Special Re-run By Popular Demand!**
20-27.9 MC. 10 push-buttons for channel selection. Continuous tuning. Squelch circuit. Complete with tubes, speaker (less dynamotor.) THIS IS BRAND NEW AND ONLY **$9.95**
Two for $18.95.
DM-34 12 v. DYNAMOTOR for above..... **$3.95**

**APR-1 RECEIVER**
Just removed from aircraft so you know it's good! Has self-contained 110 V. 60 cycles power supply. Input 110 V. 60 cyc. Excellent..... **$22.50**
**PLUG-IN TUNING UNITS FOR ABOVE:**
**TN-1**, 38-90 Mc..... **15.00**
**TN-2**, 80-300 Mc..... **15.00**
**TN-3**, 300-1000 Mc..... **19.95**

**AN/APA 38 PANADAPTOR**
115 VAC. Single phase. 400-2700 cycles. 30 Mc. adaptor. Approx. 10 Mc. band width. For conversion dope, see July/59 C.Q. Magazine. **$14.95**
Excellent cond.
**NEW TS-13 HANDSET Ea. $3.95; Two for $6.95**

**YOU GOT IT! WE WANT IT! LET'S DEAL?**
We're paying top $$$ for GRC-9; PRC-6, -8, -9, -10; GN-58A: All elect. test equip.

**BC-611 HANDIE-TALKIE CHASSIS**
Crystal controlled. 3-6 Mc. Brand new. Boxed. WITH antenna, less tubes, crystals, coils. Only ..... **$6.95**

**APX-6 TRANSPONDER**
A midget warehouse of parts! Blowers, three Veeder-Root counters, I.F. strips, cavity, over 30 tubes, etc. Includes 3E29 tube. Good cond. A STEAL AT ONLY..... **$14.95**

**BC-733 RECEIVER**
A sputnik tracker—see C.Q. Magazine Oct/59 for conversion. VHF. 10 tubes. 6-channel, crystal controlled. Freq. 108.3-110.3 Mc. Dual filter range. Excellent condition..... **$6.95**

**R-4A/ARR-2 RECEIVER**
234-258 Mc. 11 tubes. UHF, tunable receiver. See Aug/59 C.Q. Magazine for conversion. Excellent cond. **TWO** for $5.00. Each.. **$2.95**

**FAMOUS Q 5'ER RECEIVER**
190-550 kc. Excellent. With tubes..... **$9.95**

**SCR-522 TRANSCEIVER**
4-channel. Crystal controlled. 100-156 Mc. Ideal for 2 meters. Complete with tubes. Excel. ..... **$12.95**

*All items FOB Burbank, Calif., subject to prior sale. In Calif. add 4%. Min. order $3.95.*

**J. J. CANDEE CO.** Dept. R
**509 No. Victory Blvd., Burbank, Calif.**
**Phone: Victoria 9-2411**



**CRYSTAL CONTROLLED CONVERTERS**
**POLICE • FIRE • COMMERCIAL**



**For use with 12 V. Transistor type car radios— 26-50 MC.**
**$24.50**

Can be self installed in seconds. Other models for 108-162 MC available. Also complete line of conventional powered converters, tuners and receivers.

A practical converter for emergency use with powered home or auto sets. Tuneable over 12 MC, 26-50 MC or 108-174 MC..... **$13.95**



Also available crystal controlled up to 54 MC..**$18.95**

***ORDER TODAY OR WRITE FOR LITERATURE***

**KUHN ELECTRONICS**
20 GLENWOOD CINCINNATI 17, OHIO


ment for servicing transistor sets. It describes current and voltage measurements and includes a section on balancing output transistors.

Special precautions necessary when servicing transistor equipment are explained; they cover the use of ohmmeters and variable power supplies, the importance of test voltage polarities, and the dangers of testing by shorting circuits.

The author also covers transistor signal tracing and offers some practical hints on the use of high-power transistors.

### RADIO SHACK HANDBOOK

*Radio Shack Corp.*, Boston 17, Mass., is offering a semiconductor engineering guide keyed to the needs of both the engineer and the purchasing agent. Copies may be obtained by writing direct to the company, I & G Division.

The book includes two listings of the semiconductors of nine manufacturers: in sequence by parameter and function —the first such composite listing available to the industry—and a list by transistor and diode type number. Also included is a section of dimensioned mounting diagrams.

The 24-page handbook was prepared by the technical service department, Industrial and Government Division. Through revised semiconductor data and prices issued regularly, customers will have up-to-date information.

### ZENER DIODE HANDBOOK

*Motorola Inc.*, semiconductor products division, 5005 E. McDowell Rd., Phoenix, Arizona, has released a comprehensive, 130-page manual covering basic theory, design characteristics, and applications for zener (voltage limiting) diodes. Copies of the handbook are available for $1.00 from any of the company's semiconductor distributors throughout the country. Further information may be obtained from Dept. ZDH, at the above address.

This new handbook, the first of its kind, is intended to serve as a guide in the use of this component. Chapter headings include: "Characteristics of Silicon Zener Diodes," "Design Considerations," "Regulated Power Supplies," "A. C. and D. C. Amplifiers," and "Specifications and Testing Methods," among many others.

The book also contains numerous schematic drawings, tables, and curves, all based upon actual circuits that were designed and tested by the firm's engineers. References that have appeared in previous literature have been checked and incorporated to make this handbook as complete as possible.

Design engineers, hams, and hobbyists will find the book an excellent reference as well as a good introduction to a relatively little-known electrical component.

### SECO BROCHURE

*Seco Manufacturing Company*, 5015 Penn Ave., South, Minneapolis, Minn., has released a pocket-sized brochure which provides full details and specifications on the company's complete line.

Fully illustrated, this attractive 2-color folder also gives prices on all units. Free copies may be obtained by writing to the firm and requesting Form No. M-CO99.

### COMPONENTS BULLETIN

*National Radio Co., Inc.*, 37 Washington St., Melrose 76, Mass., has announced the availability of a new catalogue covering dials, drives, and mechanisms. Purchasing agents and engineers may request this new brochure by writing to the company and asking for Bulletin 59-6.

The new 8-page, two-color catalogue describes and gives specifications on an assortment of dials, rim and planetary drives, and vernier mechanisms, all available from regular stock.

### EIA STANDARDS

Electronic Industries Association has issued four new recommended standards. Copies may be obtained through the EIA Engineering Department, 11

Sylvania Electronic Tubes, a division of Sylvania Electric Products Inc., was named winner of the 1959 annual "NATESA Friends of Service Management" plaque. The award is made annually to companies which, in the judgment of NATESA, have rendered extraordinary service to the industry. This is the ninth consecutive year Sylvania has received the plaque. Present at the ceremony were (left to right) Frank J. Moch, executive director of NATESA; Donald W. Gunn, vice-president-sales for Sylvania; Matthew D. Burns, president of Sylvania Electric Tubes; Mac Metoyer, president of NATESA; and Harold H. Rainier, Sylvania distributor sales manager.

West 42nd Street, New York 36, N. Y.

RS-152-A "Land-Mobile Communication FM and PM Transmitters (25-470 mc.)." This is a revision of RS-152 from Standards Proposal 613. 80¢ each.

RS-226 "Television Picture Area—35mm. and 16mm. Motion Picture Film." This is a re-affirmation of Standards TR-136 and TR-137. 25¢ each.

RS-227 "One-Inch Perforated Tapes." This is new material from Standard Proposals 588, 577, and 544. 25¢ each.

RS-228 "Fixed, Tantalum Electrolytic Capacitors (Polarized)." This is new material from Standard Proposal 609. $1.65 each.

### REPLACEMENT BROCHURE

*G-C Electronics Co.*, division of *Textron Inc.*, 400 South Wyman St., Rockford, Illinois, is presenting a new 16-page illustrated catalogue giving complete cross-reference information on replacement knobs for leading makes of television sets. Copies of the catalogue may be obtained without charge from the company.

According to the firm, the brochure lists 97 different knobs—on-off, volume, fine tuning, channel selector—for various manufacturers. Information on colors, original parts numbers, set model numbers, and prices is included.

### CAREER BROCHURE

*Transitron Electronic Corporation*, 168 Albion St., Wakefield, Mass., has published a brochure entitled, "You . . . and *Transitron*." It is designed to be of interest to graduate engineers seeking opportunities in the field of semiconductors.

Engineering categories are described as fundamental research, applied research, advanced development and development, design, factory follow-up, manufacturing or industrial, quality control, home sales, application, and field sales or service.

Photographs introduce the reader to the general environment of the firm. In addition, the brochure devotes space to a pictorial description of the suburban New England area in which the company is situated.

### TUBE TESTERS

*CBS Electronics*, a division of *Columbia Broadcasting System, Inc.*, has made available a new "Tech Tips" bulletin, PA-500, entitled, "The Final Authority." It is available through distributors of the company's tubes.

Written by "Bud" Tomer, the booklet tells why the design of a universal tube tester is impractical, if not impossible. According to the author, ". . . tube testing is a very complicated business in spite of the popular notion to the contrary."

The pitfalls of relying on "universal" testers as the final authority to indicate whether a tube is good or bad are explained in considerable detail in this new bulletin. —30—


RADIO Handbook

AC & DC Circuits
VT Principles
Transistors & Semi-Conductors
VT Ampls.
High Fidelity
RF VT Ampl.
Oscilloscopes
Radiation, Propagation & Transmission Lines
Antennas
HF Ampls.

Fifteenth Edition
800 PAGES

Transceivers
Low Power Transmitters & Exciters
RF Feedback
Amplitude Modulation
FM & Radio Teletype Transmission
Sideband Transmission
Transmitter Design
TV & BC Interference
Transmitter Keying
HF Power Ampls.
Speech & AM Equipment
Transmitter Construction
Power Supplies
Workshop Practice
Electronic Test Equipment
Radio Mathematics & Calculations

$7.50 BUY FROM YOUR FAVORITE DISTRIBUTOR

BOOK STORES: ORDER FROM BAKER & TAYLOR CO., HILLSIDE, N. J.





"More than Citizens' Radio"...

a complete, fully engineered "industrial-type" transceiver!

VIKING Messenger

Anyone can operate—license issued by the FCC on request

from $129.75

- Complete 23 channel Citizens' Band coverage—choose 1 of any 5 channels by the flip of a switch.
- Maximum legal power—excellent range—meets all FCC requirements.
- Excellent receiver sensitivity and selectivity—full fidelity voice reproduction.

"More than just 2-way Citizens' Radio equipment"—the Viking "Messenger" will deliver the finest performance of any equipment available in the field. Designed throughout for 10 watt power level—limited to 5 watts for Citizens' Radio. Easy to install anywhere in your home, business location, car, truck or boat . . . offers many unique features found only on more expensive communications systems. Built-in Squelch, Automatic Volume Control, and Automatic Noise Limiter. Compact, modern styling—only 5⅜" high, 7" wide, and 11¾" deep. Complete with tubes, push-to-talk microphone, and crystals for one channel.

*Available from authorized Johnson Electronic or Marine Distributors. Installation and service coast-to-coast at all General Electric Communications Service Stations.*


Farming, delivery or fleet operation


Boat-to-boat or ship-to-shore communication

Your own personal or family use

Construction or "off-the-road" equipment

FREE Color Brochure

WRITE TODAY

E. F. JOHNSON COMPANY

103 Second Ave. S. W. • Waseca, Minnesota

• Please rush me your full color brochure describing the Viking "Messenger" Citizens' Transceiver.

NAME_____

ADDRESS_____

CITY_____ STATE_____

Manufacturers of the world's most widely used personal communications transmitters

**BC-603 $14.95 RE-NEW** | **BC-683 $24.95 RE-NEW**



BC-603 FM RECEIVER—20 to 27.9 MC....Re-New: $14.95
BC-683 FM RECEIVER—27 to 38.1 MC. U: $19.95—Re-N: $24.95
BC-604 FM TRNSMTR—20 to 27.9 MC..U: $4.95—Re-N: $ 7.95
BC-684 FM TRANSMITTER—27-39.1 MC.....Used: $ 7.95
FT-237 MOUNTING for Rec.-Trans....Re-New: $ 7.95
FT-346 MOUNTING for Receiver only..Re-New: $ 4.95
DM-34 DYN. 12V. f/BC-603-683—U: $2.95—R-N: $ 4.95
DM-35 DYN. 12V. f/BC-604-684—U: $6.95—R-N: $ 9.95
FT-354 TEST ADAPTER For BC-603 - 683 - 923—Used for testing various Voltages and Alignment of Receivers. Plugs into rear of set; has metering switch & provision for attaching output meter & V.T.V.M. Complete with 6 Ft. Battery Leads and Clips. Prices: USED: $2.95.....RE-NEW: $4.95

**BC-659 $16.95 RE-NEW** | **PE-120 $7.95 RE-NEW**

BC-659 FM RECEIVER-TRANSMITTER—27 to 39.1 MC FM.: 5 Watt.; Crystal Control on Two Pre-Set Channels; with Tubes and Speaker—Re-New.. **$16.95**
PE-120 POWER SUPPLY for BC-659 or BC-620; with Vibrator for 12 Volt operation—Re-New.....$7.95
BA-41 BIAS BATTERY F/BC-659-620....NEW: $4.95
AN-29 Telescoping ANTENNA F/BC-659..New: 2.95
FT-250 SHOCK MOUNT'G F/BC-659-PE-120—U: 4.95
SCHEMATICS F/BC-659-PE-120 w/voltage & Resistance: 2.00

**COLLINS ART-13 TRANS. — $49.50**
**2 TO 18.1 MC—100 WATT—PHONE, CW, MCW**

The most desired Set on the surplus market—Easily converted to 10 Meters (See Surplus Conversion Manual No. 2—$2.50). Automatic Tuning for selection of 11 Channels in the Freq. Range. Tube Line-Up: 1/837, 1/813, 2/1625, 1/12BJ7, 2/6V6, 2/811, 2/12BL7, 1/12SA7. AC Power Supply requirements: 28 VDC/10 A, 400 VDC/225 MA & 1250 VDC/250 MA. Size: 23½ x 16 x 11½. Wt.: 70 lbs. Price, USED: $49.50
Price—Same as above—except, Less Tubes..... 30.00
DY-12/ART-13 24 V. Dyn. w/Filter & Relays—U: 12.95

**ALL BAND RECEIVER**

NAVY ARB/CRV 46151—190 to 9050 KC—Four Band, 6 Tube Superhet—Local & remote tuning and band change; illuminated dial, sharp & broad tuning; AVC, CW, provisions for operation of DU-1 Loop. Complete with Tubes: 1/12SA7, 1/12A6, 4/12SF7, & 24 Volt Dynamotor. Size: 8 x 7 x 16"....Used: **$18.95**
ABOVE—Converted to 12 Volt, with Dynamotor (No electric band change) .....$24.95
Conversion for 115 V 60 cycle with Spin Dial, Phone Jack, CW, Volume Control, On & Off Switch (All on front panel) —KIT of Parts with Instructions.....$10.00
Conversion—as Above—for 12 Volt DC—KIT of Parts, with Dynamotor ..... 10.00
Remote Control Box: $2.00—Remote Control Shaft: 1.50
Remote Control Head ..... 2.00
Tuning Knob for large splined shaft..... 1.00
T-Shaft Adapter for remote and local tuning..... 1.50
PLUGS only—for Receiver or Control Box..Each: 1.00

**RECEIVERS:**

BC-783 Localizer Rec.—108.3 to 110.9 MC.Used:$ 4.95
R-23/BC-453 Rec.—190 to 550 KC.....Used: 14.95
R-4/ARR-2 Rec.—540-830 KC; 230-258 MC.R-N: 9.95
BC-1206 Beacon Receiver—200 to 400 KC.Re-N: 9.95
BC-652 Receiver—2 to 6 MC—Less Dyn...Used: 19.95
BC-342 Receiver—1.5 to 18 MC For AC op. Used: 69.50
BC-312 Receiver—1.5 to 18 MC Less Dyn.Used: 59.50
BC-344 Rec.—150 to 1500 KC—For AC op. Used: 49.50

**AC POWER SUPPLY**

F/BC-603-683 — Output: 220 VDC 80MA & 24VAC 2Amps. Tube Rectification; mounts on rear Plug of BC-603-683. Can be adapted to other Receivers. KIT: $10.00—WIRED: $14.95

**GROUND PLANE ANTENNA**
**CITIZEN—COMMERCIAL**

Made from sturdy surplus insulated Base and Screw-in type Elements. For use in the 25 to 50 MC Bands. Specially cut to your operating frequency. (Specify Freq. when ordering.) With Adapter for 1" pipe mounting..... **$14.95**

**TELEPHONES, HEADSETS, MICS., Etc.:**

TS-9 Handset.....Used: $2.95—New: $ 3.95
TS-13 Handset, w/PL-55 & PL-68..U: $2.95—N: 3.95
T-17 Microphone.....Used: $3.95—New: 6.95
EE-8 Field Telephone....Used: $12.95—Recond.: 16.95
BD-71 Switchboard—6 Line ..U: $14.95—New: 24.95
RM-29 Control Unit....New: $6.95—W/Handset 8.95
RM-52 Control Unit (Patch Found.) U: $1.95—N: 2.95
H-16/U Headset—8000 ohm.....U. $1.95—New: 2.95
HS-33 Headset—300 ohm.....U: $4.95—New: 7.95
J-45 Tel. Key—with cord and plug.....New: 1.50

***SEND FOR FREE CATALOG!***

Address Dept. RN • All Prices F.O.B., Lima, Ohio. Minimum Order $5.00, & 25% Deposit on all C.O.D.'s

**FAIR RADIO SALES**
132 SOUTH MAIN ST. • LIMA, OHIO

By
**BERT WHYTE**

# CERTIFIED RECORD REVUE

LAST month I reported on the progress that stereo is making and the change that is gradually taking place in American listening habits. On the whole it was an encouraging report, but unhappily it now becomes apparent that all is not sweetness and light and there is a very somber side to this story.

This is being written at the prime merchandising and sales time of the year and although hi-fi is no longer quite as seasonal as in years past, most companies will admit that the Christmas season constitutes a very healthy portion of their year's business. This year, according to a variety of sources, Christmas business was very "spotty." Some companies enjoyed boom sales with others falling far short of their anticipated goals. What is the reason? Steel strike? Creeping recession? Well, friends, it would be foolish to say the steel strike did not have any effect, but it is certainly not the prime reason for the falling off in sales. It appears that package manufacturers are taking the brunt of these sales setbacks, although some component manufacturers are also feeling the pinch.

In the record business, the situation is described by some as "chaotic." The recent investigations into disc jockey bribery, more commonly known as "payola," have thoroughly shaken public confidence, especially coming on the heels of the TV quiz scandals. A lot of people are really getting hurt in this confused period. *Westminster*, whose early LP's were audio landmarks for quality and who in subsequent years gained an enviable reputation among knowledgeable record enthusiasts, is a bankrupt and although frantic attempts are being made to pull it out of the fire, it may prove fruitless.

In my opinion, this whole mad situation can partially be attributed to some of the reasons outlined, but I think a more honest evaluation is that the public has been bombarded with reams of sales propaganda extolling the merits of stereo and then on finally being exposed to it, the whole thing did not meet expectations . . . just was not "as advertised." And the blame lies not just with the playback equipment, but with the recordings as well.

I have been shocked by the number of people . . . just "man in the street types" . . . who have quite vehemently stated that they thought stereo was "for the birds." These people had either purchased some junk equipment and then had compounded the sin by playing records whose over-all quality, let alone stereo attributes, was appallingly bad. An even larger percentage of these people had never arrived at the purchasing stage, having been repulsed and disillusioned by what they heard demonstrated in their local appliance and department stores. Apparently, the same individual who was victimized in the "hi-fi" days when he bought his "$69.50 hi-fi," is much more discriminating than the average package manufacturer believes, when it comes to stereo . . . evidently it is not enough to furnish him with two rudimentary amplifiers and speakers and a cheap stereo pickup.

Poor old John Q. has been oversold . . . he has been so propagandized that he approaches stereo with the preconceived notion that this is the supreme listening experience. And I have seen the situation grow more complex when some people tell me that they have stereo systems ( I should more properly say "sets") but that they prefer to play mono recordings on these sets!

While it is true that a bad recording will sound poor on the best component system and worse still on a bad one, it is unfortunately true that a good recording will also sound poor on a bad set. The worst part of this situation is that even with some of the more expensive packaged stereo outfits, the quality is marginal and under the demonstration conditions which usually prevail . . . poor acoustics, poorly maintained equipment, sales people either inadequately trained or trained not at all, and a choice of demo records that would give an audiophile a heart attack . . . it is no wonder there is a sales problem.

However, another point to be noted in this sales crisis is that despite these problems, a great deal of stereo is being sold. It is just that, with the expenditures of advertising money, the manufacturers expected a far greater return. Naturally the degree of sales loss (if it can be called that) varies greatly with individual companies . . . but obviously some companies have gotten into hot water by spending too much on advertising and merchandising without adequate product quality to support these expenditures. The lesson they are learning may be a bitter one, but they have no one to blame but themselves.

In the record end of things, there is also much public confusion, as many do not know the limitations of their equipment and thus blame the lack of satisfaction on the recordings they buy. And certain advertising practices of some record manufacturers lead the buyer "up the garden path" by implying that cost differentials have nothing to do with record quality. There are good cheap records and there are bad expensive records but, by and large, "you gets what you pays for." Everyone likes a bargain, but it seems to me a poor bargain to buy a recording just because it is cheap. All recordings should be bought on individual merit.

The economics of the record business are a pretty stable affair. It costs so much to record, press, advertise, and distribute. The profit margins, while comfortable, do not allow for extreme cuts or price wars. If quality is to be maintained a record has a certain minimum price at which it can be sold . . .

below this figure something has to suffer and it is almost always the quality—whether this be the sound quality, the material from which the record is made, what kind of wear can be expected, etc. It is also obvious that it is a great deal cheaper to record the "Braunschweiger Symphony of Lower Slobbovia conductd by Otto von Ersatz," than it is to record the Philadelphia Orchestra conducted by Eugene Ormandy.

And so the sorting out process continues . . . and the confusion of the public still must be resolved, if record and equipment sales are to progress and begin to reach anything like their potential. I believe the key to this is in taking an honest and realistic viewpoint of the stereo business, in giving the public stereo equipment sensibly engineered whatever the price range, and in advertising these products sanely and factually rather than with the ad agency's flights of fancy. Above all, *some effort,* however difficult it may be, should be expended in making certain that the people selling this equipment have at least had sufficient training to properly operate and demonstrate the models their store carries, and that they be taught a simple, honest, and factual explanation of stereo, which they can understand and which they can impart to a customer. This education, however simple it may appear, can win more people to stereo than all the fancy advertising money can buy.

The proof of the pudding in this is that those people who so shocked me with their disdain of stereo, "flipped" when I exposed them to some real stereo of good quality. One chap was positively astonished and wouldn't believe that a stereo disc was capable of such high quality. I had to play the discs of a number of companies for him and while he noted and appreciated stereo as never before . . . his education had already begun, since he also noted that there were quality differentials among the various discs.

I emphasize that this was strictly a lay person with no background or training in music or high fidelity. Perhaps of most importance was the fact that while he realized that I was playing the discs for him on top quality equipment and that lesser equipment would afford less enjoyment, he also stated that he now realized that a high quality disc was the prime requisite in stereo reproduction. Given this known quality, he would be enabled to choose more intelligently the stereo equipment he felt he could afford.

So there is the lesson stereo manufacturers would do well to learn . . . instead of moaning about the sales picture, do a little education . . . give the public a break and the sales will take care of themselves.

***HOLST***
**THE PLANETS**
**Vienna State Opera Orchestra with the Vienna Academy Chorus conducted by Sir Adrian Boult. Westminster Stereo WST14067. Price $5.95.**

Quite some years ago, Sir Adrian and *Westminster* created quite a sensation with a spectacular mono recording of this work. Now the same combination has given us a stereo "Planets" that must be accorded the same huzzahs. Boult gives us a majestic sweeping performance, that is very thrilling. Although many may prefer Stokowski's supercharged rocket-fueled reading, this is closer to the intent of the work and is certainly more idiomatic.

Boult probes the dynamic extremes of the score considerably aided by some superb stereo engineering. Here you will find excellent directivity, a fine exactitude in aural positioning of the instruments, a front-to-back sense of depth that is most realistic.

The over-all sound is very clean and this applies even in the biggest climaxes. Brass

CLIMB THE
PROFIT TOWER
in
2-WAY MOBILE-RADIO MAINTENANCE
Mobile radio communications are booming! All around . . . you can see the vertical radiators going up . . . each one is a definite lead to more and higher profits for qualified service men.
To learn more about contract fees . . . labor rates . . . and upping YOUR profits . . . mail the coupon below for your free copy of: "HOW TO MAKE MONEY IN MOBILE-RADIO MAINTENANCE."
LAMPKIN INSTRUMENTS ARE THE MOST POPULAR MOBILE-MAINTENANCE METERS.
LAMPKIN 105-B FREQUENCY METER. RANGE 0.1 TO 175 MC AND UP. PRICE $260.00 NET.
LAMPKIN 205-A FM MODULATION METER. RANGE 25 TO 500 MC. PRICE $270.00.
MAIL COUPON TODAY
LAMPKIN LABORATORIES, INC.
MFM Division BRADENTON, FLORIDA
LAMPKIN LABORATORIES, INC.
MFM Division, Bradenton, Florida
At no obligation to me, please send
☐ Free booklet ☐ Data on Lampkin meters
Name
Address
City State

FIRST and STILL BEST!
QUIETROLE
the ANSWER TO NOISY CONTROLS and SWITCHES
over
12 YEARS OF PROVEN SUPERIORITY
Costs Just Pennies more than the poorest substitute . . .
Supplied in Spray can and 2, 4, 8 oz. bottles
MFG BY QUIETROLE COMPANY, SPARTANBURG, South Carolina

Special Offer 25¢
Hear these authentic recordings of dramatic events from
"The Amazing World of Short Wave Listening"
narrated by Alex Dreier, Radio-TV "Man on the Go"
• President's voice from outer space!
• Actual capture of a desperate criminal!
• Radio amateur at Little America!
• Ships at sea . . . aircraft in action!
SX-110
receiver
$159.95
Standard broadcast plus short wave coverage from 1550 kc. to 34 mc. Cal. electrical bandspread.
MAIL COUPON TODAY!
hallicrafters
DEPT. 20, CHICAGO 11, ILL.
Gentlemen: Please rush by return mail my recording, "The Amazing World of Short Wave Listening." I enclose 25¢.
NAME
ADDRESS
CITY STATE

RCA



$200.00 Value

*factory overload!* exactly 249 sets for canny first comers

**RCA POWER AMPLIFIER *plus* RCA PRE-AMP CONTROL UNIT**

*both for only* **$74.95**

either ONE worth every penny of it!

NOT A KIT • FULLY ASSEMBLED • as illus.

*Direct from Importer to You*

STEREO-MATE or COMPLETE MONAURAL

New, exclusive electro-acoustic features include: *20-watt (40-watt peak) power output maintained to limits of audible frequency spectrum * infinitely variable loudspeaker damping factor * accurate disc record compensation * extensive filtering system * frequency response 0.2 db 20-25,000 c.p.s

ORDER NOW—NO MORE *EVER* AT THIS PRICE! 2 MONEY-BACK GUARANTEES—RCA'S AND OURS!

**RADIO CHASSIS**

*for both . . .* REGULAR RECEPTION SHORT WAVE RECEPTION

*. . . both* for less than 1/2 the price you'd expect to pay for either, with these EXCEPTIONAL FEATURES: **$34.95**

- 9 Tubes • 12" Extended Range Speaker
- Golden Throat Tone System • Superheterodyne
- Phono-Jack • 7 bands wave trap on short wave
- Magic Eye Tuning • 90 to 250 volts a/c
- Separate Treble and Bass Controls
- Short Wave—2.2 mc to 22 mc

WRITE Name, Address in Margin, enclose with Check or M. O. for 25% of order. Freight Prepaid.

**NEW YORK SALES & SERVICE**

911 Broadway, N. Y. 10, N. Y.



***engineering degree in 27 mos.***

Become an Electronics Engineer. Share rewards awaiting college men . . . higher income, rapid advancement. Important firms visit Tri-State to interview seniors. *Bachelor of Science Degree in 27 months* in Electrical (Electronics or Power major), Mechanical, Civil, Aeronautical, Chemical Engineering. *In 36 months* a B.S. in Business Administration (General Business, Accounting, Motor Transport Management majors). For earnest, capable students. Small classes. More professional class hours. Well-equipped labs. Dorms. Campus. *Modest costs.* Year-round operation. Enter Mar., June, Sept., Jan. Founded 1884. *Write J. H. McCarthy, Director of Admissions, for Catalog and "Your Career" Book.*

**TRI-STATE COLLEGE**

1620 College Ave., Angola, Indiana


sound is ultra-sonorous, especially in the "Jupiter" section, and throughout is some terrific percussion of great impact. The wordless chorus is nicely picked up in the final section and adds to the "mystic" impression of the work. Don't miss this one.

***TCHAIKOVSKY***
**MARCH SLAV**
**POLONAISE**
**EUGEN ONEGIN WALTZ**
**FRANCESCA DA RIMINI**
**Minneapolis Symphony Orchestra conducted by Antal Dorati. Mercury Stereo SR90201. Price $5.95.**

Potboilers all, to be sure but, boy, this pot is sure boiling over! This record is strictly for sound enthusiasts and Tchaikovsky buffs. The performances are all very good without gaining real distinction . . . the main thing here is the vast outpouring of hugely sonorous stereo sound. *Mercury* has really outdone themselves on this one. The brass growls and shrieks—high register and low—the strings work themselves into a fine frenzy in "Francesca" and there are monstrous bass drum thumps and much other percussion that is staggering in its power! The 60-watt amplifier and multi-woofer boys will have a ball here!

***SIBELIUS***
**SYMPHONY NO. 2**
**London Symphony Orchestra conducted by Pierre Monteux. Victor Stereo LSC2342. Price $5.95.**

This might, at first, seem an odd combination. However, Monteux shows his versatility by turning in a performance which must rank with the best to be found on records. There may be some who will quibble and state that his approach is too lyrical and in this there is probably some justification. For purists, Monteux's Sibelius lacks the sense of power and is less disciplined than the readings of such as Ehrling or Paul Kletzki. But, after all, it is a romantic symphony albeit with a heroic finale and what better man than Monteux to clearly delineate all the marvelous color and the final detail of orchestration that is so much a part of Sibelius' writing.

As with most of his recordings with the London Symphony, he elicits some of their very best playing and, technically, *Victor* always seems to achieve a better-than-average sound with this orchestra. Stereo-wise this has excellent directivity and each instrument is clearly highlighted and most articulate. The excellent acoustics of Walthamstow Town Hall in London contribute to the sense of depth and spaciousness.

The recording itself is very clean and has fairly wide dynamics with my only reservation a slightly over-heavy bass line. If you like your Sibelius in the most romantic fashion, with none of the stern character of the North with which so many other conductors try to imbue this work—this recording is for you.

***WALTON***
**FACADE SUITES #1 & #2**
***LE COCQ***
**MAM'ZELLE ANGOT (Ballet Suite)**
**Royal Opera House Orchestra conducted by Anatole Fistoulari. Victor Stereo LSC2285. Price $5.95.**

Here is a recording that should certainly keep your feet tapping and your soul full of high spirits. Both the Walton and the Le Cocq works are breezy, racy, sort of tongue-in-cheek orchestral expositions that have no particular pretentions and, above all, are very great fun.

Of course, there are probably many people who would like to have Dame Edith Sitwell make a new recording in stereo, with her reciting or doing whatever fantastic thing it is she does with her voice, the inimitable madness of her poetry. On the other hand, there are just as many people who consider her monotonous droning voice merely an obfuscation and wish she would get out of the way of the music. At any rate, this is about the best recording of the musical aspect of this work at present and is much to be preferred to the recent Kostelanetz version.

"Mam'zelle Angot" is one of those mad mixed up French pieces which seem to combine the writings of half-a-dozen or more composers. But the orchestration and the mood it engenders is very frothy and effervescent. it's a harmless little thing and should be enjoyed by almost everyone except old curmudgeons and communists.

Fistoulari is an old ballet hand and his performances are properly paced and neatly scaled and reflect an intimate knowledge of both scores. Very good stereo sound here too, with the recording perhaps a shade too reverberant for some tastes but in spite of this, a very clean recording with excellent transient response, especially in the high percussives which abound in these works.

***GRIEG***
**PEER GYNT SUITE #1**
**SYMPHONIC DANCES**
**ELEGIAC MELODIES**
**Halle Orchestra conducted by Sir John Barbirolli. Mercury Stereo 90164. Price $5.95.**

Sir John has a very straightforward way with these Grieg pot-boilers . . . no nonsense, no individualistic ideas on tempi, no mannerisms intrude on the music. The result is very acceptable after so much "interpretation" at the hands of other conductors. *Mercury's* superb stereo makes this the "best yet" recording of these works. Everything is beautifully clean, in fact the level of distortion here is virtually non-existent. The directional and depth aspects are fully realized and dynamic range is impressively wide.

There is some very powerful percussion in "Peer Gynt" and the "Symphonic Dances" which will be the delight of sound aficionados. Highly recommended.

***STRAUSS, RICHARD***
**ALSO SPRACH ZARATHUSTRA**
**Vienna Philharmonic Orchestra conducted by Herbert von Karajan. London Stereo CS6129. Price $5.95.**

This is Herbert von Karajan's debut on the *London* label and an event eagerly anticipated. The recording has been highly touted in England as a veritable *tour-de-force* in matters of sound, ranking along with *London's* fantastic "Das Rheingold."

Well, friends, I dunno what happened to the recording that was sent to me, for rarely have I been so disappointed. There are some interesting moments and some nice clean tympani shots, but outside of that, I found this one of the dullest sounding stereos ever issued by *London*. I can't understand or believe that it was intentionally recorded in that fashion. First of all the recording is at an astonishingly low level, and while wide dynamics are strived for, the whole thing is shifted in scale or perspective so that the *pianissimos* are just faint whispers. And mind you, this is at a volume setting designed to give some weight to the *fortes*. The result is that unless you possess the very top quality preamp and amplifier you will be inundated by hum and hiss in the quiet passages. My system is dead quiet, but at the level mentioned for the *fortes*, then the normally quiet *London* surfaces are heard *above* the *pianissimos!* It is beyond me . . . next time I am in England I'll get a copy over there and see if there is any difference.

Karajan's performance is good but doesn't generate the power and excitement of the

Fritz Reiner version. Of course, the sound problem may contribute to this feeling.

*SCHUMANN*
**SYMPHONY #1 ("SPRING")**
**MANFRED OVERTURE**
**Cleveland Orchestra conducted by George Szell. Epic Mono LC3612. Price $3.98.**

This follows hard on the heels of Paray's recent *Mercury* recording and is interesting in that despite national backgrounds, one of which would favor a Schumann recording and the other supposedly not, the end result is remarkably similar. Szell stays close to the score and employs no mannerisms and everything proceeds just about the way it should. Paray has the slightly lighter touch and Szell the greater sonority. The *Mercury* has a cleaner over-all sound, but lacks the better acoustics and stronger bass line of this recording. Fine playing from the Clevelanders.

*SMETANA*
**MA VLAST (Symphonic Poem Cycle)**
**Vienna Philharmonic Orchestra conducted by Rafael Kubelik. London CS2202. Two discs. Price $11.90.**

This is a hugely proportioned work in six sections which are given descriptive titles. From this is derived the lovely "Der Moldau" and "From Bohemia's Meadows and Forest." It is an intensely nationalistic piece and as you might expect a perfect vehicle for Kubelik's talents. He has done this before on a *Mercury* record with the Chicago Symphony and this new version is almost untouched as to his interpretation.

I made one of the earliest stereo recordings on that occasion and one of the problems to cope with was the acoustics of Orchestra Hall, which usually are so apropos for most music. The "Sarka," "Tabor," and "Blanik" sections of this work are as thickly scored as you are likely to find and they created textural difficulties. *London* does not entirely escape this problem, but the stereo helps out quite a bit as it did in my recording.

The *Mercury* was a fine sound despite the problems but now must give way before this stereo version. There are some huge sounds in this work, especially in "Sarka" and "Tabor." "Tabor" has nice, big, clean tympani and great weighty brass and ultra-sonorous contrabassi. Here again *London* is essaying an extraordinary wide dynamic range and once more I make the comment that although this is at a higher level than the "Zarathustra," the *pianissimos* are still so low as to be masked a bit by surface noise. But this is minor in the over-all sonic impact which is considerable. Kubelik's performance is completely authentic and should go unchallenged for a long time.

*SCHUMANN*
**ADAGIO AND ALLEGRO FOR HORN**
*HAYDN*
**TRUMPET CONCERTO IN E FLAT MAJOR**
*MOZART*
**FLUTE CONCERTO #2 (K. 314)**
**Edmond Leloir, horn; Paolo Longinotti, trumpet; and Andre Pepin, flute with L'Orchestre de la Suisse Romande conducted by Ernest Ansermet. London Stereo CS6091. Price $5.98.**

This is a wonderful recording, with the prize piece being Haydn's incredible "Trumpet Concerto." This has always been a challenge to any virtuoso and Longinotti acquits himself nobly. Even in the stratospheric reaches of the score he is very steady and his attacks are beautifully precise. The other soloists are equally distinguished and give thoroughly refined readings, which are lovely to hear.

Ansermet is quite satisfactory in this (for him) unusual role and his accompaniments are sympathetic. Fine stereo sound throughout, and a low bow to the trumpet. —30—

Now!

Checking Signal Strength *Anywhere*
. . . IS AN EASY ONE-MAN JOB!



JERROLD
MODEL TMT
*Direct Reading*
TRANSISTORIZED
FIELD STRENGTH METER
*only* $135. *net weatherprotecting leather carrying case, $12.95 net*

Now you can measure *exactly* how much signal is in the area, coming off the antenna, coming off the down lead and is at the set! Just 4½ pounds of rugged instrument, the radically new Jerrold TMT responds only to the TV sync signal to which it is tuned and is therefore immune to noise . . . carries its own power supply (4 simple "c" batteries). Tailor-made for the professional television serviceman and systems technician, the TMT:

- provides accurate (± 3 db) signal strength readings
- reads directly, not relatively in microvolts (100 to 2,000,000) in 8 switchable ranges
- for probing and orienting antenna signals and measuring distribution systems
- checks horizontal synchronizing frequencies in TV receivers

JERROLD ELECTRONICS CORPORATION, Distributor Sales Division
PD 192 The Jerrold Building, Philadelphia 32, Pa.
Jerrold Electronics (Canada) Limited, Toronto
Export Representative: CBS International, New York 22, N.Y.

The Top Technical Reference
To High Fidelity
Is Yours For Only $1.00!

**1960 HI-FI ANNUAL & AUDIO HANDBOOK**

On sale at Newsstands and electronic parts stores or order by coupon today!

If you're a man with a background in electronics theory and you know your way around hi-fi—here's a perfect workshop companion! It's the all new 1960 Edition of the HI-FI ANNUAL & AUDIO HANDBOOK that will provide you with the latest available technical information. And its cost—just $1.00.

You'll find over 30 big, definitive articles—prepared under the supervision of the Editors of ELECTRONICS WORLD. Gives you five big sections covering:

**STEREO**—Authoritative articles on low cost systems...adding a third channel...phantom channels.

**AMPLIFIERS AND PREAMPLIFIERS**—Features on the push-pull single stage for both stereo channels...single stereo amplifiers.

**LOUDSPEAKERS AND ENCLOSURES**—All that's new on loudspeakers for stereo...reflex enclosures and how they work...testing electrostatic loudspeakers...simplexing for low-level crossover...hi-fi crossover networks.

**FM, TAPE RECORDERS AND RECORD CHANGERS**—How to improve your FM tuner...tips on FM alignment...drift and A.F.C. in FM...FM Multiplex...20 CPS tape recorder switch...measuring flutter...slow speed tape recording...reducing recorder noise and hum...electronic level indicators.

**PLUS—GIANT COLOR FOLD-OUT SECTION** on "Sound": authoritative charts on audio frequency ranges...sound levels ...equal loudness curves.

All the skill and know-how of the nation's top hi-fi authorities are yours for only $1.00 in the 1960 HI-FI ANNUAL & AUDIO HANDBOOK. Use handy coupon below to order by mail today!

Ziff-Davis Publishing Company
Department EW 260
434 S. Wabash Avenue
Chicago 5, Illinois

Please send me a copy of the 1960 HI-FI ANNUAL & AUDIO HANDBOOK. I enclose $1.00 plus 10¢ to cover mailing and handling charges. (Canada and Foreign $1.25 plus 10¢ postage).

NAME_____

ADDRESS_____

CITY_____ ZONE____ STATE_____

# Sound on Tape

By BERT WHYTE

NOT much news or review material this month, although some classical four-track finally showed up. Everything seems fairly quiet in the tape world with the impetus of four-track seemingly slowed a bit . . . probably a seasonal thing, however.

In another development, *Minnesota Mining* has announced a new type of tape cartridge which, in some clever way, combines the cartridge and reel concepts. *But*, and I really flipped at this information, the tape to be used is ⅛ inch wide and is to operate at a speed of 1⅞ ips. Gadzooks! The ⅛ inch tape is said to permit a tighter wrap and thus closer contact with the recording or playback gap, with subsequent improvement in frequency response. Total frequency response was not given.

Well, I have a lot of respect for the very smart boys up at *3M*, but this one sounds like a dilly. I am really going to be from Missouri on this one. If it is to be used for speech or some such, why, no comment—but if this is ultimately intended to furnish playback of music, I can't envision it being used for anything other than low-fi background stuff. Classical music? That is another question and I would view such a development with a very jaundiced eye. I don't say that it can't be done, but it sure is going to take some doing to inscribe sufficiently high frequencies and maintain a good enough signal-to-noise ratio to please the serious audiophile.

### MUSIC FROM "FOR WHOM THE BELL TOLLS"

**Ray Heindorf and Orchestra. Warner Bros. 4-channel Stereo BST1201. Price $7.95.**

Now here is a unique side of Ray Heindorf—that of a good movie music man. He is an old hand at this trade and knows how to suffuse any score with the proper drama and expression. "For Whom The Bell Tolls" is, of course, the music from the great picture of the same name. It is typical of its genre, a strange admixture of powerful programmatic material with "love theme" and other devices which some find just too ultra-saccharine and cloying to the musical palate. It goes without saying that to listen to this music without having seen the picture is to add another burden to its acceptance.

The score is well played and equally well recorded. Balances within the orchestra are correct and all is quite clean and projects very well. The frequency range is broad and the dynamics somewhat less than you would expect. Directional and depth effects are nicely handled in the felicitous acoustics. Even on my big system there was no discernible cross-channel modulation and, at good room-filling level, the tape hiss was reasonably unobtrusive.

### *SAINT-SAENS* SYMPHONY #3

**Detroit Symphony Orchestra conducted by Paul Paray. Mercury 4-channel Stereo STC90012. Price $7.95.**

This is the first classical from a major company I have received in the four-track stereo format. If this is a forerunner of what we can expect from a major company in this medium, then we are off to a good start. This is the first four-track stereo that I can say, without reservation, is able to compete on even terms with the older two-track. It is noticeably free from distortion and, played at a good room-filling level, the background hiss was roughly equivalent to that usually found on two-track. Frequency response was excellent at both ends of the spectrum.

It may interest you to know that the very low-frequency organ passages in the first movement, at about 30 to 50 cycles, came through with startling clarity and volume . . . better than on the stereo disc I have on hand of this same recording.

All else is very articulate and the brass and strings have a brightness which signifies that the highs are well and truly being reproduced. Good as the stereo disc is, there is no denying the tape its superior separation. The stereo effects are much more pronounced.

Of the performance, I covered this in this recording's initial issue and suffice it to say, this is Paray's meat and the reading extraordinary. So I can wholeheartedly recommend this to all but those who are very cranky about hiss. There is nothing I like about hiss either and it existed on two-channel at about the same level. Nobody seems to be able to do anything about it, so we will all just have to learn to live with it.

I hope that a few more classicals will arrive before next month and we will have to wait and see if there is any improvement. —30—

## Citizens Radio Directory

(*Continued from page 40*)

hand, if one or both of the antennas are directional and are on a high hill or mountain, distances on the order of 20 to 50 miles are possible. Under unusual ionospheric conditions when the skip is right, signals have been heard for several thousand miles. However, this type of operation is not reliable nor is it the type of service for which Citizens Radio was intended.

### Features of Radio Units

You can buy a single Citizens Radio unit for as little as $40 in kit form or you can pay over $200 for an elaborate factory-wired unit. Remember that you will need two such units to set up a communications link. Also, most units require separate antennas which will add at least $5 to $10 for each unit for a simple whip to as much as $30 to $100 for each unit for more elaborate and directional antennas. What is more, some units require separate power supplies for mobile operation. This could add $5 to $10 or more for each unit. All in all, the least expensive link involving two stations would cost around $100. If you are con-

Arkay "Sky Vox" Model SQ-9 transceiver, manufactured by Arkay Radio Kits., Inc. Power requirements: 117 volts a.c. at 60 watts or 12 volts d.c. at 5 amps. Receiver: 3-channel fixed-tuned crystal-controlled superhet type with r.f. amplifier and i.f. amplifier stage; noise limiter and squelch circuits are provided. Transmitter: 3-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with one set of crystals for single-channel operation. Cabinet dimensions: 11¼" x 5½" x 8½"; weight: 12 lbs. Price: $89.95 in pre-wired sub-assembly kit form, including microphone.

Kaar Model TR-326 "D Phone" transceiver, manufactured by Kaar Engineering Corp. Power requirements: 117 volts a.c.; also available for 12 volts d.c. and for 6 volts d.c. Receiver: 2-channel fixed-tuned crystal-controlled superhet type with r.f. stage; noise limiter and squelch circuits are provided. Transmitter: 2-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with one set of crystals for single-channel operation. Cabinet dimensions: 8¾" x 5" x 8"; weight: 10 lbs. Price: $170, including microphone.


# We'd like to send you these important new books for a 7-day free trial examination

## CITIZENS RADIO by Leo G. Sands

Here is the first complete book on Citizens Radio Operation. Ever since the initial use of 2-way radiotelephone by police departments, this field has been growing in importance and application. Now, with more than a million vehicles equipped for its use, Citizens Radio is a major phase of the electronics field. This important new volume covers every aspect of the field—its history, rules, and everything about how it works—in seven big chapters with one hundred major sections. You'll learn exactly what Citizens Radio is, its applications, what equipment you need, the full story on receiver circuits and transmitters, antennas, installation, and maintenance, full FCC rulings, how to apply for licenses, etc. Many illustrations. **$4.95**




## COMPUTERS AND HOW THEY WORK by James Fahnestock

Here is a fact-filled exciting guidebook to the wonderworld of electronic computers, with more than 120 illustrations and easy-to-follow tables in 10 big chapters. Step by step, you'll see and understand the workings of every type of computer ever used. This important new book illustrates the basic principles of computers in methods that require no knowledge of electronics. You'll learn all about computer memories, flip-flops and the binary counting system. You'll learn the mathematical language of computers where $1 + 1 = 10$. Other chapters show you how computers use tubes and transistors to make complex logical decisions in thousandths of a second. COMPUTERS AND HOW THEY WORK is must reading for career minded students and for electronics pros who want a more complete knowledge of this field. **$4.95**

## THE ELECTRONIC EXPERIMENTER'S MANUAL by David A. Findlay

With a few dollars worth of basic tools, and this book to guide you, you can explore the magic of electronics experimentation more completely than ever before. In a few short hours, you'll start your first project. You'll learn about every component used in experimentation, every tool, its function and why it is used. There are 10 big sections, each covering a specific phase of construction. There is a giant section of projects you can build, test equipment you'll construct and use in your future work. THE ELECTRONIC EXPERIMENTER'S MANUAL will give you the professional know-how you must have no matter what phase of electronics is your specialty. **$4.95**

## 7 DAY FREE EXAMINATION

When your books arrive, read and enjoy their diversity of contents, their thoroughness of coverage. Then after seven days examination, if you decide that they are not everything you want, send them back and receive a complete refund of the purchase price.

**USE THIS CERTIFICATE FOR 7 DAY FREE EXAMINATION**

**ELECTRONICS BOOK SERVICE • A Division of the Ziff-Davis Publishing Co.**
**434 South Wabash Avenue, Chicago 5, Ill.**

Please send me _____ copies of CITIZENS RADIO and bill me at only $4.95 a copy plus a few cents postage.

Please send me _____ copies of COMPUTERS AND HOW THEY WORK, and bill me at only $4.95 a copy plus a few cents postage.

Please send me _____ copies of THE ELECTRONICS EXPERIMENTER'S MANUAL and bill me at only $4.95 a copy plus a few cents postage.

If I don't agree that this is one of the best electronics investments I've ever made, I may return the book(s) within seven days and get a full refund.

$_____ enclosed. (SAVE MONEY! Enclose payment with your order and we'll pay the postage.)

Name_____

Address_____

City_____ Zone_____ State_____

EW260

Easier-to-build
Grommes
HI-FIDELITY KITS
LAYER BUILT COLOR GUIDE

"Best buy in its field"
—LIFE MAGAZINE

**18 WATT AMPLIFIER**—With built-in pre-amp. 20 watts peak. All quality components. Frequency response ± 1DB. 20-20,000 CPS. 4 inputs. Outputs 4, 8, 16 ohms. Treble, Bass and exclusive Automatic Loudness Control. Punched chassis, color coded, step-by-step instructions. Easily and successfully assembled by anyone with screwdriver, pliers and soldering iron. Model LJ6K . . $24.95

20 WATT STEREO AMPLIFIER with built-in pre-amp and all controls. Model 20LJK...$59.50

PRE-AMPLIFIER Self powered. 10 controls...207AK...$44.50

60 WATT BASIC AMPLIFIER Model 250K . . . $79.50

*Many other kits available—*
*At dealers or sent prepaid with check or M.O.*

. . . . . FREE!

GROMMES Div. of Precision Electronics, Inc.
9101-Q King Ave., Franklin Park, Ill.
Please rush details on Grommes Kit Line.
Name_____
Address_____
City_____State_____
Your Dealer's Name_____

WHO NEEDS
MILES OF WIRE?
GET
HOME ELECTRICITY
ANYWHERE
WITH A
terado
CONVERTER

Change 6 or 12 volt D.C. to 110 volt, 60 cycle A.C.

**No Installation**—Just plug into cigarette lighter of car, truck, or boat, and it's ready to go!

Operate lights, electric shavers, dictation machines, record players, small electric tools, portable TV, and testing equipment.

Models from 15 to 200 watts, with prices as low as $12.95.

"Chief": 75-125 watts, for 6 or 12 volt batteries . . $64.95 LIST

See Your Electronic Parts Dealer or Jobber
terado COMPANY
DESIGNERS & MFRS. OF ELECTRONIC EQUIPMENT SINCE 1937
1058 RAYMOND AVE., ST. PAUL 14, MINNESOTA
IN CANADA: ATLAS RADIO CORPORATION LTD. ONTARIO

Philmore Model TC-11 transceiver, manufactured by Philmore Mfg. Co., Inc. Power requirements: 117 volts a.c. at 35 watts; also available for operation at 6 volts d.c. at 5 amps. or 12 volts d.c. at 3 amps. Receiver: 3-channel fixed-tuned superregenerative type with r.f. stage. Transmitter: 3-channel crystal-controlled type with 5 watts final plate input power. Units are normally supplied with one crystal for single-channel operation. Cabinet dimensions: 10" x 4⅛" x 10⅞"; weight: 11 lbs. Price: $39.95 for 117-volt model in kit form, including ceramic microphone.



World Radio Model ECBK transceiver, manufactured by World Radio Laboratories. Power requirements: 117 volts a.c. at 35 watts; separate power supply needed for 6- or 12-volt battery operation. Receiver: tunable superregenerative type with r.f. stage. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Price: $39.95 in kit form.

sidering a large number of more elaborate units with directional antennas, the system cost may be in the thousands of dollars.

Most of the units we have encountered are *transceivers*. This means that some of the tubes and circuits are used for both transmitting and receiving. The most common arrangement is to use the audio tubes as microphone amplifier and modulator while transmitting and as the audio voltage amplifier and power output tube while receiving. In addition, the power rectifier is used for both transmitting and receiving. By making some of the circuits do double-duty in this way, the manufacturer is able to cut down on the size of the unit and the number of circuits used.

Power requirements are very modest, running between about 30 to 60 watts from the 117-volt a.c. line for most units. The d.c. requirements are also quite reasonable, and most of the units draw no more current from the car's or boat's storage battery than would be drawn by a conventional auto broadcast receiver.

Receivers in use are either superregenerative types or superhets. They may either be tunable over the entire band or fixed-tuned to one or more channels. The superregenerative receiver is quite simple and much sensitivity can be obtained in the single detector stage used. On the other hand, the superregenerative detector is quite broad in its tuning and it radiates a signal that could produce harmful interference. To overcome these effects, the detector is preceded by an r.f. amplifier.

Superhet receivers used in the Citizens Radio units are either ordinary single-conversion or double-conversion types. R. f. stages are usually included for added selectivity and anywhere from one to three i.f. stages are used for high sensitivity. Noise limiters, particularly useful in reducing ignition noise interference, are common in these superhets. Also, squelch circuits, which quiet the receiver completely when there is no signal coming in, are widely used. Many of these are adjustable to control the amount of squelch. Too much squelch cuts down the sensitivity of the receiver, while insufficient squelch is not effective in reducing no-signal noise.

The transmitters are fixed-tuned to one or several channels. The circuit is a conventional crystal oscillator, which must be held to within a .005 per-cent frequency tolerance of one of the

Acton Model TCV-271 transmitter-receiver, manufactured by Acton Laboratories Inc. Power requirements: 117 volts a.c. at 45 watts or 12 volts d.c. Receiver: single-channel fixed-tuned crystal-controlled dual-conversion superhet with r.f. and i.f. stage; noise limiter and squelch circuits are provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 12" x 4" x 6"; weight: 9 lbs. Price: $179.95, including carbon microphone. (Model TCV-2 is also available with a tunable receiver and 3-channel transmitter at $189.95.)




Radio Shack Model CBK-1 transceiver, manufactured by Radio Shack Corp. Power requirements: 117 volts a.c. at 35 watts; separate power supply needed for 6- or 12-volt battery operation. Receiver: tunable superregenerative type with r.f. stage. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Price: $39.95, including crystal microphone.

Citizens Radio channels. This is followed by a power amplifier stage. Simpler units use a single dual-purpose tube for both functions.

The units are fairly small in size and light in weight so that they can be moved easily or readily installed in autos or boats.

Many of the transceivers employ ceramic microphones which, unlike some crystal types, are not affected by heat and humidity. Some of the units use rugged carbon microphones and few use the built-in loudspeaker as a dynamic microphone when transmitting. Push-buttons on some of these microphones are used to transfer the function of the unit from transmitting to receiving. In other cases, switches are mounted directly on the operating panel to perform this function.



Maxwell "Radiocom" Model 27C-1 transceiver, manufactured by Maxwell Electronics Corp. Power requirements: 117 volts a.c. at 60 watts; also available with transistor power supply for 12 volts d.c. at 4.5 amps. or for 6 volts d.c. Receiver: single-channel fixed-tuned crystal-controlled superhet type with 2 r.f. stages and single i.f. stage; noise limiter and squelch circuits are provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 7⅛" x 3½" x 11¼"; weight: 6 lbs. Price: $159.50, including carbon microphone.

Radson Model RT-70 transceiver, manufactured by Radson Engineering Corp. Power requirements: 117 volts a.c. at 50 watts. Receiver: single-channel fixed-tuned crystal-controlled superhet with r.f. stage and two i.f. stages; noise limiter is provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 9½" x 6" x 4"; weight: 9 lbs. Price: $149.95, including carbon microphone. (Model RT-75 is also available for 6 or 12 volts d.c. at $159.95.)

Wightman "We-Phone" Model WE-PTI transmitter-receiver, manufactured by Wightman Electronic Eng. Co. Power requirements: eight self-contained 1½-volt batteries. Receiver: single-channel fixed-tuned crystal-controlled transistorized superhet with r.f. stage and two i.f. stages; noise limiter circuit provided. Transmitter: single-channel crystal-controlled transistorized type with 100 milliwatts oscillator input power. Cabinet dimensions: 9¾" x 3½" x 2¾"; weight: 2¼ lbs. Price: $149.50, including speaker-microphone and built-in antenna.

Pearce-Simpson Model CBD-1 transceiver, manufactured by Pearce-Simpson, Inc. Power requirements: 117 volts a.c. or 12 volts d.c. Receiver: single-channel fixed-tuned crystal-controlled superhet type; noise limiter and squelch circuits are provided. Transmitter: single-channel crystal-controlled type with 5 watts final plate input power. Cabinet dimensions: 7" x 4 5/16" x 10"; weight: 10 lbs. Price: $159.50, including carbon microphone.

Since the user may purchase his antenna from a manufacturer other than the one making his transceiver, he should check that the antenna fitting is the proper mate for the connector on the transceiver. If it is not, it will be necessary to change the antenna fitting so that a proper connection may be made.

With the very wide selection of Citizens Radio units available, most of which are illustrated and described in this article, our readers should have no trouble in picking a pair that will meet all their requirements. —30—

## CALENDAR of EVENTS

| Sun | Mon | Tue | Wed | Thu | Fri | Sat |
|---|---|---|---|---|---|---|
| | | | | | 4 | 5 |
| | | | | | | 12 |
| | | | | | | 19 |
| | | | | | | 26 |

**FEBRUARY 3-5**

*1960 Winter Convention of Military Electronics.* Sponsored by Institute of Radio Engineers. Biltmore Hotel, Los Angeles. Details from IRE, 1 E. 79th St., New York 21, N. Y.

**FEBRUARY 10-12**

*Solid State Circuits Conference.* Sponsored by PGCT, AIEE, and University of Pennsylvania. University of Pennsylvania, Philadelphia. Program information from T. R. Finch, Bell Telephone Labs, Murray Hill, N. J.

**FEBRUARY 11-13**

*First Annual Convention.* Sponsored by Electronic Representatives Assn., Drake Hotel, Chicago. Information from ERA headquarters at 600 S. Michigan Ave., Chicago 5, Ill.

**FEBRUARY 16-18**

*First National Symposium on Non-Destructive Testing of Aircraft and Missile Components.* Sponsored by Southwest Section of SNT, Inc., and Southwest Research Institute. Hilton Hotel, San Antonio, Tex. W. E. Cory, General Chairman, Southwest Research Institute (Unclassified), 8500 Culebra Road, San Antonio, Texas.


# FIX ANY TV OR RADIO ever made!

## COMPLETE TRAINING
### FOR BETTER RADIO-TV SERVICE JOBS

These two giant Ghirardi home training manuals make it easy for you to be an expert on ALL types of TV-AM-FM service . . . **at only a fraction of the price you might expect to pay for such complete training.** Almost 1500 pages, over 800 clear illustrations and dozens of procedure charts explain each detail of every service job as clearly as A-B-C. Each book contains up to the minute data. Each is based on approved **professional** methods. You learn time-saving shortcuts. You learn to work better, more profitably. Ideal as complete training for beginners or as a handy reference library for experienced servicemen who want to look up puzzling jobs or develop new and faster methods.

### A complete guide to TROUBLESHOOTING & REPAIR

(1) This 820-page **Radio & TV TROUBLESHOOTING AND REPAIR MANUAL** guides you through each service procedure . . . from locating troubles to making repairs fast and right. Step-by-step charts cover practically every type of troubleshooting from Television problems to AM and FM realignment to IF and Detector Sections, car radios, record players, communications receivers, etc. 417 illustrations. Price $7.50 separately. (Outside U.S.A. $8.00.)

### The complete "know how" of SET CIRCUITS & OPERATION

(2) Learn all about circuits and their peculiarities and watch your service "headaches" disappear! This 669-page **Radio & TV Receiver CIRCUITRY AND OPERATION** manual covers all basic circuits and circuit variations used in modern home equipment; explains their likely trouble spots; teaches you to go right to the seat of trouble without useless testing; helps you develop fast, truly professional service techniques. Price $6.75 separately. (Outside U.S.A. $7.25.)

### SAVE $1.25—Pay As You Learn!

If sold as a course and sent to you in lesson form, you'd regard these two famous manuals as a bargain at $75.00 or more. Instead, you buy them complete in handy book form for only $13.00 for the two (regular price $14.25). You save $1.25 . . . and you have 3 months to pay if desired. No lessons to wait for! Everything is at your finger tips. You learn fast . . . and you learn right! OUR MONEY-BACK GUARANTEE PROTECTS YOU FULLY!

### STUDY 10 DAYS FREE!

Dept. RN-20, RINEHART & CO., Inc.
232 Madison Ave., New York 16, N. Y.

**MONEY-SAVING OFFER ON BOTH BOOKS!**

☐ Send Radio & TV TROUBLESHOOTING AND REPAIR and Radio & TV CIRCUITRY & OPERATION home training manuals for 10-day free examination. If I decide to keep books, I agree to pay $13.00 (plus postage) for the two . . . a saving of $1.25 over the regular price of $14.25. I will pay $4 (plus postage) after 10 days and $3.00 a month thereafter until $13.00 has been paid. Otherwise I will return books and owe you nothing. (SAVE! Send $13 with order and we pay postage. 10-day money-back guarantee if you're not more than satisfied.)

Name .....

Address .....

City, Zone, State .....

*(Outside U.S.A.—$14.00 for both books. Cash with order only, but same return privilege with money refunded.)*

All Tubes Individually Boxed
UNCONDITIONALLY GUARANTEED FOR ONE YEAR
SEND FOR FREE COMPLETE TUBE LIST & ORDER BLANK. YOUR INQUIRY WILL PUT YOU ON OUR MAILING LIST

TELTRON SMASHES PRICES on TUBES for '60!

GIFT OFFER
ONE 6BG6G tube will be shipped FREE with any $10.00 or more order accompanying this ad.

FREE
$7.50 list value. Bonus box includes 3 6SN7 tubes & 25 assorted resistors & 25 assorted condensers with each order & $25.00 or more of receiving tubes and special purpose tubes only.

FREE
EICO TUBE TESTER

By popular demand we are repeating this fabulous FREE GIVE-AWAY. You get this EICO tube tester kit #625K ABSOLUTELY FREE when you purchase $199.00 worth of receiving tubes from TELTRON within 60 days. Tube tester may be purchased outright for $34.95 Prepaid
Send for FREE list of other EICO test equipment & HI FI components that we distribute.

Partial List—Most Often Used Tubes

| | | | | | |
|---|---|---|---|---|---|
| 0Z4 | .45 | 1B3GT | .45 | 5AH6 | .47 |
| 1A5 | .52 | 1R5 | .52 | 6AL5 | .43 |
| 1B3GT | .45 | 1S5 | .51 | 6AM8 | .59 |
| 1R5 | .52 | 1T4 | .43 | 6AN8 | .64 |
| 1S5 | .51 | 1U4 | .51 | 6AQ5 | .64 |
| 1T4 | .43 | 1U5 | .51 | 6AS5 | .52 |
| 1U4 | .51 | 1X2 | .43 | 6AU4GT | .62 |
| 1U5 | .51 | 2AF4 | 1.02 | 6AU5GT | .50 |
| 1X2 | .43 | 2BN4 | .55 | 6AU6 | .60 |
| 2AF4 | 1.02 | 3AU6 | .55 | 6AV6 | .43 |
| 2BN4 | .55 | 3BC5 | .58 | 6AW8 | .59 |
| 3AU6 | .55 | 3BN6 | .90 | 6AX4GT | .50 |
| 3BC5 | .58 | 3BZ6 | .51 | 6BA6 | .60 |
| 3BN6 | .90 | 3CB6 | .51 | 6BA8 | .56 |
| 3BZ6 | .51 | 3DT6 | .51 | 6BC5 | .48 |
| 3CB6 | .51 | 3V4 | .48 | 6BC8 | .69 |
| 3DT6 | .51 | 4BC8 | .69 | 6BD6 | .59 |
| 3V4 | .48 | 4BQ7 | .75 | 6BE6 | .50 |
| 4BC8 | .69 | 4CB6 | .51 | 6BF5 | .48 |
| 4BQ7 | .75 | 5AM8 | .59 | 6BQ6G | .75 |
| 4CB6 | .51 | 5AN8 | .64 | 6BZ6 | .45 |
| 5AM8 | .59 | 5AT8 | .54 | 6BH6 | 1.18 |
| 5AN8 | .64 | 5AV8 | .54 | 6BJ6 | .51 |
| 5AT8 | .54 | 5BK7 | .68 | 6BK5 | .51 |
| 5AV8 | .54 | 5J6 | .51 | 6BK7 | .75 |
| 5BK7 | .68 | 5T8 | .51 | 6BL7GT | .75 |
| 5J6 | .51 | 5U4G | .43 | 6BN4 | .78 |
| 5T8 | .51 | 5U4GA | .43 | 6BN6 | .90 |
| 5U4G | .43 | 5U4GB | .45 | 6BQ6GT | .75 |
| 5U4GA | .43 | 5U8 | .45 | 6BR8 | .83 |
| 5U4GB | .45 | 5V4G | .49 | 6BY8G | .75 |
| 5U8 | .45 | 5X8 | .55 | 6BZ6 | .45 |
| 5V4G | .49 | 5Y3GT | .55 | 6BZ7 | .95 |
| 5X8 | .55 | 6AB4 | .30 | 6C4 | .41 |
| 5Y3GT | .55 | 6AC7 | .43 | 6CB6 | .51 |
| 6AB4 | .30 | 6AF4 | 1.02 | 6CG6G | .52 |
| 6AC7 | .43 | 6AG5 | .52 | | 1.63 |
| 6AF4 | 1.02 | | | | |

Send for FREE complete list of most often used tube types

New and Hard to Get Types. Prompt Del'y

| | |
|---|---|
| 1DN5 | .60 |
| 1Q3GT/1B3 | .70 |
| 2CY5 | .50 |
| 3AF4 | 1.02 |
| 4DE6 | .55 |
| 4DT6 | .59 |
| 5CQ8 | .59 |
| 6BJ8 | .64 |
| 6BQ5 | .74 |
| 6CQ8 | .59 |
| 6CX8 | .64 |
| 6DS8 | .69 |
| 6AW8 | .75 |
| 6CX8 | .90 |
| 11CY7 | .74 |
| 12EK6 | .59 |
| 17AX4GT | .50 |
| 17D4 | .50 |
| 50EH5 | .59 |

Send approx. cost, excess refunded.

Semiconductors for immediate delivery.

| | | | |
|---|---|---|---|
| 1N34 | .49 | 2N633 | 3.75 |
| 1N38 | .95 | 2N130A | |
| 1N60 | .34 | | 2.75 |
| 1N66 | .49 | 2N320A | |
| 1N82A | | | 40.00 |
| | 1.00 | 2N484 | |
| 1N2853 | | | 1.75 |
| | 4.25 | 2N622 | |
| 1N256 | | | 30.00 |
| | 19.95 | 2N633 | |
| 1N295 | .30 | | .35 |
| 1N460A | | CK1334.00 | |
| | 4.60 | CK2233.50 | |
| 1N1096 | | CK706 | |
| | 9.00 | | 16.50 |

Special purpose transmitting & industrial tubes for immed. ship.

| | | | |
|---|---|---|---|
| 0A2 | .70 | 807 | 1.00 |
| 2A4G | .75 | 811A | 3.25 |
| 2D21 | .65 | 813 | 6.25 |
| 2E26 | 2.50 | 833A | |
| 2X2 | .75 | | 40.00 |
| 5R4GY | | 866A | 1.00 |
| | 1.00 | 2050 | .85 |
| 6J4 | 1.00 | 5675 | |
| 12A6 | .40 | | 12.25 |
| FG27 | 8.50 | 5879 | 1.10 |
| HY69 | 1.75 | 6146 | 3.85 |

New Price Schedule of Television
PICTURE TUBES
PICTURE GUARANTEED FOR ONE (1) YEAR

| | | | | | |
|---|---|---|---|---|---|
| 8DP4 | * | 16RP4 | 11.95 | 20DP5 | 15.75 |
| 10ABP4 | * | 16TP4 | 11.95 | 20HP4 | 17.75 |
| 10BP4 | 7.95 | 17KTP4 | 16.75 | 21ACP4 | 21.95 |
| 12LP4 | 10.75 | 17AVP4 | 15.75 | 21ALP4 | 18.75 |
| 14BP4 | 11.75 | 17EP4 | 13.25 | 21AMP4 | 18.75 |
| 14CP4 | 11.95 | 17FP4 | 17.95 | 21AP4 | 21.25 |
| 14QP4 | 13.25 | 17GP4 | 17.95 | 21ATP4 | 19.25 |
| 14RP4 | 14.25 | 17HP4 | 16.49 | 21AUP4 | 19.25 |
| 16AP4 | 16.45 | 17JP4 | 16.49 | 21AVP4 | 19.25 |
| 16CP4 | 12.49 | 17LP4 | 17.45 | 21AWP4 | 18.75 |
| 16DP4 | 11.99 | 17QP4 | 13.25 | 21EP4 | 17.25 |
| 16EP4 | 15.99 | 17TP4 | 16.49 | 21FP4 | 19.25 |
| 16GP4 | 15.59 | 17UP4 | 16.49 | 21MP4 | 21.25 |
| 16HP4 | 12.49 | 17YP4 | 16.49 | 21WP4 | 17.25 |
| 16KP4 | 11.95 | 19AP4 | 18.75 | 21XP4 | 18.75 |
| 16LP4 | 11.95 | 20CP4 | 15.75 | 21YP4 | 18.75 |

Aluminized on Any Tube, $4.00 Extra.
All Picture Tubes require a deposit on your dud. Please add an additional $5.00 on tube sizes to 17". Add $7.00 on sizes 19", 20", 21" and 24"s. Your cash deposit will be refunded immediately upon receipt of your dud prepaid.
Picture Tubes are shipped promptly from our warehouse. (the US Continent and Canada only) Harrison, N. J. * Price upon request.

Obsolete & seldom used tubes. Save now.

| | | | |
|---|---|---|---|
| 1A6 | .93 | 7A7 | .42 |
| 1C5GT | .57 | 7B4 | .44 |
| 1C7G | .39 | 7B5 | .41 |
| 1F5 | .39 | 7B8 | .47 |
| 1N4G | .39 | 7C5 | .44 |
| 1LA6 | .66 | 7F8 | .77 |
| 1LB4 | .69 | 7H7 | .51 |
| 1LN4 | .66 | 7N7 | .52 |
| 1LN5 | .66 | 7V7 | .82 |
| 3LF4 | .66 | 7Y4 | .35 |
| 5T4 | .59 | 7Z4 | .60 |
| 6A7 | .59 | 12A8GT | |
| 6A8 | .40 | | .45 |
| 6AB7 | | 12K7GT | |
| 1853 | .60 | | .40 |
| 6AQ7GT | | 12Q7GT | |
| | .60 | | .48 |
| 6AST6 | | 12SR7 | .57 |
| | 1.50 | 14A7 | .43 |
| 6D6 | .59 | 14B6 | .36 |
| 6FSGT | .44 | 14Q7 | .52 |
| 6F6 | .42 | 27 | .45 |
| 6S7 | .88 | 35A5 | .48 |
| 6SB7Y | .50 | 35Y4 | .35 |
| 6SR7 | .43 | 37 | .59 |
| 6U8 | .54 | 39/44 | .39 |
| 6U7G | .40 | 45 | .55 |
| 7A4/ | | 50A5 | .48 |
| XXL | .47 | 50X6 | .53 |
| 7A6 | .47 | 56 | .48 |
| 7A8 | .46 | 71A | .65 |

Receiving Tube Specials

| | |
|---|---|
| 6SN7GT A & B | |
| Lots of 50 | $24.50 |
| Lots of 100 | $44.50 |
| 6W4GT | |
| Lots of 50 | $18.95 |
| Lots of 100 | $34.95 |
| 12AU7 & A | |
| Lots of 50 | $24.95 |
| Lots of 100 | $47.95 |
| 6AU6 & A | |
| Lots of 50 | $18.95 |
| Lots of 100 | $34.95 |
| 6CB6 & A | |
| Lots of 50 | $22.95 |
| Lots of 100 | $41.95 |
| Free postage | |

Heavy Duty Solder Gun Kit. 135 watt gun . . . dual spot-light illuminates work when gun is on. KIT INCL.: wire soldering brush, & aid; to make tight wire twists & reopen old joints, so der. Ppd. Only $4.99.
3 for $14.29

FISH FUSE CLIPS . . . 15c ea.
12 for $1.65 PREPAID

RCA CHEATER CORDS . . 39c ea.
6 for $1.95 PREPAID

Complete Outdoor All Channel Conical Antenna
Local or fringe. Incl. 8 elmt. antenna with crsbr; 5' mast alum; chimnt or 7" wall brkt (state need). 8 stand Offe. 50' 300 ohm wire. List $15. $7.99
lots of 3 . . . $7.49
Immediate delivery
FOB, Harrison, N.J.

Switch-Type Indoor Antenna
Shipped Postage Paid
New 6 position switch for use on UHF, VHF color sets.
Neat Pkg.
$2.99. Buy 6, $2.49.

PARALLEL PICTURE TUBE BRIGHTENER . . . . . 99c
Series type . . . . . $1.39

AUTO VIBRATORS
6 Volt 4 Prong Universal . . . $1.59
12 Volt 3 Prong Standard . . . $1.79
12 Volt 4 Prong Standard . . . . $1.59

NEW LIBERAL TERMS: No minimum order. Free postage on all tube & parts orders over $5.00 in U.S.A., APOs & Territories. 25% deposit required on CODs. Please send approximate postage on Canadian and foreign shipments—excess will be refunded. All picture tubes and outdoor antennas shipped FOB Harrison, New Jersey.

Tubes listed may be factory seconds or used tubes and are clearly marked.

TELTRON ELECTRIC CO.
428 Harrison Ave. Harrison, N. J. Phone HUmboldt 4-9848
Dept. EW-2

SAY YOU SAW IT IN
ELECTRONICS WORLD

WE CAN FINANCE
THIS OUTSTANDING
INVESTMENT OPPORTUNITY

Your investment dollars will be returned 3-5 times annually if you can sell 100 or more picture tubes weekly. Windsor franchised TV Tube rebuilding enables you to produce custom built, highest quality tubes. Costs are low. Local distribution eliminates freight charges.

We train your men and while so doing produce 100 or more tubes you can sell. Our engineers are at your service for duration of lease.

WINDSOR ELECTRONICS
999 N. Main Glen Ellyn, Ill.

NEVER FAIL—
ZONE YOUR MAIL

The Post Office has divided 106 cities into postal delivery zones to speed mail delivery. Be sure to include zone number when writing to these cities; be sure to include **your** zone number in **your** return address—after the city, before the state.

## Intermodulation Distortion

(*Continued from page 67*)

Two stable audio generators are used, one of these produces the low frequency and the other produces the high frequency required for the test. In some instruments these frequencies are adjustable, in others they are fixed. The two signals are then fed into attenuators for isolation and for adjustment of the amplitude ratio (usually 4 to 1). Some units permit the user to switch internal v.t.v.m. circuits in at these points to measure the relative amplitudes of the two audio signals. After suitable mixing, the combined signal is applied to the input of the amplifier to be tested.

The amplifier is terminated in an output load resistor. Some IM units even have such loads built in for limited power use. The v.t.v.m. is then switched across this load so that the output power may be monitored. It is common to operate the amplifier "wide open," and simply keep increasing the mixed input signal until rated power output (or whatever power output level is desired) is obtained. See Fig. 4.

In this regard, it is important to use the same peak output voltage as would be obtained under single-frequency conditions, since it is usually at the voltage peak that distortion is generated. If the amplifier is delivering 4 volts of low frequency and 1 volt of high frequency at the same time, its total output voltage would be 5 volts. The distortion would be equivalent to that produced by a 5-volt signal. The power that should be produced by such a signal is $E^2$ ($5^2$, or 25) divided by the load resistance. On the other hand, the true power (as indicated by a voltage measurement taken across the load) is only $4^2$ plus $1^2$ (16 +1, or 17) divided by the load resistance. This means that the indicated power output must be multiplied by 25/17 (or 1.47) when testing for IM under these conditions to obtain an *equivalent sine-wave output power*. Hence, if the voltage measures 8 volts across an 8-ohm load, the true power is 8 watts, but the equivalent sine-wave output power is $1.47 \times 8$, or 11.8 watts.

The amplifier load signal is then applied through an input attenuator to a high-pass filter. This circuit removes the large-amplitude, low-frequency signal and passes on the high frequency. If the amplifier under test has IM distortion, the amplitude of this high-frequency signal will vary, perhaps as shown at the upper waveform No. 5 in Fig. 1. If the amplifier has no IM distortion, the amplitude will be constant, as shown in the lower waveform.

The high-frequency signal is then amplified and detected. (See waveform No. 6.) After detection, the signal is fed to a low-pass filter which removes the high-frequency ripple. Now the amplitude variation shows up clearly as a low-frequency signal (upper waveform No. 7). Had there been

CLASS "D" CITIZEN BAND

CRYSTALS

TEXAS HC6/U

3rd Overtone: Hermetically Sealed .005% tolerance—Meet F C C requirements, ½" pin spacing—.050 pin diameters. (.093 pins available, add 15¢ per crystal.)

$2.95 EACH

22 CHANNELS

(add 5¢ per crystal for postage and handling)

The following Class "D" Citizen Band frequencies in stock (frequencies listed in megacycles): 26.965, 26.975, 26.985, 27.005, 27.015, 27.025, 27.035, 27.055, 27.065, 27.075, 27.085, 27.105, 27.115, 27.125, 27.135, 27.155, 27.165, 27.175, 27.185, 27.205, 27.215, 27.225.

Matched crystal sets for Globe, Gonset, Cite-Fone and Hallicrafters Units (Specify equipment make.) $5.90 per set

RADIO CONTROL CRYSTALS

in HC6/U HOLDERS—SIX FREQUENCIES

Tolerance .005%. ½" pin spacing. .050 pin diameter. (.093 pins available, add 15¢ per crystal.) Specify frequency desired.

26.995, 27.045, 27.095, 27.145, 27.195, 27.255 specify frequency $2.95 EACH

(add 5¢ per crystal for postage and handling)

Send for FREE CRYSTAL CATALOG WITH OSCILLATOR CIRCUITS

ASK YOUR PARTS DEALER FOR TEXAS CRYSTALS

See big red display . . . if he doesn't stock them, send us his name and order direct from nearest factory.

OUR FLORIDA PLANT NOW IN OPERATION
ORDER FROM NEAREST PLANT

TEXAS CRYSTALS

Texas Crystals, Dept. R-20
8538 West Grand Avenue
River Grove, Illinois
Phone: GL 3-3555

OR

Texas Crystals, Dept. R-20
1000 Crystal Drive
Ft. Myers, Florida
Phone: WE 6-2100

ALL ORDERS SHIPPED 1st CLASS MAIL



WANTED!

Equipment,

Components or Parts!

If you have something to sell, let ELECTRONICS WORLD readers know about it in our classified section. It costs very little: just 60¢ a word including name and address. Minimum message: 10 words. For further information, write:

Martin Lincoln
ELECTRONICS WORLD
One Park Ave.
New York 16, N.Y.



ENGINEERING DEGREES

PACIFIC INTERNATIONAL C.A.S.

E.E. Option Electronics or Power
Civil, Mechanical, Physics.
Also in Liberal Arts and Business Administration

Earned through Home Study

Pacific International College of Arts & Sciences
Primarily a Correspondence School
Resident classes also available
5719-R Santa Monica Blvd., Hollywood 38, Calif.


no IM distortion, the output here would be pure d.c. The remaining low frequency, representing the distortion, is then applied to the a.c. v.t.v.m. circuits for measurement. Since this meter had previously been adjusted for full-scale reading with the undistorted high-frequency applied, it will now read directly the percentage value of the intermodulation distortion.

IM distortion measurements, taken in accordance with any standard method such as the one described, allow an important specification to be quoted for evaluating high-fidelity equipment.

—30—

## Canada Puts Limit on R.F. Interference

By J. E. KITCHIN

Inspector, Telecom. Dept. of Transport

**AUDIO noises have been well tabulated in the past but how does one set a tolerable limit for radio-frequency noise? A recent Canadian Department of Transport regulation (known officially as SOR 59-116 by the Queen's Printer, Ottawa, Canada) has defined radio-frequency noise as any electrical disturbance "produced by any mechanical, electrical, or other device" and capable of being received on a radio receiver.**

**The regulation refers specifically to r.f. generators in the ISM industrial bands, in which the amount of r.f. energy produced is without limitation. However, any r.f. generator in those bands must not have any emission outside of the band in excess of 25 microvolts-per-meter at a distance greater than one-thousand feet from the r.f. generator. A provision is also made that if r.f. generators are operated on any frequency outside the ISM bands the limit shall be 15 microvolts-per-meter at 1000 feet.**

**Allowance is also made for higher power industrial equipment (over 5 kw.) and high-frequency arc welding equipment where it is not practicable to apply the limits mentioned above. In these cases the field intensity is restricted to ten microvolts-per-meter at a distance of one mile from the industrial equipment.**

**It is also interesting to note that these measurements must be made on field strength meters of a make and type approved by the Department of Transport, or by meters having an equivalent standard of measurements. Field-strength meters must be adjusted to read the "quasi peak" values of field strength and the prescribed antenna system is a horizontally polarized dipole seven and a half feet high for measuring the frequencies above 25 mc.**

**Any records of measurements made to ensure compliance with the regulation must be kept for three years and be available to Inspectors of the Department of Transport. It must also be remembered that, as usual in such regulations, the provision is made that in certain cases or circumstances suppression may be required by the Department at values lower than those specified in the regulation.**

—30—


COYNE offers LOW COST TELEVISION Training in Spare Time AT HOME

The future is YOURS in TELEVISION—RADIO COLOR TV!

A fabulous field—good pay—fascinating work—a prosperous future! Good jobs, or independence in your own business!




Coyne brings you MODERN—QUALITY Television Home Training; training designed to meet Coyne standards. Includes RADIO, UHF and COLOR TV. No previous experience needed. Practical Job Guides to show you how to do actual servicing jobs—make money early in course. You pay only for your training, no costly "put together kits."

Send coupon or write to address below for FREE Book and full details including easy Payment Plan. No obligation, no salesman will call.

Coyne — the Institution behind this training... the largest, oldest, best equipped residential school of its kind now in its new home pictured here... Founded 1899.

B. W. Cooke, Jr., President

COYNE ELECTRICAL SCHOOL

1501 W. Congress Pkwy., Chicago, Dept. 20-H6
Chartered as an Educational Institution
Not For Profit

COYNE Television, Home Training Division
Dept. 20-H6—New Coyne Building
1501 W. Congress Pkwy., Chicago 7, Ill.
Send Free Book and details on how I can get Coyne Quality Television Home Training at low cost and easy terms.

Name_____

Address_____

City_____ State_____

(It is understood no salesman will call)

PUT YOUR
OSCILLOSCOPE
TO WORK!

**Dust off that oscilloscope of yours! Put it to work fully on the dozens of jobs it can do better than any other service instrument.**

Handle jobs twice as fast. Handle them better—and lots more profitably!

This big book, MODERN OSCILLOSCOPES AND THEIR USES shows you how . . . **in a way you can really understand.** Cleary and simply, it explains exactly where and how to use your 'scope on all types of AM, FM and TV service . . . from trouble-shooting to set realigning and everything in between. No fancy theory. You quickly learn how to make connections; how to adjust circuit components; how to set the controls; **and how to analyze patterns fast and right! New section even covers quantitative measurements—the slickest way of locating many color TV troubles and aligning sets properly.**

Practice from it 10 days . . . at our risk! See for yourself how much this clear, easy instruction can mean!

**The book that REALLY TEACHES YOU TO USE 'SCOPES!**

**Modern Oscilloscopes and Their Uses**
326 pages
370 pictures

**Dept. RN-20, RINEHART & CO., Inc.,**
**232 Madison Ave., New York 16, N. Y.**

Send MODERN OSCILLOSCOPES AND THEIR USES for 10-day FREE EXAMINATION. If I decide to keep book, I will then send you $6.50 plus a few cents postage in full payment. If not, I will return book postpaid and owe you nothing.

Name .....

Address .....

City, Zone, State .....

OUTSIDE U.S.A.—Cash with order only. Price $7.00. Money back if book is returned in 10 days.

**SURPLUS**
HIGH IN VALUE • LOW IN PRICE

**DIAL TELEPHONES**
French type phone made by Conn. Tel. & Tel. Can be used for standard extension phone. With Dial, Excellent Cond. ..... Ea. **$4.95**

**LOW VOLTAGE TRANSFORMER**
This Transformer produces 6, 7, or 8 Volts. AC 20 Amps. Input 115 Volt, 60 Cycles. All New ..... Ea. **$2.95**
4 for ..... **$10.00**

**RECORDING BLANKS**
16" Recording Blanks. Make your own Recordings. Aluminum base, Lacquered both sides. Professional quality. All New Stock ..... Ea. **50c**
Package of 10 ..... $3.50
Package of 100 ..... $30.00

**HEADSETS**
Trimm, 8000 ohms H. F. Headsets with 4 Ft. Cord. All NEW ..... Ea. **$3.50**

**CODE PRACTICE OSCILLATOR**
Type TG-5 Code Oscillator provides 1000 Cycle tone for practice. Use two units for transmission over wire between 2 points. Uses 1—22½ Volt Battery actuated and will follow a bug. All New Complete and 2 Flashlight Batteries. Tone Oscillator is relay with single Earphone, less batteries. Set **$7.50**
Set of batteries for above ..... $2.00

**TELEPHONE STEP RELAY**
3 Pole 10 Position "Minor" Switch. Ideal for use with Telephone Dials for remote switching. 3 Levels —Each 1 pole 10 position. Operates from 24 DC using 1 coil to step and 1 coil to reset. WGT. Approx. 2 Lbs.
Exc. Cond. Used ..... Ea. **$4.95**

**MID RANGE DRIVER**
Racon Revux-B similar to PM 615 Operating Watts 30; Peak Watts 60; Frequency Response 90-7000 cycles, 15 ohm VC Imp., 1 7/16 mounting bushing, $50.00 Value. All New ..... **$6.95**

**RECORDING WIRE**
Magnetic Recording Wire on 3¾" Diam Alum Spool. 1 Hour Recording Time. Will fit most wire recorders or wire can be re-spooled on your own spools. All new, $1.50 per Roll. Four Rolls **$5.00**

**REVERSIBLE MOTOR**
1/40 H. P. Ball-bearing 3450 RPM in Blast-proof case. Needs only a capacitor for starting. All Brand New. 110 V., 60 Cy. Special Low Price.. **$3.95**
Starting Capacitor . . . $0.48 Ea.
WGT. Approx. 8 Lbs.

**See our previous ad for Special Surplus Items.**
*All prices F.O.B. S. F., Calif. Calif. orders add 3% Sales Tax. 20% Dep. on all C.O.D.'s. Purchases under $5.00 send full amount. Items subject to prior sale.*

**STANDARD SURPLUS**
1230 Market St., San Francisco 3, Calif.
Telephone HEmlock 1-3106


## The "Pyramid" Stylus

(*Continued from page 49*)

due to pressure per unit area must be taken into account.

What is needed, then, is a stylus designed to fit all existing microgrooves but shaped in such a way as to minimize "pinch effect" while fitting into all "corners" of the recorded modulation. *Fidelitone's* solution to this problem is the "Pyramid" stylus.

In order to understand how the "Pyramid" works, assume the stylus is ground into a pyramidal shape rather than in the form of a cone with a spherical tip. Each of the four ridge edges created by the four converging sides are rounded gently and highly polished to remove "cutting" edges and minimize friction. Consider further that the polished ridge edges of pyramid shape are formed so as to approximate the included angle of the cutter stylus. The "Pyramid" stylus thus formed is precision mounted on the needle in such a way as to cause the ridge radii to engage the side walls of the groove in the same horizontal and vertical fashion as the cutter stylus was when it formed the original groove.

Such a design permits the pyramid shape to maneuver all the sharp turns and reach into all the sharp corners the way the cutter stylus does. (Fig. 3 shows the way a "Pyramid" will trace the groove of Fig. 2 while Fig. 1 is a pictorial comparison of the two needle shapes tracing a single-tone, high-frequency groove.) Fig. 4 is an enlarged end view of the "Pyramid" showing its projection in the groove.

When such a stylus shape traces a groove, whether modulated or unmodulated, only the ridge corners of the "Pyramid" will touch the side walls of the groove, up to the maximum condition of 45 degrees inclination of groove modulation. The sides are constantly changing in proximity to the side walls but, like the cutter, they are always just following behind without interference. Throughout all this range of motion the stylus rides on an "even keel," not rising, but always in intimate gliding contact with groove side walls. Of course, the "Pyramid" corners must not have sharp cutting edges. They are rounded into contact radii much smaller than any round tip radius thus far proven practical.

One's first reaction is that such reduced radius values would also greatly reduce the contact area to the groove, thus requiring impossibly low needle pressures. The solution to this dilemma lies in the fact that the shape and mounting permits the stylus to follow the groove's contour farther up the walls of the groove than is possible with the round one.

The round stylus, to minimize pinch effect, must touch the groove walls as near to the bottom as possible. The farther up the side walls the contact radius extends, the greater will be the undesirable distortion effects. See Fig. 5.

The "Pyramid" stylus, on the other hand, is shaped so that its engagement area is a continuous line that can extend all the way up the groove's wall without affecting its tracing dimension (fore and aft) in the slightest. Thus no increased pinch effect nor decreased groove translation results. Hence it is possible to increase the contact area of the "Pyramid" to values equivalent to much larger spherical stylus areas. To be specific—a .0002 contact area of a "Pyramid" is greater than the contact area of a .0007 spherical point. This has been proved by record and stylus wear tests. It is therefore recommended that a working radius of .0002 on a "Pyramid" not be operated at greater than 6 grams needle force and a .0003 radius not exceed 10 grams needle force. When making this comparison consider that a .0005 round tipped stylus should operate at a 4-gram maximum needle force. The "line contact" of the "Pyramid" also results in a noticeable reduction in background noises, commonly referred to as "scratch noise." While this characteristic came as sort of a surprise, it is completely logical since the extended "line contact" area distributes forces up along the vinylite groove side walls, which will average out any molecular irregularities to be found at concentrated points.

Another bonus resulting with this new stylus is a noticeable reduction in needle drag, which greatly improves the so-called tangential distortion found with some pickup designs. This is a design weakness permitting motion of the needle in the fore and aft direction during the tracing of heavy modulation.

### Manufacture and Mounting

Everything looks rosy in theory. Now, how is such a stylus to be made and how can controls be set up for its mounting? These big questions took nearly two years to resolve because no stylus is worthy of so much special handling unless it is made of diamond. To produce such a stylus requires careful molecular orientation of each stone before grinding. Only the softer molecular planes can be ground away which leaves the ridges which contact the groove side walls coincidental with the hardest molecular plane of the diamond. This requirement is also a condition for optimum wear. After the stone is properly processed and highly polished, it still requires precision mounting in its needle. The rotational horizontal orientation of the stylus in its needle mounting must be selected for maximum performance conditions to be met on the inside grooves of the record, where stylus performance is most critical.

The "Pyramid" diamond stylus needle should not only be viewed in the light of its longer service life and the longer useful life of costly recordings but in the improved reproduction possible by its use. —30—

## AN/ART-13 100-WATT TRANSMITTER

(Government original cost $1,000.00)

Designed to provide radio communication by voice, (MCW) or CW telegraphy. Class "B" audio modulator system capable of modulating the carrier at least 90% on voice or MCW. Incorporates automatic tuning mechanism which may be used to select any one of 11 frequencies, range 2000 KC to 18,000 KC. Frequencies 200 KC to 1500 KC range is provided by addition of oscillator 0-16/ART-13-A. Shipping weight 90 pounds.

With Tubes and Meters— Condition Fair **$29.50**
Less Meters but with Tubes— " **$20.00**
Less Meters and Tubes— (for spare parts only) ..... $10.00
0-16 Low Frequency Oscillator ..... $ 5.95
**AN/ART-13-T47** with Tubes and Meters. Condition Good ..... **$39.50**
**T47** with Tubes and Meters. Condition Excellent ..... **$49.50**

**—For Boats or Planes—**
**MAGNESYN REMOTE READING COMPASS**—Lightweight, operates from 12 V DC with very low current. Very accurate and simple to use. Complete. Tested ..... **$24.95**

***Write for Bargain Flyer***

## R W ELECTRONICS

**2430 S. MICHIGAN AVE., DEPT. N**
**Phone: CAlumet 5-1281 Chicago 16, Illinois**



## TV PICTURE TUBES
***At Lowest Prices***

| | | | | | |
|---|---|---|---|---|---|
| 10BP4 | $ 7.95 | 17BP4 | $ 9.95 | 21AMP4 | $15.75 |
| 12LP4 | 8.50 | 17CP4 | 17.00 | 21ATP4 | 15.75 |
| 14B/CP4 | 9.95 | 17GP4 | 17.60 | 21AUP4 | 15.75 |
| 16DP4 | 12.00 | 17HP4 | 12.50 | 21EP4 | 13.50 |
| 16EP4 | 12.75 | 17LP4 | 11.50 | 21FP4 | 14.50 |
| 16GP4 | 14.50 | 17QP4 | 9.95 | 21WP4 | 14.00 |
| 16KP4 | 9.95 | 17TP4 | 17.00 | 21YP4 | 14.50 |
| 16LP4 | 10.95 | 19AP4 | 16.00 | 21ZP4 | 13.50 |
| 16RP4 | 9.95 | 20CP4 | 13.50 | 24CP4 | 23.50 |
| 16WP4 | 12.00 | 20HP4 | 14.50 | 24DP4 | 24.50 |
| 16PT4 | 9.95 | 21AP4 | 22.10 | 27P4 | 39.95 |
| 17AVP4 | 12.50 | 21ALP4 | 15.75 | 27RP4 | 39.95 |

**1 Year Warranty**

Aluminized Tubes $5.00 more than above prices. Prices include the return of an acceptable similar tube under vacuum.
These tubes are manufactured from reprocessed used glass bulbs. All parts and materials including the electron gun are brand new.

**ALL PRICES FOR CHICAGO, ILLINOIS.** Deposit required, when old tube is not returned, refundable at time of return. 25% deposit required on COD shipments. Old tubes must be returned prepaid. Tubes shipped Rail Express.

**WRITE FOR COMPLETE LIST.**

## — PICTURE TUBE OUTLET —

**3032 MILWAUKEE AVE.**
**CHICAGO 18, ILLINOIS**
**Dickens 2-2048**



## BEST IN HI-FI VALUES!

**NO DELAY SERVICE**

All orders rushed to you in factory-sealed cartons.

*Write for free catalog.*

audion

**25-W Oxford Road**
**Massapequa, New York**



## ELECTRONICS

**PREPARE FOR A GOOD JOB!**
**BROADCAST ENGINEER**
**RADIO SERVICING AUTOMATION**

**TELEVISION SERVICING**
**BLACK & WHITE—COLOR**

**APPROVED FOR VETERANS AND SURVIVORS OF VETERANS**
**BUILDING AIR CONDITIONED**
**SEND FOR FREE LITERATURE**

**BALTIMORE TECHNICAL INSTITUTE**
**1425 EUTAW PLACE, BALTIMORE 17, MD.**


## Improvements for S.W. Sets

(*Continued from page* 53)

3 and 4 may be connected in the filament string either between the 2nd detector and i.f. amplifier tubes or between the i.f. amplifier and mixer tubes.

### Audio Limiter

When the broadcast-band tuning range of a *Hallicrafters* SX-24 was extended to 460 kc. for ship radio reception, the need for additional noise limiting became apparent. The original audio noise limiter of the receiver does an excellent job on auto ignition at high frequencies and on certain other types of interference, however, it could not cope with the powerful blasting by the local harbor shore station if receiver sensitivity and audio gain were set for distant ship reception.

Numerous noise limiter circuits were tried and the simple scheme finally adopted was found to possess dual virtues. It is not only satisfactory in the reduction of blasting but very effective in the reduction of QRN. On many occasions when QRN would render 80-meter c.w. operation an annoying task, merely throwing in this limiter permits comfortable reception.

The limiter circuit consists of a 10-megohm, ½-watt resistor paralleled by a toggle switch, connected in series with the original plate-load resistor of the first audio stage. When the switch is closed, the receiver operates normally since the 10-megohm resistor is not in the circuit. When the switch is open, the 10-megohm resistor is part of the plate-load resistor and limiting occurs. (See Fig. 2.)

### Narrowing Audio Response

So well known is the principle of improving receiver selectivity by narrowing the frequency response of the audio system that many communications receivers employ audio filters. The local oscillator stability of the low-priced communications receiver is rarely sufficient to permit the use of an audio filter. However, the addition of a tone control will be found quite advantageous under certain operating conditions (such as for the attenuation of an interfering c.w. signal at a very high beat-note frequency).

The layout of the S-38B presents a problem in mounting a tone control on the front panel. A thorough investigation under actual operating conditions showed that a worthwhile improvement in c.w. selectivity can be achieved by the simple addition of a .005-$\mu$f. bypass capacitor from the plate (pin 6) of the 12SQ7 audio amplifier to the chassis (close to the tube socket). No other value of capacitance or circuit position produces the same improvement in performance. In addition, this modification does not impair the audio quality of speech or music and results in improved signal-to-noise ratio.


*prepare for your career in*

# ELECTRICAL ENGINEERING
# ELECTRONICS
# COMPUTERS
# RADIO-TV

**At MSOE,** you can equip yourself for a career in many exciting, growing fields: **MISSILES RADAR • AUTOMATION RESEARCH • DEVELOPMENT ELECTRICAL POWER AVIONICS • ROCKETRY**

When you graduate from the Milwaukee School of Engineering, you are prepared for a dynamic career as an Electrical Engineer or Engineering Technician. Under a faculty of specialists, you gain a sound technical education in modern, completely equipped laboratories and classrooms. As a result, MSOE graduates are in great demand and highly accepted by industries nationally.

At MSOE you will meet men from all walks of life and all parts of the country — some fresh out of high school or prep school, others in their twenties — veterans and non-veterans.

You can start school in any one of four quarters and begin specializing immediately. Engineering technicians graduate in 2 years with an *Associate* in *Applied Science* degree. For a *Bachelor of Science* degree in Engineering, you attend 4 years. A 3-month preparatory course also is available.

**FREE CAREER BOOKLET!**
If you're interested in any phase of electronics, radio or television, be sure to look into the programs of study offered by the Milwaukee School of Engineering. Just mail the coupon.

## MILWAUKEE SCHOOL OF ENGINEERING

**Dept. EW-260, 1025 N. Milwaukee St.**
**Milwaukee, Wisconsin**

Please send FREE Career Booklet. I'm interested in ☐ Electrical Engineering;
☐ Electronics ☐ Computers
☐ Electrical Power ☐ Radio-TV
☐ Mechanical Engineering

PLEASE PRINT

Name ..... Age .....
Address .....
City ..... Zone ..... State .....
☐ I'm eligible for veterans education benefits.
MS-123

Olson

FREE

Fill in coupon for a FREE One Year Subscription to OLSON RADIO'S Fantastic Bargain Packed Catalog — Unheard of LOW, LOW, WHOLESALE PRICES on Brand Name Speakers, Changers, Tubes, Tools, Hi-Fi's, Stereo Amps, Tuners and thousands of other Electronic Bargains.

NAME_____

ADDRESS_____

CITY_____ ZONE____ STATE_____

If you have a friend interested in electronics send his name and address for a FREE subscription also.

OLSON RADIO CORPORATION

604 S. Forge St. Akron 8, Ohio

PURCHASING A HI-FI SYSTEM?

Send Us Your List Of Components For A Package Quotation

WE WON'T BE UNDERSOLD!

All merchandise is brand new, factory fresh & guaranteed.

*FREE Hi-Fi Catalog Available on Request.*

PARTIAL LIST OF BRANDS IN STOCK

Altec Lansing
Electrovoice
Jensen
Hartley • Stephens
University
Acoustic Research
Janszen
Wharfedale
Karlson Cabinets
Viking
Concertone
Bell • G.E.
Weathers
Harman—Kardon
Eico • Pilot
Sherwood
Acrosound
Fisher
Dual Changer
Bogen • Leak
Dynakit
H. H. Scott
Ferrograph
Tanberg
Pentron
Ampex • DeWald
Revere
Challenger
Wollensak
Garrard
Miracord
Glaser-Steers
Rek-O-Kut
Components
Nareico
Fairchild
Pickering • Gray
Audio Tape
Conrac TV
Full Line of Wellcor Cabinets

AIREX RADIO CORPORATION

64-R Cortlandt St., N. Y. 7, CO 7-2137

Many hams occasionally enjoy listening to ships at sea on 600 meters and above. It is not a difficult task to extend the tuning range at the low end of the broadcast band to include frequencies to 460 kc. if an erroneous dial calibration can be overlooked. When an attempt is made to tune to 455 kc. (the usual receiver i.f.), the receiver will naturally take off in overall oscillation and no signals can be heard.

### Extending BC Band

When there is sufficient room in the tuning coil assembly, a separate toggle switch may be placed in each r.f. compartment near the broadcast-band coil. The toggle switch handles are ganged together by a piece of insulating rod which may be run through the panel and equipped with a control knob. When the switches are closed, each connects a capacitor from the "hot" end of its broadcast coil to ground.

Unfortunately, there is insufficient room in the *Hallicrafters* SX-24 to make the installation just described. An attempt was made to mount switches and capacitors above the tuning gang. While performance was satisfactory on the broadcast and ship bands, the stray capacity thus introduced made it impossible to obtain proper alignment on the high-frequency bands. The arrangement finally adopted consisted of three 230-$\mu\mu$f. capacitors; one connection of each soldered to the tuning gang frame. A small alligator clip on the other lead of each capacitor permits clipping one to each of the tuning-gang lugs for ship reception. When ship reception is not desired, the alligator clips can be connected to any convenient point on the tuning-gang frame.

The *Hallicrafters* S-38 layout permitted a somewhat neater arrangement. A toggle switch (d.p.s.t.) was mounted between the oscillator coil bank and the antenna coil bank and its handle is accessible through a hole in the bottom cover. Both switch arms are connected to the chassis. A 172-$\mu\mu$f. capacitor (a 150 $\mu\mu$f. paralleled by a 22 $\mu\mu$f.) is connected between the "hot" end of the broadcast oscillator coil and one end of the switch contact. A 200-$\mu\mu$f. capacitor is connected between the "hot" end of the broadcast antenna coil and the adjacent switch contact. These capacitor values were selected to satisfy the following requirements: (1) The broadcasting tuning range extended down to 460 kc.; (2) Tracking excellent at 500 kc. (600 meters); and (3) Progressive mistrack from 500 kc. to 460 kc. (Having no r.f. stage, the low-priced receiver has a much lower i.f. rejection ratio than larger sets. The resultant tendency to oscillate as the receiver is tuned toward 460 kc. is offset by the intentional mistrack.)

There are undoubtedly a number of other simple modifications similar to those described here that will suggest themselves to the users of the various communications receivers under their particular operating conditions. —30—

## Mac's Service Shop

*(Continued from page 56)*

is hearing Leon Deloy, 8AB, for the first trans-Atlantic reception on the short-wave band of 100 meters. This story tells about relaying a message by hams from coast-to-coast in an hour and twenty-five minutes, and this one tells of the McMillan expedition at the North Pole being picked up by an amateur."

"Wonder what those broadcasting stations were like?"

"Well, here is a description of WBZ's new 1000-watt transmitter described as one of the finest in the country. It uses 'four 250-watt oscillator and five 250-watt modulator tubes. A modulation meter and control rheostat has also been added so that the operator can listen to the programs and gauge their modulation'."

"I'll bet there were some far-out applications of radio back there."

"You're right. Here is a picture of a German *schutzman*, or police officer, carrying a portable radio for receiving orders from headquarters. The radio is about eighteen inches square with four exposed tubes sticking out the top. The poor devil is wearing earphones under his steel helmet, and a loop antenna at least four feet square is strapped to his back. The accompanying text says disorders in Germany are frequent and that the officer carries this cumbersome equipment so that he may know when his presence is needed. He's going to be in great shape to quell a riot when he arrives on the scene in that rig. Another story says that in New York City an undertaker operates a hearse equipped with a radio amplifier and loudspeaker. As the vehicle enters the cemetery, chimes, hymns, and funeral music are played. Finally, look at this headlined story about a radio device just invented by a Canadian physician that will diagnose human ills."

"Here's one for the book!" Barney exclaimed: "'Wired Service Corporation, located on Staten Island, is carrying to 500 residents of the island a six-hour program daily, to be increased when the service is extended to New Jersey. Upon payment of a certain sum, your set is installed and the programs come in.' Pay-Wired-Wireless away back there!"

"You'll find lots of familiar names in those old magazines. Herbert Hoover, Secretary of the Commerce Department that licenses radio stations, says broadcasting needs an overseer. It was to get one in the form of the F.C.C., of course. Here is a picture of a younger, heavier, hairier Arthur Murray giving an over-the-air dancing lesson. Charles Chaplin tells a reporter how frightened he was at his first radio broadcast. This strikingly handsome man is the visiting Prince of Wales who is described as an ardent radiophan. Coolidge's address to Congress is believed to have been heard

by a million and a half people. And Steinmetz dies on the morning of October 26, 1923."

"What do the magazines say about us service technicians?"

"Not much, as such. Most of the listeners, having built their own sets, also repaired them. The magazine gives instructions on how to build sets and also a lot of helpful hints, such as how to connect earphone jacks in series so that more than one person can hear, how to sandpaper tube prongs to insure better contacts, and how to employ earphones as a meter multiplier resistance so that the low-scale 'A'-battery meter can also be used to test the 'B'-batteries. I'll bet that was good on the earphones!

"And then there is this story headlined: '*Hook-ups Galore.* There are circuits everywhere. There are so many that a good radio electrician may wander into a store to buy a switch knob and actually hasten away in blushing ignorance'." Mac looked across at the metal file cabinets that contained around 2000 radio and TV diagrams and mused aloud, "I wonder what that radio electrician would think today.

"But they were trying hard to guess the future," he continued. "Some of the guesses were good, some not. Here the manager of WGR is saying seeing by radio is not far distant. And there is something sadly familiar about this editorial that declares: 'Radio-controlled mechanical devices, electrically operated, will exercise an influence difficult to foretell. Ten years and a new war will develop radio and make its uses so far-reaching. . . . that another world war will be impossible.' But listen to this: 'The near future will see small, compact, and portable radio receivers . . . in every home. There will be no outside antenna, no complicated wiring, and no batteries in the ideal foolproof set soon to be sought by up-to-date householders who will demand radio service just as they do telephone service today.' Some of the wise ones knew they were going to need us."

"This is more fun than looking through a family album," Barney declared as he leafed through the magazines.

"I think it's more than amusing," Mac said soberly. "Examining the past is the best way to understand the present and guess the future. That's why we study history. Personally, when I look back at this crude beginning of the electronic industry and realize how far and how fast it has come in thirty-seven years, I feel a little awed but very, very proud of being a part of it."

"Yes," agreed Barney with unwonted solemnity, "it is a sobering thought. Even in my scatter-brain fashion I am impressed by the fantastic contributions that the early hams made to the advance of radio every time I rattle a key and talk to some amateur half way around the world. The progress in our field is really staggering—I am glad I 'belong.' " —30—


# Full Color Giant Fold-Out Charts Still Available!

Here's a complete series of colorful, authoritative fold-out wall-charts (originally appearing in the pages of ELECTRONICS WORLD)—yours for only 15¢ each. All in full-color—each suitable for framing.

1. ***V.H.F. TV Spectrum and Interference Chart:*** Servicing aid for TV technicians and hams—saves hours by tracking down interference.
2. ***Hi-Fi Crossover Network Design Charts:*** Tells how to build speaker nets for any crossover frequency. Complete coil-winding data, capacitor values given.
3. ***Color Codes Chart:*** Gives you coding for capacitors, resistors, transformers, resistance control tapers—all in easy-to-use form.
4. ***Bass-Reflex Design Charts:*** Complete data on building own bass-reflex enclosures for any speaker, including ducted-port enclosures.
5. ***Radio Amateur Great Circle Chart:*** For Hams and short-wave listeners—gives complete listing and map of amateur prefixes by calls and countries.
6. ***Sound:*** Fundamental data on all phases of Sound: frequency ranges, sound levels, equal loudness curves. A must for all audiophiles.

ALSO AVAILABLE:

Reprints of the following authoritative articles:

7. ***"Build a Citizens Band Transceiver"***—complete details on building an 11-meter transceiver for Citizens Band service.
8. ***"Electrical Shock: Fact and Fiction"***—must reading for everyone whose work or hobby involves electricity. Ideal for utility companies . . . service associations.

IMPORTANT: ORDER BY NUMBER! OUR SUPPLY OF ALL GATEFOLDS AND REPRINTS IS LIMITED. OFFERED ONLY ON A FIRST COME, FIRST SERVED BASIS.

Send 15¢ per selection to

ELECTRONICS WORLD, Dept. N 260

Box 378 Church Street Station New York 8, New York

# ONE CENT SALE

**BUY ONE AT OUR REGULAR LOW PRICE and GET the SECOND for ONLY 1¢ MORE**

**CITIZENS BAND TRANSMITTER** (27 MC) chassis complete with crystal. $12.49 each, two for $12.50.

**TRANSMITTER** similar to above but with 5 watt RF stage instead of 1 watt. $14.99 each, two for $15.00.

**CITIZENS BAND RECEIVER** chassis tunable through all 22 channels. Complete with audio amplifier. $9.99 each, two for $10.00.

**AMATEUR BAND TRANSCEIVER** (144-148 MC) chassis with dual VHF triodes for walkie-talkie radiophone. $9.99 each, two for $10.00.

**TRANSCEIVER TRANSFORMER:** Mike to grid input and plate to low impedance headphone output. Good for telephone handsets. $1.99 pair, two for $2.00.

**TELEPHONE HANDSETS** with push-to-talk switch. $5.99 each, two for $6.00.

**MICROPHONE** High output 200 ohm carbon with terminal lugs. $1.49 each, two for $1.50.

**COILED CORD** 4 conductor 11" telephone cord. Extends to over 4 ft. .99 each, two for $1.00.

**KIT OF PARTS** for AM-FM VHF radio receiver. Tunable from 80-200 mc. which includes U.S. satellite frequencies. $6.99 each, two for $7.00.

**TRANSISTOR AUDIO AMPLIFIER** gives 50X voltage gain on low level signals. Operates on 1½ volts. $3.99 each, two for $4.00.

**CONVERTER** (crystal controlled) for 27 MC Citizens Band. Adapts any standard broadcast radio to 27 MC band. Tunes all 22 channels. Complete with tubes and crystal. $14.99, each, 2 for $15.00.

**TRANSMITTER CRYSTALS** in holders. Assorted frequencies for experimenters. Bag of 10 only $1.49 two bags for $1.50.

**ALL MERCHANDISE GUARANTEED**

**LIMITED QUANTITY—**
**NO LITERATURE OR CATALOG**

***Remit in full. Include sufficient postage.***
***No C.O.D.'s.***

**VANGUARD ELECTRONIC LABS**
**Box 12-EW2 Hollis 23, N. Y.**

# DON'T THROW OLD RADIOS AWAY!

**Here's the data you need to fix them FAST . . . and good as new!**

Just look up the how-to-do-it data on that old radio you want to fix!

Four times out of 5, this giant, 3½-pound, 744-page Ghirardi RADIO TROUBLESHOOTER'S HANDBOOK gives exactly the information you need to fix it in a jiffy. Tells what is likely to be causing the trouble . . . shows how to fix it. No useless testing. No wasted time. Handbook covers practically every radio receiver model made by 202 manufacturers between 1925 and 1942. Using it, even beginners can easily fix old sets which might otherwise be thrown away because service information is lacking. With a few simple repairs, most of these old sets can be made to operate perfectly for years to come.

## THE ONLY GUIDE OF ITS KIND!

**Cuts service time in half!**

Included are common trouble symptoms and their remedies for over 4,800 models of old home, auto radios and record changers: Airline, Apex, Arvin, Atwater Kent, Belmont, Bosch, Brunswick, Clarion, Crosley, Emerson, Fada, G-E, Kolster, Majestic, Motorola, Philco, Pilot, RCA, Silvertone, Sparton, Stromberg and dozens more. Includes hundreds of pages of invaluable tube and component data, service short cuts, etc.

**TRY IT 10 DAYS . . . see for yourself!**

**Dept. RN-20, RINEHART & CO., INC.**
**232 Madison Ave., New York 16, N. Y.**

Send Ghirardi's RADIO TROUBLESHOOTER'S HANDBOOK for 10-day free examination. If I decide to keep book, I will then remit the full price of only $6.95 plus postage. Otherwise, I will return book postpaid and owe you nothing. (SAVE! Send $6.95 with order and we pay postage. Same return privilege with money refunded.)

NAME .....

ADDRESS .....

CITY, ZONE, STATE .....

*OUTSIDE U.S.A.—Price $7.45 cash with order only. Money back if book is returned in 10 days.*

RADIO ELECTRONIC
SURPLUS

SILICON RECTIFIERS

| | | |
|---|---|---|
| 1N1454 | 25 amp. 100 volts | $3.00 |
| 1N1455 | 25 amp. 200 volts | $3.50 |
| 1N1456 | 25 amp. 300 volts | $4.00 |
| 1N1457 | 25 amp. 400 volts | $4.50 |
| 1N1446 | .750 amp. 100 volts | $ .65 |
| 1N1447 | .750 amp. 200 volts | $ .75 |
| 1N1448 | .750 amp. 300 volts | $ .85 |
| 1N1449 | .750 amp. 400 volts | $1.00 |

BC603 FM RECEIVER
20.-27.9 mc. Equipped with 10 push buttons for selecting channels. Cont. variable tuning over the entire range. Unit complete with tubes, built-in loud speaker, squelch circuit, head phone jacks, schematic diagram on bottom of case. Approx. weight 34 lbs.
Used Good.....$9.95
Like New.....$12.95

DM-34 Dynamotor 12 or 24-volt D.C....each $3.95

BC-604 Transmitter, 20.-27.9 mc
NEW.....$4.95

Crystals (set of 80) for BC604 transmitter, 20 to 27.9 mc
Price.....$5.00 per set

Schematic for BC603/BC604.
Price.....$1.00 each

DM35 DYNAMOTOR, 12 Volt Input, output 625V, .225A
Used with BC604.....$9.95
12 Eicor Dynamotor: Output 440V, 200A. NEW $7.95

NO C.O.D.'s. REMIT FULL AMOUNT WITH ORDER. ALL PRICES F.O.B. PASADENA.

C & H SALES CO.
2176 E. Colorado St. · Pasadena 8, Calif.



NEW DIMENSIONS IN C-B EQUIPMENT from ESSCO
Your guarantee of peak performance—
reliability—economy

**NEW ESSCO SUPER-CEIVER** of unmatched sensitivity and selectivity. A listing of its many features would fill this page. Suffice to say "it's got everything." Tuneable 23 channels, 9" dial spread, AVC, Squelch 4" speaker, 2.5 watt audio, 12 selected tubes, etc., etc. Special introductory price of **$99.95**

**THE ESSCO BASE-MITTER.** A top performance transmitter of maximum obtainable output eff. Sturdy industrial design, components & workmanship. Unit housed in wrinkled alum. case 10x5x9. Wt. 15 lbs. Shockmounts supplied for mobile installations. 115 volt AC std, other voltages available. Only **$99.95**

**THE ESSCO ULTIMATE,** a single unit transmitter-receiver with all the above features and more too. Wt. 40 lbs.! Special production requires 45 day delivery..... **$169.95**

**NOTE:** ALL Essco C-B transmitters supplied with complete compliance to ALL FCC rules on Citizens Radio Service.

**THE ESSCO SUPER DELUXE DUAL** Ground Plane Antenna. Uses special hardened aluminum alloy elements for liteweight durability. Guaranteed 3DB gain over std GP antenna. Gives your station a loud voice at hard to reach locations. With 25 ft. RG8/U coax cable..... **$34.95**

**STD ESSCO DUAL G-P** Antenna with hardened steel elements. With 25 ft. RG8/U cable..... **$27.95**

**THE ESSCO SUPER SINGLE G-P** antenna. Std self supporting single set of aluminum alloy radials (4) with 25 ft. coax. A durable "LOUD VOICE" radiator..... **$19.95**

**ESSCO C-B HQTS.** 88 WALKER ST. N.Y.C. 13, N.Y.



THE SURGISTOR®

For your protection and profit, install one every TV, Hi-Fi call! $1.85 List. See your jobber.



WUERTH TUBE SAVER CORP., Detroit 4, Michigan

CODE SENDING RECEIVING SPEED

Be a "key" man. Learn how to send and receive messages in International Morse code. Communicate with operators around the globe. Learn at home quickly through famous Candler System. Used by best operators. Qualify for Amateur or Commercial License. Write for FREE BOOK.

CANDLER SYSTEM CO., Dept. 2-B, Box 9235, Denver 20, Colo., U.S.A.


# What's New in Radio

## MOBILE SOUND SYSTEMS

*Lawrence Incorporated,* P.O. Box 5106, Seven Oaks Station, Detroit 35, Mich. has announced the development of a new line of transistorized mobile sound systems which has been tradenamed "Road-Commander."

Designed primarily for police, fire, and civil defense work, the system includes a mobile amplifier (Model RC-

1225) which can be operated from an automotive 12-volt system and supplies 25 watts audio output; and RC-100 flat contour speaker which is suitable for roof mounting on vehicles using roof lights; and the RC-101 concealment speaker for installation on unmarked cars or fender mounting. In addition, the system includes a microphone and microphone hanger.

Upon written request, the manufacturer will supply complete details on this system and the name of the nearest franchised dealer.

## ALUMINUM MASTING

*JFD Electronics Corporation,* 6101 Sixteenth Ave., Brooklyn, N. Y. has announced production of a new series of lightweight, corrosion-proof aluminum masts for the service trade.

The company notes that such masts offer absolute elimination of rust, staining, or corrosion; high tensile strength of 45,000 lbs. per square inch; 66% less weight than steel; protective corrugated board packing which permits convenient warehousing; and a non-slip fitted-joint lock for positive stacking of sections.

The masts are available in 5, 7½, and 10 foot lengths, 1¼" o.d., .042 (19 gauge) sections in natural silver or gold anodized aluminum.

## NEW SILICON RECTIFIERS

The Rectifier Division of *Sarkes Tarzian, Inc.,* 415 N. College Ave., Bloomington, Ind. has recently developed a new silicon rectifier that is designed to be used as a replacement for the 866 series of rectifier tubes.

The Type S-5130 is capable of operating at a full inverse peak voltage of 10,400 volts under all conditions and carries a d.c. current rating of 300 ma. with choke input and 240 ma. with capacitor input.

As a companion rectifier at lower cost, where a full 10,400 volts is not required, the company offers the S-5343 rated at 6400 peak inverse volts and 300 ma. d.c. This type will replace 816 tubes as well as 866's at reduced voltage.

For a data sheet on these new units, write the manufacturer direct. For quantities less than 500, local distributors can supply either rectifier.

## UTILITY TABLE

*Holly Electronics,* 112 W. Colorado, Pasadena, California has recently introduced a new utility table which has been specifically designed for service applications.

The Model 12A1 has an adjustable open top for under-chassis repair and is designed to accommodate most TV and radio chassis. The table is 30" high x 24" square and is mounted on swivel casters. All joints are rigid with special locknut joints. Douglas fir is used throughout.

The table is tested to withstand 250 lbs. It is shipped direct from the manufacturer unassembled. Write the company for price and additional details.

## "TRANSFILTER" CIRCUIT

*Clevite Electronic Components,* 3405 Perkins Ave., Cleveland 14, Ohio has developed two new "Transfilters"



which are said to cut at least 50 cents off the over-all parts cost of a conventional *LC* filter circuit in transistor portable radios.

The new models can be used for i.f. stages of AM radios. They permit the replacement of a double-tuned i.f. transformer and two single-tuned i.f. transformers by a single-tuned i.f. transformer and one each of the TF-01A and TO-01A "Transfilters."

The TO-01A is an interstage coupler providing impedance coupling between the first and second i.f. transistor stage. It combines the functions of impedance transformation and frequency selection of the i.f. frequency.

The TF-01A is an emitter bypass frequency selective element also resonant at 455 kc. In combination with the TO-01A, it gives the receiver's i.f.

# only 15c for this authoritative guide to building an inexpensive record library!



reprinted from HiFi REVIEW
(now HiFi/STEREO REVIEW)

Now—you can build a record library of hi-fi classics from the steadily growing catalogue of $1.98 releases! More than half a dozen big record companies are re-issuing great performances on the new $1.98 labels. You can have a guide to the best of these for 15¢—by ordering this reprint of a recent article in HiFi REVIEW. Complete with catalogue number, artist, orchestra and conductor information—it's a fabulous guide to building up a high fidelity library of basic classics!

In addition, HiFi REVIEW's Music Editor, David Hall, gives you the background of the $1.98 market . . . evaluates the discs being offered at this price . . . pinpoints the future of high-quality, low-price records.

If you've been thinking of starting a record collection or adding to the one you have—this reprint is your best guide! Order your copy today—simply mail 15¢ in coin or stamps with the coupon below. But the supply is limited, so order now!

EW 260

**HiFi/STEREO REVIEW**
**Box 1778R**
**Church Street Station**
**New York 8, N. Y.**

Please rush my copy of the HiFi REVIEW reprint on building a library of $1.98 records. I enclose 15¢ to cover postage and handling.

**Name** _____

**Address** _____

**City** _____ **Zone** _____ **State** _____


stage selectivity comparable to that obtained by the four tuned stages in the original circuit.

The company emphasizes that although the new units replace functions of i.f. transformers in the receiver circuit the new components are not direct replacements. Slight circuit modification is required. Write the company for complete details and full specifications.

### TUBE ANALYZER

*American Scientific Development*, P.O. Box 109, Redlands, California is now offering an electron tube analyzer, the Model ETA 100B, which has been designed for tube and electronic equipment manufacturers, and those requiring positive evaluation and/or matching of vacuum tubes.

The new unit measures true plate and screen current and transconductance at precise voltages specified by the tube manufacturer or at voltages



chosen by the circuit designer. The gas and leakage test, applied to every electrode, is continuously variable to 10 megohms. The unit determines the firing point of thyratrons, regulation of gaseous voltage regulators, and forward and reverse current of small dry-disc rectifiers and diodes.

The unit supplies continuously variable d.c. voltage for output circuits from 0 to 100 volts at 50 ma. It is housed in a portable hardwood carrying case.

Write the manufacturer for additional details and price.

### ELAPSED TIME INDICATOR

*Sela Electronics Company*, 545 West End Ave., New York 24, N. Y. is currently offering a compact, low-cost elapsed time indicator which has been tradenamed the "Selachron."

Suitable for applications as diverse as checking the wear on phonograph styli and timing rented machinery and


## —"TAB" Tubes Tested, Inspected, Boxed—

**Six Months Guarantee!! No Rejects!**

**NEW & Used Gov't & Mfgrs. Surplus!**

*Orders $10 or more. Receiving types only ppd., 48 states*

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| 0A2 | .80 | 6BJ6 | .99 | 12AT6 | .59 | 1B3GT | 1.00 |
| 0B2 | .65 | 6BK7 | .99 | 12AT7 | .84 | 117Z6 | 1.10 |
| 0C3 | .69 | 6BL7 | 1.25 | 12AU6 | .69 | 4-65A | 16.00 |
| 0D3 | .59 | 6BN6 | .98 | 12AU7 | .69 | 2D21 | 2/$1 |
| 0Z4 | .59 | 6BQ6 | 1.19 | 12AX7 | .79 | 3D23 | 3.85 |
| 1A7 | .89 | 6BZ7 | 1.25 | 12BA6 | .65 | 717A | 5/$1 |
| 1B3 | .78 | 6C4 | .45 | 12BA7 | .99 | 4-125 | 29.00 |
| 1R5 | .78 | 6C5 | .69 | 12BD6 | .59 | 4-250 | 35.00 |
| 1S4 | .78 | 6CB6 | .80 | 12BE6 | .59 | 4E27 | 7.00 |
| 1T4 | .78 | 6CD6 | 1.49 | 12BF6 | .59 | 4PR60 | 29.50 |

*Send 50c for Catalog!*

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| 1U4 | 3/$1 | 6H6 | 3/$1 | 12BH7 | .99 | 4X150 | 5.00 |
| 1U5 | .73 | 6J5 | .52 | 12BY7 | .98 | 4X250B | 35.00 |
| 1X2A | .68 | 6J6 | .48 | 12BZ7 | .99 | 4X500A | 38.00 |
| 3Q4 | .68 | 6K6 | .59 | 12CU6 | 1.45 | 5BP1 | 4.98 |
| 3Q5 | .86 | 6K7 | .74 | 12SA7 | .94 | 5BP4 | 4.98 |
| 3S4 | .68 | 6L6 | 1.19 | 12SG7 | .89 | 5R7 | 4.00 |
| 3V4 | .85 | 6L6 | .59 | 12SH7 | .89 | 100T | 7.00 |
| 5R4 | .98 | 6S8 | .99 | 12SJ7 | .75 | 316A | 5/$1 |
| 5U4 | .59 | 6SA7 | .69 | 12SK7 | .94 | 388A | 3/$1 |
| 5V4 | .89 | 6SB7 | 1.19 | 12SQ7 | .84 | 446B | 16.00 |

*Wanted Surplus Electronics from schools & U*

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| 5Y3 | .59 | 6SC7 | .89 | 19BG6 | 2.15 | 450T | 42.00 |
| 6AB4 | .59 | 6SG7 | .79 | 19T8 | 1.16 | 807 | 1.00 |
| 6AC7 | .70 | 6SH7 | .69 | 25BQ6 | 1.39 | 809 | 3.00 |
| 6AK7 | .89 | 6SJ7 | .89 | 25L6 | .69 | 811 | 4.40 |
| 6AH6 | .99 | 6SK7 | .72 | 25W4 | .77 | 812 | 3.00 |
| 6AK5 | .69 | 6SL7 | .89 | 25Z5 | .63 | 813 | 9.00 |
| 6AL5 | 2/$1 | 6SN7 | 2/$1 | 25Z6 | .75 | 814 | 3.45 |
| 6AQ5 | .63 | 6SQ7 | .74 | 6L34 | 3.49 | 815 | 2.75 |
| 6AS7 | 3.00 | 6SR7 | .79 | 5L37 | 2.49 | 826 | .59 |
| 6AT6 | .49 | 6T8 | .98 | 35L6 | .69 | 829B | 8.00 |

*Wanted 304TL tubes! Top $ $ Paid*

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| 6AU4 | 1.10 | 6U8 | .98 | 35W4 | .49 | 832A | 7.00 |
| 6AU5 | 1.19 | 6V6GT | .70 | 35Y4 | .69 | 866A | 2.75 |
| 6AU6 | .69 | 6W4 | .79 | 36Z5 | .63 | 1625 | 5/$1 |
| 6AX4 | .79 | 6W6 | .89 | 50A5 | .69 | 5146 | 4.00 |
| 6BA6 | .59 | 6X4 | 2/$1 | 50B5 | .69 | 5879 | .98 |
| 6BA7 | 1.00 | 6X5 | .49 | 50C5 | .69 | 5881 | 2.70 |
| 6BD6 | .69 | 6Y6 | .97 | 50L6 | .69 | 5950 | 3.90 |
| 6BE6 | .59 | 7N7 | .89 | KT66 | 3.29 | 5654 | 1.00 |
| 6BG6 | 1.50 | 12AL5 | .59 | 75 | .89 | 5894 | 12.00 |
| 6BH6 | .72 | 12AQ5 | .75 | 80 | .59 | 7193 | 10/$1 |

TUBES WANTED! WE BUY! SELL & TRADE!

## "TAB" KITS! "TAB" THE BEST KITS! "TAB"

*All Kits Contain Most Popular Values & Sizes*

Kit 2 Eng. Parallel Rules
Kit 35 Precision Resistors
Kit 10 Switches
Kit 75 Resistors ½/1-½W
Kit 150 Carbon Resistors
Kit 25 Panel Lamps
Kit 12 Electrolytic Cond's
Kit 56 Tube Sockets
Kit 65 Tubular Cond'sers
Kit 500 Lugs & Eyelets
Kit 10 Bathtub Oil Cond's
Kit 5 lbs. Surprise Pckg.
Kit 10 Xmtr Mica Condsr.
Kit 3 Phone/Patch Xfmrs
Kit 3 Searchlights
Kit Circular Slide Rule
Kit 12 Algtr Clip Asst'd.

Kit 5 Sub-Min Tubes
Kit 40 Standoff Insulators
Kit 35 Power Resistors
Kit 75 Mica Condensers
Kit 5 Crystal Diodes
Kit 100 Fuses, Assorted
Kit 150 Ceramic Condsr.
Kit 10 Germanium Diodes
Kit 5 FT243 Xtal Holders
Kit 6 Silicon Diodes
Kit 9 Microswitches
Kit 4 Asstd Rectifiers
Kit 2 PNP Transistors
Kit 4x50 Ft Hookup Wire
Kit 2 Veeder Counters
Kit 2—Computer Toroids
Kit High Gain XTAL Mike

*BUY 10 KITS—GET ONE FREE* **EACH KIT 99¢**

## "NEW "TEXSEL" SELENIUM RECTIFIERS

**FULL WAVE BRIDGE RECTIFIERS.** *ONE YEAR GTD!*

| AMP. CONT. | 18VAC 14VDC | 36VAC 28VDC | 72VAC 56VDC | 144VAC 118VDC |
|---|---|---|---|---|
| 1AMP | $ 1.30 | $ 2.00 | $ 4.90 | $ 9.45 |
| 2AMP | 2.15 | 3.00 | 6.25 | 12.30 |
| 3AMP | 2.90 | 4.00 | 8.60 | 16.75 |
| 6AMP | 4.15 | 9.00 | 18.75 | 36.15 |
| 10AMP | 6.10 | 12.15 | 26.30 | 48.90 |

Write for Complete Rectifier Catalog

**NEW Selenium Radio & TV Rectifiers! GTD.**
65Ma 48¢, @ 6 for $2; 100Ma 45¢, @ 12/$5;
250MA 65¢, @ 10/$6; 300Ma 88¢, @ 10/$8;
500Ma $1, @ 10/$8, 25/$18
*Orders this Item $10 or More, Postpaid 48 States!*

**TRANSISTORIZED DC POWER!**
**HI-EFFICIENCY DC to DC to 450 VDC "TABSTAT" KIT or BUILT!**

Output 450 & TAP 250VDC at up to 150 MA/Up to 70 Watts 80% efficiency: ripple 0.2%; low idle current one amp silicon rectifiers, oil condensers, toroid transf, fused & short circuit proof. Regulation 5% at 20 to 100% load!! Small in size! Quiet! Light wgt! Low-priced gld "TABSTAT" TR1245CB built $35. Pre-Assembled U-Build kit TR1245CK Only $30. "TABSTAT" 250VDC @ 100MA/12V in TR1225CB $27, Kit TR1225CK $24, 6V inpt TR6125CB $37, Kit TR625CK $24.

**DC POWER SUPPLIES for TRANSISTORS!**

New low-cost filtered 0.5% Ripple Power Supply. Same as specified in Transistor Manuals G.E. Ideal for powering transistor circuits, small in size!
12VDC at 150Ma-T12V150M..... $8
25VDC at 150Ma-T25V150M..... $10
40VDC at 1 Amp-T40V1A..... $19

**FOR BEST BUYS! "TAB" for BARGAINS**

AN—ARR2 Rcvr As Is Good for Parts..... $1.99
RDZ—USN 200-400 Mc's Rcvr less Tubes.... $25.00
SCR53 100 to 200W Xmtr Phone or Cw 2 to 4 Mc's includes 12V/Synmtr 9 Channels.... $39.00
"Irish" Tape 1200' Hi-Qlty Gld $1.99 @ ... 6 for $9
"Irish" Tape Mylar 2400 ft Best Qlty $4.49, 3/$12
Snooperscope Tube 2" $5 @ ..... 2/$9
2N277 $4.50; 2N278 $5.50; 2N441 $3; 2N442 $5

## NEW SILICON 500MA RECTIFIERS

**GENERAL PURPOSE SPECIAL 2 FOR $1** — **400 PIV at 250 MA 25 FOR $10**



| | | | |
|---|---|---|---|
| rms/piv 35/50 30¢ | rms/piv 70/100 45¢ | rms/piv 140/200 50¢ | rms/piv 210/300 69¢ |
| rms/piv 280/400 78¢ | rms/piv 350/500 $1.00 | rms/piv 420/600 $1.26 | rms/piv 490/700 $1.50 |
| rms/piv 560/800 $1.59 | rms/piv 630/900 $1.89 | rms/piv 700/1000 $2.98 | rms/piv 770/1100 $3.12 |

Use in F.W.Bridge or F.W.C.T. up to 750ma or 2" Fins for 1.5A. ($5 or more we pay postage 48 states.)

**"TAB"** TERMS: Money Back Guarantee! Our 14th year. $2 min. order F.O.B. N.Y.C. Add shpg charges or for C.O.D. 25% Dep. Prices shown subject to change.
111-WD LIBERTY ST., N.Y. 6, N.Y.
Send 25¢ PHONE: RECTOR 2-6245 for Catalog

**Advance** **AN 131A ANTENNA**

**F-R-E-E!** (with each order of $10 or more)

**POWER SUPPLY KIT!**
Primary 115V, 60 Cy. Sec., 400-0-400 V. @ 4 Amp., 5 VCT @ 2 Amp. std. mounting plus 8 Hy. chokes and two 4mfd. 600 V. oil condensers ..... Kit $7.50

**M A R Power Supply**
115 V. 60 cyc. input 12-14 VDC, 2 Amp. output filtered and fully housed. SPECIAL $8.95

**★ ★ POWER TRANSFORMERS ★ ★**
117 V. Pri., 800 VCT., 350 Ma.; 6.3 V., 7.5 Amps; 5 V., 6 Amps ..... $7.69
720 VCT., 200 Ma.; 12.6 V., 3 Amps; 6.3 V., 10 Amps; 5 V., 3 Amps ..... $5.75

**— TRANSFORMER Buys!! —**
**ALL WITH 115 VOLT PRIMARY**

| | | | |
|---|---|---|---|
| 6.3 V SEC. 1 Amp | $1.25 | 6.3 V SEC. 3 Amp | $1.85 |
| 6.3 V SEC. 4 Amp | 2.29 | 6.3 V SEC. 15 Amp CT | 3.95 |
| 12 V SEC. 2 Amp | 1.19 | 12 V SEC. 1 Amp | 1.19 |
| Step up/down Transformer 110 V-220 V 10 Amp. | | | 9.95 |
| Primary 115, sec. 6 V-7 V-8 V, 75 VA | | | 3.75 |
| Plate 3100 VCT 300 Ma. | | | 17.75 |
| Sola constant voltage, 95-125 V in 6.3 @ 10 Amps out | | | 9.50 |

**★ ★ RELAYS! RELAYS! RELAYS! ★ ★**

| | | | |
|---|---|---|---|
| 110 VAC DPDT | $2.75 | 24 VAC SPDT Sigma 41-F | $1.35 |
| 110 VAC DPDT, Ceramic-Leach | 3.45 | w/transformer for 110 VAC | 1.65 |
| 12 VDC DPDT | 1.35 | | |
| 24 VDC, 4 PDT | 2.95 | | |
| 24 VDC, DPDT w/ dust cover | 2.45 | 16,000-ohm plate, Sigma 5F SPDT. Will operate on 500 Mma. | 3.95 |
| 6 VDC SPDT | 1.35 | | |
| Sigma 3,200-ohm SPDT | 2.45 | | |

LARGE STOCK AC, DC RELAYS!

**SOLENOIDS**
115V 60 Cyc. cont. duty, 18 Lb. pull ..... each $4.75
8 Lb. pull ..... each 2.30
24V & 230V SORENO IN STOCK!

**CHOKES FULLY CASED**

| | |
|---|---|
| 6 hy. 100 Ma. | $1.09 |
| 22 hy. 100 Ma. | 2.59 |
| 20 hy. 110 Ma. | 2.10 |
| 10 hy. 250 Ma. | 2.75 |
| 20 hy. 300 Ma. | 7.95 |

**WESTERN ELECTRIC Volume Indicator**
with Weston meter. ±732 db. Var. 2-24 **$14.25**

**RG CO-AX CABLE . . . UG CONNECTORS**

| | |
|---|---|
| 8/U, 52-ohm impd., 100 ft. length | $7.75 |
| 59 A/U (72-ohm) w/male & female connectors. 50-ft. coils | ea. 2.45 |
| 58/U, 100-ft. length | ea. 4.25 |
| 59/U, 100-ft. length | ea. 4.25 |
| 50 239 connectors | 3 for 1.25 |
| UG 259A | 3 for 1.25 |
| Adaptors for 58/U | 22c each |

**OIL CONDENSER BARGAINS**
SPECIAL!! 3 x 8 mfd, 500 VDC ..... Only $2.25

| | | | |
|---|---|---|---|
| 2 Mfd 600 VDC | $0.45 | 2 Mfd 2000 VDC | $1.50 |
| 4 Mfd 600 VDC | .69 | 3 Mfd 2000 VDC | 2.75 |
| 8 Mfd 600 VDC | .95 | 2 Mfd 2500 VDC | 2.25 |
| 10 Mfd 600 VDC | 1.10 | 1 Mfd 3000 VDC | 1.75 |
| 15 Mfd 600 VDC | 1.90 | 2 Mfd 4000 VDC | 5.75 |
| 16 Mfd 600 VDC | 1.75 | 3 Mfd 4000 VDC | 7.50 |
| 25 Mfd 600 VDC | 3.25 | 1 Mfd 5000 VDC | 4.10 |
| 1 Mfd 1000 VDC | .55 | 2 Mfd 5000 VDC | 8.75 |
| 2 Mfd 1000 VDC | .69 | 2 Mfd 6000 VDC | 12.75 |
| 15 Mfd 1000 VDC | 2.95 | 2 Mfd 10000 VDC | 16.95 |
| 4 Mfd 1500 VDC | 1.95 | 1 Mfd 12500 VDC | 18.95 |

**S-A-L-E! PANEL METERS!**

| | | | |
|---|---|---|---|
| 1" METERS | | 0-5 Amp AC (scale marked 0-150) | $3.25 |
| 0-200 Micro-amps | $3.50 | 0-1 Mill (scale 0-50) | 4.25 |
| 0-500 Micro-amps | 3.50 | 200-0-200 VDC | 3.95 |
| 2" METERS | | 0-300 Amps DC, with shunt | 5.95 |
| 0-3 amps | 2.95 | -10.0 to + 6DB | 5.95 |
| 0-300 VAC | 2.95 | RUNNING TIME METERS! | |
| 0-7.5 VDC | 2.95 | 0-9999 GE 110V | 7.95 |
| 0-200 VDC | 2.95 | 0-9999 JBT, 230V | 9.50 |
| 0-300 VDC | 2.95 | Comb w/freq. meter, JBT, 110 VAC | 17.95 |
| 3" METERS | | Fram freq. meter | |
| 0-100 Micro-amps | 5.95 | 110-130 V 58-62 cyc. | 9.95 |
| 0-300 Micro-amps | 4.95 | 400 cyc. | 9.95 |
| 0-7.5 VAC | 3.25 | | |
| 0-150 VAC | 4.45 | | |
| 0-1 Mill | 4.45 | | |
| 0-5 Mills | 3.25 | | |
| 0-200 Mills | 3.95 | | |
| 0-250 Mills | 3.95 | | |

**★★ SELENIUM RECTIFIERS ★★**
—FULL WAVE BRIDGE—

| 130/110 VAC input | | 30/24 VAC input | |
|---|---|---|---|
| 150 mills | $1.25 | ½ Amp | $1.19 |
| 200 mills | 1.75 | 2 Amp | 2.15 |
| 300 mills | 2.50 | 5 Amp | 4.95 |
| 500 mills | 3.50 | 7.5 Amp | 6.45 |
| 12 Amps | 19.75 | 10 Amp | 7.50 |
| | | 20 Amp | 12.95 |

**4 WIRE TELEPHONE COILED CORDS**
each ..... 89c
( 6 for $5.00)

**STEPPING RELAYS!**
10 deck, 3 pos. $6.95
16 deck, 22 pos. $22.50

**NEW POWER SUPPLY KIT!**
Variable low voltage DC power supply kit for transistor use. 0-15V., 1 amp. (transistor, transformer rheostat, condenser, line cord, terminal strips, resistor, schematic explaining hook-up). ALL FOR ONLY ..... **$9.95**

**★★★★ Extra Special!! ★★★★**
**HOLTZER—CABOT MOTOR**
BBC 2S10, 3400 RPM, 110 V. 60 Cyc., sw. 3/16" shaft. w/condenser ..... JUST **$8.95**
(supply limited)

Min. Order $3.00—25% with order F.O.B. New York
10 DAY GUAR. PRICE OF MDSE. ONLY

**Advance Electronics**
6 West Broadway • New York 7, N. Y. • REctor 2-0270


equipment operation, the unit has no moving parts and is designed for direct wiring into devices for straight-scale reading of total operation time.

Models are available for equipment or devices operating on 6-, 12-, 115-volt a.c. or d.c. and total elapsed time readings of 100, 500, 1000, and 10,000 hours. Other voltage or time span combinations are available on special order.

### CAPACITOR KIT

*The Sprague Products Company,* North Adams, Mass. has just announced a new kit of silvered mica capacitors which has been especially assembled for replacement applications in electronic servicing.

The "MK-1 Sampler" kit consists of an inventory of 40 silvered mica units in the seven most popular ratings, packaged in a handy reusable plastic box. The capacitors are made of carefully selected, electrically graded mica, are molded in low-loss phenolic, and impregnated for moisture resistance and long life. Capacitance ratings (marked on each unit) range from .0001 μf. to .001 μf. ±5%, 500 volts. The compartmented box has a diagram on its lid to show at a glance where each rating is located and its list price.

The new "Sampler" is currently available at all of the company's parts distributors.

### CD ELECTROLYTICS

*Cornell-Dubilier Electric Corp.,* South Plainfield, N. J. is now in production on a line of miniaturized cannencased aluminum-foil electrolytics which are being marketed as "Electromites."

The new units are designed for electronic equipment where compactness, light weight, moderate cost, and high electrical-mechanical dependability are required. They are especially suitable for personal radio receivers, portable wire and tape recorders, portable record players, electronic timing devices, and similar industrial and consumer products.

The new units are available in can sizes from 3/16" x ½" to ⅜" x 1½". Operating temperature range is −20 degrees C to +85 degrees C; 3 volts to 150 volts working.

Bulletin No. 533A, containing complete technical data on this new line, is available from the manufacturer upon written request.

### REPLACEMENT SHAFTS

*Eastern Jewel Corp.,* Rego Park 74, N. Y. has announced the availability of an exact replacement fine-tuning shaft for *Standard Coil* TV tuners.

Designated as Part No. TS4, the new unit is made in an extra long length so it can replace the original defective part in any TV set from A to Z (*Admiral* to *Zenith*). The shaft is aluminum and is easily sawed to the exact length needed.

The TS4 is designed to be continuously rotatable a full 360 degrees and has no stop. The dielectric wafer is made thin enough to pass through the conducting metal plates of the tuner which avoids the necessity for deforming the plates during installation.

Further details are available on request from the manufacturer.

### TRANSISTOR MOUNTING KITS

*Motorola Semiconductor Products Division,* 5005 E. McDowell Rd., Phoenix, Ariz. has introduced power transistor mounting kits which provide the necessary hardware to mount all power transistors in the industry-standard TO-3 and TO-5 package.

With these mounting kits, Types MK-10, MK-15, and MK-20, power transistors can be mounted electrically isolated from a chassis or heat sink while excellent heat transfer characteristics are maintained.

Hardware in these new kits includes a transistor socket, front and back mounting templates for hole drilling guides, two #6 mounting screws and insulating washer, and complete mounting instructions.

Write Dept. PMK of the Division for complete details. —30—

## MARS SCHEDULES FOR FEBRUARY

**THE First Army MARS SSB Technical Net, which operates on 4030 kc. upper sideband, Wednesdays at 9 p.m. (EST), has announced the following speakers for February.**

**Feb. 3—"Application of Quartz Crystals in SSB Filters" by W. E. Benton, Western Electric Company.**

**Feb. 10—"Design Philosophy of A Modern SSB Transceiver" by Chuck Carney, Collins Radio Company.**

**Feb. 17—"Harmonic and Intermodulation Distortion in High-Fidelity Amplifiers" by Milton Snitzer, Technical Editor, Electronics World.**

**Feb. 24—"High-Power Transmitter Stations" by Herbert C. Hawkins, U. S. Army Signal Development Laboratory, Fort Monmouth.** —30—

### PHOTO CREDITS

| Page | Credit |
|---|---|
| 42 (top), 43 (bottom) | Radio Corporation of America |
| 42 (center) | Minneapolis-Honeywell |
| 42 (bottom) | Hoffman Semiconductor Division |
| 43 (top) | ITT |
| 43 (center left) | General Instrument Co. |
| 43 (center right), 132 | Sylvania Electric Products Inc. |
| 48, 49 | Fidelitone, Inc. |
| 50 (left) | Injectorall Co. |
| 50 (second left) | Superex Electronics Corp. |
| 50 (third left), 51 (center & right) | Chemical Electronic Engineering Inc. |
| 50 (right) | General Cement |
| 51 (left) | Electronic Chemical Corp. |
| 58, 100 | Ampex Corp. |
| 90 | Clevite Transistor Products |
| 112, 122 | Allied Radio Corp. |
| 124 | Electronic Instrument Co., Inc. |
| 128 | North Carolina Federation of Electronic Assns. |



# ELECTRONICS MARKET PLACE

RATE: 60¢ per word. Minimum 10 words. April issue closes February 9th. Send order and remittance to ELECTRONICS WORLD, One Park Ave., N. Y. C. 16, N. Y.

## FOR SALE

RADIO and television tubes, brand new, 1st quality, original box name brands only. 60% off list. Edison Tube Co., 335 Main St., Metuchen, N. J.

DIAGRAMS for repairing radios $1.00. Television $2.00. Give make, model. Diagram Service, Box 672-RN, Hartford 1, Conn.

TELEVISION Sets $9.95, plus shipping. Jones TV, Sanatoga, Pa.

RADIO & TV Tubes at Manufacturers Prices! 100% Guaranteed! Brand New! No re-brands or pulls! United Radio, Box 1000, Newark, N. J.

TELEVISION & Radio Tubes, Parts and Supplies Guaranteed. Hi-Quality Tube Co., Inc., 284 Lafayette St., Rahway, New Jersey.

GOVERNMENT sells: Surplus Electronics; Test Equipment; Oscilloscopes; Transceivers; Jeeps; Boats; Aircrafts; Misc.—Send for U. S. Depot Directory & Procedure $1.00—"Government Surplus Sales," Box 425—RT, Nanuet, N. Y.

AUTO Radio Distributor Selling Servicing Becker Blaupunkt, FM-AM, other European, American Sets. Save 30% + Square Electronics, 150-60 Northern Blvd., Flushing, N. Y.

GOVERNMENT Surplus Receivers, Transmitters, Snooperscopes, Parabolic Reflectors, Picture Catalog 10¢. Meshna, Malden 48, Mass.

SPECIAL Antennas for Citizens' Band. Dick's, 62 Cherry Avenue, Tiffin, Ohio.

PRINTED Circuit Boards designed, manufactured. Custom PC kits. Brochure. Electronic Aids, Box 137, Stamford, Conn.

PHONOGRAPH Records cheap, postpaid. Catalogue. Paramount, Box 2026-N, Pine Castle, Fla.

AUTOMATIC Door Operators, new famous make. Only $59.95. Buy direct. Save! Free Literature Demsco, Inc., Sebring 6, Ohio.

TELEVISION Appliance Repair Forms. Catalog. Jones, 1210E Dudley, Utica, N. Y.

## WANTED

CASH For Used Short-Wave Ham Receivers, Transmitters & Accessories. Treger W9IVJ, 2023 N. Hariem Ave., Chicago 35. Tuxedo 9-6429.

CYLINDER and old disc phonographs. Edison, Conqueror, Idelia, and Oratorio models. Berliner Gramophones and Zono-o-phones, Columbia cylinder Graphophones, and coin-operated cylinder phonos. Want old catalogues and literature on early phonos prior to 1919. Will pay cash or trade late hi-fi components. Classified, Electronics World, Box 50, 1 Park Ave., N. Y. C. 16, N. Y.

## RADIO ENGINEERING & INSTRUCTION

BACHELOR of Science in Electronics Engineering. Degree in 4 years of Home Study. No resident attendance necessary. Pacific International College of Arts and Sciences, Primarily a correspondence school. Resident classes also available if desired. 5719-U Santa Monica Boulevard, Los Angeles 38, California.

ELECTRONICS! Associate degree—29 months. Technicians, field engineers, specialists in communications, missiles, computers, radar, automation. Start February, September. Valparaiso Technical Institute, Dept. N, Valparaiso, Indiana.

ENGINEERING and Art Degrees earned through home study. Electronics, Electrical, Mechanical, Civil, Physics, Business Administration, Liberal Arts. When writing, specify course desired. Pacific International College of Arts & Sciences, primarily a correspondence school. Resident classes also carried. 5719-C Santa Monica Boulevard, Hollywood 38, California.

USED Correspondence Courses and Books sold and rented. Money back guarantee. Catalog Free. (Courses Bought). Lee Mountain, Pisgah, Alabama.

## HIGH-FIDELITY



INDUCTORS for Crossover Networks. 118 types in stock. Send for brochure. C & M Coils, 3016 Holmes Avenue N. W. Huntsville, Ala.

PRICES? The Best! Factory-sealed Hi-Fi Components? Yes! Send for free catalog. Audion, 25R Oxford Road, Massapequa, N. Y.

DISGUSTED with "Hi" Hi-Fi Prices? Unusual Discounts On Your High Fidelity Requirements. Write. Key Electronics, 120 Liberty St., New York 6, N. Y. CLoverdale 8-4288.

RECORDERS, Hi-Fi. Free Wholesale Catalogue. Carston 125-R East 88, NYC 28.

HI-FI lowest prices, guaranteed-new-Factory Boxed-shipped immediately from West-Recorders, Tuners, Amplifiers, Speakers, etc., Everything! Send your requirements. Free recommendations. Avalon Box 8513, Los Angeles 8, Calif.

## TAPE & RECORDERS

RENT Stereo Tapes—over 900 different—all major labels—free catalog. Stereo-Parti, 1608-L, Centinela Ave., Inglewood 3, California.

TAPE Recorders, Hi-Fi Components. Sleep Learning Kits, Tapes. Unusual Values. Free Catalog. Dressner, 69-02R 174 St., Flushing 65, N. Y.

RECORDERS, Stereo Tapes, Hi-Fi Components, Tremendous Values, Catalog, Efsco, 270-E Concord, West Hempstead, N. Y.

"HOW to Get the Most Out of Tape Recording" by Lee Sheridan. Cat. #TE-128, 128 pgs., illus. $1.00. Tells how to buy, operate, make money with recorders, Stereo, etc. "Tape Editing and Splicing." Cat. #TE-24, 24 pgs. illus. $.35. At Dealers. Free catalog. Robins Indust Corp., Flushing 54, N. Y. Att. Miss Monroe.

UNUSUAL Budget Values. Tape recorders, tapes and Hi-Fi components. Send for package quotations and free catalogue. Budget Hi-Fi Distributors, 83-06 Vietor Ave., Elmhurst, N. Y.

AMPEX, Concertone, Crown, Ferrograph, Presto, Tandberg, Pentron, Bell, Sherwood, Rek-O-Kut, Dynakit, Others. Trades. Boynton Studio, 10RT Pennsylvania, Yonkers, N. Y.

## MUSIC

SONGS into Dollars! Share $33 million dollars yearly for New Songwriters, Songpoets. Any subject, songs composed, Published, promoted by largest firm. Information, appraisal Free. Send Nordyke Music Publishers, 6000 Sunset, Hollywood 283, California.

## INSTRUCTION



SPOT TV Troubles in minutes instead of hours. Repair all makes and models without theory. Unique simplified system. Not a book. Industry approved—used by professionals to save time—make money. 3 years in development. Write for Free literature. Dept. EW, National Technical Resarch Labs., 1118 W. Hadley St., Whittier, Calif.

YOU Can Pass That FCC Phone Exam. My "Shotgun" Type Review Has Been Highly Effective for 15 Years. Very Inexpensive. Free Literature. Wallace Cook, P. O. Box 10634N, Jackson 9, Miss.

## MISCELLANEOUS

NEW 1960 Program Guide. All Shortwave Broadcasting Stations throughout world including frequencies, Callsigns, $2.70 postpaid. Gilfer, Box 239-z, Grand Central, New York 17.

## SHOPPING GUIDE *Classified*

A HANDY GUIDE TO PRODUCTS, NOT NECESSARILY ELECTRONIC, BUT OF WIDE GENERAL INTEREST.

## PHOTOGRAPHY—FILM, EQUIPMENT, SERVICES

OPTICAL — Science — Math Bargains — Request Free Giant Catalog "CJ"—128 pages—Astronomical Telescopes, Microscopes, Lenses, Binoculars, Kits, Parts. Amazing war surplus bargains. Edmund Scientific Co., Barrington, New Jersey.

## STAMPS & COINS

NEW! Revised! 1960 Coin Bargain Catalog 25¢. "Prices-Paid" List, $1.00! Sullivan, 50-FB East Sixth, St. Paul 1, Minnesota.

THREE Brilliant uncirculated Mexican silver dollars $1.00. Universal Services, Box 675, San Antonio 6-S2, Texas.

## HELP WANTED

WANT a Good Overseas or Stateside Job with Higher Pay?? Transportation Paid. Men—Women Free Information. Employment Headquarters. 79 Wall Street, Dept. R-5. New York 5.

ENGINEER. Chicago area manufacturer of electronic components has an opening for an engineer with a B.S.E.E. degree or with equivalent engineering experience and training. Past experience should be in one or more of the following fields: audio transducers, relays, electro-mechanical devices, electronic circuits, radio, TV, communications. Successful applicant will be responsible for analysis of electrical and electronic problems in manufacturing and test equipment design. Well established growing concern. Permanent position. Commercial products only. If you are a "top engineer" and willing to accept a responsible position, send resume in confidence to: Knowles Electronics, Inc., 10545 Anderson Place, Franklin Park, Illinois.

## BUSINESS OPPORTUNITIES

EARN Extra money selling advertising book matches. Free Samples furnished. Matchcorp, Dept. MD-20, Chicago 32, Ill.

## MISCELLANEOUS

ANTIQUE French-Telephones That Work. Gas Lamps & Trolley Cars. (Free Brochures.) Box 41, N. Y. C. 72.

SELL Foreign Cars $1.00. Transistor Radio $19.95. Tweco, Box 155, Indio, Calif.

"WINEMAKING: Beer, Ale Brewing." Illustrated. $2.00. Eaton Books, Box 1242-TC, Santa Rosa, California.

- **Deluxe Thermador Choke.** 4 Hy @ 900 Ma. Sealed. Beautiful construction. (Ltd. Qty.) **$8.95.**
- **Amperite Delay Relay Type 115NO60T.** 60 Second delay. Operates on 115 VAC @ 60 CPS. Fits miniature tube socket. Special: **90¢.**
- **Socket for 5D21, 715A/B/C, etc.** Ceramic. **.50¢** ea. (10 for **$4.00**).
- **G.E. Pyranol Capacitor.** 1.0 Mfd @ 6000 VDC. New Boxed **$4.95** ea.
- **BC-603 Power Supply.** Completely wired. Ready to operate the popular BC603 Receivers. Has exact connector used on BC603 Rcvr. 115 VAC @ 60 CPS operation. **$9.95.**
- **UHF Transmitter**—Compact. Near 1¼ meter band. Converts easily to 2 meters. Uses two 6201's into single Amperex 6360 twin triode. Size 4"x4"x11". Antenna is 10½". New. (Most beautiful rig, finest parts we have seen in yrs.) A real gem, complete with tubes, antenna and case (no book). **$19.95.** Schematic furnished.
- **Battery for above xmtr** furnishes 300 VDC plate and 6.3 VDC filament. **$4.95.**
- **New—Sonotone Rechargeable Battery.** Plug-in any AC outlet to recharge. Use 100's of times. Orig. jobber boxed. **$7.95.**
- **Hi-Fi Special.** Western Electric 300B Audio Output Tubes. Special **$5.50** each (2 for **$10.00**).
- **Mallory Inductuner.** Unused. This famous device is an excellent UHF front-end tuner suitable for TV, UHF, Ham/Comm'l rcvrs, etc. Brand new, unused. **$2.95.**
- **Double-Spaced Variable Capacitor.** 14 Min. to 64 Max. Mmfd. Will handle up to 100 watts AM. Ceramic insulation. **$1.00.**
- **Choke.** .35 Hy @ 2 Amps. DC resistance: 2.2 Ohms. Herm. sld: **$4.25.** Open frame: **$3.50.**
- **RCA Remote TV Control.** For use in 1955 and many earlier RCA TV sets (write for list of sets unit will accommodate). Controls picture and audio. Convenient, practical @ **$13.95,** (with 28 page manual).
- **Electrolytic Condensers.** 4x20 Mfd @ 450 VDC. Sprague. Stock #CO4X20. **69¢** each. Jennings Fixed Vacuum Capacitors: Type JCS—25 Mmf @ 10,000 V. Peak. Cat. #JCS25, **$3.75** ea. 50 Mmf @ 10,000 V. Peak. Cat. #JCS50, **$3.75** ea.
- **Oil Capacitor 2 Mfd @ 6000 VDC.** New. Mfd. by Illinois Condenser Corp. **$8.95.**
- **Oil Capacitor 2 Mfd @ 7500 VDC.** New. Mfd. by G.E. **$22.50.**
- **Crystal Oven.** 12 VAC or DC Oven for 10 Crystal type CR 18/U, or similar crystals. Heater and thermostat enc. Cat. #CFT40148A. **$2.50.**

FOLLOWING ITEMS ARE REMOVED FROM NEW EQUIPMENT AND ARE ALL IN PERFECT CLEAN CONDITION. LIMITED QUANTITIES:

- **Adjustable Time Delay Relay.** SPST. 5 Amps (N.O.). 115 VAC Coil. Adjust. from 2 to 30 sec. **$3.95.**
- **Overload Relay.** Adj. from .5 to 2 Amps DC. Westinghouse Glass enc. **$7.50.**
- **CD 2 Mfd @ 6000 VDC Oil Capacitor. $8.00.**
- **Sangamo Mica Capacitor.** .002 Mfd @ 12,500 volts. **$4.95.**
- **Filter Choke.** 11 Hy @ 300 Ma. Herm. sld. **$3.95.**
- **Swinging Choke.** 6 to 19 Hy @ 300 to 30 Ma. Herm. sld. **$4.95.**
- SPECIAL TRANSMITTING and SPECIAL PURPOSE TUBES: 3B28 @ **$3.00;** 4-125A @ **$29.00;** 4-250A @ **$38.00;** 4X150A @ **$7.00;** 4X250B @ **$35.00;** RKR-72 @ **15¢;** HF-100 @ **$8.00;** 204A @ **$12.00;** 300B @ **$5.50;** 404A/5847 @ **$6.00;** 807 @ **$1.15;** 811 @ **$3.25;** 830B @ **50¢;** 837 @ **$1.00;** 838 @ **$1.00;** 884 @ **90¢;** 5654 @ **$1.75;** 8013 @ **$3.00.** Many others. Largest diversified tube stock in country. Write for Special purpose and xmtg tube catalog (free).

Coming out soon 1960 Green Sheet. **25¢**—Write. HQS for tubes, semiconductors, tube cartons.

All at sensible prices with Barry guarantee (cost of mdse only). $5.00 minimum order. Mdse subject to prior sale. INDUSTRIAL INQUIRIES INVITED. Factory authorized distributors for Westinghouse, CBS—tubes and semiconductors.

**BARRY ELECTRONICS CORP.** Dept. EW-2
512 Broadway (near Spring St.)
NEW YORK 12, N. Y.
Walker 5-7000


# INDEX OF Advertisers

FEBRUARY 1960


| ADVERTISER | PAGE NO. |
|---|---|
| Acro Products Company Kit Div. | 12 |
| Advance Electronics | 150 |
| Aerovox Corporation | 8 |
| Airex Radio Corporation | 146 |
| Allied Radio Corp. | 9, 96, 97, 98, 99, 113 |
| Amperex Electric Corporation | Second Cover |
| Arkay | 24 |
| Ashe Radio Co., Walter | 111 |
| Astatic Corporation, The | 23 |
| Audax Division of Rek-O-Kut Co., Inc. | 90 |
| Audion | 145 |
| B & K Manufacturing Co. | 73, 103 |
| Baltimore Technical Institute | 145 |
| Barry Electronics Corp. | 152 |
| Burroughs Corporation | 16 |
| Burstein-Applebee Co. | 107 |
| CBS Electronics | 25 |
| C & H Sales Co. | 148 |
| Candee Co., J. J. | 132 |
| Candler System Co. | 148 |
| Capitol Radio Engineering Institute | 84, 85, 86, 87 |
| Carston Studios | 130 |
| Century Electronics Co., Inc. | 114, 115 |
| Channel Master Corp. | 10 |
| Chickasha Electronics, Inc. | 102 |
| Cleveland Institute of Electronics | 29 |
| Columbia Electronics | 110 |
| Coyne Electrical School | 124, 143 |
| Delco Radio | 27 |
| DeVry Technical Institute | 5 |
| Dressner | 130 |
| Dual | 92 |
| EICO | 35, 36, 100 |
| Editors and Engineers, Limited | 133 |
| Electro-Voice, Inc. | 30, 31 |
| Electronic Chemical Corp. | 103 |
| Electronics Design Company | 125 |
| Electronics Division Book Service | 139 |
| Electronics World | 18 |
| Electronics World Classified Information | 143 |
| Electronics World Direct Sales Dept. | 111 |
| Electronics World Subscriptions | 126 |
| Electronics World Reprints | 147 |
| Essco C-B Hqts | 148 |
| Fair Radio Sales | 134 |
| G & G Radio Supply Co. | 127 |
| General Electric Co. | 21 |
| General Motors Corp. | Third Cover |
| Goodheart Co., R. E. | 130 |
| Grantham School of Electronics | 11 |
| Grommes Div. of Precision Electronics, Inc. | 140 |
| Hallicrafters | 135 |
| Heath Company | 74, 75, 76, 77, 78, 79, 80, 81, 82 |
| Hi-Fi Annual & Audio Handbook | 138 |
| Hi-Fi Fidelity Center | 130 |
| HiFi/Stereo Review Reprints | 149 |
| Hi-Mu Electronics | 89 |
| Hy-gain Antenna Products | 33 |
| Indiana Technical College | 107 |
| International Crystal Manufacturing Company, Inc. | 13 |
| International Radio & Electronics Corp. | 88 |
| International Resistance Company | 93 |
| Jefferson, Inc., Ray | 121 |
| Jensen Industries, Inc. | 92 |
| Jerrold Electronics Corporation | 137 |
| Johnson Company, E. F. | 133 |
| Kuhn Electronics | 132 |
| Lafayette Radio | 108, 109 |
| Lampkin Laboratories, Inc. | 135 |
| Lektron | 118 |
| Micro Electron Tube Co. | 125 |
| Milwaukee School of Engineering | 145 |
| Moss Electronic, Inc. | 104, 105 |
| National Radio Institute | 19, 20 |
| National Schools | 17 |
| New York Sales & Service | 136 |
| Olson Radio Corporation | 146 |
| Pacific International College of Arts & Sciences | 143 |
| Paco Electronics Co., Inc. | 26 |
| Peak Electronics Company | 112 |
| Philmore Manufacturing Co., Inc. | 126 |
| Picture Tube Outlet | 145 |
| Platt Electronics Corp. | 121 |
| Quietrole Company | 135 |
| RCA Institutes, Inc. | 119, 120 |
| R W Electronics | 145 |
| Rad-Tel Tube Co. | 131 |
| Radio Corporation of America | Fourth Cover |
| Radio Electronic Master | 93 |
| Radio Shack Corporation | 122 |
| Rider Publisher, Inc., John F. | 89 |
| Rinehart & Co., Inc. | 141, 144, 147 |
| Rohn Manufacturing Company | 3 |
| Sams & Co., Inc., Howard W. | 128, 129 |
| Sarkes Tarzian, Inc. | 83 |
| Schober Organ Corp., The | 91 |
| Sherwood Electronics Laboratories, Inc. | 92 |
| Sonotone Corp. | 14 |
| Sprayberry Academy of Radio-Television | 15 |
| Standard Coil Products | 106 |
| Standard Surplus | 144 |
| Sylvania | 6, 7 |
| TAB | 149 |
| Teltron Electric Co. | 142 |
| Terado Company | 140 |
| Texas Crystals | 143 |
| Thorens | 32 |
| Tri-State College | 136 |
| Tru-Vac Electric Company | 123 |
| United Audio | 92 |
| Valparaiso Technical Institute | 89 |
| Vanguard Electronic Lab | 147 |
| Vocaline Company of America, Inc. | 28 |
| Weller Electric Corp. | 34 |
| Wigo | 92 |
| Windsor Electronics | 142 |
| World Radio Laboratories | 121 |
| Wuerth Tube Saver Corp. | 148 |
| Zalytron Tube Corporation | 101 |

# ELECTRONIC TECHNICIANS . . .

*Add a quick source of extra profits with free training in servicing the*

# GUIDE-MATIC

## POWER HEADLIGHT CONTROL

Simple when you know how it works, Guide-Matic could be your fastest growing source of new business for years to come. And it only takes one day of factory-style training to learn the skills of fast, accurate trouble-shooting and quick service to factory specifications.

The course itself won't cost you a cent . . . it's free to qualified electronic technicians. Your only outlay is for transportation and the usual living expenses. It's worth it to have a Guide Lamp diploma proving that you're fully equipped to give fast, efficient service to all the Guide-Matic and Autronic-Eye owners in your area. As an added feature, Twilight Sentinel automatic light switch training is also included.

If you are in the electronics service business, come yourself, or send your technicians. There is one of 30 GM Training Centers near you. Apply through your local United Motors Service Division Distributor or write Guide Lamp Division, General Motors Corp., Anderson, Indiana.

Jumbo-size operational panel of Guide-Matic circuit puts all parts out front for better, more efficient instruction.



GUIDE LAMP DIVISION GENERAL MOTORS CORP. ANDERSON, INDIANA

# REDUCE DAMPER TUBE CALLBACKS

## Here are some important facts about damper circuits

In the *transformer-coupled* circuit, Figure 1, the damper cathode is connected to the "low" (Boost) side of the sweep-output circuit. The voltage difference between cathode and ground is usually less than about 600 volts.

In the *direct-drive* circuit, Figure 2, and in the *auto-transformer circuits*, Figures 3 and 4, the damper cathode is connected to a "high" point in the sweep-output circuit. The peak voltage difference between cathode and ground may be several thousand volts.

Because the damper cathode is "above ground" by several hundred to several thousand volts, care must be taken to prevent voltage breakdown between heater and cathode in the damper tube. Two basic methods are used:




Figure 1. Transformer-coupled horizontal-output circuit. Note that the damper tube heater is connected to the cathode.




Figure 2. Direct-drive circuit. In some variations of this circuit, a capacitor is connected between heater and cathode in place of the direct connection. The capacitor serves to reduce the pulse-voltage difference between heater and cathode.

In one method, shown in Figures 1, 2, and 3, heater is connected to cathode. This connection eliminates voltage difference between heater and cathode, but it also makes the damper tube heater circuit "hot" with respect to ground. For this reason it is necessary to use a separate secondary winding on the power transformer just for the damper heater. This winding, and its connecting leads, must be insulated to withstand the peak voltage difference between cathode and ground.

In the circuits of Figures 1, 2, and 3, if the damper heater winding becomes grounded, or arcs to ground, high current will flow from B+ to ground through the damper tube, and the fuse will blow. Correction of this trouble usually requires costly and time-consuming replacement of the power transformer.

The second method, shown in Figure 4, takes advantage of the fact that modern damper tubes, such as the RCA-6AX4-GTA, 6AU4-GTA, and 6DE4, are designed to withstand high-amplitude positive pulse voltages between heater and cathode. These RCA tubes make it possible to ground the damper heater circuit, and for this reason, the damper heater may be connected to the regular 6.3-volt-ac grounded-heater circuit, thus eliminating the need for an additional high-voltage-insulated secondary on the power transformer.




Figure 3. Auto-transformer circuit in which the damper tube heater is connected to the cathode. In some variations of this circuit, the heater is connected to a lower-voltage tap, "X" or "Y", in order to make the heater negative with respect to the cathode, and to reduce the shunting effect of the heater-circuit capacitance.

From a servicing viewpoint, the second method has definite advantages:

In the circuit of Figure 4, if the insulation between heater and cathode should break down, high current will flow from B+ to ground through the damper tube, and the fuse will blow, but the trouble can be corrected easily, quickly, and inexpensively by installing a new RCA damper tube. This is a lot easier and cheaper than installing a new power transformer!




Figure 4. Modern auto-transformer circuit in which the damper tube heater is grounded. Tubes such as the RCA-6AX4-GTA, 6AU4-GTA, and 6DE4, which are designed to withstand high peak pulse voltage between heater and cathode, are required in this circuit.

*Momentary* arcing, or flashover, in a horizontal output tube or damper tube may be "self-correcting", that is, the flashover may not occur again. But the momentary flashover results in a heavy surge of current which will blow the conventional type of fuse. You can eliminate such unnecessary fuse failure by using RCA "chemical" fuses in the horizontal-output circuit. Three varieties, RCA Stock Nos. 104295, 105041, 105042, are available at your RCA distributor.

RCA damper tubes are designed to give long, dependable service—eliminate costly callbacks—prevent loss of your time and profits. Take for example the RCA-6DE4 and RCA-17DE4. These tubes can supply a peak plate current of 1100 milliamperes and withstand a heater-to-cathode potential of 5000 volts—with a 900-volt dc component! Assure your customers of this kind of performance by asking your distributor for RCA damper tubes.

Get your copy of RCA's Foreign-vs-U.S.A. Receiving Tube-Interchangeability Directory (ICE-197) from your authorized RCA Tube Distributor.

ANOTHER WAY RCA HELPS YOU IMPROVE YOUR BUSINESS

**RADIO CORPORATION OF AMERICA**

**Electron Tube Division** **Harrison, N. J.**

ELECTRONICS

MARCH, 1960